

Baedeker's
CENTRAL ITALY.

Y. xx 20 BÆDEKER'S GUIDE BOOKS.

- GREAT BRITAIN, with 14 Maps and 24 Plans. 1887. 10 marks.
- LONDON AND ITS ENVIRONS, with 3 Maps and 15 Plans.
Seventh Edition. 1889. 6 marks.
- BELGIUM AND HOLLAND, with 12 Maps and 20 Plans.
Ninth Edition. 1888. 6 marks.
- THE RHINE FROM ROTTERDAM TO CONSTANCE (THE SEVEN
MOUNTAINS, MOSELLE, VOLCANIC EIFEL, VOSGES MTS., BLACK FOREST,
etc.), with 36 Maps and 22 Plans. Eleventh Edition. 1889. 6 marks.
- NORTHERN GERMANY, with 32 Maps and 42 Plans.
Ninth Edition. 1886. 7 marks.
- SOUTHERN GERMANY AND AUSTRIA, INCLUDING HUN-
GARY AND TRANSYLVANIA, with 14 Maps and 30 Plans.
Sixth Edition. 1887. 7 marks.
- THE EASTERN ALPS, INCLUDING THE BAVARIAN HIGH-
LANDS, TYROL, SALZKAMMERGUT, etc. With 34 Maps,
12 Plans, and 7 Panoramas. Sixth Edition. 1888. 8 marks.
- GREECE, with 6 Maps, 14 Plans and a Panorama of Athens.
1889. 10 marks.
- NORTHERN ITALY, INCLUDING FLORENCE AND THE IS-
LAND OF CORSICA, AND ROUTES TO ITALY THROUGH FRANCE, SWITZER-
LAND, etc., with 19 Maps and 33 Plans. Eighth Edition. 1889. 6 marks.
- CENTRAL ITALY AND ROME, with 10 Maps, 31 Plans, a
Panorama of Rome and a View of the Forum Romanum. Tenth
Edition. 1890. 6 marks.
- SOUTHERN ITALY, SICILY, AND EXCURSIONS TO THE
LIPARI ISLANDS, TUNIS (CARTHAGE), SARDINIA, MALTA, AND
CORFU, with 26 Maps and 17 Plans. Ninth Edition. 1887. 6 marks.
- NORWAY AND SWEDEN, with 23 Maps and 13 Plans. Fourth
Edition. 1889. 9 marks.
- PARIS AND ITS ENVIRONS, WITH ROUTES FROM LONDON
TO PARIS. With 9 Maps and 30 Plans. Ninth Edition. 1888. 6 marks.
- NORTHERN FRANCE, with 9 Maps and 25 Plans. 1889
7 marks.
- SWITZERLAND, AND THE ADJACENT PARTS OF ITALY,
SAVOY, AND THE TYROL, with 38 Maps, 11 Plans, and 11 Panoramas.
Thirteenth Edition. 1889. 8 marks.
- LOWER EGYPT, WITH THE FAYÛM AND THE PENINSULA OF
SINAI, with 16 Maps, 30 Plans, 7 Views, and 76 Vignettes. Second
Edition. 1885. 16 marks.
- PALESTINE AND SYRIA, with 18 Maps, 43 Plans, a Pano-
rama of Jerusalem, and 10 Views. 1876. 21 marks.
- CONVERSATION DICTIONARY in four languages: Eng-
lish, French, German, Italian. 3 marks.
- THE TRAVELLER'S MANUAL OF CONVERSATION, IN
ENGLISH, GERMAN, FRENCH, AND ITALIAN. 3 marks.

Horrie Napier

Easter Monie

Jarvis

Scotland



22502699675

1151 4/6

CENTRAL ITALY

AND

ROME.


MONEY - TABLE.

(Comp. p. xiii.)

Approximate Equivalents.

| Italian. | | American. | | English. | | | German. | | Austrian. | |
|--------------|--------------|--------------|-------------|---------------|-----------|----------------|------------|-------------|------------|------------|
| <i>Lire.</i> | <i>Cent.</i> | <i>Doll.</i> | <i>Cts.</i> | <i>L.</i> | <i>S.</i> | <i>D.</i> | <i>Mk.</i> | <i>Pfg.</i> | <i>Fl.</i> | <i>Kr.</i> |
| — | 5 | — | 1 | — | — | $\frac{1}{2}$ | — | 4 | — | 2 |
| — | 25 | — | 5 | — | — | $2\frac{1}{2}$ | — | 20 | — | 10 |
| — | 50 | — | 10 | — | — | 5 | — | 40 | — | 20 |
| — | 75 | — | 15 | — | — | $7\frac{1}{4}$ | — | 60 | — | 30 |
| 1 | — | — | 20 | — | — | $9\frac{3}{4}$ | — | 80 | — | 40 |
| 2 | — | — | 40 | — | 1 | $7\frac{1}{4}$ | 1 | 60 | — | 80 |
| 3 | — | — | 60 | — | 2 | 5 | 2 | 40 | 1 | 20 |
| 4 | — | — | 80 | — | 3 | $2\frac{1}{2}$ | 3 | 20 | 1 | 60 |
| 5 | — | 1 | — | — | 4 | — | 4 | — | 2 | — |
| 6 | — | 1 | 20 | — | 4 | $9\frac{3}{4}$ | 4 | 80 | 2 | 40 |
| 7 | — | 1 | 40 | — | 5 | $7\frac{1}{2}$ | 5 | 60 | 2 | 80 |
| 8 | — | 1 | 60 | — | 6 | 5 | 6 | 40 | 3 | 20 |
| 9 | — | 1 | 80 | — | 7 | $2\frac{1}{2}$ | 7 | 20 | 3 | 60 |
| 10 | — | 2 | — | — | 8 | — | 8 | — | 4 | — |
| 11 | — | 2 | 20 | — | 8 | $9\frac{3}{4}$ | 8 | 80 | 4 | 40 |
| 12 | — | 2 | 40 | — | 9 | $7\frac{1}{2}$ | 9 | 60 | 4 | 80 |
| 13 | — | 2 | 60 | — | 10 | 5 | 10 | 40 | 5 | 20 |
| 14 | — | 2 | 80 | — | 11 | $2\frac{1}{2}$ | 11 | 20 | 5 | 60 |
| 15 | — | 3 | — | — | 12 | — | 12 | — | 6 | — |
| 16 | — | 3 | 20 | — | 12 | $9\frac{3}{4}$ | 12 | 80 | 6 | 40 |
| 17 | — | 3 | 40 | — | 13 | $7\frac{1}{2}$ | 13 | 60 | 6 | 80 |
| 18 | — | 3 | 60 | — | 14 | 5 | 14 | 40 | 7 | 20 |
| 19 | — | 3 | 80 | — | 15 | $2\frac{1}{2}$ | 15 | 20 | 7 | 60 |
| 20 | — | 4 | — | — | 16 | — | 16 | — | 8 | — |
| 25 | — | 5 | — | — | — | — | 20 | — | 10 | — |
| 100 | — | 20 | — | $\frac{1}{4}$ | — | — | 80 | — | 40 | — |

DISTANCES. Since the consolidation of the Kingdom of Italy the French *mètre* system has been in use throughout the country, but the old Italian *miglio* (pl. *le miglia*) is still sometimes preferred to the new *kilomètre*. One kilomètre is equal to 0.62138, or nearly $\frac{5}{8}$ ths, of an English mile (8 kil. = 5 M.). The Tuscan *miglio* is equal to 1.65 kilomètre or 1 M. 44 yds.; the Roman *miglio* is equal to 1.49 kilomètre or 1630 yds.




Digitized by the Internet Archive
in 2015

<https://archive.org/details/b21781886>



ITALIA CENTRALE.

Scala di 1: 1350.000



Abbreviazioni: A. Alpe, Alpi, C. Capo, C. Casale, Cus. Casina, C. Castello, G. Golfo, I. Isola, L. Lago, M. Monte, M. Monti, M. Montagna, M. Miniera, P. Pania, P. Poggio, P. Passo, P. Ponte, P. Punta, P. Pizzo, R. Rovino, S. San, Santa, Staz. Stazione, T. Torre. Tramvia

ITALY.

HANDBOOK FOR TRAVELLERS

BY

K. BAEDERER.

SECOND PART:

CENTRAL ITALY AND ROME.

With 10 Maps, 31 Plans, a Panorama of Rome, and a View of the
Forum Romanum.

Tenth revised Edition.

LEIPSIC: KARL BAEDERER, PUBLISHER.
LONDON: DULAU AND CO., 37 SOHO SQUARE, W.

1890.

All rights reserved.

93756

"Go, little book, God send thee good passage,
And specially let this be thy prayere
Unto them all that thee will read or hear,
Where thou art wrong, after their help to call,
Thee to correct in any part or all."

WELLCOME
LIBRARY

General Collections

M

10348

PREFACE.

The objects of the Handbook for Italy, which consists of three volumes, each complete in itself, are to supply the traveller with some information regarding the progress of civilisation and art among the people he is about to visit, to render him as independent as possible of the services of guides and valets-de-place, to protect him against extortion, and in every way to aid him in deriving enjoyment and instruction from his tour in one of the most fascinating countries in the world. The Handbook will also, it is hoped, be the means of saving the traveller many a trial of temper; for there is probably no country in Europe where the patience is more severely taxed than in some parts of Italy.

The Handbook is based on the Editor's personal acquaintance with the places described, most of which he has repeatedly and carefully explored. As, however, changes are constantly taking place, he will highly appreciate any communications with which travellers may favour him, if the result of their own observation. The information already received from numerous correspondents, which he gratefully acknowledges, has in many cases proved most serviceable. Hotel-bills, with annotations showing the traveller's opinion as to his treatment and accommodation, are particularly useful.

The tenth edition of Central Italy and Rome, like its predecessors, has been carefully revised and brought down to date. The introductory articles on art by *Prof. R. Kekulé* of Bonn and *Prof. A. Springer* of Leipzig have been adapted for the use of English travellers with the kind assistance of *Mr. J. A. Crowe*, the eminent historian of art. Professor Springer has also contributed many valuable incidental remarks on modern art.

The MAPS and PLANS, on which special care has been bestowed, will abundantly suffice for the use of the ordinary traveller. The *Plan of Rome* (scale 1 : 15,000) is divided into three sections with a view to obviate the necessity of unfolding a large sheet of paper at every consultation, and its use will be further facilitated by reference to the small clue-plan inside the cover at the end of the volume.

HEIGHTS are given in English feet (1 Engl. ft. = 0,3048 mètre), and DISTANCES in English miles (comp. p. ii).

HOTELS (comp. p. xxi). In no country does the treatment which the traveller experiences at hotels vary more than in Italy, and attempts at extortion are perhaps nowhere so outrageous. Besides the modern palatial and expensive establishments, the Handbook also contains a selection of modest, old-fashioned inns, where gentlemen travelling alone will not unfrequently find good accommodation at moderate charges. The asterisks indicate those hotels which the Editor has reason to believe from his own experience, as well as from information supplied by numerous travellers, to be respectable, clean, and reasonable. The value of these asterisks, it need hardly be observed, varies according to circumstances, those prefixed to town-hotels and village-inns signifying respectively that the establishments are good of their kind. At the same time the Editor does not doubt that comfortable quarters may occasionally be obtained at inns which he has not recommended or even mentioned. Although changes frequently take place, and prices generally have an upward tendency, the average charges stated in the Handbook will enable the traveller to form a fair estimate of his probable expenditure.

To hotel-proprietors, tradesmen, and others the Editor begs to intimate that a character for fair dealing and courtesy towards travellers forms the sole passport to his commendation, and that advertisements of every kind are strictly excluded from his Handbooks.

CONTENTS.

| Introduction. | | Page |
|--|--|-------|
| I. Travelling Expenses. Money | | xiii |
| II. Season and Plan of Tour | | xiv |
| III. Language | | xv |
| IV. Passports. Custom House. Luggage | | xvi |
| V. Public Safety. Begging | | xvi |
| VI. Intercourse with Italians | | xvii |
| VII. Conveyances | | xviii |
| VIII. Hotels | | xxi |
| IX. Restaurants, Cafés, etc. | | xxii |
| X. Sights, Theatres, etc. | | xxiv |
| XI. Post Office. Telegraph. | | xxv |
| XII. Climate. Health. | | xxv |
| XIII. Dates of Recent Events | | xxvii |
| Ancient Art, by <i>Prof. R. Kekulé</i> | | xxix |
| Mediæval and Modern Roman Art, by <i>Prof. A. Springer</i> | | xliii |

FIRST SECTION.

S. Tuscany. Umbria. The Marches.

| Route | |
|--|--------|
| 1. From Leghorn or Pisa to Rome by the Maremma | 1 |
| 1. From Leghorn to Civit  Vecchia by sea | 1 |
| 2. Piombino and Populonia | 2 |
| 3. From Grosseto to Rusell  | 3 |
| 4. Monte Argentario. Cosa | 3, 4 |
| 5. From Montalto to Vulci | 4 |
| 6. From Corneto to Toscanella | 6 |
| 7. From Civit  Vecchia to La Tolfa | 7 |
| 2. From Leghorn to Volterra and Colle | 7 |
| 1. From Volterra to Monte Cerboli | 8 |
| 2. From Volterra to S. Girolamo | 11 |
| 3. From Volterra to the copper-mines of Monte Catini | 11 |
| 3. Elba and the Tuscan Islands | 11 |
| 4. From Florence to Siena and Chiusi vi  Empoli | 13 |
| 1. From Poggibonsi to San Gimignano | 14 |
| 2. From Asciano to Grosseto. Monte Amiata | 17, 18 |
| 3. From Montepulciano to Pienza | 20 |
| 5. Siena | 20 |
| Excursions from Siena. L'Osservanza, S. Colomba, etc. | 36 |
| 6. From Florence to Perugia vi  Arezzo and Terontola (<i>Chiusi, Rome</i>) | 37 |
| 1. From Arezzo to Stia and Pratovecchio | 42 |
| 2. From Arezzo to Monte Sansavino, Fojano, and Betolle | 42 |
| 7. Perugia | 46 |
| From Perugia to Narni vi  Todi | 55 |
| 8. From Arezzo to Fossato. Borgo S. Sepolero. Citt  di Castello. Gubbio | 56 |

| Route | Page |
|--|--------|
| 9. From Florence to Rome viâ (<i>Arezzo</i>) Terontola and Chiusi | 59 |
| 1. From Chiusi to Città della Pieve. Cetona | 61 |
| 2. Orvieto | 61 |
| 3. Bolsena | 65 |
| 4. From Borghetto to Cività Castellana. Falerii. Mount Soraete | 67, 68 |
| 10. From Attigliano to Viterbo | 69 |
| 1. Excursions from Viterbo. Toscanella. Castel d'Asso. Vetralla. Norehia. Caprarola. Sutri. Nepi. Castel S. Elia | 72-74 |
| 11. From Perugia to Foligno and Orte (<i>Rome</i>). Assisi. Spoleto. Waterfalls of Terni. Narni | 74 |
| 12. From Bologna to Rimini, Falconara (<i>Rome</i>), and Ancona | 87 |
| 1. From Rimini to San Marino | 94 |
| 2. From Pesaro to Urbino | 96 |
| 3. From Fano to Fossato viâ Fossombrone and the Furlo Pass | 100 |
| 13. Ancona and its Environs. Osimo. Loreto | 102 |
| From Porto Civitanova to Fabriano | 107 |
| 14. From Ancona to Foligno (<i>Orte, Rome</i>) | 108 |
| From Fabriano to Sassoferrato | 109 |

SECOND SECTION.

Rome.

Preliminary Information: —

| | |
|--|----------|
| Arrival. Police. Embassies and Consulates | 110 |
| Hotels. Pensions. Private Apartments. Restaurants | 110, 111 |
| Osterie. Cafés. Confectioners. Gratuities | 113, 114 |
| Baths. Climate. Physicians. Chemists. Bankers | 114, 115 |
| Booksellers. Libraries. Reading Rooms. Newspapers | 115, 116 |
| Guides. Teachers of Italian. Music. Studios. Goods Agents | 116, 117 |
| Shops | 117 |
| Theatres | 118 |
| Carriages. Porters. Post Office. Telegraph Office | 119 |
| English Churches. Italian Protestant Churches. Clubs | 119 |
| Church Festivals. Popular Festivals. Street Scenes | 119-122 |
| Garrison | 122 |
| Collections, Villas, etc. | 122 |
| Diary. Summary of Attractions | 125, 126 |
| Bibliography | 127 |

| | |
|---------------------------------------|-----|
| History of the City of Rome | 129 |
|---------------------------------------|-----|

| | |
|---|-----|
| Chronological Table of Roman Emperors and Popes | 139 |
|---|-----|

| | |
|----------------------|-----|
| Topography | 143 |
|----------------------|-----|

| | |
|--|-----|
| 1. <i>Strangers' Quarter and Corso</i> | 146 |
|--|-----|

| | |
|--|----------|
| Piazza del Popolo. S. Maria del Popolo | 146, 147 |
|--|----------|

| | |
|----------------------|-----|
| The Pincio | 148 |
|----------------------|-----|

| | |
|--|-----|
| Villa Medici. S. Trinità de' Monti | 149 |
|--|-----|

| | |
|--|-----|
| Casa Zuccari-Bartholdy. Piazza di Spagna. Propaganda | 150 |
|--|-----|

| | |
|--|-----|
| S. Andrea delle Fratte. Fontana di Trevi | 151 |
|--|-----|

| | |
|---------------------|-----|
| The Corso | 152 |
|---------------------|-----|

| | |
|---|-----|
| S. Carlo al Corso. S. Lorenzo in Lucina | 153 |
|---|-----|

| | |
|--|--|
| Post and Telegraph Office. Pal. Chigi. Piazza Colonna. | |
|--|--|

| | |
|---|--|
| Column of Marcus Aurelius. Piazza di Monte Citorio. | |
|---|--|

| | |
|-------------------------------|-----|
| Camera de' Deputati | 154 |
|-------------------------------|-----|

| | |
|--|-----|
| Dogana di Terra. Palazzo Sciarra-Colonna. S. Ignazio | 155 |
|--|-----|

| | |
|--|-----|
| Collegio Romano. Museo Kircheriano | 156 |
|--|-----|

| | |
|--|----------|
| S. Marcello. S. Maria in Via Lata. Palazzo Doria | 157, 158 |
|--|----------|

(Rome)

Page

| | |
|--|-----|
| Palazzo di Venezia. Palazzo Torlonia. S. Marco . . . | 162 |
| Palazzo Colonna. Galleria Colonna. Tomb of Bibulus . . . | 163 |
| SS. Apostoli . . . | 165 |

II. *The Eastern Quarter. Quirinal, Viminal, Esquiline* . . . 166

| | |
|---|----------|
| Piazza delle Terme. Railway Station. Thermac of Diocletian. S. Maria degli Angeli . . . | 166, 167 |
| Via Venti Settembre. S. Maria della Vittoria . . . | 168 |
| Wall of Servius. Campo Militare. Via Nazionale . . . | 169 |
| Palazzo and Galleria Barberini. Piazza Barberini . . . | 170, 171 |
| S. Maria della Concezione. Villa Ludovisi . . . | 172 |
| Piazza del Quirinale . . . | 173 |
| Palazzo Regio al Quirinale. Palazzo Rospigliosi . . . | 174 |
| S. Silvestro al Quirinale. S. Pudenziana . . . | 175 |
| S. Lorenzo in Panisperna. S. Maria Maggiore . . . | 176 |
| S. Prassede . . . | 178 |
| Arch of Gallienus. Aquarium. Piazza Vitt. Emanuele. S. Bibiana . . . | 179 |
| Temple of Minerva Medica. Porta Maggiore . . . | 180 |
| S. Croce in Gerusalemme. Sette Sale . . . | 181 |
| Gardens of Mæcenæ. S. Martino ai Monti. S. Pietro in Vincoli . . . | 182 |

III. *Rome on the Tiber (Left Bank)* . . . 183

| | |
|--|----------|
| Via di Ripetta. Mausoleum of Augustus . . . | 183, 184 |
| Palazzo and Galleria Borghese . . . | 184, 185 |
| S. Agostino . . . | 189 |
| Palazzo Lancelotti. Piazza Navona. S. Agnese . . . | 190 |
| S. Maria dell' Anima. S. Maria della Pace . . . | 191 |
| Palazzo Madama . . . | 192 |
| S. Luigi de' Francesi. Pantheon . . . | 193 |
| S. Maria sopra Minerva . . . | 195 |
| Università della Sapienza. Corso Vittorio Emanuele. Gesù . . . | 197 |
| Palazzo Vidoni. S. Andrea della Valle . . . | 198 |
| Pal. Massimi alle Colonne. Palazzo della Cancelleria. S. Lorenzo in Damaso . . . | 199 |
| Chiesa Nuova . . . | 200 |
| Palazzo Braschi. Piazza del Pasquino. S. Carlo a' Catinari. Piazza Tartaruga . . . | 201 |
| Palazzo Mattei. S. Caterina de' Funari. S. Maria in Campitelli . . . | 202 |
| Theatre of Marcellus. Ghetto. Portico of Octavia . . . | 203 |
| Ponte de' Quattro Capi. Isola Tiberina. S. Bartolommeo . . . | 204 |
| Theatre of Pompey. Palazzo Farnese. Palazzo Spada alla Regola . . . | 205 |
| S. Giovanni de' Fiorentini . . . | 207 |

IV. *Ancient Rome* . . . 207

The Capitol . . . 208

| | |
|--|-----|
| S. Maria in Araceli . . . | 209 |
| Piazza del Campidoglio . . . | 210 |
| Palazzo del Senatore . . . | 211 |
| Collections of the Capitol. Palace of the Conservatori . . . | 211 |
| Capitoline Museum . . . | 216 |
| Tarpeian Rock. Tabularium . . . | 221 |

Forum Romanum . . . 222

| | |
|--|-----|
| Colonnade of the Twelve Gods. Temple of Vespasian . . . | 225 |
| Temple of Concordia. Temple of Castor and Pollux. Basilica Julia . . . | 226 |
| Temple of Saturn . . . | 227 |
| Arch of Septimius Severus. Rostra. Column of Phocas . . . | 228 |
| Temple of Cæsar . . . | 229 |
| Atrium Vestæ . . . | 230 |
| Temple of Faustina. SS. Cosma e Damiano . . . | 231 |

| | (Rome) | Page |
|--|---|---------|
| Basilica of Constantine. | S. Francesca Romana | 232 |
| Triumphal Arch of Titus. | Temple of Venus and Roma | 233 |
| Colosseum | | 234 |
| Triumphal Arch of Constantine | | 236 |
| Thermæ of Titus | | 237 |
| Fora of the Emperors. | Academy of St. Luke | 237 |
| Carcer Mamertinus | | 237 |
| Accademia di S. Luca | | 238 |
| Forum of Cæsar. | Forum of Augustus. Forum of Nerva | 239 |
| Forum of Trajan. | Trajan's Column | 240 |
| The Palatine | | 241 |
| Lupercal. | House of Livia | 243 |
| Palace of Tiberius. | Palace of the Flavii | 244 |
| Palace of Septimius Severus | | 246 |
| Pædagogium | | 247 |
| Velabrum and Forum Boarium | | 247 |
| S. Teodoro. | S. Giorgio in Velabro. Janus Quadrifrons. Cloaca Maxima | 248 |
| S. Maria in Cosmedin. | Round Temple. S. Maria Egiziaca. House of Crescentius or Rienzi | 249 |
| Ponte Rotto. | S. Nicola in Carcere. Via de' Cerchi (Circus Maximus) | 250 |
| The Aventine | Monte Testaccio | 250 |
| Marmorata. | Monte Testaccio. Protestant Cemetery | 251 |
| Pyramid of Cestius. | S. Sabina | 252 |
| S. Alessio. | S. Maria Aventina | 253 |
| S. Prisca. | S. Saba | 254 |
| The Via Appia within the City | | 254 |
| S. Balbina | | 254 |
| Thermæ of Caracalla | | 255 |
| SS. Nereo ed Achilleo. | S. Cesareo. Via Latina | 256 |
| Tomb of the Scipios. | Columbaria | 257 |
| Arch of Drusus | | 258 |
| The Cælius | | 258 |
| S. Gregorio Magno | | 258 |
| SS. Giovanni e Paolo. | S. Maria in Domnica. Villa Mattei | 259 |
| S. Stefano Rotondo | | 260 |
| S. Clemente. | The Lateran | 260 |
| SS. Quattro Coronati | | 264 |
| Piazza S. Giovanni in Laterano. | Baptistery. S. Giovanni in Laterano | 265 |
| Palazzo del Laterano | | 267 |
| Gregorian Museum. | Museo Profano | 268 |
| Christian Museum. | Picture Gallery | 270 |
| Villa Massimi. | Scala Santa. Villa Wolkonsky | 272 |
| Amphitheatrum Castrense | | 273 |
| V. <i>Quarters of the City on the Right Bank</i> | | 273 |
| The Borgo | | 273 |
| Ponte S. Angelo. | Castello S. Angelo | 274 |
| Palazzo Giraud | | 276 |
| Piazza di S. Pietro | | 277 |
| S. Pietro in Vaticano | | 277 |
| Cimitero dei Tedeschi | | 285 |
| The Vatican | | 286 |
| A. Paintings: — | | |
| Sistine Chapel. | Seala Regia. Sala Ducale. Pauline Chapel | 287-292 |
| Raphael's Stanze and Loggie. | Cappella Niccolina | 292-301 |
| Picture Gallery. | Raphael's Tapestry | 301-303 |

| | (Rome) | Page |
|--|--------|----------|
| B. Antiquities: — | | |
| Museo Pio. Clementino. Museo Chiaramonti. Braccio Nuovo | | 304-316 |
| Egyptian Museum. Museo Etrusco | | 316-319 |
| C. Library of the Vatican | | 319 |
| The Lungara | | 322 |
| S. Onofrio. Villa Farnesina | | 322, 323 |
| Palazzo Corsini. Museo Torlonia | | 324, 325 |
| Trastevere | | 327 |
| Ponte Sisto | | 327 |
| S. Pietro in Montorio | | 328 |
| Acqua Paola. Passeggiata Margherita. Ponte Garibaldi. S. Crisogono. S. Maria in Trastevere | | 329, 330 |
| S. Cecilia in Trastevere | | 331 |
| S. Francesco a Ripa | | 332 |

THIRD SECTION.

Environs of Rome.

| | |
|---|----------|
| 1. <i>Short Excursions in the Campagna</i> | 333 |
| From the Porta del Popolo: Villa Borghese. Parco Regina Margherita. Ponte Molle. Via Flaminia. Villa of Livia. Acqua Acetosa. Villa di Papa Giulio. Villa Madama. Monte Mario | 334 |
| From the Porta Salara: Villa Albani. Antemnae. Ponte Salaro. Fidenæ | 338 |
| From the Porta Pia: Villa Torlonia. S. Agnese Fuori. S. Costanza. Ponte Nomentano. Mons Sacer | 341 |
| From the Porta S. Lorenzo: Via Tiburtina. S. Lorenzo Fuori. Campo Verano | 343 |
| From the Porta Maggiore: Tor de' Schiavi. Torre Pignattara | 345 |
| From the Porta S. Giovanni: Via Latina. Porta Furba | 346 |
| From the Porta S. Sebastiano: Via Appia. Domine Quo Vadis. S. Sebastiano. Circus of Maxentius. Tomb of Cæcilia Metella. Deus Rediculus. Grotto of Egeria. S. Urbano | 347 |
| From the Porta S. Paolo: S. Paolo Fuori. Tre Fontane | 352 |
| From the Porta S. Panerazio: Villa Doria Pamphilj | 355 |
| The Catacombs | 356 |
| 2. <i>The Alban Mountains</i> | 363 |
| Frascati | 364 |
| Grotta Ferrata. Marino | 367 |
| Albano. Castel Gandolfo. Lake of Albano. The Emissarium | 368-370 |
| Ariccia. Genzano. Lake of Nemi. Nemi | 370, 371 |
| Palazzuola. Alba Longa. Rocca di Papa. Monte Cavo | 372 |
| 3. <i>The Sabine Mountains</i> | 373 |
| From Rome to Tivoli. Aque Albule. Hadrian's Villa | 373, 374 |
| Tivoli | 377 |
| Monte Gennaro | 379 |
| From Tivoli to Subiaco | 379 |
| Valley of the Licenza. Mandela. Subiaco | 380, 381 |
| From Rome to Palestrina | 382 |
| From Palestrina to Subiaco via Olevano | 384 |
| 4. <i>The Volscian Mountains</i> | 385 |
| Cori. Norma. Ninfæ. Sezze. Piperno. Segni | 386-388 |
| 5. <i>Etruscan Towns</i> | 389 |
| Vulturnum | 389 |
| Galera | 390 |
| Bracciano | 391 |
| Cervetri (Cære) | 392 |

| | Page |
|--|----------|
| 6. <i>The Sea-Coast of Latium</i> | 393 |
| Porto. Fiumicino. | 393 |
| Ostia | 394 |
| Anzio. Nettuno. | 397, 398 |
| List of the Artists mentioned in the Handbook | 399 |
| Index | 404 |
| Omnibus and Tramway Routes and Cab Tariff in Rome, and List of Streets in the Plan of Rome, in the Appendix at the end of the volume. | |

Maps.

1. MAP OF ITALY (1:1,350,000), facing title-page.
2. THE ROMAN CAMPAGNA (1:400,000), p. 332.
3. ENVIRONS OF ROME (1:60,000), p. 334.
4. THE ALBAN MOUNTAINS (1:100,000), p. 364.
5. ENVIRONS OF TIVOLI (1:12,500), p. 376.
6. THE SABINE MOUNTAINS (1:100,000): Plate I.: Tivoli and Valley of the Tevere, p. 378.
7. THE SABINE MOUNTAINS: Plate II. Roviano, Subiaco, Capranica, p. 380.
8. THE SABINE MOUNTAINS: Plate III.: Tivoli, Palestrina, Olevano, p. 382.
9. THE VOLSCIAN MOUNTAINS (1:150,000): p. 386.
10. RAILWAY MAP OF ITALY (1:7,000,000), at the end of the Handbook.

Plans.

1. VOLTERRA, p. 9. — 2. SIENA, p. 20. — 3. AREZZO, p. 39. — 4. CORTONA, p. 39. — 5. FERUGIA, p. 46. — 6. ORVIETO, p. 62. — 7. ASSISI, p. 78. — 8. TERNI and its Environs, p. 79. — 9. FORLÌ, p. 90. — 10. RIMINI, p. 91. — 11. ANCONA, p. 102. — 12. Large Plan of ROME, and — 13. Clue Plan of ROME, both at the end of the book. — 14. ANCIENT ROME, p. 207. — 15. PALACE OF THE CONSERVATORI, p. 216. — 16. CAPITOLINE MUSEUM, p. 217. — 17. FORUM ROMANUM, p. 222. — 18. FORA OF THE EMPERORS, p. 238. — 19. PALACES OF THE EMPERORS on the Palatine, p. 241. — 20. THERMÆ OF CARACALLA, p. 255. — 21. Section, and — 22. Ground-plan of S. CLEMENTE, p. 261. — 23. S. GIOVANNI IN LATERANO, and LATERAN MUSEUM, p. 265. — 24. S. PIETRO IN VATICANO and the VATICAN PALACE (survey-plan), p. 276. — 25. Ground-plan of S. PIETRO IN VATICANO in its present state, p. 278. — 26. S. PIETRO IN VATICANO (Bramante's ground-plan), p. 279. — 27. VATICAN PALACE, S. Wing (Sistine Chapel, Raphael's Loggia and Stanzas), p. 289. — 28. VATICAN PALACE, N. Wing (Museum of Antiquities), p. 306. — 29. HADRIAN'S VILLA, p. 377. — 30. OSTIA, p. 395. — 31. PORTO D'ANZIO and NETTUNO, p. 397.
- ARMS OF THE POPES, from 1417 to the present day, p. 142.
- VIEW OF THE FORUM ROMANUM in its former and present condition, p. 226.
- PANORAMA OF ROME (from S. Pietro in Montorio), p. 328.

The best maps of Central and Southern Italy are the *Carta Corografica ed Archeologica dell' Italia Centrale* (1:250,000; 4 sheets; price 10s., on linen 13s.) and the *Nuova Carta Generale dell' Italia Meridionale* (1:800,000; price 6s., on linen 8s.), both executed under the superintendence of Professor Kiepert of Berlin (1881-82).

Abbreviations.

R. = Room, B. = Breakfast, D. = Dinner, A. = Attendee, L. = Light. — r. = right, l. = left; applied to the banks of a river with reference to the traveller looking *down* the stream. — N., S., E., W., the points of the compass and adjectives derived from them. — M. = English miles; ft. = English feet.

Asterisks are employed as marks of commendation.

INTRODUCTION.

'Thou art the garden of the world, the home
Of all Art yields, and Nature can decree;
E'en in thy desert, what is like to thee?
Thy very weeds are beautiful, thy waste
More rich than other climes' fertility,
Thy wreck a glory, and thy ruin graced
With an immaculate charm which cannot be defaced.'

BYRON.

I. Travelling Expenses. Money.

Expenses. The cost of a tour in Italy depends of course on the traveller's resources and habits, but, as already stated in the first part of this Handbook, it need not exceed that incurred in the more frequented parts of the continent. The average expenditure of a single traveller may be estimated at 20-30 francs per day, or at 12-15 francs when a prolonged stay is made at one place; but persons acquainted with the language and habits of the country may easily restrict their expenses to still narrower limits. Those who travel as members of a party effect a considerable saving by sharing the expense of guides, carriages, and other items. When ladies are of the party, the expenses are generally greater.

Money. The French monetary system is now in use throughout the whole of Italy. The franc (*lira* or *franco*) contains 100 *centesimi*; 1 fr. 25c. = 1s. = 1 German mark (comp. p. ii). In copper (*bronzo* or *rame*) there are coins of 1, 2, 5, and 10 *centesimi*. A piece of 5c. is called a *soldo*, or *sou*, and as the lower classes often keep their accounts in *soldi*, the traveller will find it useful to accustom himself to this mode of reckoning. The gold and silver coins of France, Switzerland, Greece, and Belgium circulate freely, but the traveller should be on his guard against old coins from the papal mint, which cannot be parted with except at a loss, and should also refuse Greek copper coins. The recognized paper currency consists of the banknotes of the *Biglietti di Stato* and the *Banca Nazionale*; those of the *Banca di Toscana* are legal tender in Tuscany, and those of the *Banca di Roma* in Rome. Other notes should be refused, though those of all the large Italian banks are generally accepted at Rome without demur.

BEST MONEY FOR THE TOUR. *Circular Notes* or *Letters of Credit*, obtainable at the principal English and American banks, form the proper medium for the transport of large sums, and realise the most favourable exchange. English and German banknotes also realise their nominal value. A moderate supply of *French Gold* may

prove useful. *Sovereigns* are almost everywhere received as the equivalent of 25 fr., and sometimes a little more.

EXCHANGE. Foreign money is most advantageously changed in the larger towns, either at one of the English bankers or at a respectable money-changer's (*'cambiavaluta'*). As a rule, those money-changers are the most satisfactory who publicly exhibit a list of the current rates of exchange. The traveller should always take care to obtain an abundant supply of small notes (1, 2, and 5 fr.), as it is often difficult to change those of large amount. When a railway-fare has to be paid it is a wise precaution to be provided with the exact sum beforehand, in order that mistakes or imposition may be prevented. Besides the small notes, 1-1½ fr. in copper should also be carried in a separate pocket or pouch.

Money Orders payable in Italy, for sums not exceeding 10*l.*, are now granted by the English Post Office at the following rates: not exceeding 2*l.*, 6*d.*; 5*l.*, 1*s.*; 7*l.*, 1*s.* 6*d.*; 10*l.*, 2*s.* These are paid in gold. The identity of the receiver must be guaranteed by two well-known residents, or by a *Libretto di Ricognizione* (1 fr.; with 10 coupons) obtained beforehand in the central post-office at Rome; an exhibition of the passport, however, often suffices. The charge for money-orders granted in Italy and payable in England is 40 c. per *l.* sterling.

A convenient and safe method of carrying money for a journey in Italy is afforded by the *Titoli di Credito*, which may be procured at the post-offices of the principal Italian towns for any sum not exceeding 10,000 fr. (400*l.*) The holder of one of these orders may then draw what sum (from 50 fr. upwards) he requires at any post-office in the kingdom, until the amount for which it is issued has been exhausted. At small places the sum drawable at once is limited to 200 fr., in provincial capitals to 1000 fr., and in Rome and the nine chief towns to 2000 fr. It is necessary to state the post-office at which the *first* payment is desired. A charge of 50 c. is made for each 100 fr. up to 1000 fr., and 25 c. for each additional 100 fr.; thus an order for 10,000 fr. costs 27½ fr. In case of loss the traveller should immediately inform the postal authorities, giving his name and the number of his '*titolo*'.

II. Season and Plan of Tour.

Season. The season selected for the tour must of course depend on the traveller himself, but the colder months are those usually preferred. Most travellers bound for the South cross the Alps in September and October, and arrive in Rome about the beginning of November. Rome is the favourite winter-residence of strangers till the Carnival, but most of them leave it in Lent for the gayer scenes of Naples, and at Easter it is comparatively deserted, as the chief attractions of the festival are now gone. As summer approaches most travellers prepare to quit the country, but even during the hot season tourists are not unfrequently met with. In this vast and ever-varying influx of travellers the Anglo-American element is always greatly predominant.

No month in the year can be pronounced absolutely unfavourable for travelling in Italy, but the seasons recommended are from 15th Sept. to 15th Nov., and the months of April and May. The rainy winter months should, if possible, be spent in one of the larger

cities, of which Rome is unquestionably the most interesting. June, July, and August are hardly suitable for a tour. The scenery indeed is then in perfection, and the long days are hailed with satisfaction by the active traveller; but the fierce rays of an Italian sun seldom fail to sap the physical and mental energies. This result is not occasioned so much by the intensity, as by the protracted duration of the heat, the sky being frequently cloudless, and not a drop of rain falling for many weeks in succession. The heat generally moderates about the end of August, when the first showers of autumn begin to refresh the parched atmosphere.

Plan. The plan of a tour in Italy must of course be framed in accordance with the object which the traveller has in view. In Central Italy the principal attraction is *Rome* itself, and of the other towns described in the present volume the next in importance are *Siena* and *Perugia*, both of which afford good summer-quarters owing to their elevated situations. Two other places of great interest are *Orvieto* and *Assisi*, a short visit to which should not be omitted. *Arezzo*, *Cortona*, *Spoletto*, *Terni*, with its imposing waterfalls, and *Chiusi* and *Corneto*, with their Etruscan antiquities, are also interesting points, situated near the railway. *Volterra*, *S. Gimignano*, *Montepulciano*, and *Viterbo*, though less conveniently situated, are also well worthy of a visit. With regard to the towns lying on the coast of the Adriatic, comp. p. 87. Besides these points of attraction there are many others in the less-frequented districts of the interior, which the traveller who desires more than a superficial acquaintance with Italy should not fail to explore; and the farther he diverges from the beaten track, the more he will learn of the characteristics of this delightful country.

III. Language.

The time and labour which the traveller has bestowed on the study of Italian at home will be amply repaid as he proceeds on his journey. It is quite possible for persons entirely ignorant of Italian and French to travel through Italy with tolerable comfort; but such travellers cannot conveniently deviate from the ordinary track, and are moreover invariably made to pay '*alla Inglese*' by hotel-keepers and others, *i. e.* considerably more than the ordinary charges. French is very useful, as the Italians are very partial to that language, and it may suffice for Rome and some of the main routes; but for those who desire the utmost possible freedom, combined with the lowest possible expenditure, a slight acquaintance with the language of the country is indispensable. †

† '*Baedeker's Manual of Conversation in English, French, German, and Italian, with Vocabulary, etc.*' (Sterecotype Edit., Baedeker, Leipsic), which is specially adapted for the use of travellers, with the addition of *Baedeker's Conversation Dictionary* (in the same four languages; Leipsic, 1889; price 3 marks), will soon enable the beginner to make himself understood. — A few words on the *pronunciation* may be acceptable to persons unac-

IV. Passports. Custom House. Luggage.

Passports, though not required in Italy, are occasionally useful. Registered letters, for example, will not be delivered to strangers unless they exhibit a passport to prove their identity. The countenance and help of the British and American consuls can, of course, be extended to those persons only who can prove their nationality. The Italian police authorities are generally civil and obliging.

Foreign Office passports may be obtained in London through E. Stanford, 26 Cockspur Street, Charing Cross, W. J. Adams, 59 Fleet Street, or Lee and Carter, 440 West Strand.

Custom House. The examination of luggage at the Italian custom-houses is usually lenient. Tobacco and cigars are the articles chiefly sought for. At the gates of most of the Italian towns a tax (*dazio consumo*) is levied on comestibles, but travellers' luggage is passed at the barriers (*limite daziario*) on a simple declaration that it contains no such articles.

Luggage. If possible, luggage should never be sent to Italy by goods-train, as it is liable to damage, pilferage, and undue custom-house detention. If the traveller is obliged to forward it in this way, he should employ a trustworthy agent at the frontier and send him the keys. As a rule it is advisable, and often in the end less expensive, never to part from one's luggage, and to superintend the custom-house examination in person. Comp. p. xviii.

V. Public Safety. Begging.

Brigandage. Italy is still sometimes regarded as the land of Fra Diavolo's and Rinaldo Rinaldini's, and the impression is fostered by tales of travellers, and sensational letters to newspapers; but the fact is, that travelling in Northern and Central Italy is hardly attended with greater hazard than in any of the northern European countries, while Southern Italy is unsafe in its more remote recesses only. Even the Roman Campagna can now scarcely be looked on as less safe than lonely districts in the neighbourhood of other large cities. For information as to the safety of the roads the traveller should apply to the *Carabinieri*, or gendarmes (who wear a black uniform, with red facings and white shoulder-straps, and cocked hats), a respectable and trustworthy corps. The traveller should avoid the poorer and less frequented parts of Rome and other towns after night-fall.

quainted with the language. *C* before *e* and *i* is pronounced like the English *ch*; *g* before *e* and *i* like *j*. Before other vowels *c* and *g* are hard. *Ch* and *gh*, which generally precede *e* or *i*, are hard. *Sc* before *e* or *i* is pronounced like *sh*; *gn* and *gl* between vowels like *ny* and *ly*. The vowels *a*, *e*, *i*, *o*, *u* are pronounced *ah*, *ā*, *ee*, *o*, *oo*. — In addressing persons of the educated classes 'Ella' or 'Lei', with the 3rd pers. sing., should always be employed (addressing several at once, 'loro' with the 3rd pers. pl.). 'Voi' is used in addressing waiters, drivers, etc., 'tu' by those only who are proficient in the language. 'Voi' is the usual mode of address among the Neapolitans, but is elsewhere generally regarded as inelegant or discourteous.

Weapons, which for the ordinary traveller are a mere burden, cannot legally be carried without a license, obtainable through the traveller's consul or ambassador. Those of a secret character, such as sword-sticks and stick-guns, are entirely prohibited, and the bearer is liable to imprisonment without the option of a fine.

Begging, which was countenanced and even encouraged under the old system of Italian politics, still continues to be one of those national nuisances to which the traveller must habituate himself. The present government has adopted energetic measures for its suppression, but hitherto with only partial success. The average Italian beggar is a mere speculator, and not a deserving object of charity. The traveller should therefore decline to give anything, with the words, 'non c'è niente', or a gesture of disapproval. If a donation be bestowed, it should consist of one of the smallest possible copper coins. A beggar, who on one occasion was presented with 2c. and thanked the donor with the usual benedictions, was on another presented with 50 c. ; but this act of liberality, instead of being gratefully accepted, only called forth the remark in a half-offended tone: — 'Ma, signore, è molto poco!'

VI. Intercourse with Italians.

In Italy the pernicious custom of demanding considerably more than will ultimately be accepted has long been prevalent; but a knowledge of the custom, which is based on the presumed ignorance of one of the contracting parties, tends greatly to mitigate the evil. Where tariffs and fixed charges exist, they should be carefully consulted. In other cases, where a certain average price is established by custom, the traveller should make a distinct bargain as to the article to be bought or service to be rendered, and never rely on the equity of the other party. Nor should any weight be attached to the representations of waiters, drivers, and guides in matters in which they have an interest, and with whom even the inhabitants of the place often appear to act in concert.

Individuals who appeal to the generosity of the stranger, or to their own honesty, or who, as rarely happens, are offended by the traveller's manifestation of distrust, may well be answered in the words of the proverb, '*patti chiari, amicizia lunga*'. The equanimity of the traveller's own temper will greatly assist him if involved in a dispute or bargain, and he should pay no attention whatever to vehement gesticulations or an offensive demeanour. The slighter his knowledge of the Italian language is, the more careful should he be not to involve himself in a war of words, in which he must necessarily be at a great disadvantage. In Rome and the larger towns of Tuscany the traveller will now meet comparatively few causes for complaint, and even in smaller places he will find a little tact and good-temper all that is necessary to avoid disputes.

In a country where trifling donations are in constant demand, the

traveller should always be provided with an abundant supply of copper coins. Drivers, guides, porters, donkey-attendants, etc., invariably expect, and often demand as their right a gratuity (*buona mano, mancia, da bere, bottiglia, caffè, fumata*), in addition to the hire agreed on, varying according to circumstances from 2-3 sous to a franc or more. The traveller need not scruple to limit his donations to the smallest possible sums, as liberality is often a source of annoyance and embarrassment. Thus if half-a-franc is bestowed where two sous would have sufficed, the fact speedily becomes known, and the donor is sure to be besieged by numerous other applicants whose demands it is impossible to satisfy.

VII. Conveyances.

Railways. The remarks made in the first volume of the Handbook are also applicable to the railways of Central Italy. The rate of travelling is very moderate, and the trains are often behind time. The first-class carriages are tolerably comfortable, the second are inferior to those of the German railways, and resemble the English and French, while the third class is chiefly frequented by the lower orders. Among the expressions with which the railway-traveller will soon become familiar are — '*pronti*' (ready), '*partenza*' (departure), '*si cambia convoglio*' (change carriages), and '*uscita*' (egress), which are shouted by the officials with characteristic vigour. The station-master is called '*capo stazione*'. Smoking compartments are labelled '*pei fumatori*', those for non-smokers '*è vietato di fumare*'. Separate first and second-class compartments are reserved for ladies. Sleeping-carriages (*coupé a letti*) are provided on all the main lines at a small extra charge. Railway time is that of the meridian of Rome, 52 min. ahead of that of Greenwich and 40 min. before Paris.

When about to start from a crowded station, the traveller will find it convenient to have as nearly as possible the exact fare ready before taking tickets ('*fare il biglietto*'). In addition to the fare a tax of 5c. is payable on each ticket, and the express fares are about 10 per cent higher than the ordinary. It is also important to be at the station early. The booking-office at large stations is open 1 hr., at small stations $\frac{1}{4}$ - $\frac{1}{2}$ hr. before the departure of the trains. Holders of tickets are alone entitled to enter the waiting-rooms. At the end of the journey tickets are given up at the *uscita*, except in the case of the very large stations, where they are collected before the passengers alight.

The traveller is recommended to ascertain the weight of his luggage, if possible, before going to the station, in order to guard against imposition (1 kilogramme = about $2\frac{1}{5}$ lbs.). No luggage is allowed free except small articles (which must not exceed $20 \times 10 \times 12$ inches) taken by the passenger into his carriage. Porters who convey luggage to and from the carriages are sufficiently paid with

a few sous, where there is no fixed tariff. Those who intend to make only a short stay at a place, especially when the town or village lies at a distance from the railway, should leave their heavier luggage at the station till their return (*dare in deposito*, or *depositare*, 10 c. per day per cwt. or fraction of a cwt.).

In crossing the frontier travellers should travel with the same train as their luggage and superintend the custom-house examination in person. During the last few years an extraordinary number of robberies of passengers' luggage have been perpetrated in Italy without detection, and articles of great value should not be entrusted to the safe-keeping of any trunk or portmanteau, however strong and secure it may seem.

The enormous weight of the trunks used by some travellers not unfrequently causes serious and even lifelong injury to the hotel and railway porters who have to handle them. Travellers are therefore urged to place their heavy articles in the smaller packages and thus minimize the evil as far as possible.

The best collections of time-tables are the '*Indicatore Ufficiale delle Strade Ferrate*' (published monthly by the *Fratelli Pozzo* at Turin; price 1 fr.) and the *Orario del Movimento Treni e Piroscafi* (published by Arnaboldi at Florence; 1 fr.). It is advisable, however, not to trust implicitly to their accuracy but to consult the local time-tables as well.

THROUGH TICKETS to different parts of Italy are issued in London (at the principal railway-stations; by Messrs. Cook & Son, Ludgate Circus, Messrs. Gaze, 142 Strand, etc.), in Paris, and at many of the principal towns in Germany and Switzerland. They are generally available for 30 days, and each passenger is allowed 56 Engl. lbs. of luggage free.

Those with whom economy is an object may save a good deal by buying return-tickets to the Swiss frontier, travelling third-class through Switzerland, and then taking circular tour tickets in Italy.

CIRCULAR TICKETS (*viaggi circolari*) to the principal towns in Italy, available for 20-60 days, may be purchased in London, in France, and in Germany, as well as in Italy, at a reduction of 45 per cent (but usually without a free allowance of luggage). Farther particulars will be found in the time-tables. These tickets require to be stamped at each fresh starting-point with the name of the next station at which the traveller intends to halt. If, therefore, the traveller leaves the train before the station for which his ticket has been stamped he must at once apply to the *capo stazione* for recognition of the break in the journey ('*accertare il cambiamento di destinazione*'). When the traveller quits the prescribed route, intending to rejoin it at a point farther on, he has also to procure an '*annotazione*' at the station where he alights, enabling him to resume his circular tour after his digression ('*vale per riprendere alla stazione . . . il viaggio interrotto a . . .*'). If this ceremony be neglected the holder of the ticket is required to pay treble fare for the omitted portion of the route for which the ticket is issued.

RETURN TICKETS (*Biglietti d'andata e ritorno*) may often be ad-

vantageously used for short excursions, but they are generally available for one day only. It should also be observed that if the traveller alights at a station short of his destination he forfeits the rest of his ticket for the direction in which he is proceeding. In returning the ticket is not available unless he starts from the end-station for which the ticket was issued.

Steam Tramways. The system of *Tramvia a Vapore*, with which the traveller in Northern Italy has become familiar, has also extended to Central Italy. The rate of speed attained by them is about half that of the ordinary railways.

Steamboats. There are now so many different railway-routes from N. Italy to Rome that few travellers will care to travel by steamer from Genoa or Leghorn to Cività Vecchia, or from Trieste to Ancona, although many will still prefer the sea-voyage to the long railway-journey if bound for Naples direct (see vol. iii. of the Handbook). In fine weather, especially in summer, when seasickness need rarely be apprehended, a voyage on the Mediterranean is very enjoyable, but as the steamers generally ply at night the finest parts of the scenery are often missed. The boatmen charge 1 fr. for embarkation or disembarkation.

Diligences. As several of the most interesting places described in the following pages lie at some distance from the railway (such as Urbino, Gubbio, Viterbo, and S. Gimignano), the traveller must visit them by carriage or by diligence. The *Corriere*, which carries the mails, has seats for 2-3 passengers only, and the fares are high. The *Diligenza*, or ordinary stage-coach, conveys travellers with tolerable speed, and generally at the same fares as similar vehicles in other parts of the continent. They are in the hands of private speculators, and where several run in competition, the more expensive are to be preferred. When ladies are of the party the coupé (fare one-third higher) should if possible be secured. The drivers and ostlers generally expect a few soldi at the end of each stage. — For a party of three or four persons the expense of a carriage with one or two horses hardly exceeds the diligence fares, while the travellers are far more independent. A carriage with one horse may generally be hired for 50-75 c. per kilomètre, and a single seat in a carriage ('un posto') may often be obtained.

Walking Tours. The ordinary Italian rarely walks if he can possibly drive; and how walking can afford pleasure is to him an inexplicable mystery. The remark has frequently been made to the Editor: '*Lei è signore e va a piedi?!*' In the more frequented districts, however, such as the vicinity of Rome, the natives are accustomed to this mania of foreigners, and are no longer surprised to find them exploring the Campagna and the Sabine and Alban Mts. on foot. There seems, moreover, to be a growing taste for walking among the Italians themselves, as a great many stations of the Italian *Club Alpino* have recently been established for the purpose of ren-

dering the Apennines more accessible to travellers. Cool and clear weather should if possible be selected, and the scirocco carefully avoided. The height of summer is of course unsuitable for tours of this kind.

Riding. A horse (*cavallo*) or donkey (*sommāro*), between which the difference of expense is slight, will often be found serviceable, especially in mountainous districts. The attendant (*pedone*) acts as a guide and servant for the time being. Riding is now common among the Alban and Sabine Mts., where animals are provided for the use of ladies also. A previous bargain should be made, *tutto compreso*, a gratuity being added if the traveller is satisfied. The donkey-drivers have an unpleasant habit of inciting their animals to the top of their speed when passing through a town or village, and it is as well to warn them beforehand that their 'mancia' will suffer if they do not go quietly through the streets.

VIII. Hotels.

FIRST CLASS HOTELS, comfortably fitted up, are to be found at Rome, Siena, Perugia, and at most of the principal resorts of travellers in Central Italy. Several of those at Rome are kept by Swiss and German landlords. Room 2½-5 fr., bougie 75c. to 1 fr., attendance 1 fr. (exclusive of the 'facchino' and porter), table d'hôte 4-6 fr., and so on. The charge for dinner does not include wine, which is generally poor and dear. For a prolonged stay an agreement may generally be made with the landlord for pension at a more moderate rate. Visitors are expected to dine at the table d'hôte; otherwise the charge for rooms is apt to be raised. The cuisine is a mixture of French and Italian. The charge for the use of the hotel-omnibus from the station to the hotel is so high (1-1½ fr.), that it is often cheaper to take a cab. It is also easier for those who use a cab to proceed to another hotel, should they dislike the rooms offered to them. Rooms on the ground-floor should be avoided.

THE SECOND CLASS HOTELS are thoroughly Italian in their arrangements, and they are rarely very clean or comfortable. The charges are little more than one-half of the above. There is no table d'hôte, but there is generally a trattoria connected with the house, where refreshments *à la carte* or a dinner *a prezzo fisso* may be procured at any hour. These inns will often be found convenient and economical by the *voyageur en garçon*, and the better houses of this class may even be visited by ladies; but the new-comer should, perhaps, frequent first-class hotels only. As a rule, it is advisable to make enquiries as to charges beforehand. A dinner, for example at 2-3 fr., may be stipulated for, and in bargaining as to the charge for a room the 'servizio e candela' should not be forgotten. If no previous agreement has been made an extortionate bill can seldom be reduced without a great deal of trouble. At the

smaller inns a fee of 1 fr. per day is usually divided between the waiter and the *facehino*, or less for a prolonged stay. Copper coins are never despised by such recipients.

HÔTELS GARNIS and PRIVATE APARTMENTS are recommended for a prolonged residence. A distinct agreement as to rent should be made beforehand. When a whole suite of apartments is hired, a written contract on stamped paper should be drawn up with the aid of some one acquainted with the language and customs of the place (*e.g.* a banker), in order that 'misunderstandings' may be prevented. For single travellers a verbal agreement with regard to attendance, linen, stoves and carpets in winter, a receptacle for coal, and other details will generally suffice. Comp. p. xxvi.

Money and other valuables should either be carried on the person or entrusted to the landlord in exchange for a receipt.

The popular idea of cleanliness in Italy is behind the age, dirt being perhaps neutralised in the opinion of the natives by the brilliancy of their climate. The traveller will rarely suffer from this shortcoming in hotels and lodgings of the best class; but those who quit the beaten track must be prepared for privations. Iron bedsteads should if possible be selected, as they are less likely to harbour the enemies of repose. Insect-powder (*polvere di Persia*, or Keating's) or camphor somewhat repels their advances. The *zanzàre*, or gnats, are a source of great annoyance, and often of suffering, during the autumn months. Windows should always be carefully closed before a light is introduced into the room. Light muslin curtains (*zanzariere*) round the beds, masks for the face, and gloves are employed to ward off the attacks of these pertinacious intruders. The burning of insect powder over a spirit-lamp is also recommended, and pastilles may be purchased at the principal chemists' for the same purpose. A weak dilution of carbolic acid in water is efficacious in allaying the discomfort occasioned by the bites.

A list of the Italian names of the ordinary articles of underclothing (*la biancheria*) will be useful in dealing with the washerwoman: Shirt (linen, cotton, woollen), *la camicia (di tela, di cotone, di lana)*; collar, *il solino, il colletto*; cuff, *il polsino*; drawers, *le mutande*; woollen undershirt, *una flanella* or *giuba di flanella*; petticoat, *la sottana*; stocking, *la calza*; sock, *la calzetta*; handkerchief (silk), *il fazzoletto (di seta)*. To give out to wash, *dare a bucato (di bucato, newly washed)*; washing-list, *la nota*; washerwoman, laundress, *la stiratrice, la lavandaja*; buttons, *i bottoni*.

IX. Restaurants, Cafés, Osterie.

RESTAURANTS (*trattorie*) are chiefly frequented by Italians and gentlemen travelling alone, but those of the better class may be visited by ladies also. They are generally open from 12 to 8, but are frequented chiefly between 5 and 7. Dinner may be obtained *à la carte* (1½-3 fr.), and sometimes *a prezzo fisso (un pranzo da 2, 3, 4, 5 fr.)*. The waiters expect a gratuity of 2-5 soldi. The diner who wishes to confine his expenses within reasonable limits, should refrain from ordering dishes not mentioned in the bill of fare. Besides the old-fashioned *trattorie*, a number of 'restaurants' of a better class have recently been opened in Rome. The cookery is generally French, and the charges and arrangements are similar to those in the other European capitals. The waiter is called *cameriere*

(or *bottega*), but the approved way of attracting his attention is by knocking on the table.

A late hour for the chief repast of the day should be chosen in winter, in order that the daylight may be profitably employed, but an early dinner is preferable in summer when the midday heat precludes exertion.

List of the ordinary dishes at the Italian restaurants: —

Minestra or *Zuppa*, soup.
Consumè, broth or bouillon.
Zuppa alla Santè, soup with green vegetables and bread.
Gnocchi, small puddings.
Riso con piselli, rice-soup with peas.
Risotto (alla Milanese), a kind of rice pudding (rich).
Maccaroni al burro, with butter; *al pomodoro*, with tomatoes.
Lesso or *Bollilo*, boiled meat.
Manzo, boiled beef.
Fritto, fried meat.
Frittura mista, a mixture of fried liver, brains, and artichokes.
Frittata, omelette.
Arrosto, roasted meat.
Arrosto di vitello, or *di mongana*, roast-veal.
Bistecca, beefsteak.
Coscetto, loin.
Testa di vitello, calf's head.
Fegato di vitello, calf's liver.
Braccioletta di vitello, veal-cutlet.
Costoletta alta minuta, veal-cutlet with calves' ears and truffles.
Esgatoppe, veal-cutlet with bread-crumbs.
Patate, potatoes.
Quaglia, quail.
Tordo, field-fare.
Lodola, lark.
Sfoglia, a kind of sole.
Principi alla tavola, or *piattini*, hot relishes.
Funghi, mushrooms (often too rich).

Presciutto, ham.
Salami, sausage.
Potto, or *pollastro*, fowl.
Potaggio di pollo, chicken-fricassee.
Gallinaccio, *Gallotta*, turkey.
Umido, meat with sauce.
Stufatino, ragout.
Erbe, vegetables.
Carciofi, artichokes.
Piselli, peas.
Lenticchie, lentils.
Cavoli fiori, cauliflower.
Fave, beans.
Fagiolini, *Corneti*, French beans.
Sale, salt.
Pepe, pepper.
Mostarda, simple mustard.
Senape, hot mustard.
Ostriche, oysters (good in winter only).
Giardinetto or *frutta*, fruit-desert.
Crostata di frutti, fruit-tart.
Crostata di pasta sfoglia, a kind of pastry.
Fragole, strawberries.
Pera, pear.
Mela or *pomo*, apple.
Persici, peaches.
Uva, bunch of grapes.
Limone, lemon.
Arancio or *portogallo*, orange.
Finocchio, root of fennel.
Pane francese, bread made with yeast (the Italian is made without).
Formaggio, *cacio*, cheese.

WINE (*nero*, red; *bianco*, white; *dolce*, sweet; *asciutto*, dry; *del paese* or *nostrale*, wine of the country) is usually placed on the table in large bottles at the Tuscan restaurants and charged for according to the quantity drunk. At Rome and some other places the visitor is asked if he wishes *un mezzo litro* or *un quinto* ($\frac{1}{5}$ th litre; also called *bicchiera*). Wines of a better quality are sold in ordinary quarts and pints.

Cafés are frequented for breakfast and luncheon, and in the evening by numerous consumers of ices.

Caffè nero, or coffee without milk, is usually drunk (20-25c. per cup). *Caffè latte* is coffee mixed with milk before being served (20-30c.); or *caffè e latte*, i.e. with the milk served separately, may be preferred (30-40c.). *Mischio* or *Aura* is a mixture of coffee and chocolate (20-30c.), considered wholesome and nutritious. *Ciocolata*, or chocolate, 30-50 c. *Pane* (a roll) 5 c.; *pasta* (cake) 10 c.; bread and butter (*pane al burro*) 20 c.

The usual viands for lunch are ham, sausages, cutlets, beefsteaks, and eggs (*uova da bere*, soft; *toste*, hard; *uova al piatto*, fried).

Ices (*sorbetto* or *gelato*) of every possible variety are supplied at the cafés at 50 c. per portion; or a half portion (*mezza*) may be ordered. *Granita*, or half-frozen ice (*limonata*, of lemons; *aranciata* of oranges), is much in vogue in the forenoon. The waiter, who expects a sou or more, according to the amount of the payment, is sometimes inaccurate in changing money if not narrowly watched.

The principal Parisian newspapers are to be found at all the larger cafés, English rarely. — Roman newspapers, see p. 116.

Wine Shops (*osterie*), especially at Rome, are a favourite haunt of the lower classes. The rooms are generally dirty and uninviting, but the wine is often good. Bread and cheese may be obtained at some of the osterie and cooked dishes at a few (*Osteria con cucina*). As a rule, however, those who sup at a wine-shop must bring their own eatables from a *pizzicarolo*, or dealer in comestibles.

Cigars in Italy are a monopoly of Government, and bad. The price of the home-made cigars (*Scelti Romani*, *Virginias*, *Toscani*, *Napoletani*, *Cavours*, *Mingheiti*, etc.) vary from 7½ to 18 c. Good *Havana* Cigars (25-60 c.) and foreign *Cigarettes* may be bought at the 'Regia dei Tabacchi' (p. 114) and other large shops in Rome. Passers-by are at liberty to avail themselves of the light burning in every tobacconist's, without making any purchase.

X. Sight, Theatres, etc.

Churches are open in the morning till 12 or 12.30, and generally again from 4 to 7 p.m., while some of the most important remain open the whole day. Visitors may inspect the works of art even during divine service, provided they move about noiselessly, and keep aloof from the altar where the clergy are officiating. On the occasion of festivals the works of art are often entirely concealed by the temporary decorations. The verger (*sagrestano*, or *nonzolo*) receives a fee of 30-50 c. or upwards, if his services are required.

Museums, picture-galleries, and other collections are usually open from 10 to 3 o'clock. By a law passed in 1875 all the collections which belong to government are open on week-days at a charge of 1 fr., and on Sundays gratis. The attendants are forbidden to accept gratuities.

In Rome the collections of the Vatican and the private galleries are closed on Sundays and on ecclesiastical festivals. The national collections are closed only on the holidays recognized by government, viz. Easter Day, Sept. 20th (anniversary of the entry of the Italian troops in 1870, see p. 341), Nov. 1st (All Saints Day), and Christmas Day. In smaller towns museums and galleries are also often closed on New Year's Day, during the Carnival, on Palm Sunday, Ascension Day, Whitsunday and Whitmonday, Fête de Dieu (Corpus Domini), the Festa dello Statuto (first Sunday in June), and the Assumption of the Virgin (15th Aug.). The day sacred to the local patron saint is often observed as a holiday.

Theatres. Performances in the large theatres begin at 8, 8.30, or 9, and terminate at midnight or later, operas and ballets being exclusively performed. The first act of an opera is usually succeeded by a ballet of three acts or more. The pit (*platēa*) is the usual resort of the men, while the boxes and sometimes the stalls (*poltrone* or *posli disinli*) are frequented by ladies. A box (*palco*) must always be secured in advance. — The theatre is the usual evening-

resort of the Italians, who seldom observe strict silence during the performance of the music.

Valets de Place (*servitori di piazza*) may be hired at 6-7 fr. per day. They are generally respectable and trustworthy, but, as they are seldom good judges of what is really worth seeing, the traveller should specify to them the places he desires to visit. Their services may generally well be dispensed with by those who are not pressed for time. Purchases should never be made, nor contracts with vetturini or other persons drawn up, in presence or with the aid of a commissionnaire, as any such intervention tends considerably to increase the prices. Comp. p. 116.

XI. Post Office. Telegraph.

Letters (whether '*poste restante*', Italian '*ferma in posta*', or to the traveller's hotel) should be addressed very distinctly, and the name of the place should be in Italian. When asking for letters the traveller should present his visiting card instead of pronouncing his name. Postage-stamps (*francobolli*) are sold at the post-offices and at many of the tobacco-shops. — Letters of 15 grammes ($1\frac{1}{2}$ oz., about the weight of three sous) to any of the states included in the postal union (now comprising the whole of Europe) 25 c.; post-card (*cartolina postale*; for foreign countries, *per l'estero*) 10 c., with prepaid answer (*con risposta pagata*) 20 c.; book-packets (*stampe sotto fascia*) per 50 grammes 5 c.; registration-fee (*raccomandazione*) 25 c. — *Post Office Orders*, see p. xiv.

Letters by town-post 5c.; throughout the kingdom of Italy 20c. prepaid, or 30 c. unpaid. Post-card 10 c., with prepaid answer 15 c. Book-packets 2 c. per 40 grammes ($1\frac{1}{3}$ oz.).

Parcels, not exceeding 3 kil. (7lbs.) in weight or 2 ft. in length, may be sent from one part of Italy to another for 50 c.

In Rome the post-office is open daily from 8 a.m. to 8 or 9.30 p.m. (also on Sundays and holidays); in smaller places it is generally closed in the middle of the day for two or three hours.

Telegrams. For telegrams to foreign countries the following rate per word is charged, in addition to an initial payment of 1 fr.: Great Britain 39 c., France 14, Germany 18, Switzerland 6-14, Austria 6-14, Holland 23, Belgium 19, Denmark 23, Russia 49, Sweden 38, Norway 36 c. — To America from $3\frac{3}{4}$ fr. per word upwards, according to the state. — Within the kingdom of Italy, 15 words 1 fr., each additional word 5 c. — Telegrams with special haste (*telegrammi urgenti*, which take precedence of all others) may be sent at thrice the above rates.

XII. Climate. Health.

The climate of Rome is determined by its situation in the Campagna, almost equidistant from the Apennines and the sea (14 M.), and about 100 ft. above the level of the latter. During winter the prevalent wind is the *Tramontana*, a term applied not only to the N. wind but also to the N.N.E. wind (*tireco*); it blows more and

more frequently from October to December, then becomes gradually rarer, and by April or May ceases altogether. This dry and cool (sometimes even cold) wind is generally accompanied by a clear sky, and except when unusually violent (in which case it irritates the mucous membrane) is not found trying even by invalids. The *Scirocco*, a general name for the S.E., S., and S.W. winds, is especially prevalent in October and April. It has an alleviating effect upon colds and coughs, but is apt to take away the appetite and impair the nervous energy.

The most favourable month for a visit to Rome is *October*, during which the average temperature is about 63° Fahr. The rain that then falls is drunk in greedily by the parched earth, and all nature seems to awaken to a second spring. *November*, with a mean temperature of 54° and an average of $12\frac{1}{2}$ days of rain, is also often a pleasant month. In *December* the N. and S. winds contend for mastery, and wet weather alternates with cold, the mean temperature being 47° and the average number of rainy days eleven. *January* (mean temp. $45\frac{1}{2}^{\circ}$, wet days $11\frac{1}{3}$), and *February* (mean temp. $46\frac{1}{2}^{\circ}$, wet days 10), during which the N. wind prevails, are the two coldest months. Travellers arriving at this season from the Riviera, where the mean temperature in these months is from 48° to 54° , should be careful to guard against the sudden change by warmer clothing. *March* (mean temp. $50\frac{1}{2}^{\circ}$, rainy days 10), though often cold, and as usual in the S. the windiest month of the year, seldom passes without some charming spring days. After October *April* and the first half of *May* form the pleasantest time for visiting Rome. The heat then rapidly increases, and from the end of May till October it is almost insufferable (*June* 72° , *July* 76° , *August* 75° , *September* $69\frac{1}{2}^{\circ}$ F.).

Health. *Malaria* or Roman fever is, of course, most prevalent in summer, particularly from the middle of August till the beginning of September, but also occurs in spring and even in the milder and damper months of winter. Large parts of the city, however, enjoy an almost perfect immunity from it. The most conspicuous of these is the central district bounded towards the W. by the *Via del Babuino*, the *Via Sistina*, and the *Via del Quirinale*, extending on the S. to *S. Pietro in Vincoli* and the *Capitol*, and on the E. almost reaching the Tiber. The streets on the *Esquiline*, *Palatine*, and *Caelius* are, on the other hand, all dangerous in summer, and few of the inhabitants of the S.E. district between the *Colosseum* and the *Monte Testaccio* escape an annual visitation of fever. Some of the suburban districts, such as the W. slopes of the *Pincio*, and many of the streets on the *Viminal*, are now comparatively healthy, while on the right bank of the Tiber the neighbourhood of the *Piazza S. Pietro* and the quarter between the *Ponte Sisto* and the *Ponte Rotto* are almost exempt from the scourge.

The visitor should exercise some care in choosing his apartments

and in seeing that they are supplied with all needful comforts. Carpets and stoves are indispensable. A southern aspect is absolutely essential for the delicate, and highly desirable for the robust. An Italian proverb says: '*Dove non va il sole, va il medico*'. Rooms on the upper floor are drier than those on the ground-floor. Windows should be closed at night.

Inhabitants of more northern countries generally become unusually susceptible to cold in Italy, and therefore should not omit to be well supplied with warm clothing for the winter. Even in summer it is advisable not to wear too light clothing. Flannel is strongly recommended. — The Pincio is the safest promenade in Rome, but a prolonged sojourn in the somewhat damp gardens of the Villa Borghese is not advisable. The visitor should be careful not to drive in an open carriage after dark, or to sit in the evening in such malarial places as the Colosseum. In visiting picture-galleries or churches on warm days, it is advisable to drive thither and walk back, as otherwise the visitor enters the chilly building in a heated state and has afterwards no opportunity of regaining the desirable temperature through exercise. Exposure to the summer-sun should be avoided as much as possible. According to a Roman proverb, only dogs and foreigners (Inglesi) walk in the sun, Christians in the shade. Umbrellas or spectacles of coloured glass (grey, concave glasses to protect the whole eye are best) may be used with advantage when a walk in the sun is unavoidable. Blue veils are recommended to ladies. Repose during the hottest hours is advisable, and a siesta of moderate length is often refreshing.

The drinking-water of Rome is very palatable, but strongly impregnated with lime, which makes it unsuitable for those suffering from gout, and sometimes causes constipation. Persons with delicate chests often find a winter in Rome very beneficial. It is less dusty than the Riviera, and not so windy as the Sicilian health-resorts. — *Typhus Fever* does not occur in Rome as an epidemic.

There are several good English and German doctors in Rome, but it is sometimes wise, in the case of maladies arising from local causes, to employ native skill. German and English chemists are preferable to the Italian. Foreigners frequently suffer from diarrhoea in Italy, which is generally occasioned by the unwonted heat. Ice and rice are two of the commonest remedies. The homœopathic tincture of camphor may also be mentioned. In such cases, however, thorough repose is the chief desideratum. A small portable medicine-case, such as those prepared and stocked with tabloid drugs by *Messrs. Burroughs, Wellcome, & Co.*, Holborn Viaduct, London, will often be found useful.

XIII. Chronological Table of Recent Events.

1846. June 16. Election of Pius IX.
 1848. March 18. Insurrection at Milan. — March 22. Charles Albert enters Milan. Republic proclaimed at Venice. — May 15. Insurrection at Naples quelled by Ferdinand II. ('Re Bomba'). — May 29. Radetsky's victory at Curtatone. — May 30. Radetsky defeated at Goito; capitulation of Peschiera. — July 25.

- Radetsky's victory at Custoza. — Aug. 6. Radetsky's victory at Milan. — Aug. 9. Armistice. — Nov. 15. Murder of Count Rossi at Rome. — Nov. 25. Flight of the Pope to Gaeta.
1849. Feb. 5. Republic proclaimed at Rome. — Feb. 17. Republic proclaimed in Tuscany, under Guerazzi. — March 16. Charles Albert terminates the armistice (ten days' campaign). — March 23. Radetsky's victory at Novara. — March 24. Charles Albert abdicates (d. at Oporto, July 26th); accession of Victor Emmanuel II. — March 26. Armistice; Alessandria occupied by the Austrians. — March 31. Haynau captures Brescia. — April 5. Republic at Genoa overthrown by La Marmora. — April 11. Reaction at Florence. — April 30. Garibaldi defeats the French under Oudinot. — May 11. Leghorn stormed by the Austrians. — May 15. Subjugation of Sicily. — May 16. Bologna stormed by the Austrians. — July 4. Rome capitulates. — Aug. 6. Peace concluded between Austria and Sardinia. — Aug. 22. Venice capitulates.
1850. April 4. Pius IX. returns to Rome.
1855. Sardinia takes part in the Crimean War.
1856. Congress at Paris. Cavour raises the Italian question.
1859. May 20. Battle of Montebello. — June 4. Battle of Magenta. June 24. Battle of Solferino. — July 11. Meeting of the emperors at Villafranca. — Nov. 10. Peace of Zurich.
1860. March 18. Annexation of the Emilia (Parma, Modena, Romagna). — March 22. Annexation of Tuscany. — March 24. Cession of Savoy and Nice. — May 11. Garibaldi lands at Marsala. — May 27. Taking of Palermo. — July 20. Battle of Melazzo. — Sept. 7. Garibaldi enters Naples. — Sept. 18. Battle of Castelfidardo. — Sept. 29. Ancona capitulates. — Oct. 1. Battle of the Volturno. — Oct. 21. Plebiscite at Naples. — Dec. 17. Annexation of the principalities, Umbria, and the two Sicilies.
1861. Feb. 13. Gaeta capitulates after a four months' siege. — March 17. Victor Emmanuel proclaimed King of Italy.
1864. Sept. 15. Convention between France and Italy.
1866. June 20. Battle of Custoza. — July 5. Cession of Venetia. July 20. Naval battle of Lissa.
1867. Nov. 3. Battle of Mentana.
1870. Sept. 12. Occupation of the States of the Church by Italian troops. — Sept. 20. Occupation of Rome.
1878. Jan. 9. Death of Victor Emmanuel II.; accession of Humbert I. — Feb. 7. Death of Pius IX. — Feb. 20. Election of Leo XIII.

Ancient Art.

A Historical Sketch,

from the German of

Prof. Reinhard Kekulé.

*"As the streams lose themselves in
the mightier Ocean, so the history of
the peoples once distributed along the
Mediterranean shores is absorbed in that
of the mighty Mistress of the World".*

NIEBUHR.

The traveller who would not wander through the galleries of Rome in mere vacant wonderment may bear in mind these words of Niebuhr. As a preface to the following pages, they will not only help the intelligent observer to a worthy appreciation of the masterpieces presented to him, but enable him to invest them with appropriate historical associations.

Amongst the crowd of statues which fill the galleries and chambers of the Vatican and Capitol of Rome are to be seen the noblest examples of Antique Sculpture. These do not, however, stand in the same relation to Imperial Rome as, for example, the frescoes of Fra Angelico in the Cloisters of St. Mark, or those of Andrea del Sarto in the Church of the Annunziata to Florence, or as the masterpieces of Raphael and Michael Angelo to mediæval and pontifical Rome. These latter originated, so to speak, with her, were her peculiar attributes, the fitting emblems of her ecclesiastical supremacy. The genius which created them, she inspired, fostered, and rewarded. On the other hand, Rome, the mistress of the World, the Rome of ancient history, though attracting to herself the accumulated treasures of entire epochs of Greek art, though through her interposition names, which otherwise must have remained mere phantom sounds, survive to receive individually the homage due to their transcendent genius, had nevertheless as little influence on the marvellous development of Greek art, as London had upon the Italian Renaissance, on Giotto and Masaccio, on Raphael and Michael Angelo. In fact, those particular works, which, while they fill the mind with a wonder akin to awe, minister to our noblest gratification, and in the presence of whose marvellous perfection all subsequent efforts are dwarfed into insignificance, occupied in Rome ages ago, and still occupy, a place corresponding to that which

the masterpieces of the Italian and other schools of painting fill in the galleries of London, Paris, and Dresden. Winckelmann was the first to trace in bold and comprehensive outline the history of Art amongst the Ancients, from its infancy and earlier growth to its maturity and gradual decline. Following in the wake of Winckelmann, unceasing research, patiently and persistently pursued, has served to confirm and extend his survey, and to supply, in addition, a host of particulars pregnant with interest. Those indeed, who have conducted this laborious quest, stimulated and directed by the fortunate recovery of monuments and various relics of antiquity, have been the means of determining the history of Antique Art, so far at least as Sculpture and Architecture are concerned; and this not only in its more salient features, but with an elaboration of detail, so careful and so well authenticated, that the authorship of numerous works is clearly established, and the interest and value of their discoveries in so far unspeakably enhanced. Much indeed remains to be done, and the path of the explorer is beset with doubt and difficulty; but the future promises farther encouragement, if not complete solution.

In Art, the **Greeks** were content to learn from nations whose civilisation preceded theirs. Long before the first image was graven by Grecian hands, the *Egyptians*, as far as history acquaints us, had been the first to overcome those difficulties in the choice of a suitable form of expression inseparable from every fresh manifestation of Art. They had established a well-defined system, a traditional style, which was exemplified as well in their Sculpture as in their Architecture. On the other hand the richly-elaborated Art of the *Babylonians* and *Assyrians*, with its sumptuous wealth of decoration, must also of necessity have had its influence on the Greeks of Asia Minor. Grecian Art had, to begin with, not only adopted the method, implements, and workmanship of their predecessors; it had possessed itself of their forms and not unfrequently of the motives of their imagery. Greece did not, however, accept this heritage of art in the spirit of slavish imitation. Architectural models were not adopted in their entirety. Each part separately, each ornament in itself, became the centre of a new conception, and this conception once embodied became a distinct type, the expression of a taste purely Greek. In like manner they treated the conventional rendering of the human form transmitted to them. This, by constant reference to the living model, they continued to manipulate and modify until they attained to that profound and comprehensive grasp of nature, which to this day remains the subject of wonder and delight to our greatest artists. The way thus traversed was long and wearisome. It carries us back through an incalculable succession of ages into the impenetrable past. The oldest *Ionic* and *Doric* temples, although well-nigh of prehistoric antiquity, exhibit in all essential particulars a clearly-defined architectural system;

and, let it be borne in mind, the architecture of the Greeks did not start into being as Athena from the head of Jupiter, fully armed and equipped. Careful observation will detect in the Orders associated in name with the two principal Hellenic races evidences of a very gradual development. Subsequently, to these two orders was added a third, known as the *Corinthian*. It was inevitable that in the practice of Sculpture as well as Architecture divergences arose which may be characterised as provincialisms; and it is equally intelligible that as Art in Greece assumed more and more majestic proportions, these provincialisms should have become less and less observable.

They were finally obliterated by the glories of what may be distinguished, in reference to art, as the AGE OF PERICLES; glories associated with the talismanic names of *Phidias*, *Myron*, and *Polycletus* in Sculpture, and of *Ictinus* and *Mnesicles* in Architecture. The golden age of the Italian Renaissance, when Raphael filled the world with rapturous wonder, can alone be compared to a time which witnessed the surpassing achievements of art in Greece. Of the painters of this period, of *Polygnotus* for example, who flourished somewhat earlier, little can be ascertained. Their works have perished; and all that we can learn of them is at best too hypothetical to be worthy of record.

The name of POLYCLETUS belongs to the Peloponnesus. The connoisseur of his day claimed for him the merit of having presented the human form complete in its minutest details, correct in proportion, perfect in symmetry. One of his works in particular, the figure of a powerful youth armed with a spear (*Doryphorus*), was upheld as an example of the master's peculiar excellence, and hence was surnamed the *Canon*. As a counterpart to the *Doryphorus*, and in like manner regarded as a type or model, is the figure of a youth of distinguished beauty, who with both hands folds a band round his head (*Diadumenus*). Of one of his *Amazons* it was said, that it surpassed even the Amazon of Phidias in beauty. Finally, especial glory was claimed for his statue of *Hera* placed in a temple dedicated to this goddess at Delphi. — MYRON'S chief delight was to portray the human form in action, but his success was, to say the least of it, partial. Thus he represents his *Discobolus* actually doubled up in the act of throwing the discus. In a group on the Acropolis at Athens the same artist has chosen for his subject the incident of Marsyas in the act of seizing the pipes which the Goddess Athena has rejected, and on which he plays while dancing with delight. He recoils in terror and bewilderment as the Goddess, suddenly appearing, dashes the pipes from his hand. Finally the *Cow* of Myron was especially popular. It was boasted of her that so lifelike was she that she deceived both man and beast: nay imposed even on a living calf. But mightiest amidst this sculptor band was PHIDIAS. His colossal *Statue of Zeus* excited

wonder even in Olympia. It was accounted a reproach not to have seen it. His principal works were, however, devoted to the adornment of his native city Athens. The colossal figure of Athens' tutelary deity, the virgin goddess *Athena* in the Parthenon, was from the hand of Phidias. With him, we may assume, originated those plastic decorations of her temple the remains of which are preserved in Athens and in London; and in all that his friend Pericles undertook with a view to enhance the beauty and glory of their native city, the creative genius, if not always the hand of Phidias was active. So completely indeed had he subjected to his irresistible will the resources of his art, so far had he distanced all competitors, whether in the present or past, that the force of his genius, overstepping the narrow confines of Attica, imposed its sway upon successive generations of artists. *Alcamenes* and his favourite *Agoracritus* were his most distinguished and successful pupils. The *Statue of a Victor* in the pentathlon by Alcamenes was, in a similar way to the *Doryphorus* of Polycleetus, distinguished by the title of 'Enkrinomenus', or 'the classical'.

In the history of Art, as in the history of Poetry, there usually succeeds to what Winckelmann terms the 'lofty style', which delights rather in depicting the sublime and majestic, a reaction in favour of a vein of sentiment more tender, more expressive of beauty in her gentler and more graceful aspects; while at the same time freer and more forcible utterance is given to joy and anguish, and generally to the emotions and passions. Tenderness and grace were the divine attributes of PRAXITELES and the family of whom he was chief. At this time when Athens, weary of conflict with the Hellenic confederacy, longed for peace, one of the family, *Cephisodotus* (the Elder), produced his *Irene and Plutus*, the Goddess of Peace bearing in her arms the infantine god of riches, of which there is a copy in the Glyptothek in Munich. Praxiteles himself belongs to a succeeding generation. Above all his *Eros* in Thespia, his *Satyr* and the *Aphrodite* in Cnidus, were the wonder and delight of antiquity. His sons *Cephisodotus* (the Younger) and *Timarchides* had also considerable repute. SCOPAS is usually regarded as the representative of the more pathetic and impassioned expression in Art; and amongst his numerous works a *Group of Sea Deities and fantastical Sea Monsters* is accounted particularly impressive. — The *Niobe and her Children*, afterwards carried to Rome, was attributed variously to Praxiteles and Scopas. *Leochares*, another contemporary of Scopas, is believed to be the author of a group representing *Ganymede* borne to Olympus on the wings of an eagle.

It is said that ALEXANDER THE GREAT would entrust the execution of his portrait to none other than LYSIPPUS of Sicyon in the Peloponnesus: and with the name of Lysippus is associated a revolution in taste which culminated in this period. The painter and sculptor *Euphranor*, a contemporary of Lysippus, but older than he, whose

especial delight it was to celebrate heroic exploit, had already with purpose and deliberation modified the recognised rules of proportion. Lysippus moulded the head smaller, and the figure relatively taller than had hitherto been the practice. In posing the figures too, either standing or in movement, as well as in the entire conception and rendering of Nature, he appears to have developed anew and with dazzling effect what hitherto had not been more than suggested. His forms, though of unmistakably Greek character, are more in conformity with modern taste than those of earlier artists. Among the best known works of Lysippus is the *Apoxyomenus*, the figure of a youth fresh from a struggle in the Palæstra, in the act of using the scraping iron. Gods and heroes, scenes of war and the chase, furnished him with subjects for a host of other works. Among his sons and pupils *Laippus*, *Boëdas*, and *Euthyrates*, the last is most highly esteemed. Not only those of their generation but posterity agreed that Lysippus and the painter *Apelles* had reached the highest attainable point in the truthful rendering of nature, as well as in the more technical mastery of their art. The influence of Lysippus endured throughout and beyond the end of the following century. His method sufficed for the schools which succeeded him because the new spirit in which they worked had already triumphed in Lysippus.

The conquests of Alexander and all that followed in their train — the glories and treasures of the East unfolded, mighty monarchies founded, stately cities built, and growing into centres of wealth and luxury, new forms of worship consequent upon a more intelligent study of nature — afforded conditions both material and other, which stimulated afresh the arts of Architecture and Sculpture. Henceforward Greek art vied, in the splendour of its colossal proportions, with that of the East. The deeds of victorious monarchs were her favourite theme: she was indefatigable in the contrivance of new forms of luxury and fresh splendour for city, mansion, and palace. Meanwhile, however, the Past was losing its hold upon her. The traditions of the Periclean age, which told how art was content to serve the household Gods with simple piety and to adorn domestic life, were but feebly remembered. Places once instinct with art life were lost in the new and overwhelming growth of cities, now the emporiums of the world's commerce: *Alexandria* in Egypt, *Antioch* on the Orontes in Syria, *Pergamum*, and *Rhodes*. — As an example of what Greek art was doing about this time in EGYPT, we may mention the reclining figure of the *River-god of the Nile*. Around this colossal personage, so benignant in aspect, play, with true infantine grace, sixteen cherub-like children. These are symbols of the 16 cubits, the measure of that periodical rise in the Nile's waters which annually submerges the land and endows Egypt with perennial fruitfulness. — A pupil of Lysippus, one *Eutychides*, represented the city of ANTIOCH in a group of considerable grace. The

tutelary deity (*Tyche*) of the city is seated on a rock. In her right hand she holds ears of corn, and on her head she wears a mural crown; while at her feet appears, in the shape of a youth rising out of the earth, the river-god Orontes (the river actually flows underground for some distance).

The sculptors of PERGAMUM celebrated the victories of their kings over the Celts. The statue of the *Dying Gaul* (the so called 'dying gladiator') in the museum of the Capitol, and the *Group of Gauls* in the Villa Ludovisi are most impressive examples of the manner in which they were inspired by the theme. The northern barbarian, differing widely as he did in configuration, costume, and habit from the Greek, was a study of engrossing interest to the sculptor, and was reproduced with physiological accuracy. At the same time, that the fame of the victor might be magnified to the utmost, the sculptor sought to embody all that was admirable in the character of the vanquished: his ill-trained but chivalrous valour, his inflexible determination to die rather than suffer disgrace. So late as the 4th century A.D. there was still to be seen on the Acropolis a votive offering of King Attalus in the shape of a group with numerous figures representing the struggles of the gods with the giants, of the Athenians with the Amazons, of the Athenians with the Persians, and Attalus himself with the Celts. Quite recently, figures have been recognised as belonging to these groups in the collections of Venice, Rome, and Naples. — Of the RHODIAN SCHOOL we have examples in the so-called *Farnese Bull* in the museum of Naples, and in the *Laocoon*. The date of the *Laocoon* has not been established. Since the days of Winckelmann, who assigned it to the time of Alexander, and of Lessing, who maintained that it belonged rather to that of Titus, there has been a constantly recurring controversy on the subject. It is, however, highly improbable that the Rhodian School retained, as late as the reign of Titus, the vitality necessary for the production of so considerable a work.

From the preceding pages it will be gathered how many crises and how varied a development had been experienced by Greek art down to the time when **Rome** herself came to be included within the charmed circle of Greek culture. Transplanted to strange lands, and subjected to new influences and associations, Greek art exchanged its distinctive Greek character for one universal and cosmopolitan. Rome had not been, it may be remarked, without an art she could call her own. The old *City-Walls* raised in the time of the Kings, the *Carcer Mamertinus*, and the *Cloaca Maxima* prove that the Romans could in times comparatively remote carry out architectural works on a grand scale, although principally for utilitarian purposes. The rudiments of Sculpture they probably acquired from Etruscan artists, whose earliest attempts would be the execution of images of the gods in wood and clay. In *Etruria*,

where Greek influence had long been active, considerable proficiency as well as activity prevailed in the pursuit of art. although but scanty traces of the purity and elevation of Greek taste are discernible. In Rome, however, the Greeks of Southern Italy grafted their art on that of the Etruscans. A bronze toilet casket (the so called *Ficoronian Cista*) found in Palestrina, which was executed in the workshop of Novius Plautius in the 3rd century B.C., exhibits in its tracery a purity of design unmistakably Greek, although differing little in shape and plastic accessories from the very ordinary and often rude vessels of the period. The Romans highly esteemed faithful *Portraits*. Likenesses of ancestors were preserved in wax masks, and displayed on occasions of ceremony. The plastic art of the Etruscans gives evidence of a certain grasp of portraiture, which, though not profound, was still effective. As Roman rule extended itself over Southern Italy and Sicily, and later to Greece and the Asiatic continent, a constantly increasing number of works by Greek artists found their way to Rome, for the most part, probably, as spoil of war. Presently, too, the wealthy patrician, following the bent of his individual taste or the prevailing fashion, gave commissions for works to be executed in Greece, or in Rome itself, to which necessity had brought many artists. Rome thus became the recognised centre of a taste and fashion which she could call her own. Both stood in close relation, not only in point of time, but in a community of idea and aspiration, to the art of a period immediately following the reign of Alexander. There is no doubt, however, that a vast number of works are accepted as specifically Roman only because all traces of the Greek models have been lost. From these, it may be taken for granted, the artists of Imperial Rome derived the designs or at least the suggestion of works of utility, as well as of buildings devoted to mere display, such as temples, palaces, triumphal arches, and tombs.

The student familiar with the three orders of ARCHITECTURE, viz. the Doric, Ionic, and Corinthian, as they are to be seen in Athens, and comparing these examples with their reproductions in Rome, will have little difficulty in detecting a divergence which cannot be explained by differences either in forms of worship or in the general scope of the design (a conspicuous basement with flights of steps in front). The delicate modelling of the best period of Greek art was in Roman hands either simplified, and so denuded of its true artistic significance — looking in short like the work of the handicraftsman — or so overloaded as to become hopelessly confused. Even in their most admirable buildings a mere profusion of superficial decoration is substituted for that perfect harmony pervading and animating the Greek structure, whether as a whole or in its minutest detail, which we find in the Parthenon for example. The *Doric* and *Ionic* orders found comparatively little favour with the Romans, and where they appear, it is rather in the form of mural

columns than entire shafts. The exquisite taper of the shaft was thus sacrificed, the capitals were not happily disposed, and the Doric column instead of springing, as with the Greeks, direct from the flooring received a separate base. The favourite style was the more ornate *Corinthian*; and the Romans thought yet to add to the wealth of ornament by superimposing upon the capital already veiled with the graceful form of the acanthus leaf, the volute and abacus of the Ionic capital. The entablature of the earlier orders is easily distinguished. In the Doric the architrave rests on the column and is unarticulated, while the frieze above the architrave receives the triglyphs at short, regular intervals. The Ionic architrave on the other hand is divided into three horizontal courses, the frieze being without triglyphs. The Corinthian entablature resembles the Ionic, but the cornice is more richly articulated, corbels are substituted for the indentations, and the whole is richly wreathed with acanthus leaves and other ornamentation.

The noblest, happily also the best-preserved building of old Rome is unquestionably the *Pantheon* of Agrippa, built in the time of Augustus. In spite of much disfigurement received in later times, this vast edifice, comprised in its interior within the precincts of one majestic circle, and obtaining the light of heaven from the centre of its wondrous dome, continues to impress the beholder with un-failing, overwhelming effect. Therefore it is that the Pantheon, having survived the period of art's extinction and revival, better represents the solidity, the daring, and the splendour of Roman architecture than the stupendous remains of palace, bath, and circus.

An important innovation which PLASTIC ART experiences in the latter days of the Roman republic remains to be mentioned. The introduction of *Eclecticism* may be attributed to PASITELES, a native of Southern Italy. It would appear that he had striven, by way of protest against the unrest and violence apparent in the works of his predecessors of the Rhodian School, to restore to art something of her primitive simplicity, and to combine the excellences of the older schools while he avoided their errors. His aim was to revert to the stern simplicity and thoroughness of the earliest sculptors. At the same time he studied nature independently and carefully; while he was not neglectful of the minor graces of his art. *Stephanus* was his pupil, whose pupil again was *Menelaus*, from whose chisel we have a group now in the Villa Ludovisi, commonly known as *Electra and Orestes*. Though the real intention of the author will probably never be known, this work serves to teach us how earnest was the endeavour, and how happy the result of art-study in the school of Pasiteles. It is not, however, given to eclectic schools to exercise a powerful or enduring influence. Accordingly we find a comparatively small number of works belonging to the school of Pasiteles.

That school of art, too, which was especially encouraged by the

Emperor HADRIAN, adopting as it did not only Greek but also Egyptian models, was eclectic in the most extended sense of the word. Amongst its better known works is the figure of Hadrian's favourite *Antinous*, in which with undoubted beauty of form is combined a somewhat lugubrious solemnity together with a smooth glossy and superficial elegance little to the taste of the modern connoisseur. Far more attractive are the bas-reliefs on various public monuments — such as the *Arch of Titus* and *Trajan's Column* — celebrating the triumphs of Roman arms. With Greek artists a characteristic mode of representing in relief the triumphs, actual or mythical, of their heroes was to express battle by means of isolated groups of single combatants. And not only are the more stirring incidents of the battle thus signalled. Appeal is made to the gentler emotions: a dying warrior is carried off the field; or the victor spares the life of a prostrate adversary. For plastic purposes this was found to be the most effective mode of representation, serving as it does to awaken the interest and rivet the attention of beholders. The Assyrians had, however, already executed reliefs in which the effect of pitched battle was rendered with more literal accuracy; and that the Greeks, too, could on occasion meet the requirements of this more arbitrary taste, we learn from the friezes of the so-called Nereid monument discovered in Lycia, where the contending hosts close with each other in elaborate order of battle. The painter, favoured by conditions more submissive to his will, had already grouped the combatants in larger and denser masses. How admirably they contrived along with the crowd and confusion of battle, to give effect to traits of individual heroism and to give to single and central figures their appropriate expression, is exemplified in the celebrated mosaic to be seen in Naples of the *Battle of Alexander*, which, there is no doubt, was copied from a painting of the period. It may be premised therefore that this condensed and elaborated treatment in relief — obviously akin to painting — in which the marches, battles, and triumphs, the operations of Roman armies and their imperial chiefs, were set forth with the utmost attainable accuracy, with all detail of equipment and armament of camp and battle-field, was not the newly gathered fruit of Roman inventiveness, but must rather be ascribed to the age of Alexander and his successors. And the same may be assumed of the architectural form of these monuments. In *Portraits*, too, whether of full length or only busts, of emperors and empresses, warriors and statesmen, as of persons of less exalted position, there were not wanting impressive examples in Greek art; and here again Roman taste coincides with that of the Diadochan age. It may be conceded, however, that owing to the interest long taken in portraiture by the Romans and to the attention which this branch of art had so long received in Rome and Etruria, it had acquired a more distinctly Roman and Italian character, and so had a perceptible influence

on Greek artists resident in Rome. Thus is it that portraits of the Emperors exhibit a degree of power in execution and expression scarcely to be looked for at so late a period. Not unfrequently the Emperors were represented in the costume proper to religious ceremonies; or in fashion like to the gods themselves, and invested with their attributes. Most commonly, however, they appear in the costume and character of a general in the act of haranguing his cohorts. We have striking examples of these imperial portraits in the equestrian statue in bronze of *Marcus Aurelius* on the Capitol, and in the marble statue of *Augustus* in the Vatican. This latter gives unmistakable evidence of having been painted. From the reliefs on the richly ornamented armour which set forth with due regard to historical accuracy the more conspicuous and familiar incidents of a reign especially favoured by the gods, we are justified in the conclusion that this figure was executed about the year 17 B.C. In his treatment of the female figure, too, whether seated or standing, the sculptor knew how to impart a distinguished and imposing view by a sumptuous arrangement of the drapery. There is a peculiar gratification in finding, after a careful study of these portraits — many of them of personages famous in history — an exterior so closely corresponding to the picture of the historian. Many of the heads, indeed, which thus impress the beholder have not been identified. In portraiture, the Greek sculptor adopted the *Hermean* form, while the work of the Roman is recognised almost infallibly in the *bust* form. The latter largely preponderate, although amongst the collective works of sculpture preserved, the Greek element is considerably in excess of the Roman. An attentive observer will not fail to mark this distinction, and learn also to detect the handiwork of the modern restorer which too often disfigures these antique marbles.

The same tendency which led the wealthy citizens of Rome to adopt the literature and culture of Greece was observable in the taste displayed in the works of art they chose for the decoration of their palaces and villas, whether executed in Rome itself or in Greece. In other respects they appear to have been attracted by the same objects of interest as English collectors of the present day. Antique art taken as a whole would probably fail to interest the average man of rank, unless it were associated with some historical incident, some names of renown, or some startling anecdote. But of such works as the figures of the *Three Graces* in bas-relief (though rigid in execution) which the ciceroni of the Acropolis shew as the work of Socrates, and the group of *Harmodius and Aristogiton*, the Tyrant slayers, in the market place of Athens, of archaic antiquity, which had been carried off by Xerxes and restored to its wonted place by Alexander: — of works such as these copies at least would be in request. The powerful development displayed in the figures of Polykletus, and the action expressed in those of Myron, appear to have possessed greater attractions for the Romans than the works of Phi-

dias. Numbers of statues belonging to the Periclean age have come to light in Rome, replicas for the most part of *Victors in the Games* and of *Amazons*. *Figures of the Gods*, with few exceptions, belong to a later period. The most numerous, and also very charming, were the graceful forms of more recent Attic art, represented by Praxiteles and his compeers; also the elegant and animated creations of the Lysippian and post-Lysippian schools. It is hardly conceivable that in the museums of Rome, filled as they are with works of sculpture collected on the spot, no original works are to be found. Assuredly there has been a time when they have not been wanting in Rome: and it seems improbable that one and all should have been lost in the devastation which has more than once made wreck of the Eternal City. Certain it is, however, that the greater part of what we now see are either replicas or copies. This fact is determined by the material. The great statues of Phidias and Praxiteles set apart for the temples were of gold and ivory, while Polycleetus and Lysippus worked in bronze. In Attica, too, this costly material was preferred by the earlier sculptors. It was only by degrees that marble came into use for groups as well as single figures. The 'Discus thrower' of Myron, as well as the groups of Marsyas and Athena were originally in bronze. In the Palazzo Massimi alle Colonne there is to be seen a striking figure readily recognised as that of Myron's 'Discus thrower', but it is in marble. In like manner the Marsyas in the Lateran is of marble, and so also is the Apoxyomenus in the Vatican museum. Just as we moderns delight in the copy or engraving of some celebrated picture, the amateur of old gave his commission for the copy of some favourite statue, to be executed in bronze, or, more frequently, in marble. At any rate comparatively few works in bronze, of importance in point of size, are preserved. It was not enough to have simply repeated the celebrities of sculpture. The artists of the so-called New Attic School, which flourished in the last century B. C., we find reproducing the works of their predecessors very effectively with such departures from the original as are to be seen in a more artificial and highly wrought arrangement of drapery, a more decorative rendering of the detail generally, and an attempt to impart increased animation to the figure as a whole. Such piracies, when tolerably successful, became in their turn models for numerous imitations.

The results of this process are exactly what the connoisseur will be prepared to find, and such as present themselves in the collections of antique art in Rome. He must not expect to find himself in the presence of the simplicity and directness as well as grandeur of aim characteristic of Greek art in her loftiest moods: but rather of her attenuation in the shape of imitations and adaptations, the growth of the Imperial age. Antique art, however, exhibits throughout its career an astonishing vitality and continuity. The spirit of the Greek is mighty even in expiring: and nowhere can the course

of her marvellous development be studied with the same completeness as in Rome.

Monumental works, inconspicuous and unfamiliar as they so often are, appeal less powerfully to the imagination than statuary, where dazzling beauty enthral the senses. These monuments, however, will have a charm of their own for the discriminating observer. In the Egyptian department of the Vatican he can contemplate the relics of a primæval antiquity, while in the Gregorian Museum he is reminded of the mysterious Etruscans. It will be interesting to compare the attitude and proportions of EGYPTIAN with Græco-Roman figures, and to discover in the *Sphinxes* of the Villa Albani, in the *Lions* by the approach to the Capitol, as well as in the numerous obelisks, to be seen in the piazzas of Rome, evidence of the mastery acquired by the Egyptian in Art. And their works were in the Roman's eye fitting objects where with to celebrate his triumphs, and adorn the capital of an empire including within its far reaching bounds people of almost every race and climate.

In the Gregorian Museum the portrait busts in terracotta by the ETRUSCANS exhibit a mode of expressing individuality peculiar to themselves; the bronze vessels display that skill in the working of metals for which they had long been famous; while the large copies of mural paintings which adorned the tombs bring to light the method of painting as practised by the Etruscan as well as, in the choice of subject, their preference for scenes of sensualism and bloodshed.

Here, too, is to be seen a collection of PAINTED GREEK VASES exceedingly rich and beautiful, discovered, it is true, in Etruria, but, as is evident from the subjects represented, from the drawing, but chiefly from the inscriptions, imported from Greece — the greater part indeed from Athens. It is not difficult to distinguish those specimens, which, though borrowed from the Greeks, were of Etruscan manufacture. They are inferior in taste and execution, as well as in design and modelling, and are not to be mistaken for the work of artists. But the Greek vases themselves vary in character; those for instance having the black figures on a red ground being of earlier date than those showing the reverse arrangement of these colours. Nevertheless the painters of these vases, mere handicraftsmen as we must suppose them to have been, could render mythological subjects, and scenes of everyday life, with a vivacity and poetry of conception; they knew so well how to draw, and, with means and resources necessarily very limited, were so far masters of expression, that — despised though they may be by the superficial and ignorant — they bear not only remarkable testimony to the quality of workmanship then prevailing in Attica, but afford a glimpse at the art of their day in Athens as seen through the eyes of these unpretending artificers.

Finally there remain to be noticed the SARCOPHAGI, which, variously ornamented with reliefs, are to be seen in museum, in villa, and in palace court. The only specimen preserved to us from the old

Roman time is the Sarcophagus of L. Cornelius Scipio Barbatus in the Museum of the Vatican. It resembles an altar both in shape and style of ornamentation, and is almost the counterpart of one still standing in Pompeii. It is only consistent with the then prevailing religious rites that sepulchral monuments should have been thus architectural in character. In Greece itself this was conspicuously the case: all sarcophagi which have been discovered within the confines of Greece proper showing a distinctly architectural treatment. The Roman sarcophagi combine much that is essentially Greek with adaptations from the funeral urns of Etruria. They give signs, however, of an independent development, and although including a diversity of shapes and decoration, have for the most part their bas-reliefs arranged on the front and sides (and, where extraordinary richness of effect was desiderated, on the back also) as a frieze or band. One naturally endeavours to trace in the decoration bestowed on these repositories of the dead, some indication of their purpose. In many instances, however, it is evident, that appropriateness of design, if originally acknowledged as indispensable, was presently lost in a promiscuously lavish decoration. Certainly there is no obscurity in such allusions to the goal of life as we discover in Cupids rowing to the lighthouse tower, or when we see them careering round the goal in the circus. In such symbolical figures as those of the seasons we are taught to reflect on the inevitable course of creation, existence, and decay succeeding to maturity. As Hylas is borne away by the Nymphs, and Ganymede by the eagle, so we may fancy the soul begrudged from its earthly existence. Hippolytus may serve to recal the virtues of such as came to an untimely end, Niobe, the grief of the survivors; sleeping Cupids may symbolise sleep favoured by the Gods, while Ariadne discovered by Dionysus, Endymion visited by Selene present death itself as but sleep in unfamiliar guise. On the other hand scenes of Bacchanalian revelry can hardly be accepted as allusions to the future state; and even in a less degree are Nereids and Medeas, and more of the like, in bas-relief, capable of such interpretation: and rarely, too, does any reference of a distinctly personal character go beyond a mere vague allusion to life and death. It is tolerably certain that these sarcophagi were made in large numbers, in advance of immediate requirements. A somewhat extraordinary expedient for introducing a reference to particular individuals, was that of bestowing the lineaments of the departed upon such heroes of mythology as were made to figure in these reliefs. Thus it is we find portraits of the deceased in such mythical personages as Admetus and Alcestis, in Hippolytus, and, what is more remarkable, in Phædra herself. In a considerable number of cases these reliefs are almost identical, and are evidently made after one model, with such modifications as might be effected by the introduction or omission of single figures or groups, showing nevertheless more or less of artistic intelligence and resource. They form a

group displaying the established forms and traditional models, which in respect of means of expression and motive are the worthy inheritance of Greek art at its best. Yet these sarcophagi, regarded even as Roman works, are by no means of early origin. It must not, however, be forgotten in estimating the quality of work bestowed upon the sarcophagus, that it was not intended to be closely inspected by the light of day, but would be consigned to the twilight of the tomb, where a stray gleam of light might but for a moment reveal its detail. Hence, in the execution of these reliefs the object was to give prominence to leading features, without an overscrupulous nicety of finish, and this end has been attained with a success worthy of all admiration. It has been ascertained beyond doubt, that the introduction of the sarcophagus as described above was coeval with a mode of burial which became the fashion in Imperial times; otherwise the artistic merits of these monuments might well have misled us in computing their age. The great majority of Roman sarcophagi belong to the 2nd and 3rd centuries after Christ, and to an even later period.

The *Early Christian Sarcophagi* simply repeat and perpetuate preceding pagan models. It is a peculiar coincidence that these inconspicuous memorials should have contributed to the revival of art in the middle ages. Niccolò Pisano found a fertile source of inspiration in the Roman sarcophagi of the Campo Santo in Pisa; nor did Peruzzi and Raphael disdain to use them as models.

With this passing glance at the homage thus done by Raphael and his compeers to the art of antiquity, these pages may fitly conclude. The endeavour has not been to fetter the judgment of the reader, but rather so to direct his observation and stimulate his interest as to give him that self-reliance which alone will arouse in him an intelligent interest, and afford him a genuine pleasure in what he sees. To praise the creations of great artists in empty or mere conventional phrase would simply offend. They alone will experience the full measure of delight to be derived from the contemplation of these treasures, who rely upon their own judgment and cultivate to the utmost the delicacy of their perceptions.

Roman Art,

MEDIÆVAL AND MODERN,

by

Prof. Anton Springer.

Rome as Mistress of the world became the centre of contemporaneous culture. Art had found with her a new term: and Greece as fitting tribute to the conqueror laid at her feet the accumulated wealth of ages — the treasures of her art, which long had embodied the loftiest conception of the beautiful.

Her supremacy secured, Rome became the chief resort of artists, and their liberal patron. She dictated the tone, alike in taste and fashion, and determined the destinies of art. Down to mediæval times Rome continued to receive the proud title of 'Caput mundi'. Presently, however, she laid claim to supremacy in another realm than that of art; and this latter, as the ancient traditions were gradually outlived, finally fell into neglect. In more recent, as in former times Rome has failed to create for herself, as the outcome of her individuality, an art peculiar to and a part of herself. Her destiny seems to have been to gather from external sources the wealth in which she revelled, with the difference that while ancient Rome furnished nothing beyond a magnificent arena for the art of her day, in later times the artist found in Rome herself his sources of inspiration, compelled as he was to contemplate perfection reflected in the dazzling mirror of antique art. Ten centuries, however, elapsed ere Rome resumed this proud pre-eminence. A glance may now be directed to the interval between the fall of old Rome and the period when, animated with a new life, Rome drew to herself the foremost representatives of the Renaissance, to whom she afforded inspiration for their grandest efforts. It is not, however, the 16th century, not the glories of the Renaissance, that give to the Rome of our day her distinctive character, but rather the new and imposing exterior which she received at the hand of her architects in the 17th century. The mind must be disenchanted before the veil can be penetrated and the Rome of antiquity adequately comprehended.

The protracted suspension of all activity in art makes it apparent that Roman art has a history distinct from Italian art. For

several centuries the towns of Tuscany were the principal abodes of a natural art life. But just as in Rome Italian art achieved its most signal triumphs in the persons of Raphael and Michael Angelo and the masters of that period : so in Roman ground we find that Christian art first took root and attained to its most important dimensions. In Rome then we find the strongest inducements as well as the richest opportunity for the study of **Early Christian Art**.

In the 4th century heathendom, long tottering to its fall, was, in appearance at least, absorbed in the younger Christian world. A new era in art is inaugurated. Not that we are to assume the simultaneous extinction of the pagan art of ancient Rome, nor that it was at once superseded by an altogether new style provided as it were for the emergency. The eye and hand are to a greater extent creatures of habit than the mind. New views and altered conceptions of the Supreme Being as well as of the destiny of man found acceptance. But to embody them the artist had to resort to the old established forms. Then heathen rules were by no means uniformly hostile to Christianity (the period of bitterest persecution began with the 3rd century A.D.); and that the new doctrine should have expanded and taken root, should have been permitted to organise itself in the very midst of heathen society, is evidence that it was received even with favour.

As a consequence of these conditions it will be observed that the art of the early Christians presents no remarkable contrast to that which precedes it, and that they were content to adopt and perpetuate the traditions of the antique. The Roman CATACOMBS afford abundant proof of this. Encircling the city as with a subterranean trench, they were originally far from being what they subsequently became — secret, carefully concealed places of refuge for the early Christians; but rather their regularly ordained and publicly accessible places of burial (*e.g.* the *Catacomb of Nicomedus* and that of *Flavia Domitilla*), and were first designedly consigned to darkness and concealment during the 3rd century, a period of constantly recurring persecution. The Christian community, reared as it was in the midst of Roman paganism, probably did not dream of subverting the principles of antique art. In the adornment of the Catacombs they retain the types transmitted to them; so also in the particulars of drawing and colour the precedent of the Antique is closely followed. Christ represented as the Good Shepherd, Orpheus as the symbol of Christ, and evidences of the long standing repugnance to any rendering of the Passion-history, afford proofs of the readiness to accept the art heritage of their precursors. The older these catacomb paintings are the more closely they approximate to the types of antiquity. Even the SARCOPHAGUS SCULPTURE of the 4th and 5th centuries differs in purpose only, not in technical rendering of form, from the typical reliefs found on pagan tombs. It was only in the latter half of the 6th century that a

new style declared itself in painting which like other branches of plastic art had more or less fallen into a state of decay meanwhile. Architecture adapted itself to the exigencies of Christian worship, and in allying itself to the new architectural forms, painting acquires a new character.

The term *BASILICA* is understood to apply to Christian temples up to the 10th century. The subsequent belief that a more intimate relation than that suggested by a common name subsisted between these early Christian edifices and the forensic *Basilica* of ancient Rome, was altogether an erroneous one. The latter were in fact the Roman courts of law and places of public meeting. They had a place in most of the towns of the Roman empire and were erected in the forum, but have nothing, whether of origin or form, essentially in common with the early Christian temple or church. These forensic basilicas were not adapted to purposes of Christian worship, nor did the old Roman basilica serve as a model for the building of Christian places of worship. In proof of the one assertion may be adduced the fact that the forensic basilicas at the end of the 4th century retained intact their original destination, and in individual cases have been restored; while the other will be justified by an unprejudiced examination of the various parts of the Christian basilicas, which give evidence of having sprung from another source than that of the old Roman basilica. Neither did the Temple of antiquity furnish the model for churches built by the early Christians. The church of *SS. Cosma e Damiano*, of the 6th century, is the earliest example of a pagan temple applied to Christian use. The Christian basilica may be said rather to have grown out of the Roman dwelling-house, where at first the community was in the habit of assembling. The plan for future ecclesiastical edifices was acquired by simply extending the proportions of the dwelling-house. The church of *S. Clemente* in Rome is relatively the most perfect example existing of the architectural properties and internal arrangement of the early Christian basilica. A small portico supported by pillars leads to the outer court (*atrium*), enclosed by a colonnade and having in its midst a fountain (*cantharus*). The eastern colonnade leads into the interior of the church which was usually divided into three aisles. Two rows of columns divide the side aisles from the loftier one in the centre known as the nave; the nave and aisles abut upon a half circle or *apse*. At right angles to these aisles, between them and the apse, was sometimes interposed a third space — the *transept*; the altar stood within the apse and apart beneath a canopy supported by pillars, and in its front, enclosed by rails or *cancelli*, was the choir for the officiating priests and two pulpits (*ambones*), one used for reading the Gospel, the other the Epistles. In marked contrast to the temple of antiquity, little care was bestowed upon the external architecture of these early

Christian basilicas, the most impressive effect being reserved for the interior. And to this end, especially in earlier mediæval times, a ready expedient for supplying decorative material was adopted in the plunder of the monuments of antiquity. Columns were carried off and set up in Christian churches without regard to congruity of material or consistency of style. Thus in the churches of *S. Maria in Trastevere* and *S. Lorenzo Fuori le Mura* are to be seen pillars of different material and workmanship. The churches of *S. Sabina*, *S. Maria Maggiore* and others give evidence of similar depredations. Crosses and lustres in metal, tapestries bestowed by papal piety contributed to the ornate effect of these interiors. But the principal decorative feature were the pictures in mosaic which covered the recess of the apse in particular as well as the arch which connected the apse with the nave (the *Triumphal Arch*). These MOSAIC PICTURES, as far, at least, as the material was concerned, demanded a novel artistic treatment, massive and monumental in character. In them we find the traditions of antiquity abandoned, giving place to a style which from its harshness as well as austere solemnity of conception has been confounded with the Byzantine style. In reality the art was of indigenous growth; and its salient characteristic may be defined as the substitution of the real for the symbolical in general treatment. Now for the first time the popular mind became thoroughly imbued with ecclesiastical sentiment, of which the crucified Saviour was the chief embodiment. The oldest mosaics, composed of glass cubes, are to be seen in the church of *S. Pudenziana*. They date from the 4th century like those in *S. Costanza* and the Baptistery of Naples; while those in *S. Maria Maggiore* and *S. Sabina* belong to the 5th century. The mosaics in *SS. Cosma e Damiano* in the Forum (526-30) may be pronounced as the most beautiful.

The rudiments of Christian art are to be found in Rome; but its further development was promoted in an equal degree by other Italian states. Building was still active in the 9th century, while the Popes, especially Leo III., of the 7th and 8th centuries did good service in church decoration. But during this period there is no evidence either of progress or continuous development in the Mosaic art and as little in architecture itself. The experiment (as seen in *S. Prassede*, 9th century) of combining piers with the pillars of the nave as a support to the wall and of connecting these with transverse arches was not repeated. Finally it may be said of the Mosaics (*S. Prassede*, *SS. Nereo ed Achilleo*, *S. Marco*), that, while they bear a superficial resemblance to the works of the 5th and 6th centuries, they show unmistakable signs of corruption and decline. This may be accounted for to some extent by the evil times which had fallen upon Rome since the 9th century, culminating in a conflagration — the work of an incendiary Guiscard — which laid waste the entire southern quarter of the city,

extending from the Forum to the Lateran and to the slopes of the Esquiline. The chief employment of the architect was the construction of fortified towers and places of strength rendered necessary by the ceaseless warring of factions within the city. In 1257 Brancaloni demolished 140 of these strongholds, the majority of which had been erected on the ruins of some monument or other of antiquity. The most striking example of the rudeness of early mediæval architecture is to be seen in the *Casa di Pilato* or *di Rienzi*. Built by one Nicolao, son of Crescentius (probably in the 12th century), its chief ornamentation consists of marble fragments apparently picked up at random and put together in the wildest confusion.

At the close of the 12th century brighter days dawned for Roman art. 'Magister Romanus' now became a title which the artist was proud to append to his surname. A speciality in decorative art appeared in Rome about this time which did not connect itself, it is true, with the traditions of antique art, though ready to utilise its material, without, however, resort to the depredations of a bygone age. And material was still at hand in richest abundance, in an endless array of shattered marbles. These were divided and subdivided, cut or sawn into minute slabs, arranged in patterns, enlivened by the introduction of stained glass and gold leaf, presenting as a whole a richly coloured decorative effect. These marble mosaics adorn the flooring of churches, altar sides, episcopal chairs, pulpits, and doorways; they enliven monumental sculpture, they fill the flutings of the elegantly twisted columns which bore the Easter candles or adorn the entablature of cloistered courts. This art became the monopoly of particular families and was regularly transmitted from generation to generation. The monumental marbles of this time are generally known as *COSMATO WORK*, a name derived from two members of a family thus privileged. Such work is frequently to be met with in Rome. Conspicuous among the mosaic floorings are those of *S. Maria Maggiore*, *S. Maria in Trastevere*, and *S. Lorenzo Fuori le Mura* (12th century). *S. Clemente* and *S. Giorgio* possess altar tabernacles of Cosmato work and *S. Lorenzo* the finest example in its pulpit. Of similar work in cloisters (*S. Sabina*, *Lateran*) the best specimen is in the convent of *S. Paolo* (13th century). Cosmato work is not infrequently found elsewhere than in Rome. It is uncertain how far this Roman work is connected with kindred examples to be met with in Southern Italy. In technical detail some differences are to be detected, such as the more copious use of the glass pastes by the artists of the South. On the other hand we fancy that the identity of pattern in the mosaics of the Cappella Palatina in Palermo with those of *S. Lorenzo* cannot be accidental.

Along with this decorative mosaic work, the *MOSAIC PAINTING* of apse and choir-arch had since the 12th century successfully

asserted itself. That impress of the antique borne by the early Christian mosaics is gone; the drawing has lost its incisiveness as well as its traditional typical character, and in lieu of this, receives a new and more lively impulse from colour and wealth of ornament. The mosaics in front of the church of *S. Maria in Trastevere*, in the apse of *S. Clemente* (12th century), those in the altar-tribune of the *Lateran* (13th century) and finally those in the apse of *S. Maria Maggiore*, the work of Jacobus Torriti in 1295, are examples of this mosaic painting. — WALL-PAINTING also came once more into use as we see from paintings discovered in 1858 in the lower church of *S. Clemente* — that basilica which in 1108 was lost by a new structure being built upon it. — And, if church-architecture was confined to the rehabilitating of older edifices or the mere reproduction of earlier types, the numerous BELFRIES (the best is that of *S. Maria in Cosmedin*) show an abundant fertility of resource in the architects of that period. They tower aloft, story upon story following in light and airy succession, relieved by flights of slender pillars, and stand, eloquent tributes to the genius of mediæval Rome.

The condition of art in Rome, however (particularly in the 14th century), was far behind that of Tuscany. While in Tuscany popular forces directed by the municipalities provided an ample field for the cultivation of artistic tastes, Rome was distracted by the incessant war of factions and families, or the quarrels of the popes. Strangers were invited to execute works which were beyond the ordinary resources of art as it then existed in Rome. Dominican Friars introduced Gothic architecture into Rome — *Fra Ristoro*, *Fra Sisto* are probably the builders of the church of *S. Maria sopra Minerva* — and *Giotto* (chief of the Florentine school) was summoned to Rome during the pontificate of Boniface VIII., and at the instance of his patron Cardinal Gaetano Stefaneschi, to execute a mosaic (*Navicella*) for the Porch of St. Peter's, and to paint a *Ciborium* (in part preserved in the Sacristy of St. Peter's); probably also to execute a commission from the Pope, to represent the proclamation of the Jubilee of the year 1300. Of Giotto's Roman contemporary *Pietro Cavallini* we have unfortunately no certain information.

It was not until the return of the Popes from their exile at Avignon, when Italians held exclusive possession of St. Peter's chair, and aimed at supremacy amongst the secular powers of the peninsula; when the Humanists acquired their shortlived ascendancy at the Papal court — that Roman art first approaches its maturity. Rome indeed had no direct share in the creation of the **Renaissance**. To Florence belongs the exclusive and imperishable renown of this achievement. On the other hand it must not be forgotten how powerful an impression the spectacle of the mighty relics of antiquity must have made upon the receptive minds of the first Humanists, exciting their emulation and inciting to a more reverent

study of the Antique; neither must it be forgotten that by study of old Roman art Brunelleschi and Donatello became familiar with those forms in which they were wont to express their artistical thought, and so were led to new and unexplored paths in the realm of art.

Once more Rome occupies a foremost place in the history of art when Pope NICHOLAS V. (1447-1455), a Humanist, vies with the Medici in his passion for books and building. He is bent upon a renovation of the Vatican Quarter; his ambition is to erect a papal residence of surpassing splendour; nay, he entertains designs on the St. Peter's pile itself and contemplates its reconstruction. The most imposing work of this period was the *Venetian Palace* begun by Pietro Barbo (1455), afterwards Pope Paul II., which, like the *Albergo dell' Orso* recently as it were again discovered, is to a great extent mediæval in character. *Leon Battista Alberti*, who resided in Rome about this time and died there in 1472, is supposed to have furnished the plans for this palace.

So far indeed had the fostering of art become obligatory on the occupants of the papal chair, that they could not neglect this function without forfeiting their individual influence, and impairing the dignity of their office. The right powers were not, however, immediately at hand, which should give effect to the building projects of these Sovereign Pontiffs, enamoured as they were of splendour in every shape. The architect who during the pontificate of SIXTUS IV. (1471-1484) was most employed, *Baccio Pintelli*, was a practitioner of moderate skill, and far behind the great Florentines of his day. The building of *S. Agostino* and *S. Pietro in Montorio*, as well as the façades of *SS. Apostoli* and *S. Pietro in Vincoli* were from his plans. His most celebrated work is the Popes' private Chapel in the Vatican, called after the Pope Sixtus the *Sistine Chapel*, which owes its chief attractions far less to its architectural merits, than to the artistic decoration of wall and ceiling.

Abundant employment together with the favour which artists found with dignitaries of the Church had already allured numerous Tuscan and Umbrian PAINTERS to Rome. Amongst those thus engaged in beautifying the churches of Rome and the Vatican Palace we meet such Florentine celebrities as *Maestri Sandro Botticelli*, *Filippino Lippi*, *Domenico Ghirlandajo*, *Cosimo Rosselli*; and from the Umbrian School the immediate forerunner of Michael Angelo, bold *Luca Signorelli*, along with *Perugino* and *Pinturicchio*. An attempt is made to found an Academy, or Guild of St. Luke at Rome. Amongst its members we find (1494) *Melozzo da Forlì*, the painter of a fresco (transferred to canvas) in the Vatican Gallery, representing the foundation of the Vatican library. — The execution of the *Wall Paintings in the Sistine Chapel*, by order of Sixtus IV., was a momentous event in a time prolific in art enterprise. In accordance with the then prevailing point of view the acts of Moses are represented as symbolically parallel to those of Christ. On the left wall are incidents

in the life of Moses by Botticelli, Rosselli, Signorelli, on the right wall events in the life of Christ by Botticelli, Rosselli, Ghirlandajo, and Perugino. Those lovers of art who are unable to visit Florence before going to Rome are recommended to make these wall paintings their especial study. They will learn from them to appreciate the descriptive power of the Florentines and will be familiarised with the field subsequently occupied by the heroes of Italian Art.

Tuscan SCULPTORS, too, find their way frequently to Rome and are constantly employed either as workers in bronze or marble. Little attention seems, however, to have been paid to the former. The great bronze doors of St. Peter, the joint work of *Filarete* and *Simone*, are interesting rather from the wealth of mythological imagery with which they are embellished, than from their artistic pretensions, which will not compare with those of Ghiberti's famous gates. So much the more powerfully does the sculptor appeal to us in marble. A taste for profusion and splendour of monumental decoration in adorning the tombs, which fact declares itself in the 15th century — a result probably of that thirst for fame which is identified with the Renaissance — gave the sculptor unceasing opportunity for the exercise of his art, particularly in its purely decorative phases. There is scarcely a single church of a certain date which does not contain sepulchral monuments from the close of the 15th century. The church of *S. Maria del Popolo* possesses the largest number. These monuments — perfected in Florence and probably naturalised in Rome by Mino da Fiesole — are nearly uniform, viz. a sarcophagus surmounted by a statue of the deceased, and supported by a pedestal ornamented with a garland of fruit and flowers, and genii. A niche or panelled screen finished with a medallion of the Madonna form the usual background. The majority of these sculptures cannot be traced to any particular artist. It would appear indeed that the sarcophagi, as with the ancient Romans, were rather articles of manufacture than works of art, made wholesale fashion after some favourite pattern and bought 'ready made', a commission being given to the sculptor for a portrait of the deceased to which would be added the armorial bearings with inscription.

Whoever might have visited Rome in the earlier years of the 16th century would have found himself in the presence of an intense movement in the art world; he would have found Architect, Sculptor and Painter alike occupied with projects of more or less grandeur. So far, however, Rome did not in this respect surpass the other chief towns of Italy; so far art had not assumed that particular form of life and direction which only the atmosphere of Rome could sustain, or which the genius of the Vatican alone could quicken — during the Pontificate of JULIUS II. (1503-1513), where the golden era of Roman art began, this consummation was actually achieved.

To Julius belongs the glory of having associated with Rome three

names, *Bramante*, *Michael Angelo*, *Raphael*, everlasting beacons in the path of art — three men who in the course of the 16th century (*cinquecento*) raised modern art to its loftiest pitch of splendour. His successor LEO X. (1513-1522) of the house of Medici owes it to his lineage only that he should have transmitted to posterity so splendid a reputation, — that his name should be associated inseparably with the greatest triumphs of art in modern times. Leo X. inherited the well-earned fame of his predecessor, but knew not how either to value or to use his inheritance aright. It was not given him to sway the imperious temper of Michael Angelo, nor fully to comprehend the mighty schemes of **Bramante**. The latter's chief work, the rebuilding of *St. Peter's*, can be adequately studied only in the collection of original drawings in Florence which set forth the grandeur of Bramante's designs in all their completeness; for so many different hands were employed in giving effect to these, that little remains of the original plan. Happily this little, *viz.* the dome with the overwhelming impression of vastness it conveys, is of the very best. Bramante contemplated a central structure in the form of a Greek cross, rounded at its extremities, which, crowned by a gigantic dome, should present an ensemble at once simple and majestic. Succeeding generations have failed to embody Bramante's ideal. His career, extending probably from 1444 to 1514, is involved in obscurity. Of his works, Rome possesses numerous examples. The circular chapel in the monastery of *S. Pietro in Montorio*, the court of *S. Maria della Pace*, the arcades in the first court of the Vatican (*Cortile di S. Damaso*), the *Palazzo Giraud* and above all the *Cancelleria* are perfect examples of Renaissance.

We are wont to wonder at the profusion and splendour, too, of works to which the *cinquecento* gave birth. How much richer, how much more splendid would have been this profusion, had only these works been carried out as originally designed by the artist's creative genius!

The same fatality which pursued Bramante's mightiest projects served to mar **Michael Angelo's** (1475-1564) supreme effort in the realm of PLASTIC ART. The *Tomb of Julius II.*, begun while that pope was still living, was to consist of a large detached edifice with statues of Moses, St. Paul, and other colossal figures at its projecting angles, and ranged along its wall the naked forms of men in chains. The work, however, soon came to a standstill, and at last, 30 years after its commencement (1545), it was placed in the church of *S. Pietro in Vincoli* where it now stands, deplorably, a mere fragment of the original design. Its most striking feature is the tremendous figure of Moses, rising in wrathful indignation at the worship of the golden calf, to denounce the idolatry of the Israelites. In addition to the Moses, Rome contains two conspicuous works from the hand of Michael Angelo: the *Pietà*, badly placed in one of the chapels in *St. Peter's*, and the *Statue of Christ* in *S. Maria sopra Minerva*. The

former surpasses all other efforts of the great sculptor in the delicacy of its modelling as well as in the force with which it appeals to human sympathies.

As **FRESCO PAINTER** Michael Angelo figures exclusively in Rome. Tradition tells us how loath he was to exchange the chisel for the brush, when at the behest of the imperious Julius II. he undertook the decoration in fresco of the ceiling of the Sixtine Chapel. These frescoes are nevertheless the most important of Michael Angelo's contributions to art. They afford a wider field for the exercise of his creative power than sculpture, where plastic forms, unequal as they are to the demands of his prolific genius, betray him into exaggeration. These frescoes of Michael Angelo are closely akin to the wall paintings of Florentine and Umbrian artists at the close of the 15th century, in which the deliverer of the Israelites is made to prefigure the Saviour of mankind. How salvation came to the world, and how proclaimed, is the theme which Michael Angelo undertakes to illustrate. In the centre piece is depicted the Creation, the history of Adam and of Noah; how sin came into the world, but with sin the promise of redemption. Forecasting all this we next see the figures of Prophets and Sibyls. In the marginal pictures we see continued reference to the Redemption, in the various deliverances of the Jewish people (the brazen serpent, David and Goliath, the fate of Haman, and Judith), in conformity with mediæval conceptions, together with symbols of the Redemption. Connecting themselves with the above are the groups occupying the lunettes, portraying expectation, the anguish of suspense, and contrition, which include at once matters of fact and a twofold allusion to the vicissitudes of the Israelites and the events of our Saviour's life (progenitors of Christ and Jews captive in Babylon). The sublimity of the work is to be attributed very much to the skill with which mere matters of fact are everywhere subordinated to the claims of individual action as well as artistic purpose. Moreover Michael Angelo has contrived so to dispose the various portions of his vast work, ascending by figures, single and in groups, from the simply decorative margin to the crowning effort in the centre, so to adapt them to the place they occupy, that the entire work becomes architecturally, so to speak, self-supporting; while the composition as a whole is wielded with a wealth of resources together with a power of organisation such as no other artist has attained to. The thoughtful beholder will not confine himself exclusively to the study of the central pictures. The figures in monochrome and minor decorations are replete with a beauty peculiar to themselves.

Of the '*Last Judgment*', painted by Michael Angelo at a much later period (1541), it is difficult, owing to its dilapidated condition, to form an accurate estimate. The unerring audacity, however, with which figure and group alike are thrown into every conceivable attitude and movement, must command a mute and amazed attention.

With the names of Bramante and Michael Angelo is associated that of **Raphael** (1483-1520), whose youthful genius had very early declared itself, first in Perugia and later in Florence. In Rome are to be seen interesting mementoes of both these periods. In the *Coronation of the Virgin* in the Vatican Gallery we see him still in the trammels of the Umbrian School; the effects of his Florentine training are visible in his *Entombment of Christ* in the Borghese Gallery (belonging to later periods are the so called *Fornarina* in the Barberini Gallery, the *Violin Player* in the Palazzo Sciarra, *Navagero* and *Beazzano* in the Doria Gallery, the *Madonna di Foligno*, and the *Transfiguration*, the master's last work, both in the Vatican Gallery). The majority of Raphael's easel pictures are to be found elsewhere than in Rome.

But in Rome only could Raphael have found a field suited to the exercise of his highest powers in FRESKO PAINTING. The mural paintings in the state apartments of the Popes in the Vatican palace must first be noticed. In order rightly to appreciate these, it must not on the one hand be forgotten that fresco painting never completely loses its decorative character; nor on the other must the peculiar position of the Pontificate in the beginning of the 16th century be lost sight of. In the palace of the Vatican the same courtly tone, the same pursuit of sensuous pleasures, of the mere joys of existence, prevailed as in the courts of the younger Italian dynasties; expressions of national sentiment met with a favorable reception, while an active agitation on the part of the Humanists did not appear to have compromised the dignity of the Papal Court. These conditions are more or less distinctly reflected in the frescoes of Raphael. The courtier repeatedly asserts himself; even a delicate compliment to the patron is not disdained, nor the ceremonial spectacle excluded. Political as well as personal allusions are not wanting, while ample space is devoted to the glorification of the Humanistic ideal. Finally, when it is borne in mind that Raphael was constantly compelled to defer to the exigencies of the allotted space, to study the separate requirements of wall and ceiling, we gain an insight into the nature and extent of the restraints imposed upon the Artist. They beset him indeed on every hand, and constantly compel him to alter or modify his design. Curiously enough these restrictions are to this day interpreted as an act of the Artist's free and daring will. One wonders at the amount of theological learning, of philosophical erudition displayed in the *Disputa* and the *School of Athens*, as well as at the inventiveness which could connect subjects so remote from one another as the *Heliodorus driven from the Temple*, and the expulsion of the French from Italy. Through the entire range of subjects there runs a vein of profound and continuous thought. But especially admirable are alike the discernment which enabled Raphael to select, from apparently the most heterogeneous sources, matter

suitable for pictorial embodiment; the resolution with which he guarded the realm of fancy; and his sense of the beautiful, whereby he was enabled to bring the most intractable material into subjection to his purpose. These qualities are most conspicuous in the picture known as the *Burning of the Leonine Quarter* (the so-called *Borgo*) of Rome, or rather, as the artist's patron would have it, the conflagration, extinguished by intercession of the Pope. The spectator forgets the preposterous demand that a miracle should be thus palpably depicted: Raphael delegates the action to the heroic age, fills his picture with figures and groups of surpassing grandeur and animation (such as succeeding generations have striven in vain to imitate) and depicts the confusion, the preparation for rescue and flight with surpassingly graphic effect. The picture was not what he had been commissioned to paint; but in lieu of this we have a creation teeming with imaginative power and masterful execution. In like manner Raphael disposed of the celebrated frescoes in the first Stanza, the *Disputa* and the *School of Athens*. Had he not been required to illustrate a chapter from the history of dogma (the proclamation of the doctrine of transubstantiation) or to present a pictorial extract from the history of ancient philosophy, the task of depicting a procession of historical celebrities known to fame as fathers of the church or mundane philosophers could not be particularly inviting. And further, while Raphael mingled with historical personages figures purely typical, and in the *Disputa* represents the assembled company of believers as beholding a vision, where each individual present is naturally more or less overpowered by emotion — while in the *School of Athens* he especially emphasises the blessedness of knowledge, the good fortune which leads to the higher paths of learning (whether his representation literally coincides with the Diogenes Laertius or Sidonius Apollinaris or not) — he has asserted with brilliant success the Artist's right to supremacy in the realm of creative fancy.

After the foregoing remarks the unprejudiced reader will need a hint only as to the mental attitude he shall assume as a student of Raphael's works. If the mere subject of the picture exclusively occupies his attention, if he must know the name and history of every figure, and feels it incumbent upon him to admire the intellectual grasp of an artist who gathered his materials from the remotest provinces of learning and who abounds in literary allusions, he is no longer in a condition fairly to test the artistic value of Raphael's works. From this point of view he will fail to detect in them any essential difference from the allegorical pictures of the period, nay he may even give precedence to many of these: to the wall paintings in the Capella degli Spagnuoli (S. M. Novella in Florence) for example, which indisputably exhibit greater versatility, a superior daring in the embodiment of the preternatural and

a loftier conception of the didactic capabilities of art. It is still a matter of uncertainty how far the erudition displayed by Raphael was an acquirement of his own or how far he may have relied on the contributions of contemporary scholars, such for example as Castiglione, Bembo, and Ariosto, who would in so far share with him the merit due to fertility of thought. Assuming, however, that Raphael himself supplied the wealth of literary research which the frescoes of the Stanze are said to reveal, he would not as Artist become more intelligible to us. His intellect might thus have been exercised, but not his imagination. Raphael's pictures will not only be more thoroughly enjoyed, but his individuality and purpose will be more perfectly apprehended when the effort is made to understand, how the painter by force of his imagination could out of material for thought, dead in itself, create new and living forms; how he imparted to single figures so distinct a psychological impress that the mere bearers of historical names are made to appear as representative human characters; how subtly he balanced action and repose in his groups, not dwelling too long on mere beauty of outline and contour, but intent on giving harmonious expression to a more profound intellectual antithesis. From this point of view, interest in the works of Raphael will be enlightened and enduring. Numerous problems will present themselves to the amateur for solution: what motive Raphael might have had in treating the *Disputa* and the *School of Athens* so differently in respect of colour; how far in the latter picture the architectural character of the background is essential to the collective impression to be conveyed; for what reason the domain of portraiture is here narrowed to the utmost, while there (*Jurisprudence*) it is extended; what were the grounds for the manifold changes in composition which are accurately traced in his numerous sketches, etc.

The condition of the Stanze frescoes is such, alas, as to afford anything but unqualified gratification, just as in the Loggie we regretfully trace the departed glory of unique examples of decorative art, and with difficulty recognise the summit of Raphael's attainments in the grievously injured *Tapestries*. These latter, it is true, in the detail of their composition may be studied in the cartoons now in the Kensington Museum; but the subordinate decorations, marginal arabesques and the like are still in part preserved in the original tapestries, and are essential to the festive character of ornamentation originally designed for the Sistine Chapel. To the ten tapestries so long known, an eleventh discovered in the dépôt of the Vatican has been added. These tapestries were to have adorned the lower compartment of the chapel walls and to this end they must correspond with the companion pictures: that, while these relate the history of Redemption, they, the former, should portray the power and grace of God abiding with the Church.

In apparently irreconcilable contrast to Raphael's works in the

Vatican we have his frescoes in the gay *Villa Farnesina*. On the one hand we are awed by devotional fervour, sublime aspiration, thought earnest and profound; on the other we find Art revelling in the joys of life, each form radiant with an ecstasy of innocent mirth. Nevertheless it will cost no great effort to discern in the Farnesina frescoes the impress of Raphael's genius. He was indebted for his version of the myth of Cupid and Psyche to a work of Apuleius, familiar to readers of the 16th century as it had been to the Romans of old. Probably no author either in ancient or modern times can boast a more captivating illustration than Apuleius, while at the same time none has been more freely handled by his illustrator. In Raphael's hands the myth is moulded anew. Remembering that it was the adornment of a festive chamber he had in hand, Raphael sedulously avoided everything repugnant to the festive mood. Psyche's woes were consigned to the background; the painter is intent upon recording her triumphs only. The confined space afforded by the chamber serves only to stimulate the Artist's mastery of form. Raphael's representation of the myth is condensed: many scenes are but glanced at for a moment, though essentials never escape him; thus the claims of narration and decoration are adjusted without restraint. Harmony alike in idea and form; nobility of proportion never overstepping the bounds of refinement; the power of so losing himself in his subject as to present it devoid of individual caprice: attributes characteristic of Raphael as these are declare themselves in the frescoes of the Farnesina as unmistakably as in the wall paintings of the Vatican. The spectator's own unassisted eye will not fail to see that the pictures on the ceiling of the principal saloon are far inferior in execution to the so-called *Galatea* in the neighbouring apartment. He will find nevertheless that both are such as will reward careful study with the highest gratification — a delight it must be a lasting desire to renew.

The inaccessibility of the upper rooms of the Farnesina, adorned by *Bazzi* of Siena (1477-1549; p. 23), commonly known as *Sodoma*, with his painting of the Nuptials of Alexander with Roxane, cannot be too much regretted. In the embodiment of sensuous grace and beauty, Raphael found in Sodoma a worthy rival.

In the *Sibyls of Raphael* in S. Maria della Pace (1514) we find him competing — if the expression may be allowed — in another field. Here he trenches upon the domain of Michael Angelo; not, however, that he is for a moment betrayed into disingenuousness by contact with a presence so overpowering, or that is he beguiled into assuming a style foreign to his genius. True to himself, he accepts the limits prescribed by his subject, and combines an air of pleasing serenity and infinite grace with the expression of prophetic inspiration.

Around these three Art heroes, Bramante, Raphael, and Michael Angelo, is grouped a brilliant circle of pupils and dependents. The best works of the School of Raphael are undoubtedly those executed

in his lifetime and under his direction. *Giulio Romano* (1493-1546) and *Francesco Penni* (1488-1528) had a considerable share in the painting of the Hall of Constantine; the completion of the Loggia paintings was entrusted to them, *Perino del Vaga* (1499-1547), *Raffaello dal Colle*, and others. For the decorative ornamentation of the Loggie and the Farnesina the master engaged the services of *Giovanni da Udine* (1487-1564). Romano exhibits himself most clearly as a pupil of Raphael in the Villa Madama Giulio, less so in his Madonnas (Pal. Colonna and Borghese).

The crowd of ARCHITECTS, who appeared in Bramante's time, showed greater independence: *Baldassare Peruzzi* (1481-1563; p. 23), who built the Farnesina and Pal. Massimi, *Raphael* himself and *Giulio Romano* (Villa Madama), *Antonio da Sangallo* the younger, with whom originated the Pal. Farnese and a new plan for St. Peter's, and lastly MICHAEL ANGELO, whose influence, gradually deposing Bramante, irresistibly impelled the architecture of Rome into new courses. And just as in Plastic art he scornfully rejects the recognised forms and forces upon them a new construction, in like manner as Architect he concerns himself little about the accurate adjustment of subordinate parts, intent rather upon the effect to be produced by the structure as a whole — usually one of ponderous immensity. The colonnades in the *Palazzo Farnese*, the conversion of the Baths of Diocletian into the church of *S. Maria degli Angeli* — a work subsequently spoiled — and the *Porta Pia* are among his chief works. His chief merit consists in his having reverted to the plans of Bramante for the completion of *St. Peter's*, which since 1546 had been under his superintendence. The Cupola at least was carried out according to his designs, but the ground-plan, to the injury of the building, was much altered, and the Latin substituted for the Greek Cross.

As long as the 'divine' Michael Angelo lived, Rome was so dazzled by the splendour of his renown that no one suspected the DECLINE OF ART was at hand. In fact, however, it had already declared itself at the death of Raphael. Rome once more captured and pillaged; orthodoxy reinstated; the church recoiling from the taint of Humanism: these were incisive events in the history of art, which now received a more distinctively ecclesiastical direction. The Foreign occupation of Rome expelled a vast number of her artists and laid a chasm in the traditions of her art. As she once more recovered herself and under the pontificate of SIXTUS V. (Felice Peretti, 1585-90) was to all appearance again invested with her pristine grandeur, the encouragement of art was revived, but in a spirit which presently pervaded and brought into subjection every phase of art. To Sixtus V. the Eternal City, which 'forthwith doubled itself', owes her present aspect. The *Acqua Felice*, the *Spanish Staircase*, the *Via Sistina*, the *Piazza di S. Giovanni in Laterano*, the *Obelisk* in the Piazza of St. Peter, the restoration of the *Columns of Trajan* and *Marcus Aurelius* are his work. *Domenico Fontana* of Ticino was foremost in giving effect to

this Pope's projects. The authors of the degenerated Renaissance known as **Baroque** were really *Vignola* (1507-73) and Fontana's nephew *Carlo Maderna* (1556-1639). In the Jesuit church of *Gesù* (1568) the former furnished the type of the style which prevailed during the following century, especially in the numberless Jesuit churches then built. Maderna with *Borromini* and *Carlo Fontana* were the leaders of that band of Artists who conspired to rob architecture of its fitting repose, and by the introduction of figures posed in startling attitudes, aroused or convulsed by agency unseen, of curves instead of straight lines, of pillar piled upon pillar, substituted a turbulent unrest. Not that the style was without striking and artistic effect. An undoubted vigour in the disposition of detail, a feeling for vastness and pomp, together with an internal decoration which spared neither colour nor costly material to secure an effect of dazzling splendour: such are the distinguishing attributes of the Baroque style as in Rome it is to be seen on every hand, not only in an endless succession of churches (*S. Ignazio*, *S. Andrea della Valle*, *S. Carlo alle Quattro Fontane*, etc.), but in numerous palaces, the *Barberini* being a conspicuous example. The reader will, however, scarcely dwell on these works longer than will suffice to give him a clear general impression of their character.

A greater tenacity of life is, however, inherent in the art of PAINTING. An altogether deplorable interval now ensued, during which artistic talent was beguiled by Michael Angelo's overwhelming ascendancy into a slavish imitativeness, content with the least possible effort to crowd into a given space the greatest possible number of unmeaning figures, not devoid, however, of a certain superficial charm sufficient to captivate the eye. After an interval thus occupied and identified with this supremacy of the MANNERIST School (*Arpino*, *Zuccaro*), painting once more, at the close of the 16th century, was galvanised into a new life, destined to be of brief duration—Rome becomes a scene of conflict in which painters and their partisans are the combatants. During the reigns of the popes from Sixtus V. to Clement VIII. the fashionable artists were *Circignani*, surnamed *Pomarancio*, and his pupil *Roncalli*. It was not, however, till the accession of Paul V. (1605-21), a member of the *Borghese* family, that the interest in art became again widely spread. It was about this period that *Rubens* visited Rome, where he profited by a study of the best qualities of every school, without identifying himself with any.

Caravaggio (1569-1609) was the chief of the NATURALIST School. He was triumphant in the possession of popular favour. On the other hand it was objected that his drawing was bad, that he failed in the essential of grouping the figures in his larger compositions. Nevertheless the mass is presented with such startling reality, and animated with gesture so impassioned, that every figure fitly asserts itself, while a corresponding force in colour conveys an impression

powerfully suggestive of the turbulent license then prevailing. — The ECLECTICS took an opposite direction. Trained in a regularly-constituted school of art, such as had been established at Bologna, initiated moreover in the art of Coreggio and the Venetians, full of reverence for more remote traditions, thoroughly versed in the rules of drawing and composition as well as familiar with the fresco painter's art — thus formidably equipped, *Annibale Carracci*, *Domenichino*, *Guido Reni*, *Guercino* appeared amongst the rival aspirants to fame in Rome. They supplanted the Naturalists, appropriating as much of the latter's method as appeared available, and finally monopolised the favour of the court and aristocracy. Nor was the struggle by any means confined to the palette and the brush. Personalities arose, and amongst themselves the partisans of Carracci were seldom at peace. Their contributions are in part, at any rate, of the highest excellence. *Annibale Carracci's* frescoes in the Palazzo Farnese; *Guido Reni's* Aurora in the Casino Rospigliosi; the frescoes of *Domenichino* in S. Luigi dei Francesi, S. Andrea della Valle, in Grotta Ferrata near Rome are not mere master-pieces of technical skill, but are replete with artistic beauty and vitality.

The Neapolitan sculptor *Lorenzo Bernini* (1598-1680) flourishes up to the close of the 17th century. His works occupy the concluding chapter in the history of Roman Art. It is superfluous to bid the beholder beware of being led captive by art essentially flimsy and meretricious; rather perhaps it is necessary, as a set off against the now prevailing depreciation of Bernini's works, to plead the important historical significance they possess amidst all their too conspicuous defects; to bear in mind that throughout the course of nearly a century they were regarded as the most brilliant production of that period and were very generally imitated.

Since the 17th century, Rome has not given birth to nor nurtured any distinctive art life, though the past has held Artists of all nations spell-bound, compelling the conviction that Rome is still the true High School of Art, whose teaching is indispensable to every true Artist. So late as the close of the 18th and the beginning of the present century, Rome continued to give proofs of the potency of her influence. Without the suggestions which Rome alone could furnish, *David* would never have received that classical impulse which he turned to such admirable account in France. *Asmus Carstens*, the father of the classical style of modern German art, also made his home in Rome. Amid the art-collections of Rome alone could *Thorvaldsen*, the 'Greek of the 19th century', have worthily perfected his talents. In the absence of such inspiration as the spectacle of Rome's master-pieces alone can afford, *Cornelius* and his associates would never have had the courage to attempt the revival of fresco-painting.

Thus it was that Rome reacted on the destinies of modern art,

though without an art life she could call her own. During the last fifty years, however, she has lost much of her importance even in this respect, through the altered tendencies of the artistic schools of France, Belgium, and Germany. Foreign painters and sculptors still visit Rome, but it has entirely ceased to dictate the tone of European art. In place of this, Rome may perhaps become the centre of a new Italian school of art, though the productions of modern Roman artists have hitherto scarcely warranted the supposition. At the beginning of this century building wholly ceased at Rome, and the works of monumental painting, such as *Podesti's* frescoes in the Stanza dell' Incendio, prove that the traditions of the classic period had been utterly forgotten. Since, however, Rome has been the capital of a united Italy, increased activity has been manifested in the field of art, and the clever Roman stonemasons have had abundant opportunity to show their skill in the ornamentation of handsome modern edifices. The resuscitation of a truly elevated style of sculpture is hindered by the tendency to exaggerated realism and the undue value laid upon mere mechanical dexterity, which seem nowhere so much out of place as at Rome. In painting Rome has not yet outstripped the flourishing schools of North Italy.

FIRST SECTION.

S. TUSCANY. UMBRIA. THE MARCHES.

1. From Leghorn or Pisa to Rome by the Maremme.

208 M. (from Pisa 207½ M.). RAILWAY. Express in 7-7½ hrs., fares 41 fr. 65, 29 fr. 15 c. (from Pisa 41 fr. 55, 29 fr. 10 c.); ordinary trains in 8½ hrs., fares 37 fr. 90, 26 fr. 50, 17 fr. 5 c. (or 37 fr. 75, 26 fr. 45 c, 17 fr.).

The MAREMME RAILWAY coincides with the ancient *Via Aurelia*. It runs inland as far as Cecina, where it approaches the coast, commanding fine views of the sea with its promontories and islands. Views always on the right. — This is perhaps the least picturesque of the routes to Rome; yet the traveller who desires to explore it may devote several days to the journey, though, owing to the malaria, this is not practicable between the end of May and the end of October (comp. p. 2).

STEAMBOAT. Another route from Leghorn to Rome is by sea as far as Civit  Vecchia, and thence by railway. This route is somewhat more expensive than the railway journey. Embarkation at Leghorn in the inner harbour 1 fr., in the outer harbour 1½ fr. The steamers generally weigh anchor towards evening. Arrival at *Civit  Vecchia* (landing ½ fr. each person, trunk to the station 1 fr.), and journey thence to Rome, see pp. 6, 7.

Leghorn and *Pisa*, see *Baedeker's Northern Italy*. — The lines unite at *Vicarelle*, near the first station *Colle Salvetti*, which is 10 M. distant from Leghorn and 9½ M. from Pisa. To the right we see the *Monte Nero*, a celebrated place of pious resort, with an ancient picture of the Virgin brought from the East and especially revered by sailors.

13 M. (from Pisa) *Faugia*; 18 M. *Orciano*; 24 M. *Rosignano*, the village of which name is situated on a hill to the right; 28 M. *Vada*. The train crosses the *Cecina*, the ancient *Caecina*. The family of that name was once settled in this district, as is proved by numerous inscriptions at Volterra.

31½ M. *Cecina* (poor caf  at the station), where a branch-line to *Volterra* diverges (see p. 8), is, like all the above-mentioned villages, of modern origin.

The line now approaches the coast. The loftily-situated, ancient Etruscan Populonia (p. 2) becomes visible to the right, on a chain of hills projecting into the sea; beyond it the island of Elba (p. 12).

42 M. *Castagneto*; 47 M. *S. Vincenzo*, with a small harbour.

53½ M. *Campiglia*; the small town lies to the left on the height, with a ruined castle and Etruscan tombs of no great interest.

FROM CAMPIGLIA TO PIOMBINO, $7\frac{1}{2}$ M., diligence every evening in about 2 hrs., returning thence at noon (fare $1\frac{1}{2}$ fr.).

Piombino (*Albergo delle Api*, unpretending, bargaining advisable), a small town with 4000 inhab., originally belonged to Pisa, in 1399 became a principality of the *Appiani*, in 1603 was acquired by Spain, and then by the family of *Buoncompagni-Ludovisi*, from whom it was wrested by Napoleon in 1805 in favour of his brother-in-law, the Corsican *Felix Bacciocchi*. In 1815 it was assigned to Tuscany, with which it remained united till 1859. It lies at the S. end of a wooded promontory, bounded on the land side by a flat district. A weather-beaten tower on the harbour commands a grand view of the sea and the island of Elba (in front of which rise the cliffs of Cerboli and Palmajola), of S. Giglio and the coast, and Corsica in the distance. — Steamboat to Elba daily, returning the following morning (p. 12).

A forenoon suffices for a visit to (6 M.) the ancient **Populonia**, the Etruscan *Pupluna*, at the N. end of the peninsula. The shorter route through the woods requires a guide. The town with its mediæval castle, situated on a lofty and precipitous hill, is conspicuous from all sides. Once a prosperous seaport, it suffered greatly from a siege by Sulla; in the time of Strabo it had fallen to decay, and it is now a poor village. In ancient times the iron of Elba was smelted here. The old town-walls may still be distinctly traced, and are particularly well preserved on the side next the sea; they consist of huge blocks, approaching the polygonal style. The views towards the land and the sea are striking and extensive. Several vaults, erroneously said to belong to an amphitheatre, and a reservoir may also be mentioned as relics of the Roman period. The Etruscan tombs in the vicinity are hardly worthy of a visit.

The district now begins to exhibit the distinguishing characteristics of the Maremme: a world of its own, consisting of forest and swamp, in summer poisoned by malaria, and still but sparsely cultivated, in spite of repeated attempts (especially near the railway-stations) to bring it under tillage. During the Etruscan period the Maremme possessed several considerable towns: *Populonia*, *Vetulonia*, *Rusellæ*, *Cosa*. On the decline of agriculture in Italy and the conversion of the farms into pasture-land, the desolation of the coast-district made rapid progress. During the present century the first successful attempts were made to counteract the malaria by the drainage and filling up of swamps and the establishment of new farms; but the evil is still very great. Charcoal-burning and in winter cattle-grazing are the chief resources of the inhabitants, most of whom withdraw to the Tuscan hill-country in May, when the malaria begins.

64 M. **Follonica**, near the sea, possesses considerable smelting-foundries for the iron from Elba. Beautiful view towards the sea; to the right the promontory of Piombino and Elba, to the left the promontory of Castiglione with a lighthouse, and the small, grotesquely shaped island of *Formica*. On a hill to the left is *Massa Marittima*, one of the largest towns of the Maremme, with 13,000 inhabitants. In the vicinity are extensive copper-mines. — The train again quits the coast and skirts the *Promontory of Castiglione*.

73 M. **Gavorrano**, the station for the place of the same name, situated higher up, to the right. Farther on, also to the right, on a hill, is *Colonna*; and in the distance, at the mouth of the *Bruna*, the small fortified harbour of *Castiglione della Pescaja* is visible. Here, as in

the other seaports of the Maremme, wood and charcoal form the chief exports.

82½ M. *Monte Pescali*, junction of a branch-line from Siena. which runs parallel to our line as far as Grosseto. The village is picturesquely situated on a hill to the left.

90½ M. **Grosseto** (**Rail. Restaurant; Stella d'Italia*, with a good trattoria; *Bella Toscana*), the capital of the Maremme, a pleasant town with 7400 inhabitants. The *Cathedral*, begun in 1294, was restored in 1855. The *Municipio* contains a collection of Etruscan cinerary urns, sarcophagi, and other antiquities. Branch-line to *Asciano* (Siena), see p. 17.

About 3½ M. to the N.E. of Grosseto (carriage-road) lie the sulphureous *Bagni di Roselle*, whence the ruins of *Rusellæ* are reached in ½ hr. (guide necessary). *Rusellæ*, anciently one of the twelve capitals of the Etruscan confederation, has been deserted since the middle of the 12th cent. and is thickly overgrown with underwood. The walls, which are nearly 2 M. in circumference, and in most places accessible, consist partly of horizontal courses, partly of polygonal blocks (6-8 ft. high, 6-12 ft. long).

Around Grosseto, and to the W., in the direction of Castiglione, extends a considerable plain, in ancient times a lake (the *Lacus Pretius* of Cicero), which gradually became shallower and productive of malaria (*Palude di Castiglione* and *di Grosseto*). By skilful drainage, and by conducting hither the deposits of the neighbouring rivers, the government has almost entirely filled up the morass and converted it into a valuable pasture, 12-15 M. long.

Beyond Grosseto the *Ombro* is crossed. 99 M. *Albarese*. The line skirts the wooded *Promontory of Talamone*; towards the S. the imposing *Monte Argentario* (see below) is visible.

At (105 M.) *Talamone* a beautiful view of the sea is disclosed. The village lies at the end of the promontory and possesses an anchorage sheltered by the island of Giglio and the Mte. *Argentario* (steamer to Elba, p. 12). The creek has been much diminished by alluvial deposits. Here, in B.C. 225, the Roman legions landed and signally defeated the Gauls who were marching against Rome.

The train crosses the small river *Osa*, then the more important *Albegna* (ancient *Albinia*), at the mouth of which are salt-works. 109 M. *Albegna*.

113½ M. **Orbetello** (**Rail. Restaurant*). On the arrival of the train an omnibus (1 fr.) starts for (1½ M.) *Orbetello* (*Albergo Rosa, Albergo Nazionale*, both unpretending), with 6000 inhab., situated at the extremity of a promontory, near the foot of *Monte Argentario*, which rises immediately from the sea, and is connected with the mainland by two narrow tongues of land, whereby a large salt-water lagoon is formed. The only object of interest is the polygonal wall on the side next the sea, which testifies to the great antiquity of the town, although its ancient name is unknown.

From Orbetello an embankment has been constructed across the shallow lake, which abounds in fish, to Mte. *Argentario*. A carriage-road leads to the N. harbour, *Porto S. Stefano* (steamboat to Elba, every Friday at 5 a.m., see p. 12), and to *Port' Ercole* on the S. side. The **Monte Argentario** (2090 ft.) culminates in two peaks, on one of which is situated a monastery of the Passionists. The ascent is very interesting (from Orbetello, 2-3 hrs.; guide). The View embraces the coast of Tuscany and the surrounding district as

far as Mte. Amiata, and the sea with its numerous rocky islands as far as Sardinia. If time is limited, the first and lower eminence, $\frac{3}{4}$ hr. from Orbetello, with a picturesque view of the coast, should be visited.

Orbetello is the most convenient starting-point for an excursion to the ($1\frac{1}{2}$ M.) interesting ruins of the ancient *Cosa*, the present *Ansedonia* (carriage there and back, including stay of 5 hrs., 8 fr.); and also for a visit to the ancient towns of *Saturnia* and *Sovana*, 30-35 M. inland. *Cosa* is an old Etruscan town, deserted in the 5th century. The polygonal walls (1600 yds. in circumference) with their towers are admirably preserved. A beautiful prospect of the sea and coast is enjoyed hence.

The train soon enters the former Papal territory, and traverses the Roman Maremma; scenery unattractive. 121 M. *Capalbio*; 125 $\frac{1}{2}$ M. *Chiarone*. It then crosses the *Fiora* and reaches (135 M.) *Montalto*, a poor village.

From Montalto the traveller may ascend by the *Fiora* to the ancient *Ponte della Badia* and the site of *Vulci*, where thousands of Etruscan vases and other antiquities have been discovered since 1828. The ancient Etruscan city itself, the circumference of which is ascertained to have been 5 M., has disappeared with the exception of its tombs.

Beyond Montalto the country is undulating. We cross the small rivers *Arrone* and *Marta*, the outlet of the Lake of Bolsena.

144 $\frac{1}{2}$ M. *Corneto*. On a hill (350 ft.) 1 $\frac{1}{2}$ M. to the left of the station (seat in a carriage $\frac{1}{2}$ fr.) is the antiquated town of *Corneto* (*Alb. & Tral. Grassi*, fair), with numerous towers and a population of 5000. The town sprang up at the beginning of the middle ages near the ruins of the ancient Etruscan town of *Tarquini*, to which fact it owes its modern official name of *Corneto Tarquinia*.

The handsome but unfinished Gothic *Palazzo Vitelleschi*, in the main street, immediately to the left of the gate, was erected by Cardinal Vitelleschi in 1437. — On the N. buttress of the plateau on which the town stands is the imposing *Castello* of Countess Matilda, containing the recently restored church of **S. Maria in Castello*, begun in the 11th cent., with a façade dating from 1121. This church (key kept by the keeper of the Museo) contains a tabernaculum of 1168 and a pulpit of 1209. — Adjacent is *Scappini's Ceramic Factory*.

The smaller Romanesque churches of *S. Anastasia*, *S. Salvatore*, *S. Martino*, and *S. Pancrazio* have all been more or less restored. Adjoining the last is the old *Palazzo Municipale*, with three of its original eight towers. On a height above the town is the Gothic church of *S. Francesco*. — A genealogical tree 'al fresco' in the new *Palazzo Comunale*, professing to trace the origin of the place to a remote mythical era, shows an amusing disregard for history.

The lower story of the **Museo Municipale* contains a number of sarcophagi, the most interesting of which is the so-called 'Sarcophago del Magnate', embellished with reliefs (battles of Amazons) and with handsome polychrome figures on the lid. On the upper floor are smaller antiquities, vases, gold ornaments, weapons, etc. Among these are an antique set of false teeth (3rd room), and a fine painted bowl, which bears the names of *Oltos* and *Euxitheos* as the artists and represents the Arrival of *Bacchus* in

Olympus, the types of the deities recalling the character of pre-Phidian art. The last rooms contain the products of the excavations carried on since 1881 in the oldest part of the Necropolis. The pottery is of the rudest description and evidently produced without the aid of a wheel. Four cinerary urns in the form of huts give us an idea of the Italian dwelling of the period. The conical helmets, with bars at the top, were evidently imported; their type seems to have served as a model for the 'Apices', or caps of the Roman priests. Among the remaining contents are Carthaginian scarabæi and idols in fused glass. The keys of S. Maria in Castello and of the Museum are kept by *Frangioni*, the custodian of the Necropolis of Tarquinii (fee 1 fr.).

The *Palazzo Bruschi* contains a very fine collection of Etruscan antiquities, formed by the mother of the present count; and a few Etruscan and Roman relics are also preserved in the *Giardino Bruschi*, outside the town. — Corneto commands a fine view of the sea with Monte Argentario and the neighbouring islands, and also an interesting survey of the bleak environs.

On the *Turchina*, a stony hill opposite, separated from *Montarozzi*, the hill of the tombs, by a ravine, lay *Tarquinii*, a town with walls about 5 M. in circumference, anciently one of the twelve Etruscan capitals, and remarkable for the influence which it exercised on the development of the national religion of Etruria. It participated in the war of the Etruscan confederation against Rome, but was compelled to surrender after the Samnite war and to receive a Roman colony. The town continued to flourish during the empire, but subsequently declined and was devastated by the Saracens; it was, however, inhabited down to 1307, when its last remains were totally destroyed by the inhabitants of Corneto. No ruins are now visible save the scanty vestiges of walls and foundations. Of its seaport *Gravisca* a few relics on the right bank of the *Marta*, $1\frac{1}{2}$ M. from its mouth, still remain.

TOMBS. The principal interest attaching to Corneto is derived from its tombs, the "NECROPOLIS OF THE ANCIENT TARQUINII, which spreads over a great part of the hill upon which the town itself stands. The keys are kept by the keeper of the Museo (fee $1\frac{1}{2}$ -2 fr., for a party more in proportion; carriage, hardly necessary, bargaining advisable). The Necropolis was accidentally discovered in 1823 by Carlo Avvolta, a native of Corneto, who while digging penetrated into a tomb, and through the aperture beheld a warrior extended, accoutred in full armour. The influence of the air caused the body to collapse after a few minutes' exposure. Even in ancient times the tombs were frequently plundered for the sake of the precious trinkets they contained, and modern excavations have despoiled them of every movable object which remained. A visit to them is nevertheless extremely interesting to those who desire to form an idea of the civilisation, art, and religion of the Etruscans; and for this purpose the tombs of Corneto are well adapted owing to the good preservation of their paintings. The decoration of the chambers is in a style that was prevalent chiefly in the towns of southern Etruria, and indicates a close relationship to Hellenic art. The *Tumuli* which externally distinguished the tombs have in the lapse of ages been entirely destroyed; the subterranean chambers now alone remain, of which the following are the most interesting: —

No. 4. *Grotta della Caccia del Cignale* (boar-hunt), or *Grotta Querciola*. The faded paintings, copied in the Museo Gregoriano (p. 316), represent a banquet with music and dancing, and a boar-hunt. — Opposite to this tomb —

No. 5. *Grotta del Convito Funebre*, or *del Triclinio*, also with the representation of a banquet. The admirable drawing bears witness to the in-

fluence of the best period of archaic Greek art. The men here, as in all the others, are coloured dark red, the women sketched in outline on the walls in whitish colours.

No. 8. *Grotta del Morto*, small; mourning for the deceased, and dancers.

No. 11. **Grotta del Tifone*, more extensive, supported in the centre by a pillar, on which are Typhons, or winged genii of death terminating in serpents. The sarcophagi bear Latin as well as Etruscan inscriptions, a proof that they belong to a comparatively recent epoch. To the right on the wall are souls escorted by genii; under them is Charon with the hammer.

No. 12. *Grotta degli Scudi*, with banquetting scenes.

No. 13. *Grotta del Cardinale*, the most spacious tomb of Tarquinius, supported by four pillars, opened last century; colours almost entirely faded.

No. 14. **Grotta dell' Orco* or *del Polifemo*: in the anterior chamber, a banquet; in the one beyond it a scene from the infernal regions, with Pluto, Proserpine, Geryon, Tiresias, Agamemnon, Memnon, and Theseus; in a niche in this chamber is Ulysses blinding Polyphemus. — The paintings here exhibit unmistakable Greek influence.

No. 15. *Grotta dei Vasi Dipinti*, and No. 16. *Grotta del Vecchio*, with banquets and dances, both not later than the first half of the 5th cent. B. C.

No. 18. *Grotta delle Iscrizioni*, so called from the numerous Etruscan inscriptions, with warlike trials of skill.

No. 19. **Grotta del Barone*, so called from the Hanoverian ambassador Baron Kestner, by whom it was opened, contains warlike games, riders, etc., partly in the archaic style; colours well preserved.

No. 20. *Grotta delle Bighe*, discovered in 1827 by Baron Stackelberg. A copy of the paintings (funeral games and dances) is preserved in the Vatican. Adjacent —

No. 21. *Grotta del Mare*, small, with sea-horses.

No. 23. *Grotta degli Auguri* (with funeral games; a criminal with veiled head fighting with a large mastiff, hounded on by a figure in a mask), of the same date as Nos. 15 and 16.

From Corneto to (16 M.) *Toscanella* (p. 73) a diligence runs thrice a week (carriage 8 fr.).

The train skirts the foot of the hill of Corneto, which remains visible for a long time. To the right, farther on, is the insignificant *Porto Clementino*, which is entirely abandoned in summer on account of the malaria. The horizon is bounded inland by the mountains of *Tolfa* (p. 7), which yield an abundance of alum and sulphur. The line crosses the small river *Mignone*, at the mouth of which stands the *Torre Bertaldo*, where, according to a legend, an angel dispelled St. Augustine's doubts respecting the Trinity.

157 M. **Civita Vecchia**. — Halt of 5-14 min.; **Railway Restaurant*.

Omnibus to the town (within a few minutes' walk) 25 c.; one-horse carriage $\frac{1}{2}$ fr., two-horse 1 fr.; porter for a box 40 c.

Hotels: **ORLANDO*, to the right at the entrance of the town, a large hotel, expensive; *EUROPA*, moderate.

British Consular Agent, L. Sperandio; *American*, G. Marsanich.

Civita Vecchia, the seaport of Rome, with 12,000 inhab., the ancient *Centum Cellae* founded by Trajan, and sometimes called *Portus Trajani*, was destroyed by the Saracens in 828, but in 854 the inhabitants returned into the 'ancient city'. The fortifications, built in the 16th and 17th cent., were recently restored by the French. The entrance to the harbour, in front of which lies a small fortified island with a lighthouse, is defended by two strong towers. Visitors are permitted to inspect the Bagno, where the galley-convicts are at work. The town is uninteresting. The traveller may best spend a leisure hour in walking on the quay.

A good road leads from Civit  Vecchia to the volcanic mountains of *La Tolfa* (2040 ft.) and the loftily-situated village of that name, in the vicinity of which are extensive mines of alum. The scenery is picturesque, and the locality interesting to geologists. Some mineral springs, with the ruins of ancient baths (*Aquae Tauri*), lie about 3 M. from Civit  Vecchia.

FROM CIVIT  VECCHIA TO ROME. The best views are on the right till Rome is approached, and then on the left. The line traverses a dreary tract, running parallel with the ancient *Via Aurelia* near the sea-coast as far as Palo. On clear days the Alban and Volscian Mts. are visible in the distance, and still farther off the promontory of Circeii. 163 M. *Santa Marinella* possesses a medi val castle rising above a small bay. — 166 M. *Santa Severa*, a picturesque baronial castle, formerly the property of the Orsini family, and now of the S. Spirito Hospital at Rome. Here in ancient times lay *Pyrgos* or *Pyrgi*, the harbour of the once powerful Etruscan city *Caere*, now *Cervetri* (p. 392), situated on a height, 6 M. to the left.

171 M. *Furbara*. The solitary towers on the shore were erected in the middle ages for protection against the dreaded Turkish corsairs.

177 M. *Palo*, the junction of a branch-line (opened in Nov., 1889) to Trastevere, with a ch teau and villa of the Odescalchi, occupies the site of the ancient *Alsium*, where Pompey and Antoninus Pius possessed country-residences. Relics of antiquity now scarce. The sea-baths of *Ladispoli*, near Palo, recently founded by Prince Odescalchi (fine beach), attract a considerable number of summer visitors (special trains from Rome on Sun. and Thurs.).

181 M. *Palid ro* lies on the river of that name, which has its source on the heights near the Lago di Bracciano. The line now approaches the plantations of (186 M.) *Maccarese* to the right, supposed to be the ancient *Fregenae*, which lay near the mouth of the *Arrone*. The *Lago di Ponente* or *Stagno di Maccarese* is now skirted.

193 M. *Ponte Gal ra*, whence a branch-line diverges to *Porto* and *Fiumicino* (p. 393). Near (201 M.) *Magliana* the Tiber becomes visible, and the line follows its course (comp. Map, p. 334). A freer view is now obtained of the extensive *Campagna di Roma*; to the right, in the background, the Alban Mts. (p. 363; comp. panorama, p. 328) and to the left the Sabine Mts.; in the foreground is the grand basilica of *S. Paolo fuori le Mura* (p. 352). The train crosses the Tiber by an iron bridge and skirts the S.E. walls of Rome.

207½ M. *Rome*. — Arrival, see p. 111.

2. From Leghorn to Volterra and Colle.

A visit to Volterra, the antiquities of which are interesting, is best accomplished from Leghorn. RAILWAY vi  Cecina to Volterra station, 51 M., in 3-3¼ hrs.; express to Cecina (no through-connection) 6 fr. 35. 4 fr. 45 c.; ordinary trains 5 fr. 95., 4 fr. 15., 2 fr. 65 c.; from Cecina to Volterra station 3 fr. 40., 2 fr. 40., 1 fr. 55 c. — DILIGENCE from the station to Volterra in 2 hrs. (fare 1½ fr.; one-horse carr. 10 fr.). Those who intend to continue their journey southwards by the Maremma line should leave their luggage at Cecina. — DILIGENCE to Colle twice a week only; one-horse carriage about 12 fr.

Volterra may also be reached from *Pontedera*, a station on the Florence and Pisa line, by driving up the valley of the Era (5-6 hrs.).

FROM LEGHORN TO VOLTERRA. To (32 M.) *Cecina* (*Maremma Railway*), see pp. 1, 2. The branch-line to Volterra ascends hence on the right bank of the *Cecina*, traversing a district of great mineral wealth. — $5\frac{1}{2}$ M. *Riparbella*; $10\frac{1}{2}$ M. *Casino di Terra*; 15 M. *Ponte Ginori*.

19 M. *Volterra*. The station is situated at the foot of the lofty hill on which the town lies. The extensive salt-works (*Le Saline*) in the vicinity supply the whole of Tuscany with salt.

The following excursion, for which a carriage may be hired at Volterra Station, is interesting to geologists. We first drive to *Pomarance*, a pleasant town, famed in the Renaissance period for its earthenware, with a large château of Count Larderello, and in about 3 hrs. reach *Larderello* on the *Monte Cerboli*, the central point of the boracic acid works belonging to the Larderello family, which are politely shown to visitors. The excursion may be extended towards the S., by *Bagno a Morbo* (with springs, good for gout, used perhaps by the Romans), *Castelnuovo*, *Sasso*, and *Monterotondo*, to *Massa Marittima* (p. 2), a drive of 3 hrs. more. Near *Sasso* and *Monterotondo* in particular the country is covered with clouds of smoke, and the hot surface of the earth with incrustations of sulphur, sulphate of iron, &c. Near *Monterotondo* is the hot *Lago Zolforeo*, a small lake strongly impregnated with boracic acid, which is obtained from it by evaporation by M. Duval, a Frenchman. Count Larderello's works yield about 1650 tons, and M. Duval's 500 tons annually, and the whole quantity is sent by contract to England, where it is chiefly used in the manufacture of glass and pottery. The *lagoni*, or pools through which the *soffioni* or jets of boracic acid in the form of steam bubble up, are all, with the exception of those of *Travale*, in the region of the *Cecina* and *Cornia*, and most probably have a common volcanic origin.

The road from the station to (5 M.) Volterra ascends (diligence $1\frac{1}{2}$ fr.). The country presents a peculiarly bleak appearance. The effect of the rain on the soft and spongy soil is most prejudicial to agriculture.

Volterra. — *ALBERGO NAZIONALE, R. $1\frac{1}{2}$ -2 fr.; UNIONE. — *Cafè Etrusco*, in the market-place.

The celebrated *Alabaster Works* of Volterra afford occupation to nearly two-thirds of the population, but most of the patterns are unfortunately in very bad taste. The ordinary kinds of alabaster are found in the vicinity, the more valuable in the mines of *Ia Castellina*, to the S. of Leghorn. The traveller should visit the interesting work-shops, where souvenirs may be purchased far more cheaply than at Florence or Leghorn.

Volterra (1805 ft.), chief town of an official district and one of the most ancient Etruscan cities, is an episcopal residence with 5700 inhab. (commune 14,000 inhab.), commanding in clear weather charming prospects as far as the heights of Pisa, the Apennines, and the sea with the islands of Gorgona, Elba, Capraja, and Corsica.

Volterra (the ancient *Volaterræ*, Etruscan *Velathri*) was one of the twelve ancient confederate cities of Etruria, and was so strongly fortified that during the civil wars it withstood a siege by Sulla's troops for two years. It afterwards became a Roman municipium, but gradually fell to decay and was totally destroyed in the 10th century. It was re-erected under the Æthos, but does not now cover one-third of its ancient area. In the middle ages it was a free town, until it became subject to Florence in 1361. The last revolt of the inhabitants against the Florentines terminated on 17th June, 1472, when the town was captured and ruthlessly pillaged.




VOLTERRA.

1: 15,700



1. Antico Condotto
2. Festiche di Muri ant.
3. Piazza di S. Pietro
4. " " S. Agostino
5. " " S. Michele
6. " " S. Giovanni
7. " " S. Francesco
8. Cattedrale
9. S. Michele
10. S. Francesco
11. S. Filippo
12. Conservatorio di S. Lino
13. Convento delle Monache di S. Lino
14. Collegio delle Scuole Pie
15. Spedale di S. M^{re} Maddalena
16. Mensa Vescovile
17. Amministrativione del Sale
18. Pretura
19. Pal. dei Priori
20. Pal. Taguassi Museo nazionale



Among the ANTIQUITIES the ancient ***Town Walls**, once upwards of $4\frac{1}{2}$ M. in circumference, and nearly three times as extensive as those of Fiesole and Cortona, are especially worthy of notice. Their dimensions (40 ft. in height, 13 ft. in thickness) and construction of horizontal courses of sandstone blocks (panchina) are best inspected outside the Porta Fiorentina and in the garden of the monastery of Santa Chiara. One of the ancient gateways, the ***Porta dell' Arco**, 20 ft. in height, is also still in existence. The corbels are adorned with almost obliterated heads. The *Porta di Diana* ('*il Portone*'), another gateway, outside the Porta Fiorentina, has been much altered. Outside the same gate, below the burying-ground, is situated the ancient *Necropolis*, about halfway up the hill, at the place now called *S. Marmi*. A number of the curiosities in the museum were found here, but the tombs have all been closed up again.

The *Piscina*, outside the castle, a reservoir resting on six columns, is only shown by permission of the bishop, and is reached by a long ladder. The *Thermæ*, near the Fonte S. Felice, are of Roman origin. Traces of an *Amphitheatre* near the Porta Fiorentina.

THE PALAZZO DEI PRIORI or PALAZZO PUBBLICO (Pl. 19) in the *Piazza*, a handsome edifice, begun in 1208 and completed in 1257, is unfortunately somewhat modernised; the exterior is adorned with mediæval coats-of-arms. It contains a collection of pictures, of which the following are the most important: *Signorelli*, Madonna and saints, 1491 (much injured); *Dom. Ghirlandajo*, Christ in glory (ruined by restoration in 1874), and a Madonna, by the same.

Adjoining, to the right, is the entrance to the ***CATHEDRAL** (Pl. 8), consecrated in 1120 by Pope Calixtus II., and enlarged in the 13th cent. by *Niccolò Pisano*. The façade dates from 1254.

INTERIOR. Above and beside the entrance are reliefs from the life of St. Octavianus (14th cent.); the pulpit is adorned with sculptures of the end of the 12th century. The two angels on the high-altar are by *Mino da Fiesole*. The sarcophagus of St. Octavianus is by *Raffaele Cioli* (1527); the elaborate roof by *Fr. Cipriani* (1570). — In the S. transept is a wooden group (13th cent.) of the *Descent from the Cross. The chapel of S. Carlo, opposite, contains on the left an *Annunciation by *Signorelli* (1491), of rich colouring and attractive grace; above the altar, Mary Magdalene by *Camillo Incontri* (1634); on the right, *Ben. di Giovanni*, Nativity, with predelle by *Ben. Gozzoli*; and *Rosso Fiorentino*, Descent from the Cross (unfinished).

Opposite to the cathedral rises the baptistery of S. GIOVANNI (Pl. 6), an octagonal church, supposed to date from the 7th cent., and occupying the site of an ancient temple of the sun. The portal dates from the 13th century. To the left of the entrance is an ancient sarcophagus, with a relief of Narcissus. The fine arch of the high-altar is by *Balsimelli da Settignano* (16th cent.), the octagonal font by *Andrea Sansovino* (1502), and the ciborium by *Mino da Fiesole* (1471).

S. LINO (Pl. 13), a church founded in 1480 by *Raffaele Maffei*, contains the tomb of that scholar, with a recumbent statue by *Silvio da Fiesole*.

In the *Via Ricciarelli* is the house in which *Daniele da Volterra*, the celebrated pupil of Michael Angelo, was born in 1509 (he died at Paris in 1567). The house still belongs to the family of Ricciarelli, who possess the artist's *Elias.

S. FRANCESCO (Pl. 10), with the Gothic chapel of the *Confraternità della Croce di Giorno* of 1315, contains frescoes from the life of the Saviour and the legend of the Cross by *Cienni di Francesco di Ser Cienni* of Florence, 1410.

The most interesting object in Volterra is the *MUSEO NAZIONALE, a valuable collection of inscriptions, coins, bronzes, statues, and vases, now contained in the *Palazzo Tagassi* (Pl. 20), *Via Vittorio Emanuele*. Admission 1 fr., Sun. free.

The museum, established in 1731, and greatly enriched by the collections of the erudite *Mario Guarnacci* in 1761, has lately been admirably arranged by *Cavaliere N. Maffei*. Seven rooms on the lower floor and as many on the upper are occupied by the collection of *Cinerary Urns* (upwards of 400). These are generally about 3 ft. in length, and date from the latest period of Etruscan art, i.e. the 3rd or 2nd cent. B.C. The subjects are more interesting than the execution, which is for the most part very mediocre. A few of them are composed of terracotta and sandstone, but most of them are of the alabaster of the environs. On the lid is the greatly reduced recumbent effigy of the deceased; the sides are adorned with reliefs, and some of them bear traces of painting and gilding. The representations on the urns are partly derived from the peculiar sphere of Etruscan life, partly from Greek mythology. From the former, parting scenes are the most frequent; the deceased, equipped as a rider, is escorted by a messenger who bears a long sack containing provisions for the journey or is accompanied by Charon with the hammer. Sacrifices and funeral-processions occur frequently, as well as banquets, races, contests of skill, etc. Greek mythology has supplied an abundant selection of subjects, e.g. Ulysses with the Sirens and with Circe, the abduction of Helen, death of Clytemnestra, Orestes and the Furies, the Seven before Thebes (the gate a copy of the *Porta dell' Arco*, p. 9), Polynices and Eteocles, Œdipus with the Sphinx, Œdipus slaying his father. There is a singular blending of luxuriance and melancholy in the subjects and treatment of these works, and the same peculiarity is often observed in the subsequent development of Etruscan art. — Five other rooms contain marble sculptures (archaic sandstone relief of a warrior), vases (mostly of a later style), coins, bronzes, utensils, gold ornaments, and fine glass vessels. — In the third story are the *Archives* and the *Library*, containing 13,000 vols., and a collection of coins and seals. On the staircase are a frieze in relief (9th cent.) from S. Giusto, an inscription of Gundibert, King of the Lombards, and other mediæval sculptures.

The CITADEL (*Fortezza*) consists of two parts, the *Cassero* or *Rocca Vecchia*, erected on the ancient town-walls in 1343 by Walter de Brienne, Duke of Athens, and the *Rocca Nuova*, built by the Florentines after the capture of the town. At the same time they constructed the prison *Il Mastio* for the incarceration of political offenders, where the mathematician *Lorenzo Lorenzini* was confined as a suspected person by the Grand-Duke Cosimo III. for 11 years (1682-93). The citadel, now a house of correction, may be visited with permission of the Sotto Prefetto.

The *Palazzo Maffei-Guarnacci*, opposite the church of S. Michele, with its three towers, the oldest dating from the 13th cent., contains pictures and a valuable collection of letters of *Salv. Rosa*.

The Gothic *Palazzo Inghirami* contains a small collection of pictures, comprising a *Portrait of the learned Fedra Inghirami, an original work of *Raphael* (replica in the Pitti Gallery at Florence).

The *Casa Ducci* bears the Roman epitaph of a boy, five years of age, probably a member of the family of the poet *Persius*, who was born at Volaterræ in A.D. 34.

Outside the Porta Pisana is the ruined Romanesque church of *S. Stefano*, near which are a fountain and a Roman marble portrait-statue, known as the *Protomazio*, from a corruption of Prato Marzio, the ancient name of the place. — Farther from the town, between the churches of *S. Giusta* and *La Badia*, lies a deep ravine called *Le Balze*, which was comparatively recently formed by the action of water and continues to increase. Several buildings have already been undermined and destroyed, and the celebrated Camaldulensian abbey of *San Salvatore*, founded in the 11th cent., is threatened with the same fate.

In the valley to the E. is the convent of *S. Girolamo*, the vestibule chapels of which contain terracotta altar-pieces from the studio of the *Della Robbia*'s, one representing St. Francis with SS. Clara and Louis, another the Last Judgment (1501). In the church is an Annunciation by *Benvenuto di Giovanni*. — Farther on is the *Villa Inghirami* (fine view), with some *Etruscan Tombs*, in which the burial-urns are still *in situ* (the gardener supplies a light, 1/2 fr.). Hence the rock-caves named *Le Buche de' Saraceni* may be visited.

A pleasant EXCURSION may be made to the copper-mines of *La Cava di Caporciano*, near *Monte Catini*, 10 M. from Volterra. The road leads across the hill of *La Bachelona* to *Monte Catini* on the summit of the *Scaligile*, a mountain of volcanic origin. The square tower of the old castle commands an extensive prospect. The mines have been worked since the 15th cent., and the operations were very successful till within the last few years, but since 1870 the yield has fallen off. The present possessor is Count Buturlin. The mineral was found in pockets or clusters, between serpentine, known here as *gabbro verde*, and a peculiar species of red rock, *gabbro rosso*. The whole vicinity is extremely interesting for geologists. A number of peaks, such as *Monte dell' Abete*, *Poggio alla Croce*, and *Monte Massi*, consist of *gabbro rosso*, which has been upheaved at a comparatively recent period through the surrounding sand and limestone. The view from **Monte Massi* (1910 ft.) or from *Poggio alla Croce* (1/2 hr. from *Monte Catini*) extends from the heights near *Massa* and *Carrara* towards the N. to *Monte Amiata* on the S., and embraces the sea with the islands of *Elba*, *Capraja*, and *Corsica*.

FROM VOLTERRA TO COLLE, 15 1/2 M. The high-road leads towards the E. through an undulating and attractive district. To the left is seen *S. Gimignano* (p. 14), to which a good road (fine views) diverges after 7 1/2 M. (reaching it after 11 M. more; pedestrians may take a short-cut, diverging 1 M. farther on, *vià Ranza* and *S. Donato*). To the right lies *Pomarance* (p. 8). *Colle*, see p. 13.

3. Elba and the Tuscan Islands.

A visit to *Elba*, which is strongly recommended to the scientific traveller and the lover of nature, is accomplished either from *Leghorn* or from *Piombino* (p. 2). Between both these points and *Porto Ferrajo*, the capital of the island, communication is kept up by the *Società Riunite Florio-Rubattino*. FROM LEGHORN to *Porto Ferrajo* every Sun. forenoon in 4 1/2 hrs., returning on Mon. forenoon. — FROM PIOMBINO to *Porto Ferrajo* every afternoon in 2 hrs., returning every forenoon. — A steamboat of the same company also makes a trip once weekly to the small neighbouring islands (*Linea Livorno-Porto-San-Stefano*).

About 4 M. to the W. of Leghorn rises the cliff of *Meloria*, where the Pisans were so signally defeated by the Genoese in 1283, that they never regained their former supremacy. Farther to the W. (21½ M. from Leghorn) is *Gorgona*, inhabited by fishermen, a sterile island, affording pasture to wild goats only. Between the latter and Elba lies (40 M.) *Capraja* ('island of goats', so called by the ancients also), with 2000 inhab., where wine is produced.

Elba, Lat. *Ilva*, Greek *Æthalia*, consisting of an imposing mountain-group, lies 5½ M. to the S.W. of Piombino (p. 2), beyond the islets of *Palmajola* and *Cerboli*. The *Torre di Giove*, situated on the highest point, serves as a landmark to sailors. The vessel rounds the *Capo della Vita* and enters the beautiful bay of *Porto Ferrajo* (Albergo delle Api, fair), the capital, enclosed amphitheatrically by mountains. The island was celebrated in ancient times for its iron ore; in the middle ages it was subject to the Pisans, then to Genoa, to Lucca, and to the Appiani of Piombino, and was finally presented by the Emp. Charles V. to the Grand-Duke Cosimo I. of Florence, who fortified the harbour of Porto Ferrajo in 1548. As the name of the town indicates, the mining and export of iron form the principal occupation of the inhabitants (22,000), others of whom are supported by the tunny and sardine fisheries. Elba has acquired a modern celebrity as the retreat of the dethroned Napoleon, from 5th May, 1814, to 26th Feb., 1815. The *Villa S. Martino*, the house occupied by the emperor, is still shown at Porto Ferrajo, on the height above the harbour, between the forts *Stella* and *Falcone*, which were erected by Cosimo I., and command a view of the bay in front, and of the sea in the direction of Piombino at the back. It contains several Napoleonic relics. Below, adjoining the harbour, is the *Bagno*, or prison, in which several hundred galley-convicts are confined. — The island is about 18 M. long, 6½ M. broad, and 90 sq. M. in area; it contains several fertile valleys, but lofty and precipitous mountains predominate. *Monte Capanne*, the highest point, near the village of *Marciana*, is 3300 ft. in height. The coast on the side next the mainland is less abrupt, and produces admirable wine and fruit, especially near *Capoliveri*, where excellent Aleatico is grown. — An excursion from Porto Ferrajo to the iron-mines is best made by taking a boat to the *Borgo dei Magazzini*, and walking or riding thence (horse there and back 3 fr.) over the hill to *Rio Castello* and on to *Rio Marina*, where a guide to the mines (scarcely necessary) may be obtained. The ferriferous strata lie on the surface, and are recognised at a distance by the reddish-black appearance of the hills. On the coast, to the S. of Rio Castello, lies the picturesque stronghold of *Porto Longone*, founded by the Spaniards.

About 7½ M. to the S. W. of Elba lies the island of *Pianosa*, the ancient *Planasia*, which, as its name indicates, is perfectly flat. To this island Agrippa Postumus, grandson of Augustus, was once

banished, and to him are referred the considerable Roman remains which still exist here. Farther to the S. (25 M. from Elba) rises *Monte Cristo*, consisting of granite-rock, 6 M. in circumference. It contains numerous springs, and the ruins of a monastery destroyed by pirates in the 16th century. The name is familiar through the well-known romance of the elder Dumas. Opposite the *Monte Argentario* (p. 3) and about 6 M. from the mainland is *Giglio*, Lat. *Igitium*, a considerable island containing a village and vestiges of Roman palaces. The highest point is 1630 ft. above the sea-level.

4. From Florence to Siena and Chiusi viâ Empoli.

114 M. RAILWAY. TO SIENA, 59½ M., in 3-3½ hrs.; fares 10 fr. 90, 7 fr. 65, 4 fr. 95 c. — From Siena to CHIUSI, 54½ M., in 2¾-4½ hrs.; fares 9 fr. 95, 6 fr. 95, 4 fr. 45 c. — No quick trains.

Florence, see *Baedeker's Northern Italy*. — 6 M. *S. Donnino*; the valley of the Arno expands. 7 M. *Signa*, with its grey pinnacles and towers, is famed for its straw-plaiting. The line crosses the *Ombrone*, which falls into the Arno, and enters the defile of the *Gonfolina*, which separates the middle from the lower valley of the Arno. Crossing the Arno, the train reaches (16 M.) *Montetupo*. Farther on we cross the small river *Pesa*.

20 M. **Empoli** (*Rail. Restaurant*, unpretending), a small town with 6000 inhab., with antiquated buildings and narrow streets, situated in a fertile district. Halt of 6-25 min.; passengers to Siena have often to change carriages. The main line pursues a W. direction towards Pisa and Leghorn; see *Baedeker's Northern Italy*.

The line to Siena traverses the fertile valley of the *Elsa*, on the right bank of the stream. To the right, on the hill, *S. Miniato dei Tedeschi*, picturesquely situated, with a lofty mediæval tower. 23 M. *Ponte a Elsa*; 26 M. *Granaiole*. 30½ M. *Castel Fiorentino*; the town, on the height to the left, is the principal place in the *Val d'Elsa*.

35½ M. *Certaldo*; the town, on the hill to the left, was the native place of *Giovanni Boccaccio*, who died here, 21st Dec., 1375, at the age of 62. His tomb in the church of *S. Michele e Giacomo (La Canonica)*, erected in 1503, was removed some time after 1783 and his bones scattered. The house of Boccaccio, now denoted by a tablet, was restored in 1823 by the Countess Carlotta Lenzone-Medici, and fitted up in the mediæval style. The remains of his monument were also brought hither.

43½ M. **Poggibonsi** (*Aquila*, opposite the station, tolerably comfortable); the town (4000 inhab.) lies to the right. On the hill above it rise the old castle and the monastery of *S. Lucchese*. In the church of the castle is an altar-piece and in the former refectory are frescoes by *Gerino da Pistoja*.

FROM POGGIBONSI TO COLLE, 5 M., railway in 26 min. (70, 40 c.).
Colle (*Alb. del Buon Soggiorno*, tolerable), generally called

Colle di Val d'Elsa to distinguish it from other places of the same name, is an old town with 1000 inhab., frequently mentioned in the history of the Renaissance. It now consists of two parts, *Colle Alto* and *Colle Basso*. The first of these contains the palaces of the old, but now greatly impoverished aristocracy; the house of the celebrated architect Arnolfo di Cambio; and the Cathedral, dating from the 13th cent., with a façade modernised in bad taste, a marble pulpit (of which the lower part belongs to the 13th cent., and the upper part, with reliefs of saints, to the 16th), and handsome carved choir-stalls and episcopal throne of the 17th century. At *Colle Basso* there are now important iron and glass works.

The interesting little town of *S. Gimignano* may be conveniently visited from Poggibonsi or Colle, from each of which it is about 6 M. distant. Carriages may be hired at the stations for 4 frs.

S. Gimignano (1180 ft.; *Albergo Leone Bianco*, Via S. Matteo, near the gate, well spoken of), an ancient and loftily situated town, with 8200 inhab., was a prosperous and independent place in the 13th and 14th cent., but in 1353, after having suffered terribly in consequence of the dissensions of the leading families of the *Salvucci* (Ghibellines) and *Ardinghelli* (Guelphs), it became subject to Florence. Its walls, its towers (whence the name 'S. Gimignano delle belle torri') and its streets, all carry us back to the middle ages. Perhaps no other town in Tuscany presents so faithful a picture of Dante's time. Architecture of the Gothic type prevails.

In the centre of the town is the PIAZZA DELLA COLLEGIATA, or *del Duomo*, with several important buildings.

The *PALAZZO PUBBLICO or *Comunale* was erected in 1288-1323.

The SALA DEL CONSIGLIO, on the second floor, contains a *Madonna with saints and angels, and the kneeling donor Podestà Nello dei Tolomei (1317), a fresco by *Lippo Memmi* of Siena; also pictures from suppressed monasteries in the neighbourhood: 8, 9. *Mainardi*, Madonnas; 13. *Filippino Lippi*, Annunciation (two round paintings); 16. *Fra Paolino*, Madonna; 18. *Pinturicchio*, Madonna with two saints. — To the left of the exit into the court is the CAPPELLA DEL PRETORE, or *delle Carceri* (now divided by a wall into two parts), containing a *Scene from the legend of St. Yvo, and allegorical figures of Truth, Prudence, and Falsehood, frescoes by *Sodoma*. There are also many traces of frescoes in other parts of the palace.

The *Torre del Comune* (160 ft.) is the highest of the 13 towers which still exist out of the original number of 50. The largest of its three bells dates from 1328.

Adjacent is the cathedral, usually called *LA COLLEGIATA, of the 12th cent., altered in the 15th by *Giuliano da Majano*, and now entirely modernised. It contains frescoes of the 14-15th centuries.

On the entrance-wall, *Martyrdom of St. Sebastian, a fresco of colossal proportions by *Benozzo Gozzoli*, 1465; Annunciation, two wooden figures (14th cent.) by *Martino Bartolomei* of Siena. In the N. aisle, scenes from the Old Testament (some in bad preservation) by *Bartolo di Fredi* of Siena, 1356; in the S. aisle, Life of Christ by *Barna da Siena*, 1380. In the nave, above the arch, Paradise and the Inferno, by *Taddeo Bartoli*. — The visitor should particularly notice the decorations in the last side-chapel to the right, the *CAPPELLA S. FINA, which contains the bones of this local saint, who

died at the age of 15 years. The chapel was designed by *Giuliano da Majano*; altar-piece (recently restored) by *Benedetto da Majano*. The two *Frescoes on the side-walls, representing the vision of the youthful saint and her burial, by *Dom. Ghirlandajo*, are among the finest works of that master, and combine a fresh and life-like style with majestic gravity. — In the choir, centre of the right wall, Coronation of the Virgin, an altar-piece by *Piero del Pollajuolo* of Florence, 1483; to the right of this, Madonna and four saints, by *Benozzo Gozzoli*; on the left wall, same subject by *Tamagni*; adjacent, *Marquetry ('intarsia') choir-stalls of 1490. — The ORATORIO S. GIOVANNI contains an Annunciation by *Dom. Ghirlandajo*, 1482, a work of no great importance.

Opposite the cathedral is the PALAZZO DEL PODESTÀ, with an imposing loggia (now a theatre). It is surmounted by the *Torre della Rognosa* or *dell' Orologio*, which indicates the height beyond which private individuals were prohibited from building.

The VIA S. MATTEO descends from the Piazza, passing the two towers of the Salvucci, to an ancient gateway, which marked the limits of the town until the 13th century. Immediately to the right in this street is the *Biblioteca Comunale* (librarian, Preposto Ugo Nomi), which contains 9000 vols. and 200 codices. One of its treasures is a copy of *Alciati's Emblemata* (Lyons, 1564), along with which are bound up several interesting autographs, including those of Luther and Melancthon. Adjacent is a small Museum. — Farther on are *S. Bartolo* (originally S. Matteo), a church of the Knights Templar, with a 12th cent. façade, and the *Palazzo Pesciolini*. — In the VIA NUOVA, which diverges to the right, are the church of *S. Chiara* on the left, and farther on, on the right, the Hospital, with numerous majolica vases, and the church of *S. Girolamo* (behind the high-altar, Madonna and saints by *Vincenzo Tamagni*, 1522, with a glory by a later painter), and finally, to the left of the gateway, the 12th cent. church of *S. Giacomo*, another church of the Templars, with frescoes by a Siennese master of the 13th century.

The Via delle Romite, diverging from the Via Nuova at *S. Chiara*, leads to *S. AGOSTINO, begun in 1280 (chief entrance usually closed; sagrestano, Via Nuova 17).

This church owes its fame to the *Frescoes in the Choir by *Benozzo Gozzoli* (1465), where the master has portrayed the life of St. Augustine in 17 scenes, from his school-days to his death. Though not of uniform excellence, nor in equally good preservation, these pictures alone repay a visit to S. Gimignano (the finest are: St. Augustine as teacher of rhetoric in Rome; Death of St. Monica; *St. Augustine on the bier). — The CAPPELLA S. GUGLIELMO, to the right of the choir, contains a Nativity and Death of the Virgin, by *Bartolo di Fredi*, in which several touches of real Italian life are traceable. — To the left, in the CAPPELLA DEL S. SAGRAMENTO, are frescoes by *Vincenzo da S. Gimignano*. — On the N. side of the church, St. Geminianus and three worshippers, a fresco by *Seb. Mainardi*, a pupil of *Dom. Ghirlandajo*; farther on, St. Sebastian, the deliverer from the plague, the effects of which are symbolised by flashes of lightning, by *Benozzo Gozzoli*, 1464, of less importance than the frescoes in the choir. To the right of the principal entrance: *Altar-piece (St. Bartoldus) by *Benedetto da Majano*, 1494; under the organ are frescoes by *Seb. Mainardi*, representing Saints in simple groups.

From S. Agostino we return to the market-place, which is ad-

joined by the *PIAZZA DELLA CISTERNA*, distinguished by the two low towers of the *Ardinghelli*, on the right. The *Via del Castello* leads to the left to the church of *S. Lorenzo in Ponte*, with a portico, now built up, of the 13th century. — The terracotta ornamentation of the windows of the buildings, many of which are in the form of a horseshoe, should be observed.

From the *Piazza della Cisterna* the *Contrada di San Giovanni* descends to the right to the *Palazzo Pratellesi*, in which the principal saloon of the upper floor contains a Madonna with saints, a fresco by *Tamagni*. Farther on, to the left, are *S. Giovanni Evangelista*, a Johannite church of the 12th cent., and, in the street, a figure of the Madonna, by *Mainardi*.

A private garden at the *Fortezza*, the highest part of the old fortifications (ascend to the right from *La Collegiata*), commands a fine view of the town and neighbourhood.

We may drive in $\frac{3}{4}$ hr. to the venerable church of *S. Maria Assunta di Callori*, or *Cellole*, situated outside the *Porta Matteo*, and dating from the 11th, or perhaps from the 10th cent., containing remarkable capitals and curious ornamentation in the apse. Fine view.

Beyond *Poggibonsi* the RAILWAY begins to ascend considerably. To the right, *Staggia* with a mediæval château; farther on, to the right, the ancient and picturesque château of *Monte Riggioni*. The train then passes through a long tunnel (3 min.).

59 $\frac{1}{2}$ M. *Siena*, see p. 20.

Siena is a terminal station, loftily situated, from which the train backs out. On the journey to *Orvieto*, the train returns part of the way to *Empoli*, and then diverges at an acute angle towards the S.E. We traverse the hills which form the watershed between the *Ombrone* and the valley of the *Chiana*. Several tunnels. 65 M. *Arbia*. This district is one of the bleakest in Italy, the chief features being grotesquely shaped hills of sand, and barren fissured mountains, interesting to the palæontologist only.

79 M. **Asciano**; the pleasant little town (*Alb. del Sole*, clean; 7400 inhab.), 1 $\frac{1}{2}$ M. to the right of the railway, possesses fortifications constructed by the *Siene*se in 1351, and several handsome churches with pictures of the early *Siene*se School.

Asciano is the most convenient starting-point for a visit to the famous, but now suppressed, Benedictine convent of ***Monte Oliveto Maggiore** (6 M.; a drive of 1 $\frac{3}{4}$ hr. there, and 1 $\frac{1}{2}$ hr. back; carriages at the *Alb. del Sole*, fare 10-12 fr.). The road, leading by *Chiusure*, is rough and more suitable for walking.

Visitors apply beforehand to the 'Ispettore' of the *Istituto delle Belle Arti* at *Siena* (p. 32), from whom they receive a 'permesso' to present to the 'Soprintendente' at the monastery. Those who have not time to send this two days in advance should provide themselves with eatables for one day. Ordinary visitors are not allowed to stay more than two days at the convent ('pens'. 5 fr.).

The convent, founded in 1320 by *Bernardo Tolomei* and afterwards greatly enriched by donations, still affords an excellent idea of a great

establishment of the kind. The monks must have been wonderfully energetic to have been able to transform the sterile chalk-soil here into a smiling oasis. Æneas Sylvius Piccolomini (Pius II.; p. 28) gives an interesting description of the monastery in his 'Commentaria'.

The walls of the MONASTERY COURT are adorned with celebrated *Frescoes by *Luca Signorelli* (1497) and *Ant. Bazzi*, called *Sodoma* (1505), representing scenes from the legend of St. Benedict. The order of the pictures does not correspond with the date of their execution. The series begins with the first picture on the wall opposite the entrance (adjoining the entrance to the church), representing St. Benedict's departure from home, by *Sodoma*. The earliest part of the series are the frescoes on the entrance-wall, executed by *Signorelli*, eight in number: Totila kneeling to the saint; Soldier in disguise, attempting to deceive the saint; Temptation of the fasting monk; Punishment of two monks addicted to dainties; Resuscitation of a dead man whom Satan has thrown from a wall; Exorcism of Satan; Overthrow of the idol; Resuscitation of a youth killed by the fall of a house. — The 'Sending forth of Missionaries', on the left of the corner to the right, is by *Riccio*, but all the other pictures are by *Sodoma*, whose sense of beauty is everywhere apparent, though he is doubtless far inferior to *Signorelli* in depth and excellence of conception and execution. In the first pictures by *Sodoma* we can trace a resemblance to the frescoes of *Pinturicchio* in the Cathedral library at Siena, and, in the others, features that recall *Leonardo da Vinci*. — The CHURCH (entrance to the left of the monastery court), which was modernised last century, contains little to detain us beyond the handsome choir-stalls and reading-desk, in inlaid work, by *Fra Giov. da Verona* (1502-5). — In the *Libreria* are a door and a cabinet, also beautifully inlaid by the same master. — The visitor should notice the extensive stables at the back of the monastery, the different sections of which bear tablets with the names of the chief towns of Italy, in order that guests might know on arriving where to put up their horses.

The Emperor Henry VII. died, Aug. 24th, 1313, at *Buonconvento*, 4½ M. to the S.W., on the *Arbia*. The churches contain a few ancient pictures of the Sienese school.

FROM ASCIANO TO GROSSETO, 59½ M., branch-line in 3½ hrs. (fares 11 fr., 7 fr. 70, 4 fr. 95 c.) — 8 M. *S. Giovanni d'Asso* (tolerable inn). The Canonica contains six small and ancient paintings of the Sienese school. Mte. Oliveto is reached hence in 1½ hr. (p. 16; a car with one horse may be obtained). — 14 M. *Torrenieri*, on the old road from Siena and Buonconvento (see above), viâ *S. Quirico*, *Radicefani*, and *Bolsena* (p. 65), to Rome.

— [About 5½ M. to the S.W. of *Torrenieri* (omnibus 2 fr.) lies **Montalcino** (*Albergo del Giglio*, tolerable, bargaining necessary), a town which early in the middle ages belonged to the abbey of *S. Antimo*, and afterwards to *Siena*. In the *Palazzo Municipale* is the *Cappella delle Carceri*, which contains a small collection of pictures from suppressed monasteries, including a Descent from the Cross (1382) and a Coronation of the Virgin (1388) by *Bartolo di Fredi* of *Siena*. The Cathedral was begun in 1818. The dissolved *Franciscan Monastery* is now a hospital. Over the chief entrance of the church belonging to it is a group of the Madonna, John the Baptist, SS. Peter and Sebastian, of the school of *Della Robbia* (1507). A room adjoining the sacristy is adorned with frescoes of the latter part of the 15th cent., and the monastery court contains others dating from 1438. Fine view from the piazza adjacent to the modern church of the Madonna, on the E. side of the town. — The railway-station of *Monte Amiata* (p. 18) lies about 8 M. to the S.E. of *Montalcino*. To the N. of *Castelnuovo dell'Abate*, within about 2½ M. of *Monte Amiata*, is *S. Antimo*, which was an independent abbey down to the 13th century. The handsome church was built of white alabaster and travertine in the 11th cent., and its rich portal dates from 1292.

About 4 M. to the S.E. of *Torrenieri* (omnibus 1½ fr.) lies *S. Quirico* (*Albergo del Lepre*, tolerable), which was the residence of an imperial governor during the Hohenstaufen régime and was fortified by *Siena* in 1472. The handsome **Collegiate Church* in the Lombard style was founded

in the 8th cent.; highly ornate porch of 1298; interior disfigured in the 17th cent.; choir-stalls of the 16th century. The adjacent *Misericordia* church contains a high-altar-piece by *Sodoma*. The *Palazzo Chigi*, erected in 1685-87, deserves a visit (keys at the *Fattoria Chigi*). The *Orti Leonini* (keys at the same place), a neglected park of the 16th cent., adjoining the town-wall, afford an admirable view. — The hot *Baths of Vignoni*, $3\frac{1}{2}$ M. to the S. of Quirico, were much frequented in ancient times, and again during the Renaissance period, but are now neglected. The ante-chamber of the bath-house contains an ancient votive stone. Among the famous mediæval visitors were St. Catharine of Siena and Lorenzo il Magnifico. — From S. Quirico to Pienza (p. 20) $4\frac{1}{2}$ M.] —

21 M. *Monte Amiata*, the best starting-point for a visit to the mountain of that name, the highest in Tuscany, lies $2\frac{1}{2}$ M. to the S.E. of *Castelnovo dell'Abbate* (p. 17) — [By omnibus in 3 hrs. to *Castel del Piano* ($2\frac{1}{2}$ fr.; *Locanda Amiatina*), where a guide may be obtained at the Municipio; thence on horseback in $3\frac{3}{4}$ hrs., or on foot in $4\frac{1}{2}$ hrs., to the summit of the **Monte Amiata* (5645 ft.), which affords an admirable survey of the whole country between the Tyrrhenian Sea, the Apennines, and the Ciminian Forest (p. 73). The rock-formation is volcanic and interesting to geologists. A pleasant return-route leads through beautiful woods to *Vivo*, a suppressed Camaldulensian monastery, now the property of Count Cervini, where a one-horse carriage may be hired of the miller. — From *Vivo* to stat. *Monte Amiata* 11 M., or to *Torrenieri* 17 M. The latter road leads by *Castiglione d'Orcia*, not far from the Baths of Vignoni (see above), and by S. Quirico (p. 17).] —

28 M. S. *Angelo* and *Cinigiano*. The train follows the right bank of the *Orcia*, the E. affluent of the *Ombrone*, and crosses the latter. — $32\frac{1}{2}$ M. *Monte Antico*. At *Paganico* the train quits the *Ombrone* and begins to thread its way among the hills. 42 M. *Rocca Strada*, a village (1640 ft.) on the right; then *Sticciano*. At (53 M.) *Monte Pescali* the line unites with the *Maremma Railway*, to the N. of *Grosseto* (p. 3).

$82\frac{1}{2}$ M. *Rapolano*. The village, to the right, possesses baths which are frequented in summer. The country becomes more attractive.

$90\frac{1}{2}$ M. *Lucignano*; the mediæval village lies on the hill to the left. The improving cultivation of the soil indicates the proximity of the charming valley of the *Chiana*. To the left, in the distance, the chain of the Apennines. — 94 M. *Sinalunga*; on the right the village, where Garibaldi was captured on his march to Rome, 24th Sept. 1867. — 98 M. *Torrita*. Montepulciano becomes visible to the right.

103 M. *Montepulciano*; the lonely station is 6 M. from the town (omnibus in $1\frac{1}{2}$ hr., meeting nearly every train; fare 2 fr.); the road passes through several small villages.

Montepulciano. — ALBERGO MARZOCCO (*Bruzichelli's*), with trattoria, Via Garibaldi 32, tolerable, R. 1- $1\frac{1}{2}$ fr., D. 2-3 fr. — The Wine of Montepulciano is justly celebrated. The red wine is strong and somewhat rough. 'Vino santo' is a sweet white wine (2 fr. per bottle). *Vermouth* is a white wine flavoured with fragrant herbs and wormwood.

Montepulciano, a picturesque town with 3000 (or with the adjoining suburbs 13,000) inhab., surrounded by mediæval walls, lies conspicuously on the slope of a mountain (2070 ft.). It was the birthplace of the scholar and poet *Angelo Ambrogini* (1454-94), surnamed *Politianus* after this his native place ('*Respublica Politiana*'), the friend of Lorenzo il Magnifico and preceptor of his children. The beautiful situation as well as the monuments of the place repay a visit. The sights may be inspected in 4-5 hours.

We follow the main street, generally running from E. to W., and ascending from the gate next the railway-station to the plateau of the hill on which the town lies. It is first named *Via Garibaldi*, then *Via Cavour*, and lastly *Via Poliziano*. — In the *Via Garibaldi*, No. 32, on the left, is the *Palazzo Tarugi* (containing the above-mentioned Alb. Marzocco), built by Vignola. Opposite, Nos. 35-37, *Palazzo Avignonesi*, dating from the latter half of the 16th century. Then, also on the right, *S. Agostino*, of the 17th cent., with curious touches of Gothic. — In the *Via Cavour*, on the left, *Chiesa del Gesù*, a characteristic example of the Jesuit style. On the right the **Mercato* (market-halls) by Vignola. — In the *Via Poliziano*, on the left, No. 1, is the house in which *Angelo Poliziano* was born, a brick building of the 14th cent., with an inscription.

We next reach the *PIAZZETTA DI S. MARIA*, with the small church of *S. Maria* of the 13th cent. (handsome portal). It commands an admirable view of the lakes of Montepulciano, Chiusi, and Trasimeno; to the left rises Monte Amiata; farther up we obtain a survey of Pienza, S. Quirico, Montalcino, and the valley of the Chiana. — A road hence descends to the left in 12 min. to the —

**Madonna di S. Biagio*, in the valley, designed by *Antonio da Sangallo* and begun in 1518. The fine marble chapel of the high-altar, by *Giovanozzo* and *Lisandro Albertini*, dates from 1584.

Returning to the hill, and again following the main street, we next reach the *PIAZZA GRANDE*. The interesting fountain in the centre dates from 1520. On the left is the —

Palazzo Municipale, of the 14th cent., resembling the *Palazzo Pitti* at Florence, and containing a few pictures and curiosities.

Ante-chamber of first floor: *Madonna*, John the Baptist, and saints, of the school of *Della Robbia*. — PICTURE GALLERY on the second floor. I. Room: *Matteo da Siena* (?), *Madonna*. II. Room: 9. *Seb. del Piombo*, Pope Paul III.; 80. *Pacchiarotto*, *Madonna*; *86. *Umbrian School* (ascribed to Raphael), Portrait of a lady. A collection of dies once used by the engraver *Cerbano* is preserved here.

On the W. of the piazza is the *Cathedral*, with a ruinous façade.

In the INTERIOR, over the principal entrance, are the Death, Assumption, and Coronation of the *Madonna* by *Taddeo Bartoli*. The church was once adorned with an imposing monument to Bartolommeo Aragazzi, secretary of Pope Martin V., erected in 1427-29 by the famous architect *Michelozzo Michelozzi*, with the assistance of his master Donatello. It was taken down, however, during last century, when several parts of it were lost and others were placed in different parts of the church: thus, to the left of the principal entrance, two reliefs; by the two first pillars, two allegorical *Statues; by the high-altar, marble group of cherubs with garlands, forming the top of the monument.

To the right, opposite the *Palazzo Municipale*, is the *Palazzo Contucci*, by A. da Sangallo, and adjoining it the *Palazzo Nobile-Tarugi*, attributed to the same master.

We next enter the *Via Ricci*, where on the right rises the **Palazzo Bombagli*, a Gothic brick building. — Crossing the *Piazzetta della Misericordia*, with the church of *S. Francesco* (Gothic portal) and fine view, we now descend the *Via del Poggiolo*. Immediately

to the left in this street is the entrance to the *Oratorio della Misericordia*, which contains a Christ in a glory and an Annunciation over the high-altar of the school of the Della Robbia.

A visit to PIENZA is most conveniently made from Montepulciano: about 9 M., one-horse carr. there and back 10, two-horse 20 fr. Comp. p. 18.

Pienza (*Albergo Franci*, poor), a small town with about 2000 inhab., was originally called *Corsignano*, but subsequently named the 'town of Pius' after *Pius II.* (*Æneas Sylvius Piccolomini*, p. 28), who was born here on 18th Oct. 1405, and who adorned the town with very handsome buildings, chiefly designed by the Florentine *Bernardo Rossellino* and the Sienese *Francesco (Ciccio) di Giorgio* (1439-1502). As all these buildings date from about the same period (1460) and are situated in the same piazza (del Duomo), they afford a more compact survey of early-Renaissance architecture than is to be obtained in most Italian towns. The chief edifices are the *Cathedral*, with its studiously simple façade; to the right of it is the *Vescovado* or episcopal palace; opposite the cathedral the *Palazzo Pubblico*, with a colonnade; to the right the finest of all, the **Palazzo Piccolomini*, which like the *Palazzo Rucellai* at Florence exhibits the rustica style in combination with pilasters (handsome court and colonnade); in front of the palace is a charming *Fountain* of 1462. — The right transept of the cathedral contains a Madonna with four saints by Matteo da Siena; the choir-stalls, carved in the Gothic style, date from 1462; in the chapel to the left of the high-altar is an Assumption of the Virgin by Vecchietta; in the left transept a Madonna and four saints by Sano di Pietro. The *Cathedral Treasury* (shown by the sagrestano in presence of one of the canonici, sacristan 2 fr.) contains some early Renaissance works: crozier in gilded and embossed silver, a Paxvobiscum, a silver censor in the Gothic style, *Mitre of Pius II. decorated with pearls and jewels, reliquary of St. Andrew of Salerno, crucifix with rich filigree-work, etc. — The *Opera del Duomo*, to the left of the cathedral, contains the ecclesiastical vestments, including those of Pius II., one of which is of Flemish, the other of Italian workmanship.



CONTINUATION OF JOURNEY. To the right we soon observe the *Monti di Cetona*, which are connected with the Monte Amiata (p. 18). To the left stretches the long *Lake of Montepulciano*, beyond which is the *Lake of Chiusi*, connected with the other by a canal. The lakes exhale unhealthy malaria in summer.

108½ M. *Chianciano*. — 114 M. *Chiusi*, see p. 60.

5. Siena.

Hotels. *GRAND HÔTEL ROYAL DE SIENNE (Pl. a; E, 3), Via Cavour, with its back to the Lizza (p. 35), R. from 2-3, D. 4, B. 1½, L. & A. 1, omn. 1 fr.; *GRAND HÔTEL CONTINENTAL (Pl. b; E, 4), Via Cavour 15, opposite the post-office, R. from 2½, L. & A. 1, B. 1¼, luncheon 2½, D. 4½, omn. 1 fr.; AQUILA NERA, Via di Città (Pl. D, 5), a good house in the Italian style, similar charges. — SCALA (Pl. d; D, 4), Piazza S. Giovanni, opposite the Baptistery (p. 26) unpretending, but with large rooms (1½ fr.); TRE MORI (Pl. F, 3), Via Garibaldi, near the station, for moderate requirements, R. 1½ fr.; IL SASSO, with restaurant, Via Cavour, near the post-office, well spoken of. — For a prolonged stay: *Pension Chiusarelli*, Via S. Domenico, near the Protestant church; *J. Gatti*, Palazzo Bianchi, Via de' Servi; *Masini*, Via Cavour 12, well spoken of; *Francesco Tognazzi*, Via Sallustio Bandini 19; *Mme. Marion*, Via Ricasoli 37; *Pasquini*, Via delle Belle Arti 19 (pension at each 5-7 fr. per day, even for a short stay).

Trattorie. *Aquila Nera*, see above; *Sasso*, see above, good; *La Toscana* (formerly *Minerva*), Via del Re 4, with rooms (1-2 fr.), unpretending;



Scala, see above. — *Wine* and fine view at *Talliani's*, *Via delle Belle Arti* 31, and at the *Fiaschetteria il Confortabile*, *Via del Castoro*, near the *Piazza del Duomo* (sometimes open in the evening only). — *Beer* at *Bader's*, on the *Lizza* (p. 35).

Caffè Greco, near the *Casino de' Nobili* (p. 25).

| Cab Tariff: | By Day | | At Night | |
|---|-----------|-----------|-----------|-----------|
| | one-horse | two-horse | one-horse | two-horse |
| <i>In the town:</i> to or from the station | 1 fr. — | 1 fr. 50 | 1 fr. 50 | 1 fr. 80 |
| — first half-hour | — 80 | 1 — | 1 — | 1 30 |
| — each additional $\frac{1}{2}$ hr. | — 50 | — 60 | — 60 | — 70 |
| <i>Beyond the town</i> , as far as 2 M., for one hour | 2 — | 3 — | 3 — | 4 — |
| — each additional hour | 1 50 | 2 50 | 2 50 | 3 — |
| Box above 22 lbs. 30 c. | | | | |

Vetturini. *Turillazzi* and *Nal. Ceccarelli*, *Via Cavour* 23 and 25; carriage per day 25 fr., half-day 8-10 fr. Saddle-horses, per day $7\frac{1}{2}$ fr., half-day 5 fr.

Post and Telegraph Office, *Via Cavour* 16, in the *Pal. Spannocchi* (Pl. 25).

Baths. Swimming-bath near the *Fontebranda* (poor; water cold); warm baths at *Mazzei's*, *Via Dupré* 45.

English Church Service at the *Grand Hôtel Continental*, from March to May.

Good *Photographs* at *Cav. Paolo Lombardi's*, *Alla Costarella* No. 8, near the *Caffè Greco*. — *Carved Wood* (comp. p. 23): *Gosi, Guidi, & Querci*, *Via Belle Arti* 31, near *S. Domenico*; *Carlo Cambi*, *Via del Capitano* 5, near the cathedral.

Principal Attractions. *Piazza del Campo* (*Vittorio Emanuele*; p. 23), *Duomo* and *Opera del Duomo* (pp. 26, 28); walk through the town. To the town and its treasures of art the traveller should devote $2\frac{1}{2}$ -3 days at least. On 2nd July and 15th August, horse-races, called *il Palio*, take place, presenting a very picturesque scene (seat on grand-stand 2-2 $\frac{1}{2}$ fr.).

Siena, the capital of the province of that name, with 25,000 inhab. (incl. the suburbs), the seat of a university which was in high repute as early as the 14th cent., and the residence of an archbishop, is picturesquely situated 25 M. due S. of Florence, and 1330 ft. above the sea, on three connected hills (the clayey soil of which is called 'Terra di Siena'). It is now a busy trading and manufacturing place; it also possesses several libraries and scientific societies, and is one of the pleasantest towns in Tuscany, suitable for a stay of some duration. The climate is healthy, the atmosphere in summer being tempered by the lofty situation; the language and manners of the inhabitants are pleasing and prepossessing. Most of the streets are narrow and crooked, but they contain many palaces and handsome churches. Next to Rome, Florence, and Venice, Siena is perhaps the most important town in Italy for the study of the art of the 13-16th centuries.

SIENA, the ancient *Sena Julia*, or *Colonia Julia Senensis*, is said to have been founded by the Senonian Gauls and converted into a Roman colony by Augustus, whence it derives its arms, the she-wolf and the twins. The only Etruscan antiquities here are a few tombs which were discovered in 1864 near the *Porta Camollia*. The town attained to the height of its prosperity in the middle ages. After the death of the Countess Matilda (1115) her extensive dominions were dismembered, and the citizens of Siena, as well as those of Pisa, Lucca, and Florence, succeeded in establishing their independence. The government then fell into the hands

of the nobility, but was wrested from them by the people in 1133. The ensuing conflicts, however, terminated in favour of the nobles, and Siena became the leader of the Ghibelline party in Central Italy, while Florence was the stronghold of the Guelph faction. Farinata degli Uberti and the Ghibellines from Florence were welcomed in Siena, and on 4th Sept., 1260, a great victory over the Guelphs, the bloodiest recorded in the annals of Tuscany, was gained near *Monte Aperto*, on the *Arbia* (6 M. distant), with the aid of the German troops of King Manfred of Naples. Ten years later *Charles of Anjou* succeeded in gaining possession of Siena and in making it a member of the Tuscan-Guelph confederation of towns; but the city kept a jealous watch over its privileges, and, notwithstanding several attempts on the part of the nobility to re-assert their influence, its constitution remained unchanged. In the 14th and 15th centuries Siena numbered nearly 100,000 inhab., and vied with Florence in wealth and love of art. At length the supremacy was usurped by tyrants, such as (about 1487) *Pandolfo Petrucci*, surnamed *Il Magnifico*, whom *Machiavelli* represents as a pattern of a despot. In 1493, when *Charles VIII.* of France arrived in Italy, Siena concluded an alliance with him, and during the troubles of the first half of the 16th cent. the citizens for the most part sided with the French, by whom the town was usually garrisoned. On 22nd April, 1555, the French garrison was compelled by famine to capitulate to the Spanish besiegers, by whose aid Duke Cosimo I. of Tuscany succeeded in gaining permanent mastery of the place.

History of Art. The bitter political fate which overtook Siena, and converted the mighty rival of Florence into a quiet provincial town, will strike the antiquarian as a very fortunate circumstance; for here are still preserved many monuments and reminiscences of mediæval life comparatively unaffected by the vicissitudes and the progress of subsequent ages. The conservative character of Siena has not, however, been produced, as in the case of Bruges, by the withdrawal of the stream of history; for even when at the height of its power, particularly as compared with Florence, it manifested a preference for old established rules and a dislike for innovations. In the province of **Art**, despite the abundant supply of artists at their disposal, the citizens never seem to have taken the initiative, but adhered with remarkable tenacity to the earlier style. The best period of Siennese art still belongs to the middle ages, when the towns of Italy had begun to pride themselves on their practice of art, but before the pedantic element had given way to the pure sense of the beautiful. There is no town in Italy which presents such instructive examples of the Italian Gothic **Architecture** of the 13th and 14th centuries as Siena, where we find magnificent stone buildings vying with graceful structures in brick. If the *Cathedral* had been built according to the intentions of the citizens, it would have been one of the largest and most imposing churches in existence, and even in its reduced proportions it is one of the finest in Italy. In the secular buildings (of which perhaps the *Palazzo Buonsignori* is the finest example) the pointed style predominates; the windows are generally divided by small columns, and the whole edifice is crowned with pinnacles. In the 15th cent., when the motive of the castellated mansion was clothed with Renaissance forms, Siena was not slow to imitate the example of Florence. It is, however, uncertain whether *ROSSELLINO* and *FRANCESCO DI GIORGIO* have been correctly designated as the architects of the *Piccolomini*, *Spannocchi*, and *Nerucci* palaces. The most interesting of the Renaissance churches is the small round church *degli Innocenti*, adjoining the *Spedale della Scala*.

Siena has produced no independent school of **Sculpture**, though a liberal patron of foreign masters. As throughout the rest of Tuscany, the development of art did not progress rapidly here till the beginning of the 13th century. *NICCOLÒ PISANO*, the most famous sculptor of the 13th cent., and his son *GIOVANNI* were employed at Siena; and the sculptures on the font of S. Giovanni and on the *Fonte Gaja* are admirable works by *JACOPO DELLA QUERCIA* (1374-1438), the earliest representative of the Renaissance style.

Painting was the favourite art of the early Siennese. As early as the

13th cent. they could boast of **DUCCIO DI BUONINSEGNA**, a painter whose works far surpass those of Cimabue in beauty and gracefulness. On his completion in 1310 of the 'Majestas', or Triumphant Madonna, for the high-altar of the cathedral of Siena, the picture was carried to the church in solemn procession (p. 28). An equally important master was **SIMONE MARTINI** (1283-1344), who has been immortalised by a sonnet of Petrarch, and who, like his contemporary Giotto, practised his art and exercised his influence far beyond the limits of his native city. Works by his hand are, or were, to be found at Naples, Orvieto, Assisi, and Avignon, as well as in the Palazzo Pubblico at Siena. So famous indeed was his name that it was usual to attribute to him all the best works of his period. His compositions are of a very primitive character, but he certainly possessed great skill in his rendering of tender sentiment. Closely akin to these two masters was **LIPPO MEMMI**, who executed large frescoes with the same elaborate care as miniatures in missals. Several painters of the 14th cent. followed in Simone's footsteps, such as **BARNA** or **BIENA**, **LUCA THOME**, and **LIPPO VANNI**, without however exhibiting much individuality. The easy narrative style and the imaginative allegory were cultivated by the brothers **PIETRO** and **AMBROGIO LORENZETTI** (both of whom probably died of the plague in 1348), and the approach of the Sienese school to that of Giotto was thus accomplished. A little later, however, the works of **BARTOLO DI FREDI** (1330-1409) fell short of those of his predecessors, and this was still more the case with those of **TADDEO BARTOLI** (1362-1422?), who was far inferior to his Florentine contemporaries. For a time all artistic progress at Siena seemed to be at an end, and throughout the 15th cent. the city did not give birth to a single master of note. The painters **DOMENICO DI BARTOLO**, **LORENZO DI PIETRO** (nicknamed **VECCHIETTA**), **BENVENUTO** and **MATTEO DI GIOVANNI**, and others of this period adhered tenaciously to the limited methods of their predecessors, from whose influence they were unable to emancipate themselves. At the close of the century, owing to contact with neighbouring schools, whose representatives were frequently invited to Siena, and to the introduction of the study of Florentine, Umbrian, and Lombard masters, the tide of progress at length began to set in. The most distinguished Sienese masters of this period, far surpassing their contemporaries *Pungai-Pacchia*, *Pacchiarotto*, and others, were **BALDASSARE PERUZZI** and **GIOVANANTONIO BAZZI**, surnamed **IL SODOMA**. Peruzzi (1481-1537), who was associated with Raphael at Rome, was endowed with an admirable perception of beauty of proportion, and was famous both as an architect and a decorative painter, but Siena now possesses none of his works. Sódoma (c. 1473-1549), on the other hand, may be thoroughly studied at Siena. A Lombard by birth, he brought to Siena some traces of Leonardo's style, but instead of cultivating this, he seems to have trusted to his own natural ability, and with such success that in one respect he vies with Raphael himself. In the delineation of beautiful and youthful figures he is unsurpassed, and his technical skill in fresco painting and his fertility are marvellous; but, in spite of his strong sense of the beautiful, his works are apt to pall upon the taste owing to the superficiality of their composition. With **DOM. BECCAFUMI** (1486-1551), who frequently altered his style, begins the final period of decline from which Siena never recovered.

In the art of **Wood Carving** Siena has always taken the lead among the towns of Italy. In the 15th and 16th cent. the *Barili* family (particularly *Antonio*, d. 1516, and *Giovanni*, d. 1529) distinguished themselves in this branch, and their modern representative is *Giusti*, whose pupils *Gosi*, *Guidi*, and *Querci* are mentioned at p. 21.

In the centre of the town, at the union of the three hills on which it stands, is the picturesque ***Piazza del Campo**, now officially called *Vittorio Emanuele* (Pl. D, 5), which has been mentioned by Dante (*Purg.* xi. 134). It is semicircular in form, and depressed towards the centre, somewhat resembling an ancient theatre. The popular assemblies and festivals of the ancient re-

public took place here, and it is here that the Palio horse-races (p. 21) are now held. — The piazza is enclosed by pinnacled palaces. On the diameter of the semicircle rises the —

***Palazzo Pubblico** (Pl. 22; D, 5), a huge brick edifice of four stories, erected in 1289-1309, with pointed windows divided by small columns, and wings lower than the central part of the building. (The wings of the second floor are of a later date; comp. p. 28.) Adjacent rises the slender tower *del Mangia*, begun in 1325, and finished about 1345, so named after the stone figure of a man which used to strike the hours (a popular figure somewhat resembling the Roman Pasquino, p. 201); fine view from the top. At the foot of the tower is the *Cappella di Piazza*, in the form of a loggia, begun after the cessation of the great plague of 1348 which carried off 30,000 persons, and completed in 1376, with damaged frescoes by Sodoma. The upper part was added in 1460 by *Federighi*. The she-wolf on the column in front of the right wing, the arms of Siena (p. 21), dates from 1429.

The ***Interior** (custodian 1/2-1 fr.; best time 10-2) is embellished with numerous frescoes of the Siennese school. Among those on the GROUND FLOOR are a Coronation of the Virgin, by *Sano di Pietro*, 1445; a Madonna with SS. Ansano and Galgano, and another with St. Leonard, both by *Sodoma*; Madonna with saints, by *Vecchietta*; a Risen Christ, by *Sodoma*, 1535 (?), in the room of the Sindaco.

On the FIRST FLOOR, the custodian first shows the SALA DEL GRAN CONSIGLIO (or *del Mappamondo*, or *delle Balestre*), adorned with large frescoes: *Madonna and Child under a canopy borne by saints, by *Simone Martini*, 1315, a composition with numerous figures, somewhat stiff, but with beautiful details; opposite, *Equestrian portrait of Guidoriccio Fogliani de Ricci by *Simone Martini* (1328); beneath, Madonna by *Guido da Siena*, the date of which, 1221, appears to be spurious (prob. 1281; formerly in S. Domenico); then, to the right and left, *S. Ansano and *S. Vittorio, and, on the other wall to the right, S. Bernardo Tolomei, all by *Sodoma*; then S. Bernardino by *Sano di Pietro* and S. Catarina by *Vecchietta*. — The vestibule of this hall is adorned with frescoes by *Taddeo Bartoli*, representing ancient heroes, Judas Maccabæus, and St. Christopher and other saints (1441). The vault of the archway is occupied by a curious view of Rome. — A beautiful iron railing (1435-45), adjoined on the right by a font by *Turini*, separates this vestibule from the COUNCIL CHAPEL, which is embellished (left) with frescoes of the Death and Assumption of the Virgin by *Taddeo Bartoli*, and contains handsome benches carved by *Domenico di Niccolò* (1429). The altar-piece is a Holy Family by *Sodoma*; on the right is an organ by *A. Pifferio* (1519). — To the right of the Sala del Consiglio is the SALA DELLA PACE, or DEI NOVE, with frescoes by *Ambrogio Lorenzetti*, painted in 1337-43, representing 'Good and Bad Government', three pictures which are indispensable to those who desire an insight into the disposition of the proud citizens of Siena in the middle ages. The allegories and allusions of a more or less obscure character which they contain are at least interesting as being of a much more homely kind than those customary in modern times. One of these mural paintings represents the ideal of a state, under the guidance of wisdom, justice, and other virtues, while the two others portray in a realistic style the consequences of good and bad government. The preservation is imperfect, but the spectator will not fail to admire the heads of Peace, Justice, and Concord in the first of the series. — Adjoining is a room with portraits of the eight popes and thirty-eight cardinals to whom Siena has given birth. — Another Room contains some frescoes recently transferred from other buildings, a Madonna by *Matteo da Siena*,

1484, and S. Bernardino preaching in the Campo (p. 23), by *Sano di Pietro*, interesting for its representation of the piazza at that period. — The adjoining SALA DI BALIA, or DE' PRETORI, is adorned with ostentatious *Frescoes from the history of Pope Alexander III. by *Spinello Aretino* (1408; including a naval victory of the Venetians, and the Emp. Frederick Barbarossa and the Doge leading the Pope's horse). In the centre of the room are two fine coffers, one carved by *Barili*, the other adorned with paintings said to be by *Fra Angelico*. — The last room is the SALA DEL CONCISTORO, with ceiling-paintings by *Beccafumi*, a fine marble doorway by *Jacopo della Quercia* (above which is the Judgment of Solomon by *Luca Giordano*), Florentine 'Arazzi' or tapestry (partly of the 16th cent.) on the walls, and modern busts of statesmen and other illustrious citizens of Siena.

The rear of the palace, abutting on the *Piazza del Mercato* (Pl. D, 5, 6), or vegetable market, is also very picturesque. The piazza commands a good view of the environs.

At the E. end of the Piazza del Campo is the Palazzo del Governo (p. 30; façade towards the Via Ricasoli). — In the centre of the piazza, opposite the Palazzo Pubblico, rises the marble **Fonte Gaja*, a modern reproduction (1868) by *Tito Sarrocchi* of the original fountain of 1343. The beautiful bas-reliefs of the Christian virtues and of the Creation of Adam (left) and the Expulsion from Eden (right) were executed by *Jacopo della Quercia* in 1409-19 (originals, in a very damaged condition, now preserved in the Opera del Duomo, p. 28). A subterranean conduit, 18 M. in length, supplies the fountain with delicious water.

Ascending by steps through one of the passages beyond the Fonte Gaja, we reach the beginning of the VIA DI CITTÀ, which presents a busy scene, especially in the evening.

To the right, the **Loggia* of the *Casino de' Nobili* (Pl. 2; D, 5), once the seat of the commercial tribunal. It was built in imitation of the Loggia de' Lanzi of Florence in 1417, but the upper story is later. The sculptures are by Siennese masters of the 15th cent., such as Ant. Federighi (who executed the figures of S. Ansano, S. Savino, and S. Vittore, and the stone bench on the right), Lorenzo di Mariano (stone bench on the left), and Vecchietta (figures of SS. Paul and Peter). — The N. prolongation of this street towards the Porta Camollia is the Via Cavour (p. 35). — A little to the N. of the Loggia is the Piazza dell' Indipendenza, with a *Statue of Italia* by Sarrocchi, in memory of Siennese patriots who fell in the struggle for the union of Italy (near Pl. 27; D, 5).

Proceeding to the left, past the Caffè Greco, and then ascending the VIA DEI PELLEGRINI, a side-street to the right, we reach the small Piazza S. Giovanni. Here, in the corner to the left, is situated the *Palazzo del Magnifico* (Pl. 18; D, 5), erected in 1508 for the tyrant Pandolfo Petrucci (p. 22), from designs by *Giacomo Cozzarelli*. The bronze ornaments and flag-brackets on the outside are in admirable keeping with the style. One room is embellished with frescoes by *Pinturicchio*, discovered in 1882.

In a straight direction we obtain a fine survey of the choir of the loftily situated cathedral, under which is the old baptistery,

forming a kind of crypt, now the church of ***S. Giovanni** (Pl. 5), with a fine, but unfinished Gothic façade (after 1317).

The marble ***Font** is an admirable early-Renaissance work, designed by *Jacopo della Quercia* (1416), who also executed the statuettes of John the Baptist and the four prophets, and one of the six bronze-gilt ***Reliefs** from the history of John the Baptist (Zacharias led out of the Temple, 1430). The others are by *Lorenzo Ghiberti* (Baptism of Christ and John the Baptist brought before Herod, 1427), *Donatello* (Head of John the Baptist brought before Herod and his guests, 1427), and *Turino di Sano* and his son *Giovanni di Turino*. The last also executed the figures of Charity, Justice, and Prudence; those of Faith and Hope are by *Donatello*. — The frescoes by Siennese painters of the 15th cent. are of inferior value. — Over the high-altar is a Baptism of Christ by *And.* and *Raf. Puccinelli* of Brescia.

From the Piazza S. Giovanni we may either follow the street to the right, past the *Palazzo Arcivescovile* (Pl. 13), or we may ascend the steps to the left. By either way we reach the Piazza del Duomo.

The ****Cathedral**, or *Chiesa Metropolitana* (Pl. C, 4, 5), occupying the highest ground in the town, is said to stand on the site of a temple of Minerva, which was succeeded by a church of S. Maria Assunta. The present building was begun early in the 13th cent.; the dome was completed in 1264; and about 1317 the choir was prolonged to the E. over the church of S. Giovanni (see above). Owing to certain structural defects, to which the present irregularity of the edifice is still perhaps partly due, it was resolved in 1339 to erect a huge nave, of which the present cathedral was to form the transept only, according to a plan preserved in the *Opera del Duomo* (p. 28). Parts of this building, designed in a beautiful style, still exist on the S. side of the cathedral in the form of a ruin. After the plague of 1348 this ambitious plan was abandoned, and the original structure was then completed. (Length 97 yds., width $26\frac{1}{2}$ yds., length of transept 55 yds.) The ***FAÇADE**, constructed in 1284-1380 from a design by *Giovanni Pisano*, showing a combination of the pointed and circular styles, is composed of red, black, and white marble, and richly decorated with sculptures representing prophets and angels by different masters; the mosaics were added in 1878 by *Mussini* and *Franchi*. The campanile, consisting of six stories, does not taper towards the top. On each side of the entrance is a column bearing the wolf of Siena.

The ***Interior** consists of a nave and aisles extending to the choir and intersected by a double transept, with an irregular hexagonal dome over the centre. The horizontal bands of colour, the continuous rows of busts of popes (in terracotta; about 1400) over the arches, and the pillars with the half-columns will at first produce an unfavourable impression on northern travellers, but they will find that the pleasing ornamentation in marble compensates to a great extent for organic defects.

The stained glass in the large circular window in the wall of the entrance was designed by *Perino del Vaga*, 1549. Over the entrance is a graceful tribune of 1483, borne by two columns. The ***Basins** for holy water are by *Ant. Federighi*, a pupil of Jac. della Quercia, 1462-63.

The marble ****PAVEMENT** is quite unique, being covered with 'Grafitto' representations from designs by eminent artists: scenes from Old Testament history, Moses, Samson, Judas Maccabæus, Solomon, and Joshua by *Domenico di Niccolò* (1423); Abraham's sacrifice, Adam and Eve, Moses on Mt. Sinai, etc., by *Beccafumi*; the symbols of Siena and the towns allied with

it, Hermes Trismegistus, Socrates and Crates, the Sibyls, and other figures by masters of less note. The execution varies. The oldest scenes are simple outlines engraved on the white marble and filled with black stucco. Shading was then introduced by the use of grey and also of coloured marble, so that the graffito gradually developed into an elaborate mosaic. The pavement is generally covered by a wooden flooring, which is, however, removed on Aug. 15th (Feast of the Assumption). Some of the original works are now in the Opera del Duomo (p. 28).

LEFT AISLE: At the entrance-wall, statue of Pope Marcellus II., by *D. Cafaggi*. — 4th Altar (of the Piccolomini), with sculptures by *Andrea Bregno* (1485) and statues of SS. Peter, Pius, Gregory, and James, by *Michael Angelo*, and St. Francis, begun by *Torrigiani* and completed by *Michael Angelo*. — The entrance-wall of the Libreria is embellished with fine sculptures in marble, by *Lorenzo Marrina* (1497). Over the door: Coronation of Pius III. (Piccolomini; 1503), who reigned 27 days only, by *Ber. Pinturicchio*, who also painted the frescoes in the library (p. 28). — Farther on is the Monument of Bandino Baudini, with the Risen Christ and angels, attributed to *Michael Angelo*.

The ***PULPIT**, octagonal in form and constructed of white marble, borne by ten columns, some of which rest on lions, and adorned with admirable reliefs from the New Testament, is by *Niccolò Pisano*, his son *Giovanni*, and his pupils *Arnolfo* and *Lapo* (1266-68). The flight of steps was designed by *Bernardino di Giacomo* (1513).

The **LEFT TRANSEPT** contains the **CAPPELLA S. GIOVANNI**, with a portal by *Marinna*. In the interior are a *Statue of John the Baptist by *Donatello*, 1457; statues of SS. Catharine and Ansanus, by *Neroccio* (1487) and *Giov. di Stefano*, respectively; a font, perhaps by *Jacopo della Quercia*; stucco enrichments on the walls by *Peruzzi*; and five small frescoes by *Pinturicchio*, three being scenes from the life of Alberto Arringhieri, the donor. — Farther on in the same transept are statues of Popes Pius III. and Pius II. by *P. Balestra* and *G. Mazzuoli* respectively. — The chapel to the left of the choir contains a relief of the 11th cent., representing the Annunciation, the Nativity, and the Adoration of the Magi, removed hither from the old church of Ponte allo Spino, about 3½ M. from the town (p. 37). The bronze relief in the pavement in front of this work is by *Donatello*, and marks the tomb of Bishop Giovanni Pecci (d. 1426).

The **CHOIR** contains a high-altar executed from a model by *Baldassare Peruzzi* (1532); and behind it richly carved *Choir-stalls, reading-desk, etc., by *Bartolo Neroni*, surnamed *Riccio* (1567), and inlaid work (intarsia) by *Fra Giovanni da Verona* (1472). The bronze *Canopy is by *Lorenzo di Pietro*, surnamed *Vecchieta* (1472); the angels, acting as candelabra, are by *Giovanni di Stefano* and *Francesco di Giorgio* (1489), the front row of stalls and the reading-desk by *Raffaele da Brescia* (1520). The frescoes, by *Beccafumi* (1544), were entirely renewed and altered at the beginning of the present century. — By the pillars of the dome are two flagstuffs from the standard-wagon of the Florentines (*il carroccio*), captured at Monte Aperto in 1260, or, according to some authorities, those of the victorious wagon of the Sienese. Over a neighbouring altar is the crucifix which the Sienese carried with them on that occasion. — To the left of the high-altar is an organ-loft by *Barili* (1511), above the entrance to the sacristy, which contains (to the left) a font by *Turini*.

In the chapel to the right of the choir are reliefs of the Evangelists and St. Paul, by *Francesco da Imola* and *Giov. Turini*.

The **RIGHT TRANSEPT** contains statues of Popes Alexander VII. (by *E. Ferrata*) and Alexander III. (by *A. Raggi*). — The tomb of Bishop Tommaso Piccolomini (d. 1483) is by *Neroccio*. — The **CAPPELLA DEL VOTO**, belonging to the *Chigi*, built by Alexander VII. (Fabio Chigi of Siena, papal nuncio at the Peace of Westphalia in 1648, pope in 1665-67) in 1661, is richly adorned with lapis lazuli, marble, and gilding, and contains statues of St. Jerome and Mary Magdalene (said originally to have been an Andromeda) by *Bernini*. At the end of the right aisle is a statue of Pope Paul V., by *F. Signorini*.

In the left aisle, as already mentioned, is the entrance to the celebrated **Library of the Cathedral (Libreria*; fee $\frac{1}{2}$ fr.), formerly the *Sala Piccolominea*, erected by order of Cardinal Francesco Piccolomini, afterwards Pope Pius III., in 1495, and adorned in 1505-07 with ten frescoes by *Pinturicchio*, representing scenes from the life of *Æneas Sylvius Piccolomini* of Pienza (p. 20), afterwards Pope *Pius II.* (1458-64): (1) Departure of *Æneas Sylvius* for the Council of Basle; (2) *Æneas Sylvius* in presence of King James of Scotland, to whom he had been sent by the Council; (3) His coronation as a poet by Emperor Frederick III. at Frankfort in 1445; (4) *Æneas Sylvius* doing homage to Pope Eugene IV. in the name of the Emperor; (5) Betrothal of Emperor Frederick III. with Eleonora of Portugal at Siena by *Æneas Sylvius*; (6) *Æneas Sylvius* created a cardinal by Pope Calixtus III.; (7) *Æneas Sylvius* elected Pope Pius II.; (8) Pius II. at the diet of princes in Mantua; (9) Canonisation of Catharine of Siena; (10) Death of Pius II. at Ancona, while preaching a crusade against the Turks. Some of these pictures, which are connected by beautiful figures of nude or half-nude children, are admirably preserved. Vasari asserts that Raphael assisted in their execution. It is tolerably certain that Raphael was at Siena at the same time as Pinturicchio, and it is not improbable that he furnished the older and less imaginative master with designs of which the latter availed himself more or less freely. Designs for these frescoes attributed to Raphael are now preserved in the Uffizi (that of No. 1), in the Brera at Milan (No. 3), by the Duke of Devonshire at Chatsworth (No. 4), and by Sign. Baldeschi at Perugia (No. 5; p. 49). — The **Missals*, embellished with beautiful miniatures, also deserve attention (No. 5 and No. 9 by *Liberale da Verona*, No. 12 by *Girolamo da Cremona*, No. 11 by *Sano di Pietro*). — The S. side-entrance of the cathedral is surmounted by a relief of the Madonna by *Michelozzo*.

Opposite the S. side of the cathedral, in the corner where the steps ascending from S. Giovanni terminate under the arches of the uncompleted nave (p. 26), is the **Opera del Duomo (della Metropolitana*; Pl. 12; C, 5), which contains several interesting works of art.

In the entrance-passage is the custodian's bell ($\frac{1}{2}$ fr.).

The hall on the GROUND FLOOR contains a famous antique **Group of the Graces*, found at Rome in the reign of Pius II. and presented by him to the cathedral library, but removed thence in 1857 by desire of Pius IX. From this work Raphael made his first studies from the antique (drawing at Venice). The superb Renaissance pedestal is also interesting. The **Sculptures from the Fonte Gaja* (p. 25) by *Jacopo della Quercia*, representing a Madonna, the Virtues, the Creation of Man, and the Expulsion from Paradise, which are among the master's finest works, are unfortunately much damaged. *Sculptures from the Cappella di Piazza* (p. 24), and others from the façade of the cathedral before its restoration. — Antique sarcophagus with sea-gods; ornamentation of an organ-screen, representing the Transfiguration, by *Sodoma*. On the FIRST FLOOR: Drawings and copies of the **Graffiti of the Cathedral Pavement*, destined to replace the originals; also some of the originals themselves (comp. p. 27) and four copper-plates with the four chief designs. — On the SECOND FLOOR several interesting plans and architectural designs; handsome embroideries; crosiers; ring of Pius II. Also several early Sienese paintings, the chief of which is the large **Picture* by *Duccio di Buoninsegna*: on the left the Triumphant Madonna with the Child and saints, the once highly revered 'Majestas', which was placed over the high-altar in 1310 (p. 23), with the inscription: *Mater Sancta Dei, sis causa Senis requiei, sis Ducio vita, te quia pinxit ita*. On the right is the Life of Christ, in 25 sections, originally forming a background to the Majestas. Also four saints by *Ambr. Lorenzetti*; a Byzantine Madonna of the 12th cent.; a Credo by *Taddeo Bartoli*; a **Nativity of the Virgin* by *Pietro Lorenzetti* (1342), in a lifelike genre style; and a picture of the 15th cent. (perhaps by *Sano di Pietro*), showing the original form of the Palazzo Pubblico (p. 24).

Adjoining the Opera is the *Palazzo Reale* (Pl. 23), erected by

Bern. Buontalenti in the 16th cent., now the seat of the prefecture. — Farther on, in the Via del Capitano (see below) which diverges here, is the *Palazzo Pecci* (Pl. 20), a Gothic brick building of the 13th century. About 1360 it was appointed the official residence of the Capitano di Giustizia, or chief judicial functionary of Siena; in 1457 it was acquired by the jurist Tom. Pecci; and it is now the property of Sign. E. Grotanelli di Santi, who has had it restored without and within by Siennese artists.

Opposite the façade of the cathedral are the church and hospital of **S. Maria della Scala** (Pl. C, 5), of the 13th century. Over the high-altar of the church is a Risen Christ, a statue in bronze by *Vecchietta*. The choir-stalls are by *Ventura*, the organ by *B. Peruzzi*. Adjoining the handsome entrance-hall of the hospital is a large sick-room called 'Il Pellegrinajo', adorned with frescoes from the history of the monastery by *Domenico di Bartolo* (1440-43) and other masters. Pleasing view from the windows (fee 1½ fr.). — Descending to the left at the N. angle of the Piazza del Duomo by steps and under several arches, we reach the church *Degli Innocenti* (Pl. C, 4), externally a very rude edifice, but 'with a charming interior in the form of a Greek cross' (Burckhardt).

The above-mentioned VIA DEL CAPITANO leads to the quarters of the town situated on the S. and S.W. hills. It soon crosses the small Piazza Postierla, with the *Palazzo Chigi*, now *Piccolomini* (Pl. 16; C, 5), on the right, which contains two saloons adorned with frescoes by Bernhard van Orley, a Fleming who joined Raphael's school. The column with the wolf in the piazza dates from 1487. — Not far off, in the Via di Città, which diverges here to the left, is the *Palazzo Piccolomini*, now *Nerucci* (Pl. 19; C, D, 5), erected by Bernardo Rossellino in 1463 for Catharine, the sister of Pius II. Beyond it is the *Palazzo Saracini*, the vaulting in the court of which is tastefully painted. — In the Via di Stalloreggi, diverging from the Piazza Postierla to the right, is the *Casa Bambagini-Galletti*, on the façade of which is a fresco by Sodoma ('Madonna del Corvo').

On the left, in the VIA S. PIETRO, the continuation of the Via del Capitano, is the **Palazzo Buonsignori* (Pl. 15; C, 5), a handsome Gothic edifice of the 14th cent., in brick, with a rich façade, restored in 1848. The vestibule, court, and staircase are in a heavy rococo style. — At the church of *S. Pietro alle Scale* (Pl. 9; C, 6), which contains paintings by Salimbeni and Rutilio Manetti (16th cent.), the street bends to the right. — Following the main street and passing under an archway, we enter the PIAZZA S. AGOSTINO (Pl. C, 6), with the *R. Collegio Totomei*, formerly a monastery and now a much frequented grammar-school (Liceo), and the church of — **S. Agostino** (Pl. C, 6), remodelled by *Vanvitelli* in 1755, the entrance to which is in the Liceo, to the left.

Over the 2nd altar on the right, a Crucifixion by *Pietro Perugino*. Massacre of the Innocents by *Matteo da Siena* (1482), in a chapel on the right. Statue of Pius II. by *Dupré*. Altar-piece, an Adoration of the Magi by

Sodoma. At the back of the choir, on the left, the **Legend of S. Agostino Novello* in three sections, by *Lippo Memmi*, probably his best work. Also pictures by *Salimbeni*, *Rutilio Manetti*, and others.

About 250 paces beyond the *Porta Tufi* (Pl. B, 7) is the *Cimitero della Misericordia*, containing among its monuments a good *Pietà* by Dupré and several statues by Sarrocchi (fee 30-50 c.). — Following the *Via della Cerchia* (where the small *Palazzo Finetti* should be noticed) to the W. of S. Agostino, and bending to the right, we enter the *Via Baldassare Peruzzi*, on the left side of which are the suppressed monastery (now a barrack) and the church of —

S. Maria del Carmine (Pl. B, 5), a handsome brick edifice, with campanile and cloisters, by *Baldassare Peruzzi* (open 7-9 a.m. only). On the right is the *Cappella del Sacramento* with a *Nativity of Mary* by *Sodoma*; 5th altar on the left, *St. Michael* by *Beccafumi*.

Opposite is the *Palazzo Pollini*, formerly *Celsi* (Pl. 21; B, 5), attributed to Peruzzi. — We may now proceed straight on through the *Via delle Fosse di S. Ansano* (with the *R. Istituto Toscano dei Sordo-Muti*, or Deaf and Dumb Asylum) either to the *Piazza del Duomo*, or, by turning a little to the left towards the end of the way, we may reach the *Porta Fontebranda* (see p. 34).

Outside the *Porta S. Marco* (Pl. A, 5) there is a fine view.

The E. angle of the *Piazza del Campo* is occupied by the ***Palazzo del Governo** (Pl. 17; D, E, 5), one of the most imposing private edifices at Siena, erected for *Giacomo Piccolomini* in 1469-1500, probably from a design by *Bernardo Rossellino*. The principal façade with its tasteful decorations in wrought iron (horses' heads, etc.) looks towards the *Via Ricasoli* and the small *Piazza Piccolomini*. The palace now contains the extensive **Archives* (director, Sign. Lisini), one of the most important collections of the kind in Italy.

Parchment Charters, 52,000 in number, the oldest dating from 736. Under glass are a number of interesting specimens of these documents, *Autographs* of celebrated men (Pius II., Leo X.), *Miniatures*, etc. There is also a valuable collection of the *Covers of the old Treasury Registers (Bicchierne)*, in chronological order, painted with scenes from sacred and profane history, and affording an admirable survey of the development of Sienese art. They include works by *Dietisalvi*, *Duccio*, and the *Lorenzetti*.

In the vicinity is the *University* (see p. 31). — The **Loggia del Papa* (Pl. 11; E, 5), in the *Piazza Piccolomini*, opposite the *Pal. del Governo*, was erected in 1460 by the Sienese *Antonio Federighi* by order of Pius II. (*Æneas Sylvius Piccolomini*), and dedicated by the pope 'gentilibus suis'.

Adjacent is the church of **S. Martino** (Pl. 8; E, 5, 6).

Over the 2nd altar on the right, a *Circumcision of Christ* by *Guido Reni*. On each side of the 3rd altar are ornamental sculptures in marble by *Lorenzo di Mariano*, surnamed *Il Marrina*; on the left: *Nativity of Christ* by *Beccafumi*. The choir contains gilded wooden statues, attributed to *Jacopo della Quercia*.

The *VIA RICASOLI*, which passes the *Loggia del Papa*, traverses the crest of the S.E. hill and leads to *Porta Pispini* and

Porta Romana, the two S.E. gates. — Immediately to the right in this street is the *Fonte di Pantanelo*, dating from 1352, recently restored. To the left, a little farther on, the Via di Follonica descends to the *Fonte di Follonica*, constructed in 1239 and situated in a garden far below. — After 5 min. more, a few paces beyond the church of *S. Giorgio* (Pl. E, 6), the VIA DE' PISPINI diverges to the left, in which we first reach the church of —

S. Spirito (Pl. E, 6, 7), with a dome dating from 1508, and a portal from 1519, the latter designed by *Baldassare Peruzzi*.

The 1st chapel on the right (Cappella degli Spagnuoli) contains, above a St. Rosa by Viterbo, the following *Paintings by *Sodoma*: Madonna presenting the gown of the Order of the Dominicans to St. Alfonso, in the presence of SS. Octavia and Lucia; to the right and left SS. Sebastian and Anthony the Abbot; in the lunette, St. James on horseback (fresco). To the right is a Nativity of Christ in terracotta by *Ambrogio della Robbia* (1504). — Over the door leading to the sacristy, Crucifixion, by *Sano di Pietro*. — Over the 3rd altar to the left, Coronation of the Virgin by *Pacchia*. — In the CLOISTERS (sagrestano 5-6 soldi): Crucifixion by *Fra Paolino* (1516).

The *Fonte de' Pispini* dates from 1534. The neighbouring *Porta Pispini* is adorned with a damaged fresco (Nativity) by *Sodoma*.

Opposite S. Spirito we enter the Vicolo del Sasso, follow to the right the broad Via S. Girolamo, and passing the column with the wolf, reach *S. Girolamo* (Pl. D, 7), belonging to a nunnery (3rd altar to the left: Madonna by Matteo da Siena, framed in marble by Lor. di Mariano). On the left we next reach the church of —

SS. Concezione, or **Servi di Maria** (Pl. D, 8), erected in 1471, with a beautiful interior (1511-33) attributed to *Bald. Peruzzi*.

First altar to the right: Madonna, by *Coppo di Marcovaldo*, 1261. Fourth altar to the right: Massacre of the Innocents, by *Matteo da Siena*, 1491; above, Adoration of the Shepherds, by *Taddeo Bartoli*. — In the right transept, above the first door leading to the sacristy: 'La Vergine del Popolo', by *Lippo Memmi*, an able work. — At the back of the high-altar, 'Madonna del Manto', ascribed to *Giovanni di Pietro*, 1436. The Coronation of the Virgin, by *Fungai* (1500?), is one of his earlier works.

The *Porta Romana* (Pl. D, 8) is adorned with a fresco (Coronation of the Virgin) begun by *Taddeo Bartoli* and finished by *Sano di Pietro*. — About $\frac{1}{3}$ M. beyond the gate is the church of *Madonna degli Angeli*, the choir of which contains a Madonna with saints, by *Raffaele da Firenze*, 1502.

Opposite the N. side of the Palazzo del Governo (p. 30) the VIA S. VIGILIO leads to the E. to the church of the same name and to the **University** (Pl. 28; E, 5). The entrance to the latter is in the corner to the right; in the corridor is the monument of the celebrated jurist *Niccolò Aringhieri* (d. 1374), with a bas-relief representing the professor in the midst of his audience.

The neighbouring church of *S. Maria di Provenzano* (Pl. 7; E, 5) dates from 1594. — Traversing several streets to the E. we reach the PIAZZA DI S. FRANCESCO (Pl. F, 5), in which rise the church of S. Francesco and the Oratorio di S. Bernardino.

The church of **S. Francesco**, now undergoing restoration, has fine cloisters of 1518, in which, adjoining the side-entrance to the church, are architectural sculptures from tombs of nobles dating from the 14th century. To the left of the entrance to the seminary is a relief of the Madonna by *Cozzarelli*. The chapel contains a *Madonna nourishing the Child, by *Lorenzetti* (wall facing the windows), and a Madonna and saints by *Barna* (left wall). Farther on in the cloisters are some relics of a fresco of the Madonna by *Ambrogio Lorenzetti*.

The ***Oratorio di S. Bernardino** (Pl. F, 5) possesses admirable pictures, especially by *Sodoma*. Afternoon light best. The 'custode' lives at No. 6, adjoining (fee 1/2 fr.).

LOWER ORATORIO: Scenes from the life of St. Bernardino, of the close of the 16th century. — *UPPER ORATORIO: Presentation in the Temple, Salutation, Assumption, and Coronation of the Virgin; SS. Anthony, Bernardino, Louis, and *Francis, by *Sodoma*, 1518-32, the single figures being of great beauty. Betrothal and Death of the Virgin, by *Beccafumi*, 1518. Nativity of the Virgin, and Annunciation, by *Girol. del Pacchia*, 1185. The visitor should observe the admirable enrichments of the ceiling, the frieze, etc., which are among the most tasteful of early-Renaissance work, executed by *Giuliano Turapilli* after 1496. Altar-piece by *Beccafumi*, 1537.

The Via dei Rossi leads straight to the VIA CAVOUR, which with its prolongation, the Via Camollia, extends from the Casino de' Nobili (p. 25) to the Porta Camollia, a distance of nearly 1 M. Approaching from the Casino de' Nobili, we first reach a small piazza, named after the *Palazzo Tolomei* (Pl. 26; E, 4), a Gothic edifice of 1205, on the left, and also adorned with a wolf. Farther on are the Palazzi *Palmieri* (1540), *Bichi* (1520), with a fine loggia with modern paintings, *Gori* (1677), and **Spannocchi* (Pl. 25; E, 4), built in 1470 by a Florentine master, with a bold colonnaded court, and recently thoroughly restored. The last now contains the Post and Telegraph Office. — In the vicinity is the Piazza Salimbeni, with a statue of *Sallustio Bandini* (1677-1766), the drainer of the Sienese Maremme, by *Tito Sarrocchi*, erected in 1880.

To the left diverges the VIA DELLE BELLE ARTI, which contains the Art Institution and the Library and leads straight to the church of S. Domenico (p. 35).


The ***Istituto delle Belle Arti** (Pl. 10; D, E, 4) contains a valuable collection of pictures, principally of the older Sienese school, formed at the beginning of the present century of works procured from suppressed monasteries and from the Palazzo Pubblico, and gradually extended since that period. Adm. 9-3 daily (1 fr.), except on Sundays and holidays (bell below, to the right).

The numbering of the pictures is as nearly as possible chronological, though a few of the most important canvases have been transferred out of order to the better light of the cabinets. There is no catalogue, but the names of the artists, so far as known, are attached to the frames.

At the entrance, Reliefs of little value. — I. CORRIDOR, to which the attendant directs us: 1-15. Pictures of the 13th cent., still in the Byzantine style; 16. *Margaritone d'Arezzo*, St. Francis; 17. *Guido da Siena*, Madonna; 22-24. *Duccio di Buoninsegna*, Madonnas; 39. *Ambrogio Lorenzetti*, Annun-

ciation (1344); 55, 58. Works by *Pietro Lorenzetti*; 59. *Lippo Memmi*; 62. *Niccolò di Segna*, Crucifixion; 604. *P. Lorenzetti*, Madonna and saints; *86. *Lippo Memmi*, Madonna and four saints. — II. CORRIDOR: 404-410. *Beccafumi*, Cartoons for the pavement of the cathedral; 394. Ascribed to *Alb. Dürer*, Portrait of an old man; 335. *Morone*, Portrait; 495. *Steenwyck*, St. Jerome. — III. CORRIDOR: Pictures by *Taddeo Bartoli*, *Giovanni di Paolo*, *Sano di Pietro* (the 'Sienese Fra Angelico'), *Neroccio di Bart. (Landi)*, etc. 188. *Pietro di Giovanni*, St. Bernardino. — IV. CABINET: 265. *Sano di Pietro*, Madonna and St. Calixtus; *374. *Sodoma*, Scourging of Christ (fresco); 375, 376. *Girotamo Genga*, Flight of Æneas, Ransoming prisoners. *Wooden pilaster by *A. Barili*. — V. CABINET: 269-280. Paintings by *Sano di Pietro*; 152-155. *Andrea di Vanni*, Triumphs.

We next traverse Room VI. and enter Room VII., which contains prize-works by pupils of the Academy. In the middle is a Madonna and saints by *Pietro Lorenzetti* (1329), transferred from panel to canvas. — VIII. CABINET: 122. *Taddeo Gaddi*, Madonna; 123, 124. *Spinello Aretino*, Death and Coronation of the Virgin. 345. Antique sarcophagus with Nereids. — IX. CABINET: 132. *Lippo Memmi*, SS. Michael, Jerome, and John the Baptist; 162. *Sano di Pietro*, Coronation of the Virgin. — X. CABINET: 176, 178. Two large altar-pieces by *Sano di Pietro*, Madonnas and saints; *366. *Pacchiarotto*,



Annunciation; 170. *Taddeo di Bartolo*, Annunciation; 138. *Luca di Tommè*, Madonna (1367). — We now return to the door and enter the —

XI. LARGE HALL. To the right and left of the entrance, *362, 363. *Sodoma*, Christ on the Mt. of Olives, Christ in Purgatory, two frescoes brought from S. Croce. To the left: 307. *Francesco di Giorgio*, Nativity; 361. *Fungai*, Madonna and saints; 371. *Pinturicchio*, Holy Family; *355. *Sodoma*, Judith; *347. *Pacchiarotto*, Madonna and SS. Onuphrius and Erasmus; 345. *Beccafumi*, Fall of the angels; 310. *Francesco di Giorgio*, Coronation of the Virgin; 344. *Gir. del Pacchia*, Annunciation and Visitation (after the picture by Albertinelli in the Uffizi); *343. *Sodoma*, Descent from the Cross; 342. *Beccafumi*, Christ in Purgatory; 326. *Fungai*, Madonna and saints; 331. *Pinturicchio*, Holy Family; 329. *Pacchiarotto*, Ascension; 314. *Francesco di Giorgio*, Crucifixion. — XII. Room: *459. *Domenichino*, Landscape; 454. *Jan Brueghel*, Sea-piece; 412. *Palma Giovane*, Brazen Serpent; 414. Old copy of *Raphael's* Madonna della Perla (in Madrid); 478. *Caravaggio*, Morra-players; 419. *Palma Vecchio*, Madonna; 422. *Pinturicchio*, Holy Family; 425. *Lucas Cranach*, Lueretia; 427. Copy of *Amberger*, Charles V.; 429. *Morone*, Portrait (1453); 430. *Beccafumi*, St. Catharine; 436. *Altdorfer*, Martyrdom of St. Christina of Bolsena; 437. *Bart. de Bruyn*, Portrait; *Sodoma*, Holy Family, 440. Body of Christ and two angels, 441, 442. Madonnas, 439. St. Catharine, 443. Two guild-brothers worshipping the Cross; 447. *Paris Bordone*, Annunciation; 445, 451. *Fra Bartolommeo*, Two saints.

Two rooms on the first floor accommodate the GALLERIA DELLE STAMPE, the bulk of which consists of old Italian engravings, though there is also

a number of Dürer's wood-engravings. The second room contains the bust of Count Gori Tannilini (1880), the donor of the collection; to the left is an engraved Pietà from a drawing by Michael Angelo (1547).

Travellers who desire to visit the Monte Oliveto Maggiore (p. 16) must obtain a 'permesso' from the 'Ispettore' of the Istituto delle Belle Arte, which they should forward to the 'Soprintendente' at the convent.

The **Biblioteca Comunale** (Pl. 1; D, 4), containing 60,000 vols. and 5000 MSS., was founded in 1663 (open daily, 10-2, and 5 or 6 to 8). In the 17th cent. Siena possessed sixteen libraries, and in 1654 even one for women.

The chief objects of interest are: the *Greek Gospels, formerly in the chapel of the imperial palace at Constantinople, of the 11th cent., originally bound in silk, with pictures in enamel mounted at a later period in silver-gilt; *Treatise on architecture by *Francesco di Giorgio*, with sketches and drawings by the author; *Sketch-books of *Baldassare Peruzzi* and *Giuliano da Sangallo*; letters of St. Catharine.

Beyond the library, to the left, we descend the Via Costa S. Antonio, and enter the first side-street to the right, which leads straight to the upper entrance of the **House of St. Catharine** (Pl. 3; D 4): 'Sponsæ Christi Katherine domus'. Visitors knock at the door to the left ($\frac{1}{2}$ fr.). St. Catharine of Siena, the daughter of a dyer named Benincasa, was born in 1347, took the veil at the age of eight, and having become celebrated for visions, she prevailed on Pope Gregory VI. to retransfer the papal throne from Avignon to Rome (1377). She died in the year 1380, and was canonised in 1461. The best-known vision is that of her betrothal with the Infant Christ, a favourite theme with painters. Her festival is on 30th April.

The different rooms in the building have been converted into small chapels or ORATORIES, which belong to the *Confraternità di S. Caterina*. Above the altar in one of the UPPER ORATORIES, once a kitchen, is a portrait of the saint, by *Fungai*; the other pictures are by *Salimbeni* and *Fr. Vanni*; attention should also be paid to the beautiful ceiling, the pilasters, and the *Pavement of glazed tiles in the Renaissance style of the 15th century. — The pretty little court is attributed to *Bald. Peruzzi*. — The ORATORIO DEL CROCIFISSO contains the wonder-working Crucifixion, a painting by *Giunta Pisano* (?), from which St. Catharine, according to the legend, received the stigmata. — Below is the CHURCH (key kept by another custode), containing the following paintings: *Girol. del Pacchia*, St. Catharine healing Matteo di Cenni from the plague; St. Catharine resending Dominicans from murderers; The dead body of St. Agnes of Montepulciano stretching out her foot to be kissed by St. Catharine. The fourth picture, representing the saint being attacked by Florentine soldiers, is by *Salimbeni*, 1604; over the altar, *Statue of St. Catharine by *Neroccio*; above, *Angels by *Sodoma*.

On leaving the church we come to the VIA BENINCASA (formerly *dei Tintori*; Pl. D, 4), which is still inhabited, as in ancient days, by dyers and fullers. Over the door of the house on the left is a bust of St. Catharine by *Cozzarelli*. Not far off is the celebrated fountain of *Fontebranda* (Pl. C, D, 4), picturesquely situated at the base of the hill of S. Domenico, mentioned as early as 1081, renovated in 1198, and praised by Dante (*Inf.* 30, 78: 'Per Fontebranda non darei la vista'). Close by is a bathing establishment. — The Via di Fontebranda ascends to the Campo (left), and to the cathedral (right). — Passing the fountain, and ascending to the right, we reach —

S. Domenico (Pl. D, 3, 4), a lofty brick edifice in the Gothic style (1220-1465), the massive substructions of which rest on the slope of the hill, with a campanile dating from 1340.

The INTERIOR is destitute of aisles, and has a transept and open roof. At the entrance, to the right, is the CAPPELLA DELLE VOLTE (closed), containing an altar-piece of St. Catharine by *Andrea Vanni*. — Farther on, to the right: Monument of the mathematician *Gius. Pianigiani* (d. 1850), by *Becheroni*. — Third altar: St. Peter the Martyr, by *Salimbeni*, 1579. — The *CHAPEL OF ST. CATHARINE, in which the head of the saint is preserved in a silver reliquary enclosed in a shrine dating from 1466, is adorned with admirable frescoes by *Sodoma* (best light about midday). On the wall near the altar, St. Catharine in ecstasy, supported by two sisters (the so-called 'Svenimento', or faint), and an angel bringing her the host; on the wall to the left, The prayer of the saint saving the soul of a decapitated culprit; to the right, Healing of the possessed, by *Francesco Vanni*, 1593. The two saints on the right and left of the entrance are by the same master; the ceiling was executed by *Sodoma*. — The pavement of the chapel is richly decorated with graffito representations on marble. — Last altar to the right: Nativity of Christ by *Franc. di Giorgio*, executed under the influence of Luca Signorelli, to whom the work was formerly attributed; the upper part is probably by *Matteo da Siena*, the foreground by *Fungai*.

CHOIR. The beautiful *Marble Ciborium at the high-altar, hitherto ascribed by the Sienese to Michael Angelo, is more probably the work of *Benedetto da Majano*. — A beautiful *View of the lofty and imposing Cathedral may be obtained from the door at the back of the high-altar. — The 2ND CHAPEL to the left of the high-altar contains to the right: SS. Barbara, Mary Magdalene, and Catharine by *Matteo da Siena*, 1479; in the lunette above, a Pietà by *Girol. Benvenuto*; the Madonna with saints to the left is by the same master, 1508; the lunette representing the Adoration of the Magi is by *Matteo da Siena*. — The 2ND CHAPEL to the right of the high-altar contains numerous old tombstones with coats-of-arms, many of which belong to Germans who studied at the university in the 15th and 16th centuries.

We now return by the Via del Paradiso and the small Piazza Giuseppe Pianigiani, in which stands the little church of *S. Maria delle Nevi* (Pl. 6; E, 4), with a charming Renaissance façade (towards the Via Cavour), and a good picture by Matteo da Siena (Madonna with numerous saints, 1477), to the VIA CAVOUR (p. 25), which farther on contains the *Pal. Mocenni*, *Pal. Ciaia*, and others.

We next come to the small Piazza S. Petronilla (Pl. E, F, 3), on the right, whence the *Via Garibaldi* leads to the Porta S. Lorenzo and the railway-station. — The streets to the left of Via Cavour open into the **Lizza** (Pl. E, 2, 3), a small promenade which was laid out in 1779 on the site of a former fortress erected by Charles V., commanding good views of S. Domenico and the Cathedral. These walks extend as far as the entrance to *Fort St. Barbera*, built by Cosimo I. in 1560, open to the public and commanding a fine view.

Farther on, the Via Cavour takes the name of VIA DI CAMOLLIA (Pl. F, 1, 2). We diverge to the right to the old monastery *di Campani*, now the poor-house (Pl. F, 2; ring); the cloisters are adorned with a fresco by *Matteo Balducci*. Handsome rococo church.

We follow the Via Camollia for some minutes more; opposite a small piazza we turn to the left under an archway, and descending the Via Fonteginsta, arrive at the little church of —

Fonteginsta (Pl. F, 2), belonging to a brotherhood (it closed,

ring the bell to the right), and built by *Francesco di Cristofano Fedeli* and *Giacomo di Giovanni* in 1479. The vaulting, borne by four marble columns, dates from 1482; the N. Portal from 1489. Beautiful *High-altar by *Lorenzo di Mariano* (1517), one of the finest existing sculptures of Raphael's time. The simple but fine bronze holy-water basin is by *Giov. delle Bombarde* (1480). The 2nd altar to the right is adorned with a Madonna by *L. Vanni*, with a view of Siena and its towers (1590); the 3rd altar on the same side has a Coronation of the Madonna by *Fungai*; the 2nd to the left a *Fresco by *B. Peruzzi*, the Sibyl announcing to Augustus the Nativity of Christ. Over the entrance are a sword, helmet, shield, and some bones of a whale, presented by Columbus. Above the side-entrance (outside) is a relief of the Madonna by *Neroccio*.

Farther on in the *Via Camollia*, to the right, No. 48, opposite the small Templar church of *S. Pietro della Maggione*, is the house of *Baldassare Peruzzi* (p. 23), indicated by an inscription.

A pleasant WALK may be taken by a road skirting the town-walls to the right, outside the *Porta Camollia* (Pl. F, 1), with fine views of the Tuscan hills. On a height opposite, beyond the railway-station, lies the monastery of *Osservanza* (see below); in the valley below, outside the *Porta Ovile* (Pl. F, 4), is the picturesque *Fonte Ovile*. In about $\frac{1}{2}$ hr. we reach the *Porta Pispini* (Pl. F, 8; p. 31). — About $\frac{1}{2}$ M. beyond the *Porta Camollia*, on the road to Colle, stands the *Palazzo dei Turchi*, generally known as the *Pal. dei Diavoli*, a fine brick building of the close of the 15th century.

Excursions (most of them best made by carriage). — About $2\frac{1}{2}$ M. to the N.E. of Siena, beyond the railway-station, is situated the suppressed Franciscan monastery of *l'Osservanza*, erected in 1423 and enlarged in 1485 by *Cozzarelli*. The N. aisle of the church contains a *Coronation of the Virgin, by *Andrea della Robbia*; at the back of the high-altar, in which is preserved the silver reliquary of S. Bernardino, by *Ant. Federighi*, are two *Statues, Mary and the Archangel Gabriel, of the same school. Pandolfo Petrucci is interred in this church (d. 1512; p. 22). In the sacristy is a *Pietà* in terracotta, by *Cozzarelli*.

S. Colomba, Celsa, and Marmoraja are most conveniently visited on horseback; there and back, with stay, in $5\frac{1}{2}$ hrs.; horse 5 fr.; one-horse carriage (carozzino) 6 fr. For larger carriages the road is only good as far as S. Colomba. — Leaving the *Porta Camollia*, we follow the high-road for $2\frac{1}{2}$ M. and then diverge to the left by the road descending between two cypresses into the valley. This road leads us to the villa *S. Colomba* ($4\frac{1}{2}$ M.), designed by *Bald. Peruzzi*, now the property of the Collegio Tolomei (p. 29), with handsome staircase, and fine view from the balcony. — After descending from S. Colomba we continue to follow the road by which we arrived, which leads through beautiful woods to *Celsa* ($3\frac{3}{4}$ M. from Colomba), a castellated villa, also designed by *Bald. Peruzzi*, where Mino Celsi, a defender of the doctrines of Luther, lived at the beginning of the 16th century. View from the highest story (refreshments sold by the fattore of the villa). — About $2\frac{1}{4}$ M. beyond Celsa is *Marmoraja*, where on 7th Sept., 1187, peace was concluded between the Republic of Siena and Bishop Hugo of Volterra. The piazza in front of the church affords a fine view of Volterra, Colle d'Elsa, S. Gimignano, etc.

The *Certosa di Pontignano*, 5 M. from the *Porta Ovile*, was founded in 1343, fortified in 1383, and suppressed in 1810. The church was modernised in the 17th century. *View from the Parocchia.

S. Ansano in Dofana, 9 M. from Porta Pispini, is reached by a good road diverging from the high-road to the left about $1\frac{1}{4}$ M. beyond the *Taverna d'Arbia*, near the bridge over the *Arbia*. The parish-church contains a Madonna by *Bald. Peruzzi*. Visitors should apply at the parsonage for a guide with the keys of the (8 min.) *Martirio di S. Ansano*, a handsome brick edifice by *Bald. Peruzzi*.

The **Abbazia di S. Eugenio**, $1\frac{1}{4}$ M. to the S. of the Porta S. Marco, commonly known as *Il Monastero*, is an ancient Benedictine monastery said to have been founded by Warnfried, a Lombard, in 750, fortified in 1553 by Pietro Strozzi, and secularised last century. The buildings are thoroughly modernised. The church contains several early Sienese pictures, some of which have been ruined by restoration. *View from the garden.

The high-road next leads to the *Osteria della Volte*, about 5 M. beyond the Porta S. Marco, whence a road diverges to the right to (4 M.) *Cetinale*, a villa erected by Flavio Chigi, a nephew of Pope Alexander VII., from designs by Carlo Fontana in 1680. With the villa is connected the 'Thebais' park, profusely embellished with sculptnres and containing fine old timber. *View from the hill ('Romitorio') above the villa. Permessi in the Palazzo Chigi at Siena, Via di Città.

About $1\frac{1}{2}$ M. beyond the *Osteria della Volte* lies the venerable church of *S. Giovanni di Ponte allo Spino*, dating from the beginning of the 11th century. About 3 M. further is *Rosia*, the church of which contains a holy-water basin of 1332. We may then proceed to (2 M.) *Torri* or *S. Mustiola a Torri in Val-di-Merse*, an old monastery belonging to the Vallombrosians, possessing a church, consecrated in 1189, and a fine Romanesque monastery-court, now used as farm-buildings.

About 9 M. to the S. of *Rosia* (along the road to Massa Marittima, and then to the left) lie the ruins of the Cistercian monastery of ***S. Galgano**, founded in 1201 by Ildebrando Pannocchieschi, Bishop of Volterra. The abbey-church, a building of travertine and brick, erected in 1240-68, is imposing even in its ruins. The only relics of the original architecture in the secular buildings, now used as a farm, consist of a few windows. The monks were distributed among other monasteries in 1652, and in 1781 the church, which had been injured by lightning, was closed.

The château of ***Belcaro**, to the W. of Porta Fontebranda, reached by carriage in $1\frac{1}{2}$ hr., commands a splendid view of Siena and its environs. On the ground-floor is a ceiling-painting by *Bald. Peruzzi*: Judgment of Paris. The frescoes in the chapel, by the same master, have been sadly injured by recent restorations.

6. From Florence to Perugia viâ Arezzo and Terontola (*Chiusi, Rome*).

103 M. RAILWAY. Express in $4\frac{1}{4}$ hrs., fares 20 fr. 10, 14 fr. 5 c.; ordinary trains in 6-8 hrs., fares 18 fr. 70, 13 fr. 25, 8 fr. 40 c. — To *Arezzo*, $5\frac{1}{2}$ M., in 2-4 hrs., fares 10 fr. 85 c., 7 fr. 55 c., or 9 fr. 85, 6 fr. 85, 4 fr. 45 c.; thence to *Cortona*, $17\frac{1}{2}$ M., in $\frac{1}{2}$ - $\frac{3}{4}$ hr.; fares 3 fr. 45, 2 fr. 45 c., or 3 fr. 15, 2 fr. 25, 1 fr. 40 c. — Those who wish to see *Arezzo* and *Cortona* and arrive at *Perugia* in one day, had better leave *Florence* in the afternoon or evening and sleep at *Arezzo*.

The EXPRESS TO ROME quits the *Perugia* line at *Terontola* (see R. 9), where passengers for *Perugia* generally change carriages.

Florence, see *Baedeker's Northern Italy*. The train describes a curve round the town and runs along the N. bank of the *Arno*. By degrees the valley contracts; Fiesole on the height to the left long remains visible. $7\frac{1}{2}$ M. *Compiobbi*. To the left rises the mountain-chain of the *Pratomagno*. 10 M. *Sieci*. $12\frac{1}{2}$ M. *Pontassieve*, at the influx of the *Sieve* into the *Arno*; to the left a beautiful glimpse of the valley of the *Sieve*. The train passes through a short tunnel,

and then crosses to the left bank of the Arno. From (17½ M.) *Rignano* a pleasant excursion (a drive of ¾ hr.) may be made to the fine *Villa San Mezzano*, belonging to Marchese Panciatichi of Florence. The train passes through another tunnel and reaches (22 M.) *Incisa*, with a conspicuous castle. The river forces its way here through the limestone rock, whence the name of the village. 25 M. *Figline*. The valley of the Arno near Figline, and farther on, near *Montevarchi* and *Arezzo*, is very interesting to palæontologists owing to the numerous fossil bones of the elephant, rhinoceros, mastodon, hippopotamus, hyæna, tiger, bear, etc., which have been found here. This basin seems to have once been filled with a fresh-water lake.

30 M. **S. Giovanni**, a small town to the left, the birthplace of the famous painter *Masaccio* (in 1401) and of *Giov. da S. Giovanni*, surnamed *Manozzi* (1590-1636). The *Cathedral* contains pictures by the latter: Beheading of John the Baptist, Annunciation, etc. The sacristy of *S. Maria delle Grazie*, on the old town-wall, contains a Madonna, once ascribed to Masaccio, and other old paintings.

33½ M. **Montevarchi** (*Loc. d'Italia*, in the main street), with 9600 inhabitants. The loggia of the principal church in the piazza is embellished with an elaborate relief by *Della Robbia*; opposite is the house of *Benedetto Varchi* (d. 1555), the Florentine historian and independent favourite of Cosimo. The *Accademia di Val d'Arnese* contains a valuable collection of fossil bones (see above).

Views as far as Arezzo on the left. The train ascends, passing through four tunnels, to (38 M.) *Buçine*, a village close to the line on a hill to the right. Four more tunnels. 41½ M. *Laterina*; 44½ M. *Ponticino*. The train now gradually ascends to (54½ M.) *Arezzo*.

Arezzo. — *INGHILTERRA, *VITTORIA, R. 2, L. 1½, A. ½ fr., opposite each other in the *Via Cavour*; LA STELLA, Corso Vittorio Emanuele 67, with a good trattoria. — *Ristor. d'Italia, Corso Vittorio Emanuele 15. — *Caffè dei Constanti*, *Via Cavour*. — *Italian Protestant Church*, *Via S. Lorentino* 10.

Arezzo (780 ft.), the ancient *Arretium*, the seat of a bishop and a prefect, is a clean and pleasant town with 12,000 (or, including the neighbouring villages, 39,000) inhab., in a beautiful and fertile district, abounding in historical reminiscences.

Arretium was one of the most powerful of the twelve confederate cities of Etruria, and (like Cortona and Perugia) concluded peace with the Romans in the great war of B.C. 310, after which it continued to be an ally of Rome. In 187 the Consul C. Flaminius constructed the *Via Flaminia* from *Arretium* to *Bononia* (Bologna), of which traces are still distinguishable. In the civil war *Arretium* was destroyed by Sulla, but was subsequently colonised (*Colonia Fidens Julia Arretium*), and again prospered. Its manufactures were red earthenware vases, of superior quality, and weapons. — In the middle ages the town suffered greatly from the Goths and the Lombards, and at a later date from the party-struggles of the Guelphs and Ghibellines, in which it generally took the part of the latter against the Guelphs of Florence. In the 14th cent. it was for a time subject to the rule of the *Tarlati*, and in 1337 temporarily, and in the 16th cent. under Cosimo I. finally to that of Florence.

Arezzo is the birthplace of many distinguished men, of whom may



be mentioned: *C. Cilnius Maccenas* (d. 9 A.D.), the friend of Augustus and patron of Virgil and Horace; the Benedictine monk *Guido Aretino* or *Guido Monaco* (1000-1050), the inventor of our present system of musical notation; *Francesco Petrarca*, the greatest lyric poet of Italy, born of Florentine parents in 1304 (d. 1374); *Pietro Aretino*, the satirist (1492-1557), several members of the noble family of the *Accolti*, jurists and historians; in the 15-17th cent.; *A. Cesalpini*, the botanist and physician (1519-1603), *Franc. Redi*, the physician and humourist (d. 1698). — Arezzo has also produced several artists: *Margaritone* (about 1236), a painter and sculptor of no great importance; *Spinello Aretino* (1318-1410), an able pupil of Giotto, whose style he steadily followed and rendered popular (his best works are in S. Miniato near Florence, in the Campo Santo at Pisa, and in the Palazzo Comunale in Siena); at a later period *Giorgio Vasari* (1512-74); the painter, architect, and biographer of artists. The town, however, never possessed a school of its own. Its requirements in the province of art, which were at their height in the 13-14th cent., were fulfilled by Florentine and Siennese masters, and Giotto, Lippo Memmi, Lorenzetti, and others were employed here.

Leaving the station, we follow the Via Guido Monaco, which leads straight into the heart of the town. In the PIAZZA GUIDO MONACO is a statue of *Guido Monaco* (see above), by Salvini, erected in 1882. In the Piazza del Popolo, to the left, is a column, erected in 1880 to commemorate the Italian struggles for independence.

A little farther on the Via Guido Monaco ends in the Via Cavour. Here, in the small PIAZZA UMBERTO, is a *Monument to Count Fossonbroni* (b. at Arezzo 1754, d. 1844; Pl. 1; p. 43).

The church of **S. Francesco** (Pl. 2), founded in 1322, at the corner of the piazza, contains fine frescoes of the 15th century.

On the entrance-wall is a fresco representing Christ at table with Mary Magdalene, by *Spinello Aretino* (see above), perhaps the greatest of the followers of Giotto. The wheel-window, by *Guglielmo da Marsilia* (c. 1500) represents St. Francis receiving the rules for his order. — The LEFT AISLE, recently freed from whitewash, contains frescoes by *Spinello Aretino*, sadly injured; the best in the restored chapel of St. Anthony of Padua. At the end is the tomb of Antonio Roselli (d. 1467). — At the end of the wall on the right is an Annunciation by *Spinello Aretino* (c. 1385).

In the CHOR: *Frescoes by *Piero della Francesca*, the master of Luca Signorelli (best light in the evening). They narrate the legend of the Holy Cross, according to which a seed of the tree of knowledge, planted upon Adam's grave, grew up to be a tree. Solomon caused the tree to be felled and a bridge to be constructed of the wood, of which the Queen of Sheba afterwards discovered the origin. At a later period it was used for making the Holy Cross. The Emp. Heraclius rescued the cross in a battle with the Persians, and it was afterwards re-discovered by St. Helena. All these scenes, from the death of Adam down to the finding of the Cross, are portrayed by Piero with great technical skill, in which respect, as well as in his appreciation of the nude, he surpassed all his contemporaries. His pictures, however, are stiff and destitute of gracefulness. — The Evangelists on the ceiling have been attributed to *Bicci di Lorenzo*. — The chamber at the bottom of the CAMPANILE, entered from the choir, also contains frescoes by *Spinello Aretino*: Madonna enthroned, St. Michael overcoming the dragon, and St. Michael appearing to Gregory the Great above the tomb of Hadrian (castle of S. Angelo) during the plague at Rome; opposite, Gregory distributing alms, St. Egidius hunting, the Mass of St. Gregory.

The Via Cavour forms a right angle with the Corso VITTORIO EMANUELE, the principal street of the town. Ascending this street, to the left, we observe on the right the interesting church of —

S. Maria della Pieve (Pl. 3), founded at the beginning of the 11th cent., which retains the original choir, seen from the Piazza Vasari; the tower and façade were added by Marchione in 1216, but the latter was left unfinished till 1330. Above the main portal are a Madonna between angels, and figures of the months; and at the door to the right is a Baptism of Christ, of 1221. The interior consists of a nave and aisles with a broad apse, a crypt, and an open wooden roof above the crossing, all restored in the ancient style. On the entrance-wall is an alto-relief of the Adoration of the Child (11th cent.); and behind the high-altar are a *Madonna and saints, Annunciation, and other works by *Pietro Lorenzetti* of Siena (1320). The font in front is perhaps of the same date.

At the back of the church is the picturesque **PIAZZA VASARI**, with a fountain and a *Monument of Ferdinand III.* (Pl. 4), erected in 1822. On the N. side are the *Loggie* (Pl. 5) built by Vasari in 1573. — Adjoining the choir of S. Maria della Pieve is the building of the *Fraternità della Misericordia* (Pl. 6), now occupied by the law courts, with a handsome Gothic façade, begun by Florentine artists in 1375, and adorned with figures in 1434 by Bernardo di Matteo of Settignano.

Passing under Vasari's Loggie we now return to the Corso, which we reach just opposite the *Palazzo Pubblico* (Pl. 7). This edifice, built in 1322, and adorned with numerous armorial bearings of the ancient Podestà, is now used as a prison.

A little farther on the Via dell' Orto diverges to the left, near the entrance to which, No. 22, a long inscription indicates the house (Pl. 8) in which *Francesco Petrarca* was born (p. 39). Adjacent rises the —

***Cathedral**, a fine specimen of Italian Gothic, begun in 1177, with later additions; façade unfinished.

The INTERIOR, which has no transept and is of handsome and spacious proportions, contains stained-glass windows, dating from the beginning of the 16th cent., by *Guillaume de Marseille*; the middle window in the choir is modern. G. de Marseille also painted the first three arches of the nave, the others being by *Salvi Castelucci* (1668). In the RIGHT AISLE is the Tomb of Gregory X., by *Margaritone* (? Pisan school). This indefatigable prelate expired at Arezzo, 10th Jan., 1276, on his return from France to Rome, after having proclaimed a new crusade. Adjacent, an ancient sarcophagus (lid modern), with the bones of several martyrs of Arezzo. Above are a Gothic tabernacle and a fresco of the Crucifixion by *Berna* (c. 1380). — On the HIGH ALTAR, marble *Sculptures by *Giovanni di Francesco* of Arezzo and *Betto di Francesco* of Florence, executed in 1369-1375: Madonna with SS. Donatus and Gregory, and bas-reliefs from their lives. — In the LEFT AISLE, at the E. end, is the *Tomb of Guido Tarlati di Pietramala, the warlike bishop of Arezzo, the work of *Agostino* and *Agnolo da Siena*, about 1330, from the design of *Giotto*, as Vasari conjectures, in 16 sections, representing the life of this ambitious and energetic prelate, who, having been elected governor of the town in 1321, soon distinguished himself as a conqueror, and afterwards crowned the Emperor Louis the Bavarian in the church of S. Ambrogio at Milan (d. 1327). — Close to the door of the sacristy is a St. Magdalene, al fresco by *Piero della Francesca*. The large Chapel of the Madonna, erected in 1796, contains five *Terracottas by *Andrea della Robbia*.

The *Marble Statue of Ferdinand de' Medici* in front of the cathedral was erected by *Giovanni da Bologna* in 1595. In the piazza (No. 1) is the *Palazzo Comunale* (Pl. 9), with old armorial bearings.

We now follow the *Via Ricasoli*, and turn to the right into the *Via Sassoverde*, at No. 12 in which, the *Palazzo Capel di Ferro*, is the small municipal **Pinacoteca Bartolini** (open 10-3; 1/2 fr.), containing ancient frescoes, old and modern oil-paintings, and engravings, but little that is particularly striking. In the first large room (No. IV.): *No. 8. *Luca Signorelli*, a large altarpiece with the Madonna, David, and St. Jerome, and the kneeling donor, the jurist Niccolò Gamurrini (painted about 1520). There are also some good portraits, a St. Rochus, and drawings by *Vasari*.

Above the door of the church of *S. Domenico* (Pl. 10) is a Madonna 'al fresco' by Angelo di Lorentino (c. 1480). The interior contains a Crucifixion by Parri Spinello, and, on the right, a painted Gothic *Tabernacle, with coats-of-arms, by Giovanni di Francesco of Florence.

In the Borgo di S. Vito, on the right, is the *House of Giorgio Vasari* (No. 27; Pl. 11), containing works by the master. The street leads back to the W. end of the *Via Cavour* (p. 39).

The municipal ***Museum** stands at the corner of the *Via Garibaldi* and the *Via S. Lorentino* (adm. daily 9-4; fee 1/2 fr.).

Room I. Black Etruscan vases, with reliefs; glass; stone-weapons; in the middle, Greek vases, with representations of the battles of the Amazons and the Abduction of Hippodamia. — R. II.: Bronze statuettes, coins, etc. — R. III. Cinerary urns, fragments of vases of red glazed clay (*Vasa Arretina*, p. 38), and numerous moulds. — R. IV. Mediæval articles and majolicas with designs after Raphael; 37. Carved ivory casket of the 7th cent.; bronzes; in the middle, seals; above, Renaissance figure from a fountain. — R. V. Weapons, various utensils; in the middle, a bronze reliquary by *Forzore* (1488). — R. VI. Antique urns and reliefs (62. Lady at her toilet). — RR. VII-XI.: Natural History collections. R. VII. and VIII. contain a palæontological collection, chiefly from the Val di Chiana.

The same building also contains the **TOWN LIBRARY**, which comprises a few MSS. (open 9-12 and 2-5).

In a small piazza adjoining the *Via Cavour* stands the church of **SS. Annunziata** (Pl. 12), a handsome Renaissance structure chiefly by *Antonio da Sangallo*; the *Interior, with its barrel and dome vaulting, is very picturesque; at the last altar on the right, Madonna in clouds with St. Francis, by *Pietro da Cortona*; stained glass by *Guillaume de Marseille* (1525).

Farther on in the *Via Cavour* is the **Badia di S. Fiore** (Pl. 13), also situated in a small piazza, which is now the seat of the *Accademia Aretina di Scienze, Lettere ed Arti*. The **LIBRARY**, formerly the refectory, contains the Feast of Ahasuerus by *Vasari*, 1548.

At the lower end of the *Corso*, near the *Porta S. Spirito*, the *Via dell' Anfiteatro* (to the left) leads to the church of *S. Bernardo* (Pl. 14); the frescoes in the anterior quadrangle (God the Father and the four Evangelists) were painted by *Vasari* at the age of seventeen (1529); below is the Madonna appearing to St. Bernar-

dino, attributed to *Bartolommeo della Gatta*. — The cloisters to the left contain some indifferent frescoes in chiaroscuro (life of Guido Monaco and St. Bernardino) and a view of mediæval Rome. In the garden are the insignificant remains of a Roman amphitheatre.

About $\frac{3}{4}$ M. from the Porta S. Spirito (outside which we take the avenue to the left, and then at the corner, after 3 min., the road to the right) is situated the church of S. Maria delle Grazie, with an elegant early-Renaissance porch borne by columns, by *Benedetto da Majano* (?), and a handsome marble altar by *Andrea della Robbia*.

Railway from Arezzo to Fossato, see R. 8.

FROM AREZZO TO STIA AND PRATOVECCHIO, 28 M., railway in 2 hrs. (fares 5 fr. 10, 3 fr. 60, 2 fr. 30 c.). — At (5 M.) *Giovi*, the first station, the line enters the valley of the Arno, which it thenceforwards ascends. — 9 M. *Subbiano*; 12½ M. *Santa Mama*; 15 M. *Rassina*.

19½ M. *Bibbiena* (*Albergo Amorosi*; carriage from the station to the town ½ fr.), pleasantly situated on a hill above the Arno, was the birthplace of Cardinal Bernardo Dovizio, surnamed Bibbiena (1470-1520), the patron of Raphael. A little to the N. of the town is the former monastery-church of *Madonna del Sasso*, a domed structure in which the axis of the choir forms a slight angle with that of the nave. It contains some interesting terracotta work and a good altar-piece. — Bibbiena is the starting-point for a visit to the convent of *La Verna* (about 7½ M.; carriage 8 fr.); comp. *Baedeker's Northern Italy*.

22½ M. *Poppi*, on a hill (1425 ft.) on the left bank of the Arno. 23½ M. *Porrena*.

23 M. *Pratovecchio-Stia*. The station lies between *Pratovecchio* (1410 ft.; *Alb. Bastieri*) and *Stia* (1460 ft.; *Alb. della Stazione Alpina*, well spoken of), two pleasant little towns, with about 3000 inhab., well-adapted as starting-points for expeditions to *Camaldoli* (guide 3-4 fr. per day and food) and other points in the *Casentino* or upper valley of the Arno. *Stia* has an old and partly Romanesque church. — About 1½ M. to the S.W. of *Pratovecchio* is the large ruined castle of *Romena*, mentioned by Dante in the *Inferno* (xxx). For farther details see *Baedeker's Northern Italy*.

FROM AREZZO TO MONTE SANSAVINO, 12½ M., diligence daily, in 2 hrs. The small town of —

Monte Sansavino (*Alb. del Sole*, by the Porta Fiorentina, tolerable) was the birthplace of the famous sculptor *Andrea (Contucci da) Sansovino* (b. 1460, d. 1529). — The church of S. CHIARA, in the principal piazza, contains (left) groups of St. Anthony and the **Madonna and Christ* with four saints, designed by *Sansovino* and executed by the *Robbia's*. On the right SS. Sebastian, Lawrence, and Rochus, by *Sansovino*; **Adoration of the Shepherds* by the *Robbia's*; on the central pillars Sienese paintings of the 15th cent.; to the right and left of the high-altar are prophets by *Vasari*. In the '*Ruga Maestra*', or principal street, on the right, is the *Pal. Municipale*, erected about 1517; the Sala del Consiglio contains a carved **Door* of the 16th century. Opposite the town-hall is a **Loggia* by Ant. da Sangallo the Elder. On the right, farther on, is the church of the *Misericordia*, containing a monument of 1498. On the right we next observe S. *Agostino*, with a façade of the 14th cent.; it contains an Assumption by *Vasari*; the monastery-court is by Ant. da Sangallo the Younger. The *Pal. Filippi*, on the left, No. 17, has fine balcony-railings and lantern-holders in wrought iron, of the 18th century.

From Monte Sansavino to *Smatunga* (p. 18), 9½ M.; or a pleasant round may be made by Fojano and Betolle to *Torrila*, another railway-station (p. 18; one-horse carr. 8-10 fr.). — **Fojano** (*Alb. della Vittoria*, tolerable) is 8 M. from Monte Sansavino. On the right, near the entrance to the town, is S. *Francesco*, with a fine loggia, dating from the end of the 15th cent.; in the interior are several Della Robbia's. S. *Domenico* and the *Collegiata* in the town also contain Robbia's; the latter possesses a Coronation of Mary by Luca Signorelli (?). — At Betolle is the *Villa of Count Passerini*, containing a valuable collection of Etruscan antiquities

(golden bracelet with rams' heads, huge dish with contests of the giants and Bacchic scenes, etc.). One-horse carr. to Torrita ($\frac{3}{4}$ hr.) $2\frac{1}{2}$ -3 fr.

On leaving Arezzo we obtain a beautiful retrospect of the town. To the left is the chain of hills which separates the valleys of the Arno and Chiana from the upper valley of the Tiber. Beyond a tunnel the train runs straight across the plain to (62 M.) *Frassinetto* and (66 M.) *Castiglione Fiorentino*, the latter on a mountain spur. Farther on, to the left, the dilapidated fortress of *Montecchio*. The high-lying *Cortona* next becomes visible to the left in the distance.

The luxuriant *Valley of the Chiana*, which was anciently a lake, was a noisome swamp down to the middle of last century. The level was raised and carefully drained, the brooks being so directed as to deposit their alluvial soil in the bottom of the valley. This judicious system was originated by *Torricelli* and *Viviani*, celebrated mathematicians of the school of Galileo, and carried out by the worthy *Count Fossombroni*, who combined the pursuits of a scholar and a statesman (p. 39). The *Chiana*, Lat. *Clanis*, which once flowed into the Tiber, now discharges most of its waters into the Arno by means of a canal, and only one arm, which joins the Paglia at Orvieto (p. 61), reaches the Tiber.

72 M. *Cortona*. The station lies at the foot of the hill on which the town itself is situated, near the village of *Camuscia*.

A carriage-road ($\frac{3}{4}$ hr.; omnibus 1 fr.) ascends to Cortona, passing S. Spirito on the right, and reaching the town on the S. side. Pedestrians cut off the windings by following the old road, which passes the *Madonna del Calcinajo* (a small early-Renaissance building by Francesco di Giorgio, 1485-1514, with a handsome altar of 1519) and leads to the low-lying S.W. gate of the town (p. 44).

Cortona. — ALBERGO DELLA STELLA, at the W. entrance of the town; ALB. NAZIONALE, farther up in the Via Nazionale, both clean and good. (Enquiry as to charges had better be made beforehand.) Comp. the small Plan at p. 38.

Cortona (2170 ft.), a small, loftily-situated town with 9000 inhab. (whole parish 26,000), lying above the valley of the Chiana, and not far from the Trasimene Lake, is one of the most ancient cities in Italy. Its situation and views, its Etruscan antiquities, and several good pictures it possesses, render it well worthy of a visit.

It appears that the Etruscans, immigrating from the plain of the Po, wrested the place from the Umbrians, and constituted it their principal stronghold when they proceeded to extend their conquests in Etruria. Cortona was one of the twelve confederate cities of Etruria, and with them shared the fate of being converted into a Roman colony. After various vicissitudes and struggles it came under the dominion of Florence in 1410.

LUCA SIGNORELLI, one of the most distinguished painters of the 15th cent., was born at Cortona in 1441. He has justly been called a precursor of Michael Angelo. Like his master Piero della Francesca (pp. 39, 56), he was a zealous student of anatomy; in the embodiment of the nude, in the conception of movement and foreshortening he surpasses all his contemporaries. On the other hand, his deficiency of refined pictorial sentiment forbids the full development of plastic vigour in his pictures. He therefore prefers extensive fresco-paintings to easel-pictures as a suitable field

for his abilities. Frescoes of this kind he has executed in the Sixtine Chapel at Rome (1508; p. 288), at Monte Oliveto (1497; p. 17), and at Orvieto (1499; his principal work, p. 63). His native town, where he held several municipal appointments and lived almost constantly for the last twenty years of his life (d. 1523), still contains a number of his works, none of which, however, are of much importance. — Cortona was also the birthplace of *Pietro Berettini*, surnamed *Pietro da Cortona* (1596-1669), the painter and decorator, who was chiefly employed at Rome and Florence.

From the S. entrance of the town, which we have reached by the road, the VIA NAZIONALE leads in 3 min. to a semicircular terrace on the left, commanding an unimpeded view of part of the Trasimene Lake and the surrounding heights. On the right is the church of —

S. DOMENICO, dating from the beginning of the 13th cent.; on the high-altar an *Assumption by *Bart. della Gatta* (?); on the right, *Madonna with St. Peter Martyr and a Dominican monk, by *L. Signorelli* (1515); on the left, Coronation of the Virgin, by *Lor. di Niccolò* (1440), presented by Cosimo and Lorenzo de' Medici; on the right, *Madonna with saints and angels, an early work of *Fra Angelico*.

The Via S. Margherita, which ascends steeply to the right, see below. The Via Nazionale leads straight to the PIAZZA VITTORIO EMANUELE, where the *Municipio* (Pl. 1) is situated. Here, to the left, diverges the Via Guelfi, in which are situated, to the right, a beautiful palazzo of the 16th cent., and lower down the church of *S. Agostino*, with a Madonna and saints by Pietro da Cortona (beyond this the street leads to the S.W. gate, Porta S. Agostino, p. 43).

Turning to the right from the Piazza Vitt. Em., we immediately reach the small PIAZZA SIGNORELLI, where we observe, opposite to us, the Palazzo Pretorio, and on the left an ancient Marzocco (lion).

The *Palazzo Pretorio* (Pl. 2), with numerous armorial bearings of old magistrates, is now occupied by various public offices, and contains the *Accademia Etrusca*, founded in 1726, which possesses a *MUSEUM OF ETRUSCAN ANTIQUITIES, well worth visiting. (Fee 1/2-1 fr. to the custodian, who lives close by.)

The gem of the collection is a circular Etruscan **Candelabrum* (*lampadario*), made to hold 16 lights; on the lower side in the centre a Gorgon's head, surrounded with a combat of wild beasts; then wave-like ornamentation; and finally eight ithyphallic satyrs, with dolphins below them, alternately with eight sirens; between each pair of lamps a head of Bacchus. — An encaustic painting on slate, representing '*Polyhymnia*', is said to be ancient. — Remarkable *Etruscan Bronzes*, a *Votive Hand* with numerous symbols, *Vases*, *Urns*, *Inscriptions*, etc.

The PONBUNI LIBRARY, in the same building, possesses a fine MS. of Dante.

The Via Casali descends from the Palazzo Pretorio to the —

*CATHEDRAL, a handsome basilica, ascribed to *Antonio da Sangallo*, altered in the 18th cent. by the Florentine *Aless. Galilei*.

The Choir contains a Descent from the Cross, and *Institution of the Last Supper, with predella, by *Luca Signorelli*, very quaint compositions (1512). Also a Pietà, a Conception of Christ, and a Nativity, by the same master. — In the SACRISTY, a Madonna by the same. To the left of the choir, an ancient sarcophagus, representing the contest of Dionysus against the Amazons, erroneously supposed to be the tomb of the Consul Flaminius (p. 46).

Opposite the cathedral is the **Baptistery*, formerly a Jesuit church, containing three pictures by *Fra Angelico da Fiesole*: the Annunciation and two **Predelle*, representing scenes from the life of the Virgin and S. Domenico.

Passing the colonnades of the theatre in the Piazza Signorelli, we follow the Via Dardano straight to the Porta Colonia, where we obtain the best survey of the **ANCIENT ETRUSCAN TOWN WALLS*, constructed of huge blocks, and for the most part well preserved, which surround the town in a circumference of about 2860 yds., and along the outside of which we may descend. Even the gateways are still recognisable.

Ascending the Via S. Margherita from S. Domenico, we reach (20 min.) the hill commanding the town, on which are situated the church of S. Margherita, and a dilapidated fortress (see below). — About halfway up, the Via delle Santucce diverges to the left, and leads in a few minutes to the church of S. Niccolò, with a small entrance-court planted with cypresses.

The INTERIOR (1½ fr.) contains a freely-restored fresco and an **Altarpiece*, painted on both sides (in front the Body of Christ borne by angels and surrounded by saints; at the back, Madonna della Seggiola with SS. Peter and Paul), by *Luca Signorelli*. — The sacristan will point out a direct route, ascending hence by steps to S. Margherita.

The church of S. MARGHERITA, a Gothic building by *Niccolò* and *Giovanni Pisano*, possesses a handsome rose-window, which has of late been partly renewed and enlarged. In the high-altar is the tomb of the saint (14th cent.); the silver front with the golden crown was presented by *Pietro da Cortona*. The platform of the Campanile commands a splendid view. — The visitor should not omit to ascend somewhat higher to the old **FORTEZZA*, 2165 ft. in height (trifling fee; custodian sometimes difficult to find), from the walls of which the noble prospect is entirely uninterrupted, except at the back, where it is bounded by the mountain-chain (*Alto di S. Egidio*, 3430 ft.).

Besides the town-walls, there are several less interesting antiquities: an ancient vault beneath the *Palazzo Cecchetti*; near S. Margherita, remains of *Roman Baths*, erroneously called a '*Temple of Bacchus*'; outside the gate of S. Agostino, an Etruscan tomb, the '*Grotta di Pitagora*'.

The visitor may (by presenting a visiting-card) possibly obtain access to the private collection of *Sig. Colonnese* in the Palazzo Madama, Via Nazionale 5: beautiful half-length picture of St. Stephen and a Nativity by *Luca Signorelli*.

76 M. **Terontola**, an unimportant place near the N.W. angle of the Trasimene Lake, is the junction of the lines to Chiusi, Orte, and Rome (see R. 9), and to Perugia and Foligno. Passengers in the latter direction change carriages here.

The **Lago Trasimeno**, the ancient *Lacus Trasimenus* (845 ft.), is 30 M. in circumference, and 8-14 M. across, and is surrounded by wooded and olive-clad slopes, which as they recede rise to a

considerable height. The lake contains three small islands, the *Isola Maggiore* with a monastery, the *Isola Minore* near Passignano, and the *Isola Polvese* towards the S.; on the W. side an eminence abuts on the lake, bearing the small town Castiglione del Lago (p. 59). Its shores abound with wild-fowl, and its waters with eels, carp, and other fish. The brooks which discharge themselves into the lake gradually raise its bed. The greatest depth, formerly 30-40 ft., is now 20 ft. only. In the 15th cent. a drain (emissarium) conducted the water into a tributary of the Tiber. In ancient times the area of the lake appears to have been smaller. A project for draining it entirely, formed by Napoleon I., is still frequently canvassed.

The reminiscence of the sanguinary victory which *Hannibal* gained here over the Roman consul *C. Flaminius* in May, B.C. 217, imparts a tinge of sadness to this lovely landscape. It is not difficult to reconcile the descriptions of Livy (22, 4 et seq.) and Polybius (3, 83 et seq.) with the present appearance of the lake. In the spring of 217 Hannibal quitted his winter-quarters in Gallia Cisalpina, crossed the Apennines, marched across the plains of the Arno, notwithstanding an inundation, devastating the country far and wide in his progress, and directed his course towards the S., passing the Roman army stationed at Arezzo. The brave and able consul followed incautiously. Hannibal then occupied the heights which surround the defile extending on the N. side of the lake from Borghetto to Passignano, upwards of 5 M. in length. The entrance at Borghetto, as well as the issue at Passignano, were easily secured. Upon a hill in the centre (site of the present Torre) his principal force was posted. A dense fog covered the lake and plain, when in the early morning the consul, ignorant of the plan of his enemy, whom he believed to be marching against Rome, entered the fatal defile. When he discovered his error, it was too late: his entire left flank was exposed, whilst his rear was attacked by the hostile cavalry from Borghetto. No course remained to him but to force a passage by Passignano, and the vanguard of 6000 men succeeded in effecting their egress (but on the following day were compelled to surrender). The death of the consul rendered the defeat still more disastrous. The Romans lost 15,000 men, while the remaining half of the army was effectually dispersed; and the Roman supremacy in Italy began to totter. The slaughter continued for three hours. From the Gualandro two small brooks fall into the lake. One of these, crossed by the road, has been named Sanguinetto in reminiscence of the streams of blood with which it was once discoloured.

The line skirts the lake and passes through a tunnel. 80 M. *Tuoro*; 83 M. *Passignano*. Two tunnels. 89 M. *Magione*, with an old watch-tower of the time of Fortebraccio and Sforza; 97 M. *Ellera*.


103 M. *Perugia*, picturesquely situated on the hill to the left.


7. Perugia.

Arrival. Omnibus to the town (1 fr., in $\frac{1}{2}$ hr.; down 20 min.) in great request, so that no time should be lost in taking a seat (rarely cabs). (Before the first bend of the road to the left, a good path to the right ascends to the town in 20 min.)

Hotels. *GRAND HÔTEL DE PEROUSE, well situated at the entrance to the town near the Prefettura, first class, with corresponding charges (D. 5 fr.); English landlady; rooms not always obtainable unless previously ordered. — GRANDE BRETAGNE or POSTA, at the beginning of the Corso Vannucci, R. from 2, D. 4, B. $1\frac{1}{2}$, L. & A. 1, omn. 1 fr. — Second class: ALBERGO & *REST. BELLE ARTI, Via Danzetta, a side-street of the Corso. R., L., &



[illegible][illegible]



1. Accademia del disegno C.3.
2. Arco di Augusto C.3.5
3. Biblioteca pubblica C.4.
- Chiese
4. Madonna della Luce A.3.
5. S. Agostino C.2.
6. S. Ercolano C.5.
7. S. Domenico C.6.
8. S. Fiorenzo C.4.
9. S. Francesco de' Conventuali A.3.
10. Chiesa nuova B.4.
11. S. Lorenzo (Duomo) B.4.
12. S. Maria Nuova C.D.3.
13. S. Pietro de' Casmensi D.3.
14. S. Severo C.3.
15. S. Spirito B.5.
16. S. Teresa A.4.
17. Banca Nazionale B.5.
18. Casa del Perugino B.4.
19. Palazzo Baglioni C.4.
20. Baldello B.4.
21. Balbeschi B.4.
22. Comunale B.4.
23. Conestabile C.4.
24. Donini B.5.
25. Meniconi C.3.
26. Monaldi B.5.
27. della Penna C.5.
28. Sorbello C.4.
29. del Capitano C.4.
30. Episcopio B.4.
31. Il Cambio B.4.
32. Maestri delle volte B.4.
33. pio Marzia B.5.
34. Torre degli Scalvi A.4.
35. Tribunale C.4.

1 : 15.000

| | X | Piazza d'Armi | C.3 |
|------|--------------------|---------------|------|
| III | Piazza | del Duomo | A.3 |
| IV | de' S. Donato | del Duomo | C.3. |
| V | degli S. abati | del Duomo | D.3 |
| VI | di S. Paolo | del Duomo | C.3 |
| VII | degli Oddi | del Duomo | C.2 |
| VIII | della Chiesa Nuova | del Duomo | E.2 |
| IX | dell'Annunziata | del Duomo | B.7 |



A. 1½ fr., unpretending but clean; ALB. & REST. BELVEDERE, Via Sette, another side-street of the Corso.

Restaurants. *Progresso*, Via Mazzini 31 (Pl. B, C, 4), near the Piazza Sopramuro; see also above. — **Beer** at Via Baglioni 39a.

Cafés. **Baduel*, *Trasimeno*, both in the Corso; *Melinelli*, in the Piazza S. Lorenzo, opposite the cathedral-fountain.

Post Office (Pl. B, 4, 5), Via Baglioni 33. — *Telegraph Office* at the Prefettura, in the Piazza Vittorio Emanuele. — *Diligence Office*, Corso 38; to *Umbertide* (p. 57), daily at 7 a.m. and 4 p.m., 3 fr.; to *Todi* (p. 55), daily at 5.30 a.m., 5 fr.

English Church Service at the Grand Hotel. — *Italian Protestant Church*, Piazza Vittorio Emanuele.

Perugia is well adapted for a summer-resort, and apartments are not expensive. — At least a day or a day and a half should be devoted to the town. Guides are not indispensable, and dilettanti are cautioned against purchasing their 'antiquities'.

Perugia, the capital of the province of Umbria, with 17,000 inhab. (including the villages 51,400), residence of the prefect, of a military commandant, and a bishop, and the seat of a university, lies on a group of hills about 1300 ft. above the valley of the Tiber (1705 ft. above the sea). The town is built in an antiquated style, partly on the top of the hill, and partly on its slope. Numerous buildings of the 14-15th cent. (when the town was at its zenith), the paintings of the Umbrian school, and the fine views of the peculiar scenery, make Perugia one of the most interesting places in Italy.

Perusia was one of the twelve Etruscan confederate cities, and not less ancient than Cortona, with which and Arretium it fell into the hands of the Romans, B. C. 310. It subsequently became a municipium. In the war between Octavianus and Antony, who in the summer of 41 occupied Perusia, and after an obstinate struggle was compelled by the former to surrender (bellum Perusinum), the town suffered severely, and was finally reduced to ashes. It was afterwards rebuilt and became a Roman colony under the name of *Augusta Perusia*. In the 6th cent. it was destroyed by the Goth Totila after a siege of seven years. In the wars of the Lombards, Guelphs, and Ghibellines it also suffered greatly; in the 14th cent. it acquired the supremacy over nearly the whole of Umbria, but in 1370 was compelled to surrender to the pope. Renewed struggles followed, owing to the conflicts between the powerful families of Oddi and Baglioni. In 1416 the shrewd and courageous Braccio Fortebraccio of Montone usurped the supreme power, whence new contests arose, until at length Giovanni Paolo Baglioni surrendered to Pope Julius II. Leo X. caused him to be executed at Rome in 1520. In 1540 Paul III. erected the citadel, '*ad coerendam Perusinarum audaciam*', as the inscription, destroyed during the last revolution, recorded. In 1708 the town was captured by the Duke of Savoy, on 31st May 1849 by the Austrians, and in 1860 by the Piedmontese.

Umbrian School of Painting. As early as the time of Dante an Umbrian artist, the miniature painter ODERISI of *Gubbio*, was celebrated, and art was practised in *Gubbio*, *Fabriano*, *Perugia*, etc. The neighbouring Siena doubtless exercised an influence on the prevailing style of art, which was confirmed by the situation of the towns, the character of their inhabitants, and the religious atmosphere diffused by Assisi and Loreto. Neither dramatic power, nor wealth of imagination is to be found in the Umbrian style, its characteristic features being reverie, tranquillity, and gentleness of sentiment. The men portrayed often appear destitute of individuality and vigour, the female figures, on the other hand, excite our admiration owing to their winning and devout expressions. Technical improvements seem to have been introduced but slowly, but the old style was thoroughly cultivated and rendered more attractive by frequent use of decorative adjuncts.

Setting aside the painters of the 14th cent., who were dispersed among various small towns, we find that *Ottaviano Nelli* of *Gubbio* (15th cent.) was the first able representative of this school. Works by this master are preserved both at his native town and at *Foligno*. Nelli was, however, eclipsed by *Gentile da Fabriano* (b. about 1360), who probably had studied the Siennese masters in his youth, and who afterwards undertook long journeys (e.g. to Venice and Rome), thus establishing his reputation throughout Italy. His style not unfrequently resembles the Flemish. Besides *Gubbio* and *Fabriano*, other Umbrian towns possessed local schools of painting, such as *Camerino* and *Foligno*. The latter, about the middle of the 15th cent., gave birth to *Niccolò Alunno*, a man of limited ability, which, however, he cultivated to the utmost. His prevailing theme is the Madonna, to whose features he imparts beauty in happy combination with reverie; and in this department he may be regarded as the precursor of *Perugino* and *Raphael*.

Meanwhile *PERUGIA*, the largest city in this district, by no means remained idle. In this wider and more enterprising field the old conventional styles were soon abandoned as unsatisfactory, and the necessity of adopting the Florentine style was urgently felt. In the latter half of the 15th cent. *Benedetto Buonfigli* was the first who strove to throw aside the local style of painting, and the same effort was made by *Fiorenzo di Lorenzo*, a younger master and perhaps a pupil of *Benedetto*.

This improved style was brought to maturity by *PIETRO VASNUCCI* of *Città della Pieve* (1446-1524), surnamed *PERUGINO*, after the chief scene of his labours, a master to whom the Umbrian school is chiefly indebted for its fame. *Perugia* was, however, by no means the only sphere of his activity. He repeatedly spent years together in Florence, and was employed for a considerable time in Rome. His endeavours to overcome the defects of his native school were crowned with success. In *Verrocchio's* studio in Florence he was initiated into the secrets of perspective and the new mode of colouring, and in both respects attained consummate skill. Down to the beginning of the 16th cent. his excellence continued unimpaired, as his frescoes in the *Cambio*, and several works in the Gallery at *Perugia* sufficiently prove. During the last twenty years of his life, however, his works show a falling off, occasioned, doubtlessly, by his accepting more orders than he could conscientiously execute, whereby his art was degraded to a mere handicraft. He seems, indeed, to have had more studios than one at the same time, as for example in 1502-5 both at Florence and Perugia, in the latter of which the young *Raphael* was employed.

Another great master of the Umbrian school, vying with *Perugino*, is *BERNARDINO BETTI*, surnamed *PINTURICCHIO* (1454-1513). Although he exercised no considerable influence on the progress of Italian art, and introduced no striking improvements like *Leonardo*, and others, yet he thoroughly understood how to utilise the traditional style and the current forms, and was marvellously prolific as a fresco painter. The Vatican and Roman churches, the Cathedral Library at Siena, and the Collegiate Church at Spello, are the chief scenes of his activity. — Amongst the younger contemporaries of *Perugino* we must next mention *Giovanni di Pietro*, surnamed *Lo Spagna* after his native country, whose paintings are hardly inferior to the early works of *Raphael*, and who, in common with all the Umbrian masters, exhibits great ease of execution.

Other assistants of *Perugino*, but of inferior merit, were *Giannicola di Paolo Manni* (d. 1544) and *Eusebio di S. Giorgio*. The latter was so successful in imitating *Raphael* in superficial respects, that several of his pictures, amongst others the Adoration of the Magi in the picture-gallery at *Perugia* (*Sala del Pinturicchio*, No. 23, p. 50), have been attributed to *Raphael* himself. Of *Sinibaldo Ibi* and *Tiberio d'Assisi*, who flourished during the first twenty years of the 16th cent., little is known, and their works are rare. *Gerino of Pistoja* seems to have been a good painter of the average class, and the works of *Domenico di Paris Alfani*, a friend of *Raphael*, possess considerable attraction. These last masters, however, show little individuality, and before the middle of the 16th cen-

tury the Umbrian school was completely merged in those of Rome and Florence.

At the entrance to the upper part of the town, on the site of the citadel, which was removed in 1860, extends the *Piazza Vittorio Emanuele* (Pl. B, 5), in which rises the *Prefettura*, a simple and handsome modern building, adorned with arcades on the ground-floor. The garden-terrace affords a superb *View of the Umbrian valley with Assisi, Spello, Foligno, Trevi, and numerous other villages, enclosed by the principal chain of the Apennines extending from Gubbio onwards; the Tiber and part of the lower quarters of Perugia are also visible. (A band plays here two evenings a week.)

Northwards from the *Piazza Vittorio Emanuele* runs the *Corso Vannucci* to the left, leading to the cathedral-square; and the *Via Baglioni* to the right, leading to the *Piazza del Sopramuro* (p. 53).

We follow the *CORSO VANNUCCI*, the busiest and handsomest street in the town. On the right (No. 8) is the *Palazzo Baldeschi* (Pl. 21; B, 4); on the 2nd floor is preserved a *Drawing by Raphael (Pinturicchio?) for the 5th fresco in the library of Siena Cathedral (p. 28; fee 1/2 fr.).

On the left, farther on, is the **Collegio del Cambio* (Pl. 31; B, 4), the old chamber of commerce, with the **UDIENZA DEL CAMBIO*, containing celebrated frescoes by *Perugino*, dating from his best period, 1500. (Adm. from 9 a.m.; custodian 1/2 fr.; best light in the morning.)

On the wall to the left of the door. 1st Arch: to the left, *Fabius Maximus*, *Socrates*, and *Numa Pompilius*, with *Prudence* above; to the right, *Enrius Camillus*, *Pittacus*, and *Trajan*, with *Justice* above. 2nd Arch: to the left, *Lucius Sicinius*, *Leonidas*, and *Horatius Coeles*, with *Valour*; to the right, *Scipio*, *Pericles*, and *Cineinnatus*, with *Temperance*. On the pillar between the arches is a portrait of *Perugino*. — Opposite the entrance: to the left, the *Transfiguration* as the fulfilment of faith; to the right, **Adoration of the Magi*, as a revelation of love. — Right wall. 1st Arch: to the left, *Prophets*, to the right *Sibyls*, as the heralds of hope; above, *Jehovah*. The 2nd Arch is occupied by the finely-carved judicial throne and the money-changers' bench. — On the ceiling are medallions of the seven planets, surrounded by admirable arabesques. *Raphael* is said to have been one of *Perugino's* assistants in the execution of these frescoes; his style is traceable in the *Madonna of the Nativity*. *Perugino* received 350 ducats for his work from the guild of merchants. The exquisite carved and inlaid work ('tarsia') of the judicial benches, doors, etc., by *Antonio Mercatello*, which are amongst the finest Renaissance works of the kind, also deserve notice. — The adjacent *CHAPEL* contains an altarpiece and frescoes by *Giannicola Nanni*.

Immediately adjoining the *Collegio* is the **Palazzo Pubblico* (or *Comunale*, Pl. 22; B, 4), a huge edifice of 1281 and 1333, recently skilfully restored, with its principal façade towards the *Corso* and a second towards the *Piazza del Duomo*. It is adorned with fine windows, a handsome portal, and Gothic sculptures (the armorial bearings of the allied towns, saints, etc.). Over the portal in the *Piazza del Duomo* are a griffin and a lion in bronze (14th cent.); below are chains and bars of gates, commemorating the victory gained by the Perugians in 1358 over the Sieneſe. The chief

entrance is in the Corso. On the 2nd floor is the SALA DELLA STATISTICA, with a fine Renaissance door, in a lunette above which is a Madonna by *Fior. di Lorenzo*. On the same floor is the SALA DEL CAPITANO DEL POPOLO, an apartment of noble dimensions. On the 3rd floor is the municipal *PICTURE GALLERY (*Pinacoteca Vannucci*), formed since 1863 of works collected from suppressed churches and monasteries, and of great value to the student of Umbrian art. (Adm. from 9 a.m.; tickets 1 fr., in the Sala della Statistica.) Catalogues provided.

The Vestibule contains a few unimportant pictures and also works of art for sale. Adjoining it is the SALA DEI CINELI (A): 1. *Meo da Siena*, Madonna and saints, a drawing. No. 2. Two saints, and No. 3. The Apostles (the latter as predelle) evidently belong to the same work. 12. *Ambrogio Lorenzetti*, Madonna and four saints; *26. *Margaritone d'Arezzo* (1272), Large crucifixion; 22-24, perhaps by the same master. — SALA B (formerly the *Cappella dei Decemviri*), with frescoes by *Benedetto Bonfigli*. To the right of the windows and on the entrance-wall are scenes from the life of St. Louis of Toulouse. Opposite the windows are the Burial of that saint and the Martyrdom of St. Herculanius on the occasion of the capture of Perugia by Totila. On the adjacent wall is the Burial of St. Herculanius. — From the corridor (C) we enter the SALA DEI STACCHI (D): Frescoes of the Umbrian School (14th and 15th cent.), transferred to canvas. The glass-cases contain codices and choir-books with miniatures. — SALA DI TADDEO BARTOLI (E): Sienese pictures of the 15th cent., most of them valuable. *Taddeo Bartoli* (1403): 9. Madonna with angels and saints; 10. Descent of the Holy Ghost. *Tom. d'Arcangelo of Cortona*: Exploits of the condottiere Braccio Fortebraccio (frieze). — SALA DEL ANGELICO (F): *1-20. *Fra Angelico da Fiesole*, Fragments of a large altar-piece (Madonna with angels, Annunciation, Saints, Miracles of St. Nicholas of Bari); *21. *Piero della Francesca*, Madonna and four saints, with the Annunciation above. — SALA DEL BONFIGLI (G). *Bonfigli*: 7. Annunciation, with St. Mark; 10. Adoration of the Magi; 13. Madonna with angels playing on instruments. *Giovanni Boccati da Camerino*: 16, 19. Madonna and angels. — SALA DI BERNARDINO DI MARIOTTO (H). *Bernardino*: 1. Marriage of St. Catharine; 2. Madonna and saints. 10. *Bonfigli*, 'Gonfalone' (sacred banner) of the Fraternity of S. Bernardino di Siena (Christ blessing the saints, below which are believers burning objects of luxury). 12. *Caporali*, Christ and the Madonna in glory (fresco). *14. *Niccolò Alunno*, Gonfalone of the Brotherhood of the Annunziata (1466). — SALA DI FIORENZO DI LORENZO (J): *4. *Fiorenzo*, Adoration of the Magi (among whose followers is the young Perugino to the left); 24. *Perugino*, Coronation of the Madonna. — GABINETTO DI FIORENZO DI LORENZO (L): *2-9. *Fiorenzo*, Miracles of S. Bernardino (2-6, masterpieces; 7-9, in the same style, but inferior); 16. *Fiorenzo* (?), Bust of the Madonna in a garland, with angels' heads below. — SALA DEL PERUGINO (M). *Carattoli*, Marble bust of Perugino. *Perugino*: 11. Baptism of Christ; 20. Nativity; 21, 16, 12, 7. Predelle; 8, 9, 13, 14, 17, 18, 22, 23. Saints; all being fragments of a large altar-piece. Below No. 4. (St. James, by *Perugino*) is an autograph letter of the master to the Prior of S. Agostino. — SALA DEL PINTURICCHIO (N). *Perugino*: 2. Transfiguration; *3-5. Predelle; 6. Madonna and saints. *7. *Spagna*, Madonna and saints. **Pinturicchio*: Large altar-piece in its original frame, the Madonna with the infant Child and St. John; on the left, SS. Augustine and Jerome; above, the Annunciation; in the pediment, a Pietà; in the predelle, scenes from the lives of SS. Augustine and Jerome; 12. Gonfalone with St. Augustine (on silk). *Perugino*: 14. Madonna, worshippers, SS. Francis and Bernardino; 15. Madonna and saints; 16. John the Baptist with saints. *Raphael*: *17. Strip of decorative painting; 24. God the Father with angels (both belonging to the Entombment in the Galleria Borghese at Rome). *Eusebio di San Giorgio*: 18. Madonna with saints; *23. Adoration of the Magi. 20. *Pupil of Raphael* (?), Madonna, resembling the Conestabile Madonna, formerly in Perugia. — SALA DI GIANNICOLO MANNI E DI BERTO

(O). — SALA DELLA SCUOLA DI PERUGINO (P): 36. *Alfani*, Holy Family, designed by *Raphael*. — The following rooms are the SALA DOMENICO ALFANI, SALA DELLA TORRE, and SALA ORAZIO ALFANI.

The **Biblioteca Pubblica**, which has recently been transferred to this Palazzo, contains about 30,000 vols., and some fine MSS. of the 11-15th cent., with miniatures.

In the PIAZZA DEL MUNICIPIO rises the **Fonte Maggiore*, dating from 1277, and one of the finest fountains of that period in Italy. It consists of three admirably-constructed basins, adorned with numerous biblical and allegorical figures in relief, executed by *Niccolò* and *Giovanni Pisano* and *Arnolfo del Cambio* (1280; two of the statuettes are modern substitutes). — The W. side of the piazza is occupied by the *Episcopal Palace* (Pl. 30), behind which is the so-called *Maestà delle Volte* (Pl. 32), a relic of the Palazzo del Podestà, which was burned down in 1329 and again in 1534.

The **Cathedral of S. Lorenzo** (Pl. 11; B, 4), dating from the 15th cent., is externally unfinished. Adjoining the entrance from the Piazza del Municipio is a pulpit.

The ***Interior**, consisting of nave and aisles with a short transept, is of spacious but heavy dimensions. — On the right of the entrance is the tomb of Bishop Baglioni by *Agostino di Duccio* (1451), beyond which is the CAPPELLA S. BERNARDINO, with a Descent from the Cross, the masterpiece of *Barocci* (1569); the painted window representing the Preaching of St. Bernardino of Siena is by *Constantino di Rosato* and *Arrigo Fiammingo* of Malines (1565; restored in 1863). — Opposite, in the left aisle, is the CAPPELLA DELL' ANELLO, which down to 1797 contained the celebrated Spasializio by Perugino, now at Caen in Normandy. The beautifully carved stalls were begun by *Giulio da Majano* and finished by *Domenico del Tasso* in 1491; the elegant tabernaculum was executed by the goldsmith *Cesarino del Roscello*, in 1519. — Farther on in the nave is a Pietà in relief, by *Agostino di Duccio* (?). — In the RIGHT TRANSEPT, a marble sarcophagus containing the remains of Popes Innocent III. (d. 1216), Urban IV. (d. 1264), and Martin IV. (d. 1285). — The adjoining WINTER-CHOIR contains an *Altar-piece by *Luca Signorelli*: Madonna with SS. John the Baptist, Onuphrius the Hermit, Stephen, and a bishop as donor. Below the 2nd window to the left: Christ imparting his blessing, and saints, by *Lodovico di Angelo*.

In the LIBRARY are preserved precious MSS., such as the Codex of St. Luke of the 6th cent., in gold letters on parchment.

On the W. and N. side of the Cathedral is situated the PIAZZA DANTI (Pl. B, C, 3, 4), with a bronze statue of *Pope Julius III.* by Vinc. Danti (1556). — From the N. angle of the Piazza Danti the Via Vecchia descends to the **Arco di Augusto* (Pl. 2; C, 3), an ancient town-gate with the inscription *Augusta Perusia*. The foundations date from the Etruscan period, and the upper part perhaps from the Augustan epoch after the conflagration. From this point the partly preserved walls of the ancient city, which occupied the height where the old part of the present town stands, may be distinctly traced.

The small space in front of the Arco di Augusto is called the PIAZZA FORTEBRACCIO (Pl. C, 3); to the left is the *Palazzo Galenga*, formerly *Antinori*, by Alessi. — A little to the N. lies the church of *S. Agostino* (Pl. 5; C, 2), to the right of which is an oratory containing several pictures by Alfani, Scaramucci, etc.

From the Palazzo Galenga the Via dell' Università leads in a few minutes to the **University** (Pl. B, 2), established in 1320 in a monastery of Olivetans, which was suppressed by Napoleon. It possesses a small *Botanic Garden*, *Natural History* and *Art History Collections*, and a **MUSEUM OF ETRUSCAN AND ROMAN ANTIQUITIES** (curator, *Sig. Angelo Lupatelli*).

The Museum of Antiquities is on the first floor. On the *Staircase* are Etruscan and Latin inscriptions and unimportant Roman sculptures. The *Corridor* chiefly contains Etruscan urns and a few casts from antique and Renaissance sculptures. *No. 279. Terracotta urn in the form of a recumbent man, who is being seized by a goddess of death with the features of a fiend; the hollow interior once contained the ashes of the deceased. The *Gabinetto di Antiquaria* contains stone weapons, urns, and Etruscan and Roman anticaglias. In the 3rd Room, Mountings of a chariot with figures and ornamentation resembling the most ancient Asiatic style (in a cabinet opposite the windows); large gold Earring with a female head (in a the cabinet in the middle of the room); two Mirrors with scenes from the myths of Meleager and Helen. In the 4th Room, Vase of admirable Attic workmanship, with red figures of Dionysus and Ariadne (cabinet opposite the windows). — The *Guardabassi Collection*, at the end of the second corridor, contains various interesting objects from Etruscan graves. In the 1st Room, Collection of cut stones. In the 2nd Room, fine *Mirror-case, with a representation of Dionysus on the panther, toilette articles, and amber and coral ornaments (catalogue 1 fr.). — *Gabinetto Cristiano*: Central Room, Coffin of Bishop Baglioni, with a sumptuous velvet covering (15th cent.); episcopal vestments of the 16th cent.; richly carved slabs from the confessionals of S. Agostino, perhaps by *Barili*; voting-urn used in municipal elections, with the arms of the Guilds (15th cent.). 2nd Room (to the right), Reliquary containing the remains of the condottiere Braccio Fortebraccio, who fell at the siege of Aquila on 5th June, 1424 (formerly in S. Francesco dei Conventuali); Seal of Card. Bembo by *Lautirio di Perugia*; Madonna by *Agostino di Duccio*, and other terracottas; fine marble *Relief of St. Francis, by *Luca della Robbia*; bust of one of the Baldeschi family (15th cent.); weapons; majolica. In the 3rd Room (to the left) three masterpieces of enamel-work ('champs levés'): a goblet which once belonged to Pope Benedict XI. (d. 1304), and a cup and plate or saucer executed by *Catalorizio di Pietro* of Todi (14th cent.); to the right, ivory carvings, including a circular piece with chessmen, and a representation of French knights starting for the chase (14th cent.). — The Corridor contains mediæval sculptures; statues from the *Maestà delle Volte* by *Agostino di Duccio*; and a model of the *Fonte Maggiore* (p. 51).

The *Natural History Collections* are unimportant.

The *University Church*, the key of which is kept by the curator of the Museum, contains mediæval works of art and plaster casts, including those of an 8th cent. tabernaculum and an early-Christian sarcophagus.

Near the Gate of S. Angelo (Pl. A, 1), to which the Via Longara leads from the Piazza Fortebraccio, is situated the architecturally interesting church of *S. Angelo*, a circular structure with 16 antique columns in the interior, in the style of S. Stefano Rotondo in Rome, probably dating from the 6th cent., with additions of a later period. — On the other (S.) side of the Longara is *S. Agnese*, adorned with frescoes from the later period of Perugino and his pupils.

Ascending from the Piazza Fortebraccio (see above) by the Via Pinturicchio to the S.E. (or from the Piazza Danti, p. 51, by the Via Bontempi to the E.), crossing the Piazza de' Gigli, and then taking the first side-street (Via Raffaello) to the left, we reach ***S. Severo** (Pl. 14; C, 3), formerly a convent of the order of Camaldoli,

now a college, in the chapel of which *Raphael* painted his first fresco, probably in 1505, having left Perugino's school the year before, and gone to Florence. Entrance adjoining the chapel (custodian $\frac{1}{2}$ fr.).

The fresco, which was seriously damaged, and of late has been restored by Consoni, resembles the upper part of *Raphael's* *Disputa* in the Vatican; above, God the Father (obliterated) with three angels and the Holy Ghost; below, the Redeemer and the saints *Maurus*, *Placidus*, *Benedict*, *Romuald*, *Benedict* the Martyr, and *John* the Martyr. The inscription (added at a later period) runs thus: *Raphael de Urbino dom. Octaviano Stephano Volaterrano Priore Sanctam Trinitatem angelos astantes sanctosque pinxit. A. D. MDV.* At the sides, lower down, *St. Scholastica*, *St. Jerome*, *St. John Ev.*, *St. Gregory* the Great, *Boniface*, and *St. Martha*, by *Pietro Perugino*. Inscription: *Petrus de Castro Plebis Perusinus, tempore domini Silvestri Stephani Volaterrani a dextris et sinistris div. Christopherae sanctos sanctasque pinxit A. D. MDXXI.*

A vaulted passage under the clock of the *Palazzo Pubblico* (p. 49) leads from the *Corso Vannucci* to the *VIA DE' PRIORI*, the best route to the sights of the W. quarter. The *Via Deliziosa*, diverging to the left near the small piazza in front of the *Chiesa Nuova* (Pl. 10; B, 4), contains (Pl. 18) the *House of Perugino* (?; denoted by a tablet).

We continue to descend the *Via de' Priori*, passing the mediæval *Torre degli Sciri*, or *degli Scalzi* (Pl. 34; A, 4), and the *Madonna della Luce* (Pl. 4), a pleasing little Renaissance church of 1518, and reach an open space on the right. Opposite us here rises the —

***Oratorio di S. Bernardino** (*Confraternità della Giustizia*; Pl. A, 3). The façade, executed by *Agostino di Duccio*, a Florentine sculptor, in 1459-61, is a magnificent polychrome work, in which both coloured marble and terracotta are employed, while the ground of the numerous and very elaborate sculptures is also coloured. A picture in the interior, representing the festival of the church, contains an admirable view of the façade.

Immediately adjacent is the church of **S. Francesco dei Conventuali**, or *del Prato* (Pl. 9; A, 3), for which *Raphael* painted the Entombment now in the *Borghese Gallery* at Rome (p. 185). Several frescoes of the 13th cent. have recently been discovered in the crypt (Betrothal and Death of the Virgin). The church is in a very precarious state.

To the E. of the *Corso*, and parallel with it, stretches the *PIAZZA DEL SOPRAMURO* (Pl. C, 4), resting on extensive substructions, part of which belong to the ancient Etruscan town-walls. On the E. side of the Piazza rises the *Palazzo del Capitano del Popolo*, afterwards the *Palazzo del Podestà* (Pl. 29), dating from 1472; adjoining it is the *Old University*, built in 1483; both edifices are now occupied by courts of justice (Pl. 35).

The *Via Baglioni* leads hence towards the S. to the *Piazza Vittorio Emanuele* (p. 49). We descend here immediately to the left, passing the substructions of the old citadel, where an ancient gate, called *Porta Marzia* (Pl. 33; C, 5), with interesting sculptures, and the

inscriptions *Augusta Perusia* and *Colonia Vibia*, which was removed from its old site to make way for the fortress, has been re-erected. — We turn to the left here, and follow the broad main street with an avenue of acacias, at the end of which, to the left, rises the small Gothic church of *S. Ercolano* (Pl. 6; C, 5), with an altar consisting of an ancient sarcophagus.

Following the *Corso Cavour*, the continuation of the *Via S. Ercolano*, to the left, we reach a small square in which stands the church of —

S. Domenico (Pl. 7; C, 6), originally a Gothic edifice of the 13th and 14th cent., built by *Giov. Pisano* in 1304, and almost entirely re-erected by *Carlo Maderna* in 1614, with a lofty campanile, part of which has been taken down.

In the *LEFT TRANSEPT* is the *Monument to Pope Benedict XI., who fell a victim to the intrigues of Philip IV. of France, and died in 1304 from eating poisoned figs. It was executed by *Giovanni Pisano*, and is one of the most famous monuments of its kind; above the recumbent figure of the pope rises a lofty canopy, borne by spiral columns and adorned with mosaics (above is a Madonna between St. Dominicus and the kneeling pope on one side and St. Hereulanus on the other). On the adjacent wall is the monument of Bishop Benedetto Guidolotti (1429). — The *CHOIR*, with a rectangular termination, contains a huge Gothic window filled with rich stained glass, the largest of its kind in Italy (218 sq. yds.), executed in 1441 by *Fra Bartolommeo* of Perugia, and recently restored. This window belonged to the original church of *Giov. Pisano*. — The inlaid *Choir Stalls* (tarsia) date from 1476.

After a few minutes more we pass through the *Porta S. Pietro*, richly decorated by Agostino di Duccio (1473), and reach the old monastery and church of —

***S. Pietro de' Casinensi** (Pl. 13; D, 7, 8; entrance in the first court in the corner diagonally opposite, to the left). The church, founded about the year 1000 by S. Pietro Vincioli of Perugia, is a basilica, consisting of nave, aisles, and a transept, with a richly gilded flat ceiling, borne by 18 antique columns of granite and marble and two pillars, and contains numerous pictures.

In the *NAVE*, above, are eleven large pictures by *Ant. Vasillacchi*, surnamed *l'Aliense*, of Perugia, a pupil of Tintoretto and Paolo Veronese, executed in 1592-94. — The *RIGHT AISLE* contains several Umbrian pictures. The chapel of St. Joseph, adorned with modern frescoes, contains, on the left, the monumental *Relief of a Countess Baldesehi, in terracotta, from a drawing by *Fr. Overbeck*; on the right, Holy Family, a copy from Andrea del Sarto, by *Pontorno*. — Then, above the door leading to the monastery, Two saints by *Sassoferrato*, after Perugino, and a Holy Family after *Bonifacio* of Venice. Above the door leading to the Sacristy, Three saints, also after Perugino by *Sassoferrato*. — In the *SACRISTY* (shown by the custodian, 5 soldi) are five small half-figures of *Saints, by *Perugino* (which formerly surrounded the Ascension by the same master, removed by the French, now in Lyons); Holy Family, by *Parmeggianino*; *Infant Jesus and St. John, after Perugino, by *Raphael* (?); S. Francesca Romana, by *Caravaggio*. — The *Choir-books* are embellished with good miniatures of the 16th century.

The **CHOIR STALLS*, in walnut, are admirably carved and inlaid (tarsia) by *Stefano da Bergamo*, 1535; the doors at the back are by his brother *Damiano*. — Under the arch of the Choir, on each side, are ambones (pulpits) in stone, with reliefs on a golden ground, by *Franc. di Guido*, 1517-21.

The LEFT AISLE, beginning at the upper end by the choir, contains a picture by *Buonfigli* (?), Mary with the body of Christ and two saints, 1469. In the adjoining chapel is a marble altar with reliefs, partly gilded, by *Mino da Fiesole*, 1473. In the next two chapels: pictures by *G. Reni*, *Giorgio Vasari*, and others. Between these, on the wall of the aisle: Judith, by *Sassoferrato*. Then, Adoration of the Magi, by *Eusebio di S. Giorgio*; Annunciation, after Raphael, by *Sassoferrato*; Pietà, a late work of *Perugino*, part of a large dismembered altar-piece from the church of S. Agostino.

Close to S. Pietro, on the opposite side of the street, are the gardens of the *Passeggiata Pubblica* (Pl. D, 8), extending to the Porta S. Costanzo, and commanding a magnificent *Prospect of the valley of Foligno and the Apennines.

The visitor may also inspect the following private collections: the collection of *Avv. Romualdi*, Via del Bufalo, No. 5 (near the Albergo Gran Bretagna), comprising bronzes, coins, cameos, drawings and paintings by *An. Carracci*, *Perugino* (?), etc. (for sale). — The *Galleria Monaldi* (Pl. 26; B, 5), in the palazzo of that name, at the corner of the Via Baglioni and the Piazza Vittorio Emanuele, and the *Galleria Meniconi* (Pl. 25; C, 5), Via di Porta Romana, both chiefly contain works of later masters (end of 16th and 17th cent.).

Outside the Porta del Carmine lies the Cemetery (Pl. E, 3), containing a monument to the champions of liberty in 1859.

Outside the Porta S. Costanzo, on the road to Assisi, lies the church (restored) of *S. Costanzo* (Pl. D, E, 8), dating from the 11th cent., with an ancient portal. — About 3 M. to the E. of Perugia, $\frac{3}{4}$ M. on this side of *Ponte S. Giovanni* (p. 72), the first station on the route to Foligno and Rome, the ANCIENT ETRUSCAN NECROPOLIS of Perugia was discovered in 1840. Carriage there and back, a drive of $1\frac{1}{2}$ -2 hrs., 12 fr. — The most interesting of the tombs, and one of the handsomest, though not oldest in N. Etruria, is the **Sepolcro de' Volumnii* (the tomb of the Volumnii, 3rd cent. B. C.), close to the road, where it is intersected by the railway. It consists of ten chambers, hewn in the coarse-grained tufa. A number of cinerary urns, with portraits of men and women, and various kinds of decoration, were found here. Some of the objects found in the tomb have been left in their original positions, but most of them are now preserved in a chamber built above it. The custodian is to be found at the neighbouring *Villa Baglioni* (fee $\frac{1}{2}$ fr., for a party 1 fr.).

The convent of *Montefiorentino*, between Perugia and Assisi, contains a Madonna by *Giov. Santi* (1489).

FROM PERUGIA TO TODI, about 28 M. (diligence, see p. 47). This road, once greatly frequented, but now of merely local importance, descends rapidly into the valley of the Tiber, which it crosses, and then remains on its left bank. The scenery presents no great attractions. About halfway between Perugia and Narni, and 19 M. to the E. of Orvieto, lies —

Todi (*Posta*, at the gate), the ancient Umbrian *Tuder*, a high-lying town (1495 ft.) with 4-5000 inhab. (commune 15,500); the hill is so abrupt that the upper part of the town is not accessible to carriages. Its ancient importance is indicated by the fragments of walls and the extensive ruin of a *Temple*, or *Basilica*, usually styled a temple of Mars. Although poor in treasures of art, the town boasts of several interesting edifices, among which are the *Cathedral* and the *Town Hall* in the Piazza. The church of *S. Fortunato* possesses a handsome portal. The finest building of all, however, is the pilgrimage-church of **S. Maria della Consolazione*, in the form of a Greek cross and covered with a dome. The arms of the cross are also surmounted with domes, and are polygonal in shape with the exception of the choir, which is semicircular. The exterior is remarkable for its simple and massive style, and the interior for its symmetrical proportions and the delicately graduated ornamentation of its pillars. Being one of

the noblest creations of the Renaissance period, this edifice was naturally attributed to Bramante. Documents, however, name *Cola di Matteuccio da Caprarola* (1508) as the architect, and *Baldassare Peruzzi* as his adviser. The progress of the building was remarkably slow, and it was not completed till 1604. — Todi was the birthplace of *Jacopone da Todi* (d. 1306), author of the 'Stabat mater dolorosa'.

FROM TODI TO NARNI, 28 M., by the villages of *Rosaro*, *Castel Todino*, and *San Gemine*. About 1½ M. from the last, on the ancient, now abandoned *Via Flaminia*, are the interesting ruins of the once prosperous *Cursulae*. From *San Gemine* (7½ M. from *Narni*) two roads descend gradually to the beautiful valley of the *Nera*, one leading S.E. to *Terni* (see p. 84), and the other S. to *Narni* (p. 87).

8. From Arezzo to Fossato.

84 M. RAILWAY (*Ferrovia dell' Appennino Centrale*): one through-train daily in about 5 hrs. (fares 12 fr. 25, 7 fr. 65 c.).

Arezzo, see p. 38. — For a short distance the train follows the line to *Rome* (p. 20), but it soon diverges and begins to ascend more rapidly towards the hills to the E. of *Arezzo*, affording a picturesque retrospect of the town and plain. It mounts as far as the *Scopettone*, the W. parallel chain of the Umbrian Apennines, separating the valleys of the *Arno* and *Tiber*. This part of the line, the most interesting from an engineering point of view, traverses 20 tunnels and several viaducts. — Beyond (11 M.) *Palazzo del Pero* we descend to the N. E. through the wooded valley of the *Cerfone*, a tributary of the *Tiber*. — 19½ M. *Ville Monterchi*, situated in a hollow, from which a steeper ascent leads to (20½ M.) *Citerna*. — 24½ M. *Anghiari*, a small town picturesquely situated on a hill, commands an extensive view of the upper valley of the *Tiber*, here about 7 M. wide.

The train traverses the highly cultivated plain, crosses the *Tiber*, and reaches (28½ M.) *Borgo S. Sepolcro* (*Alb. Venezia*), a little town at the foot of the *Monte Maggiore* (4430 ft.). The churches and the *Palazzo del Comune* contain several pictures by *Piero della Francesca* (b. 1423; teacher of *Luca Signorelli*; comp. p. 39) and *Raffaello dal Colle* (16th cent.; a pupil of *Raphael*), both of whom were born here. In *S. Antonio Abbate*, a fine *Crucifixion* by *Signorelli*, originally a church-banner.

From *Borgo S. Sepolcro* a road crosses the Central Apennines to *Urbania* (31 M.), formerly *Castel Durante*, the probable birthplace of *Bramante*, and *Urbino* (p. 88). — The Source of the *Tiber*, near the village of *Le Balze*, about 16 M. to the N., may be visited from *Borgo S. Sepolcro*.

The railway proceeds to the S.E. along the left bank of the river. 31 M. *S. Giustino*; 33½ M. *Selci Lama*, a little to the right of the village of that name.

38 M. *Città di Castello* (*Locanda la Cannoniera*), with 7000 inhab. (commune 24,000), occupying the site of *Tifernum Tiberinum*, which was destroyed by *Totila*. In the 15th cent. it belonged to the *Vitelli* family, and afterwards to the Church. The town, built in the form of a rectangle, and still surrounded by the walls erected in 1518, contains many interesting small buildings of the early-Renaissance period, but few mediæval monuments.

Of the numerous churches *S. Domenico* alone has preserved a Gothic character. All that remains of the old CATHEDRAL OF *S. FLORIDO*, founded in 1012, is the campanile and the N. portal; the present building, an admirable specimen of the Renaissance style, was begun in 1480 and completed in 1540. Bramante has been frequently named as the builder, but *Elia di Bartolommeo Lombardo* is mentioned in the records as the architect.

Among the secular buildings, the *Palazzo Comunale*, built in the 14th cent. by a certain Angelus of Orvieto, in the style of the Florentine palaces, retains most closely its original form. The Vitelli, the lords and masters of the town, like most of the magnates of the Renaissance period, were passionately addicted to building. The oldest of the four palaces of the 15th and 16th cent. bearing their name is the *Palazzo di Alessandro Vitelli*; the handsomest is the *Palazzo Vitelli a S. Giacomo*, and the largest the *Palazzo Vitelli a Porta S. Egidio*. The small summer-house (*Pallazzino*) of the latter deserves special notice.

The PINACOTECA, newly opened, now contains the more important paintings and works of art formerly in the churches.

Raphael, it is well known, painted his first independent works for churches in Città di Castello, but they have since disappeared, or (like the *Sposalizio* now in the Brera at Milan) have been carried elsewhere. The only work of his now here is a church-banner, with (No. 32) the Trinity and (No. 16) the Creation, painted on linen. An Adoration of the Shepherds by *Luca Signorelli*, a Coronation of the Virgin of *Signorelli's* school (No. 8), and several terracottas by *Luca della Robbia* and his school, are also noteworthy.

The church of *S. Cecilia* contains a Madonna by *Luca Signorelli*, and the *Palazzo Mancini* a *Nativity by the same master, as well as several other valuable pictures.

Beyond Città di Castello the train follows the right bank of the Tiber. 43 M. *S. Secondo*, at the mouth of a lateral valley. On a height to the right, $1\frac{3}{4}$ M. from this station and as far from ($45\frac{1}{2}$ M.) *Trestina*, the next, lies *Canoscio*, a frequented pilgrim-resort. Beyond (50 M.) *Montone Monte Castelli* we cross the Tiber and reach (53 M.) *Umbertide* (Alb. Guardabassi), a small town on the left bank of the Tiber, the valley of which is here somewhat narrow. In the church of *S. Croce* is a Descent from the Cross by *Luca Signorelli*. Diligence to Perugia, see p. 47.

Beyond (55 M.) *Monte Corona* the railway quits the Tiber and ascends to the N. through the narrow valley of the *Assino*, crossing the stream six times. — 57 M. *Serra Partucci*; $59\frac{1}{2}$ M. *Campo Reggiano*. At (64 M.) *Pietralunga* we reach the fertile tableland of Gubbio. To the left rise the *Monte Calvo* (2965 ft.) and the *Monte d'Ansiano*.

70 M. *Gubbio* (*Albergo del Giardino*, formerly the *Leon d'Oro*; *Rosetta* or *Colomba*, both in the Piazza Vittorio Emanuele and well spoken of), with 5000 inhab., lies at the foot and on the slopes of *Monte Calvo*, at the entrance to a gorge flanked by steep cliffs.

The town presents quite a mediæval appearance, and the proximity of the Apennines also gives it a different character from most other Italian towns. Conspicuous among the houses is the huge Palazzo dei Consoli, and above them towers the church of S. Ubaldo.

Gubbio is the ancient *Iguvium* or *Eugubium*, mentioned by Cicero and Cæsar. It was destroyed by the Goths, was besieged in 1155 by the Emp. Frederick I., then became an independent state, afterwards belonged to the duchy of Urbino, and with it finally accrued to the States of the Church.

Gubbio was the native place of *Oderisi*, a famous miniature painter (d. about 1300), who is called by Dante in his *Purgatorio* (xi,80) 'l'Onor d'Agobbio'; but no authentic work by his hand now exists. In the 14th and 15th cent. a branch of the Umbrian school flourished here, and among its masters, whose renown extended even beyond their native place, were *Guido Palmerucci* (1280-1345?) and several members of the *Nelli* family, particularly *Ottaviano Nelli* (d. 1444). — Gubbio occupies a still more important page in the history of ARTISTIC HANDICRAFTS. Like Urbino, Pesaro, and Faenza, it was noted for the manufacture of *Majolica*, or earthenware vases and tiles which were covered with a white coating of colour before being baked. One of the most distinguished majolica painters was '*Maestro Giorgio*' of Gubbio, who is said to have invented, or rather rediscovered and perfected, the metallic, ruby-coloured glazing for which the Italian majolicas are remarkable.

At the bottom of the spacious Piazza Vittorio Emanuele is the church of *S. Francesco*. We ascend hence by old-fashioned streets to the PIAZZA DELLA SIGNORIA, on the slope of the hill, supported by massive vaults, where the most conspicuous building is the —

*PALAZZO DEI CONSOLI, a huge pinnacled edifice with a tower, erected in 1332-46 by *Giovanello Maffei* of Gubbio, surnamed *Gattapone*, and at present disused. The ground-floor contains a slab with an inscription of the Augustan period. The Loggia affords a beautiful view, embracing the ruins of the Roman theatre in the plain (p. 59), and on the other side, the old façade of the Palazzo Ducale (fee $\frac{1}{2}$ fr.).

The PALAZZO PRETORIO, now 'Residenza Municipale', contains several collections recently united here (fee $\frac{1}{2}$ -1 fr.).

On the first floor are the so-called *Eugubian Tablets*, which were discovered in 1440 near the ancient theatre. They are of bronze, and bear inscriptions, four in Umbrian, and three in Latin characters, which long baffled the investigation of the learned. They contain in the Umbrian language, an old Italian dialect akin to Latin, liturgical regulations and formulæ of nearly uniform import, dating from different periods. The older, in the Umbrian character, are read from right to left. The later, in Latin letters, date from about the 2nd cent. B.C.

The upper saloon (handsome door) contains a number of pictures, including several fine works, chiefly of the Umbrian school; admirable *Wood-carving of the 15th and 16th cent.; cabinets, chairs, and a number of ancient and modern *Majolicas.

The third side of the piazza is occupied by the modern *Palazzo Ranghiasci-Brancalone*. — *Conte Fabiani-Beni*, Piazza S. Martino, possesses several good pictures.

Ascending the Via dei Duchi to the left, and then following the Via di S. Ubaldo, we reach the *PALAZZO DEI DUCHI, an old Gothic edifice, which was remodelled by *Luciano Lauranna*, the architect of the palace of Urbino. The colonnaded court is almost an

exact reproduction of that of Urbino. The interior is quite a ruin and accessible only with difficulty.

Opposite the entrance to the court of the Pal. dei Duchi rises the CATHEDRAL OF SS. MARIANO E JACOPO MARTIRE, a structure of the 13th cent., destitute of aisles and so built against the slope of the hill that its back is embedded in the ground. The façade is adorned with sculptures of the Evangelists (13th cent.).

Among the pictures in the interior (first altar on the left) is a Madonna with SS. Ubaldo and Sebastian, by *Sinibaldo Ibi* of Gubbio. By the 2nd altar a *Coronation of Mary Magdalene by *Timoteo della Vite*. The sacristy contains a Flemish vestment, presented by Pope Marcellus II.

The church of S. MARIA NUOVA, situated near the E. end of the Via delle Fonti, running above and parallel with the Corso, at the corner of the Via Nelli, contains an admirably-preserved Madonna by *Ottaviano Nelli*, 1403 (apply to the sacristan), a Madonna in fresco by *Bernardino di Nanni*, frescoes by *Guido* on the entrance-wall, and a St. Anthony by *Guido*, on the wall to the left of the door.

The Via Paoli leads from the end of the Corso Garibaldi to the fine Gothic church of *S. Giovanni* (13th cent.). — At the other end of the Corso is the church of *S. Pietro*, with a 12th cent. façade (decayed). — *S. Domenico*, *S. Agostino* (frescoes in the choir ascribed to Ottaviano Nelli), and *S. Maria della Piaggiola* (outside the Porta Vittoria; over the high-altar, *Madonna by Gentile da Fabriano) also contain pictures of the same period.

The ancient town extended farther into the plain than the modern. Among the ruins still existing is a *Theatre*, discovered in 1863, apparently of the republican era. It is not entirely excavated, but part of the external row of arches is preserved, and the stage, facing the town, is distinctly traceable. (We quit the Piazza Vittorio Emanuele by the Porta Trasimeno, turn to the right, and lastly pass through a modern gateway on the left, towards a farm.)

73 M. *Padule*. Beyond (78½ M.) *Branca* we cross the *Chiascio* and traverse the valley of that stream to —

84 M. *Fossato*, see p. 109.

9. From Florence to Rome viâ (*Arezzo*) Terontola and Chiusi.

195 M. RAILWAY. This is the shortest route from Florence to Rome. Express in 7½-7¾ hrs. (fares 39 fr. 5, 27 fr. 30 c.); ordinary train in 12¾ hrs. (fares 35 fr. 50, 24 fr. 80, 16 fr.); no change of carriages.

From *Florence* to *Terontola*, 76 M., see pp. 37-46. The main line to Rome diverges to the right (S.) from the branch-line to Perugia, Assisi, and Foligno, and at first skirts the W. bank of the Trasimene Lake (comp. p. 45).

82 M. *Castiglione del Lago*, lying to the left on a promontory extending into the lake, possesses an old palazzo of the Duchi della Cornia, built by Alessi.

86 $\frac{1}{2}$ M. *Panicale*, a small place with unimportant frescoes in its churches by Perugino and his school. The line takes a W. direction and joins the line from Siena in the valley of the *Chiana* (R. 4).

93 $\frac{1}{2}$ M. **Chiusi**. — The RAILWAY STATION (**Restaurant*) is about 1 $\frac{1}{2}$ M. from the town, on the hill to the right. 'Posto' (seat in a carriage) to the town 1 fr., two 'posti' 1 $\frac{1}{2}$ fr.

AQUILA D'ORO, well spoken of; CORONA, Via Porsenna 1, unpretending and moderate; ETRURIA, at the station.

Travellers who wish to inspect the ETRUSCAN ANTIQUITIES should enquire for the custodian, who sells tickets for the museum ($\frac{1}{2}$ fr.) where he is generally to be found, and accompanies visitors to the tombs (2 fr.; or, for the whole day, 3-4 fr.). The road to the tombs is very muddy in wet weather. — Travellers are cautioned against making purchases of Etruscan antiquities at Chiusi, as 'antiquities' from Etruscan tombs are largely manufactured here.

Chiusi (5000 inhab.), the ancient *Clusium*, one of the twelve Etruscan capitals, frequently mentioned in the wars against Rome, and as the headquarters of Porsenna, was fearfully devastated by malaria in the middle ages; but under the grand-dukes of the House of Lorraine the Val di Chiana was gradually drained, and the town recovered from these disasters. The walls are mediæval; a few relics of those of the Etruscan period are traceable near the cathedral, outside the *Porta delle Torri*. A walk thence round the town to the *Porta Romana*, also called *Porta di S. Pietro*, affords pleasing views of the S. portion of the Chiana Valley, Città della Pieve, the mountains of Cetona, to the N. the lakes of Chiusi and Montepulciano, and the latter town itself. Under the town extends a labyrinth of subterranean passages, the precise object of which is unknown (inaccessible); but they probably belonged to an elaborate system of drainage, as the ancient Etruscans excelled in works of this kind, and were even in advance of many modern nations.

The interesting MUSEO ETRUSCO, founded a few years ago, contains a valuable collection of objects found in the Etruscan tombs around Chiusi, such as vases (including several curious polychrome urns), dishes, bronzes, mirrors, sarcophagi, and especially cinerary urns, chiefly of terracotta, with a few of alabaster and travertine.

The *Cathedral of S. Mustiola* consists almost entirely of fragments of ancient buildings; the eighteen columns of unequal thickness in the interior, and the tomb of S. Mustiola are derived from a similar source. The sacristy contains a mass-book illuminated with admirable miniatures of the 15th cent., chiefly by artists of the Siennese school. The walls of the arcades in the cathedral square bear numerous Etruscan and Roman inscriptions.

The great attraction of Chiusi are the ETRUSCAN TOMBS (tickets of admission and guide, see above), situated in isolated hills at some distance from the town. The most important are the following: to the N.E. the *Deposito del Granduca*, 3 M.; near it, the **Deposito della Scimia*, with mural paintings representing gladiatorial combats. The *Deposito del Poggio Gajelli*, which is supposed, but without authority, to be the *Mausoleum of Porsenna* mentioned by Pliny and

Varro, is 3 M. distant and much dilapidated. To the N.W., the *Deposito delle Monache*, 2 M.; then, to the S.E., the *Deposito del Colle*, with mural paintings, 1 M. from the town.

Near *S. Calerina*, on the way to the station, are small catacombs of the early-Christian period, and near them a Roman tomb.

About $3\frac{1}{2}$ M. to the S.W. of Chiusi lies the little town of *Sarteano* (about 1970 ft.), above which rises an ancient castle. The *Villa Bargagli* contains a collection of sarcophagi, vases, small bronzes, and other antiquities found in the neighbourhood, to which admission is courteously granted.

A diligence runs from the Chiusi station in 1 hr. to the (5 M.) lofty situated town of *Città della Pieve* (1010 ft.), with 6000 inhab., the birth-place of *Pietro Vannucci* (1446-1524), surnamed *Perugino* after Perugia, which was the chief scene of his labours (comp. p. 48). The town possesses several of his pictures, but they are works of his later period, hastily painted and chiefly done by his pupils, as the master apparently deemed his native place not capable of appreciating works of a more elaborate kind. — The oratory *dei Disciplinati*, or *S. Maria dei Bianchi*, contains an Adoration of the Magi, one of the largest pictures by Perugino; two letters of the artist from Perugia (1504) are shown with regard to the price of this fresco, reducing it from 200 to 75 ducats. — In the *Cathedral* (interior modernised) is the Baptism of Christ (first chapel to the left), and in the choir a Madonna with SS. Peter, Paul, Gervasius, and Protasius, 1513. The picture of St. Antony with St. Paulus Eremita and St. Marellus, now (since 1860) in *S. Agostino*, belonged originally to the church of S. Antonio. All these pictures are by Perugino. — Outside the Orvieto gate is the church of *S. Maria dei Servi*, containing remains of a Crucifixion by Perugino, dating from 1517.

The road leading from Città della Pieve in an E. direction to Perugia (31 M.) was formerly much frequented.

About $7\frac{1}{2}$ M. to the S.W. of Chiusi (carriage in $1\frac{1}{4}$ hr.), and at the same distance to the W. from Città della Pieve, lies the small town of *Cetona*, commanded by a mediæval castle. The *Palazzo Terrosi* contains a small collection of antiquities found in the neighbourhood (visitors generally admitted on presenting their cards), such as handsome polychrome and richly gilded urns; an *Elephant's tusk with archaic reliefs from the *Odyssey*, etc. — Picturesque grounds at the back of the palace.

The RAILWAY descends the Chiana valley. $104\frac{1}{2}$ M. *Ficulle*; the village, $2\frac{1}{2}$ M. distant, lies on a hill to the right. 111 M. *Allerona*. Near Orvieto the Chiana falls into the *Paglia*, a turbulent tributary of the Tiber, which causes great damage in rainy seasons. The rock here is tertiary sandstone, while at Orvieto the volcanic district begins, of which the central point is the lake of Bolsena (p. 65).

$118\frac{1}{2}$ M. Stat. *Orvieto* (440 ft.), at the base of the hill occupied by the town, to which a cable-tramway (*Funicolare*; 5 min.; 30 c.), 520 yds. in length, ascends at a gradient of 27 : 100, passing through a tunnel under the Fortezza.

Orvieto. — GRAND HÔTEL DELLE BELLE ARTI (Palazzo Bisenzi), Corso Cavour, well spoken of; R. from 3, D. 5, déj. 3, B. $1\frac{1}{2}$, L. & A. $1\frac{1}{2}$, omn. $1\frac{1}{4}$ fr. — ALB. D'ITALIA, near the Piazza del Popolo, fair; AQUILA BIANCA, Via Garibaldi, behind the Palazzo Comunale, unpretending, R. 2 fr. — **Locanda Valentini*, Via S. Andrea 17, unpretending. — *Caffè Benedetti*, Piazza Vittorio Emanuele.

The Wine of Orvieto is esteemed both here and at Rome.

Photographs of Signorelli's frescoes sold by Armoni, near the Cathedral.

who are zealous in their endeavours to secure works by the best artists, they did all in their power to obtain the services of the first masters of the day for the embellishment of their church.

The ***FAÇADE* (1310-30), with its three gables, 44 yds. wide and 160 ft. high, is gorgeously enriched with sculptures and mosaics, and is probably the largest and most gorgeous 'polychrome' monument in existence.

The excellent **BAS-RELIEFS* on the lower parts of the pillars, which in many respects are characteristic of the transitional style preceding the Renaissance, represent scenes from the Old and New Testament: 1st pillar to the left, from the Creation down to Tubal Cain; 2nd, Abraham, genealogy of the Virgin; 3rd, History of Christ and Mary; 4th, Last Judgment with Paradise and Hell; above are the bronze emblems of the Evangelists, by *Lor. Mailani*. Above the principal portal, a Madonna under a canopy, in marble, by *Andrea Pisano*. On the margin of the large square panel, in the centre of which is a rose-window, are small marble statues of prophets, and above, of the Apostles, executed by Sienese sculptors.

Above the doors and in the three pointed gables are **MOsaics* on a golden ground, of various periods (14-19th cent.): Annunciation, Nuptials of the Virgin, Baptism of Christ, Coronation of the Madonna; the latter, the principal picture, is the highest.

The **Interior* is at present undergoing restoration, and, except to the Cappella Nuova (see below), admission is only granted by leave of the superintending engineer (Pal. de' Papi, to the S. of the Cathedral; p. 64). It is constructed, like that of the Siena cathedral, of alternate layers of dark and light stone (black basalt and greyish-yellow limestone from the vicinity). On each side four columns and two pillars separate the nave, which is 131 ft. in height, from the lower aisles. Above the round-arched arcades is a gallery adorned with rich carving. The windows are pointed, and the upper parts filled with stained glass. The visible framework of the roof was formerly richly ornamented.

At the sides of the principal entrance, to the right, St. Sebastian by *Scalza*, to the left, St. Rocco. In the *LEFT AISLE*, Madonna and St. Catharine, a fresco by *Gentile da Fabriano*. Before this stands a marble **Font*, the lower part by *Luca di Giovanni* (1390), the upper by *Sano di Matteo* (1407). — In the *NAVE*, to the right, a fine marble holy water basin in the Renaissance style; in front of the columns, statues of the Apostles, by *Mosca*, *Scalza*, *Toti*, *Giov. da Bologna*, and other masters. — In the *CHOIR*, frescoes from the life of the Virgin by *Ugolino d'Ilario* and *Pietro di Puccio*. By the high-altar the Annunziata and Archangel, by *Mocchi*, one on each side. The beautifully inlaid stalls in the choir are by artists of Siena, of the 14-15th cent.; on each side is an altar with reliefs in marble: on the left, Visitation of Mary, executed by *Moschino* when 15 years of age, from designs by *Sammicheli*; to the right, Adoration of the Magi, by *Mosca*.

Right Transept. The ***CAPPELLA NUOVA*, containing a miraculous image of the Virgin (*Madonna di S. Brizio*), may be entered from the back at any time by passing round the cathedral to the left. This chapel occupies an important page in the annals of Italian art. Don Francesco di Barone, the superintendent of the cathedral-mosaics, having heard that the 'famous painter and monk' *Fra Angelico da Fiesole* was not engaged during the summer in Rome (p. 299), invited him to Orvieto, and secured his services for the decoration of the chapel. In 1447 *Fra Angelico* accordingly worked here, but for three months only, during which time he executed two panels of the vaulting above the altar, representing Christ in the glory as Judge, and saints and prophets to the right. Nothing more was done till 1499, when the work was continued and completed by *Luca Signorelli*. These ***Mural Paintings* are the chief attraction here. The first fresco to the left of the entrance shows the overthrow of Antichrist, who is represented in the foreground, preaching; the two devout figures, in the corner to the

left, are said to be portraits of Signorelli and Fra Angelico. The wall on the side by which we enter has been skilfully covered with representations of (left) the Last Judgment, and (right) the Fall of the Condemned. — Next in order are the Resurrection of the Dead and the Punishment of the Condemned; then, on the wall of the altar, (right) Descent into Hell, and (left) Ascent into Heaven, and lastly, adjoining the first picture, Paradise. — Below these pictures runs a series of scenes from Dante's Divine Comedy, and mythological subjects. On the ceiling: Apostles, 'signa iudicium indicantia', patriarchs and doctors, virgins and martyrs. — These paintings are the most important work produced during the 15th century. In the mastery of form, in the boldness of motion and of foreshortening, and in the acquaintance with the nude, Signorelli is by no means unworthy of comparison with Michael Angelo, who, according to Vasari, borrowed several motives from these works for his Last Judgment in the Sistine Chapel. — *Signorelli* also completed the decoration of the vaulting, and painted the 'Entombment in the niche behind the Pietà of *Scalza* (1572).

Opposite, in the *Left Transept*, is the *CAPPELLA DEL CORPORALE*, where, behind the principal altar, is a canopy of marble mosaic, containing a silver reliquary, in which is preserved the blood-stained chalice-cloth (corporale) connected with the Miracle of Bolsena (p. 66). The reliquary, executed by *Ugolino di Vieri* of Siena in 1338, and resembling in form the façade of the cathedral, is about $4\frac{1}{2}$ ft. broad, 2 ft. high, and 440 lbs. in weight. The Passion and the 'Miracle' are represented on it in brilliant enamel; it is exhibited to the public on Corpus Christi and on Easter Day, but at other times it is shown only by permission of the Sindaco. Modernised frescoes of the 'Miracle of Bolsena' by *Ugolino*. Over the altar on the left, a Madonna by *Lippo Memmi*.

Opposite the cathedral are *Conte Faina's* private collection of Etruscan antiquities, and, to the right, the **OPERA DEL DUOMO* (Pl. 2), containing the *Museo Municipale*. Tickets are obtained at Armoni's photograph-shop (p. 61), at the corner of the Piazza S. Maria and the Via del Duomo.

GROUND FLOOR. *Room I.* Weapons, bronzes, pottery, etc., from the Etruscan Necropolis (p. 65). Plan of the excavations. (The formation of an Etruscan Museum in the *Palazzo del Capitano*, in the Piazza del Popolo, is contemplated.) — *Room II.* Architectural ornaments in terracotta, from a Roman temple, the remains of which were discovered in a new street near the Giardino Pubblico. Reconstruction of an Etruscan tomb.

The **FIRST FLOOR** contains mediæval works of art belonging to the Opera del Duomo. Designs on parchment for the façade of the cathedral, and for a pulpit, which was never completed; a beautifully carved and inlaid reading-desk; a precious *Reliquary by *Ugolino di Vieri* and *Viva da Siena*; vestments; two statues representing the Annunciation, by *Friedrich of Freiburg* (14th cent.); two specimen frescoes by *Signorelli*, representing himself and a certain Niccolò Franceschi; a *Madonna, a statue by *Giov. Pisano*, partly coloured, etc.

Adjoining the cathedral on the right, behind, are the *Palazzo Vescovile* (12-13th cent.), and more in front the *Palazzo dei Papi*, or *Palazzo Soliano*, founded by Pope Boniface VIII. in 1294, with a large meeting-hall. — In the street behind the latter is the *Palazzo Marsciano* ('degli Uffizi governativi'), by *Ant. da Sangallo*.

The Via del Duomo leads to the N.W. from the cathedral to (8 min.) the Piazza del Mercato, with the *Pal. del Popolo* or *del Capitano*, the rear of which is interesting (12-13th cent.). — S. *Giovenale* (Pl. 5), at the N.W. angle of the town, is an 11th cent. church, with early-Gothic choir, altar of 1170, and fragments of old frescoes (1312, 1399).

The Corso leads to the Piazza Maggiore, now Vittorio Emanuele, with the *Palazzo del Comune* (Pl. 4), dating from the 12th cent., the still unfinished façade of which was renewed by *Scalza* in 1585. — Adjacent is the church of *S. Andrea* (Pl. 3), with a twelve-sided tower of the 11th cent. and a restored façade. In the interior are paintings of the 14th and 15th cent., and a late-Gothic pulpit, the ornamentation on the back of which dates from the 9th century.

In the S. transept of *S. Domenico* (Pl. 6) is the monument of Cardinal de Braye, by *Arnolfo di Cambio* (1282); the crypt was built by *Sammicheli*.

The *Fortress*, constructed by Cardinal Albornoz in 1364, and situated at the N.E. entrance of the town (p. 62), has been converted into a garden with an amphitheatre for public performances. Fine view of the valley of the Tiber and the Umbrian mountains. — The custodian of the garden keeps the key of the famous adjacent well, *Il Pozzo di S. Patrizio*, which was begun by *Sangallo* in 1527, and completed by *Mosca* in 1540. It is partly hewn in the tufa rock, partly built of masonry, and is 203 ft. deep, and 43 ft. wide. Two separate spiral staircases wind round the shaft; the traveller may descend by one, and ascend by the other (fee $\frac{1}{2}$ -1 fr.).

On the N.W. slope of the hill on which the town stands, below the ancient town-wall, an extensive ***Etruscan Necropolis** has recently been discovered (most conveniently visited on the way back to the station, about halfway, a digression of less than 200 paces; comp. Plan, p. 63). The tombs, which are arranged in groups and rows, date chiefly from the 5th cent. B. C., and some of them were found intact. Their façades, as elsewhere, are constructed of three large stones, two of which, placed nearly upright, are roofed by the third. Adjoining the entrance is inscribed the name of the deceased in the ancient Etruscan character. The inner chamber is square in form, and covered with the primitive kind of vaulting in which the stones are laid horizontally, each overlapping the one below it. The tombs contained many painted vases, of Greek, and particularly of Corinthian and Attic workmanship, and articles of native manufacture, the most important being black terracotta vases with patterns impressed on them (now in the Opera del Duomo, p. 64). — Since 1863 a number of similar tombs have been discovered $2\frac{1}{2}$ M. to the S.W. of Orvieto, near a suppressed Capuchin monastery (comp. Plan). Two of these contain paintings. The route to them is rough. The custodian must be enquired for in the town. — About $1\frac{1}{2}$ M. beyond the Porta Romana is *La Badia*, the ruined abbey-church of San Severo, dating from the 11th century.

On the lake of Bolsena, 12 M. to the W. of Orvieto, is the little town of **Bolsena** (*Hotel* in the Piazza), with 3000 inhab., situated below the site of the Roman *Volsinii*, the birthplace of Sejanus, the favourite of Tiberius. It was one of the twelve capitals of the Etruscan League, and after various vicissitudes was at length conquered and

destroyed by the Romans. The spoil is said to have included 2000 statues. Its wealth has been proved by the discovery, in the vicinity, of numerous vases, trinkets, and statues. The present town contains inscriptions, columns, and sculptures of the Roman municipium which replaced the Etruscan city. The ancient site is reached in a few minutes by an antique causeway of basalt. Among the ruins is an amphitheatre, worthy of special attention, now converted into a vegetable-garden. Beautiful views of the lake.

The church of *S. Cristina* was founded in the 11th cent., and embellished with its fine Renaissance façade by Cardinal Giov. Medici, afterwards Pope Leo X., in 1503. Above the doors are two terracotta reliefs by *Andrea della Robbia*.

Interior. To the right of the choir is a bust of *S. Lucia*, of the school of the *Robbia*, beneath a wooden crucifix of the 14th century. A portal in the left aisle dates from the 11th cent.; the relief represents the Five Wise Virgins and the Adoration of the Magi. Beneath the church, in the space before the entrance to the *Catacombs*, stands a terracotta altar, of the school of the *Robbia*; to the right, above the stone with which *St. Christina* was drowned, is the *Altar del Miracolo* (see below), beneath a canopy of the 8th century. Adjacent is the *Tomb of the Saint*, below a modern canopy. The church also contains a small *Museum*, with inscriptions and glass vessels from the catacombs. Lombard antiquities, and a terracotta *Statue of *St. Christina*, dating from the beginning of the 16th century.

The '*Miracle of Bolsena*', the subject of a celebrated picture by *Raphael* in the Vatican, occurred in 1263. A Bohemian priest, who was somewhat sceptical as to the doctrine of transubstantiation, was convinced of its truth by the miraculous appearance of drops of blood on the host which he had just consecrated. In commemoration of this, Pope Urban IV. instituted the festival of *Corpus Domini* in 1264 and ordered the erection of the superb cathedral of *Orvieto* (p. 62).

The *Museum Comunale*, in the Piazza, contains a Roman sarcophagus, with the triumph of *Bacchus*.

The *Lake of Bolsena*, the ancient *Lacus Vulsiniensis*, 995 ft. above the sea-level, a circular sheet of water, 28 M. in circumference, is the vast crater of an extinct volcano, which formed the central point of a wide sphere of volcanic agency, extending as far as *Orvieto*. The lake abounds in fish (its eels are mentioned by *Dante*, *Purg.* xxiv, 24); but the banks, especially on the W. side, are bleak and deserted, owing to the malaria confined in the basin of the lake, which is not easily dispelled by the wind. The monotony of the surface is relieved by the two picturesque islands of *Bisentina* and the rocky *Martana*. On the latter *Amalasuntha*, Queen of the Goths, the only daughter of *Theodoric the Great*, was imprisoned in 534, and afterwards strangled whilst hating, by order of her cousin *Theodatus*, whom she had elevated to the rank of co-regent. The church in the island of *Bisentina* was erected by the *Farnese* family and embellished by the *Carracci*. It contains the relics of *St. Christina*, a native of *Bolsena*.

From *Bolsena* the road ascends towards the S. on the bank of the lake, through woods, to (7 M.) *Montefiascone* (p. 69).

THE RAILWAY FROM ORVIETO TO ORTE AND ROME now traverses the wooded valley of the *Tiber*, the broad, stony bed of which bears traces of numerous inundations. To the left lies *Baschi*. 125½ M. *Castiglione Teverino*; the river is crossed. 135 M. *Attigliano* (junction for *Viterbo*, p. 69); 138½ M. *Bassano Teverino*, on a hill to the right.

The small *Lake of Bassano*, formerly *Lacus Vadimonis*, now much diminished in extent, is famous in ancient history as the scene of the great victories of the Romans over the Etruscans, B.C. 309 and 283. Pliny the Younger (Ep. viii. 20) has described the lake with its 'floating islands'. — About 3 M. farther to the W. is *Bomarzo*, picturesquely situated on a precipitous rock, near the ancient *Polimartium*, where extensive excavations have been made.

The train passes through several tunnels, and afterwards skirts the right bank of the Tiber, till it approaches Orte, which becomes visible on the height to the left. It then traverses a longer tunnel and reaches the station of Orte, where the railway from Foligno (Perugia and Ancona; R. 11) unites with the main line.

144 M. **Orte** (**Rail. Restaurant*), loftily situated about 2 M. to the N., the ancient *Horta*, presents no object of interest beyond its situation. — The train descends the valley of the Tiber on the right bank, affording pleasant glimpses of both banks. The lofty and indented ridge of *Mount Soracte* (p. 68) becomes visible, at first to the left, then to the right. To the left, on the other side of the river, lie *S. Vito* and *Otricoli*, the latter a small place 6 M. distant from Orte, near the site of the ancient *Otriculum*, where numerous antiquities, including the celebrated Bust of Jupiter in the Vatican (p. 306), have been excavated. — 149½ M. *Gallese*. Farther on, high above the left bank, is the small town of *Magliano*.

152 M. *Borghetto*, with a ruined castle on the height to the right. The Tiber is crossed by the handsome *Ponte Felice*, constructed by Augustus, and restored in 1589 by Sixtus V., over which most of the traffic between Rome and the N.E. provinces formerly passed.

About 5 M. to the S.W. of *Borghetto* (carriages at the station) lies **Cività Castellana** (*Alb. Natalucci*, good table), picturesquely situated 500 ft. above the sea, near the site of *Falerii*, the town of the *Falisci*, which was captured by Camillus in B.C. 396. A lofty bridge, erected in 1712, and recently restored after having been damaged by an earthquake, carries the road into the town across a ravine, 120 ft. in depth. The *Cathedral of S. Maria*, rebuilt in the 16th cent., retains a handsome portico erected in 1210 by *Jacobus Romanus* and his son *Cosmus*; the bust in mosaic of Christ over the door to the right is by Jacobus. The choir-screens also date from the 13th century. A flight of steps leads from the high-altar to a chapel on the left with two tablets of rich *Cosmato* work. Some of the columns in the crypt are ancient. — The *Citadel*, erected by Alexander VI. in 1500 from a design by *Sangallo*, was enlarged by Julius II. and Leo X. The deep ravines by which the town is enclosed testify to vast volcanic convulsions. They contain a few fragments of ancient walls and numerous Etruscan tombs hewn in the rock, especially near the citadel.

Interesting excursion to the ruins of *Falerii* (pronounced Fálleri), 3 M. distant. Near the citadel the *Ponte del Terreno* is crossed to the left, where tombs honeycomb the rocks on all sides, this being the more direct route to *Falerium Novum* or *Colonia Junonia*, founded by the Romans about 240, situated in the plain, 3 M. to the N. of *Cività Castellana*. Etruscan and Roman tombs

are here seen side by side. The town was nearly in the form of a triangle, $1\frac{1}{2}$ M. in circumference; the well-preserved walls are protected by strong square towers and penetrated by gates, one of which on the W. (*Porta di Giove*) is still in good condition. Another gate towards the S. E., the *Porta del Bove*, is also worthy of a visit; near it are the theatre (of Roman construction), the piseina, and what is regarded as the forum, at the back of the theatre. — At the *Porta di Giove*, within the walls, is the **Abbadia di S. Maria*, of the 12th century. In the nave, antique columns; in 1829 the roof fell in, but the damage has been repaired. The adjoining building contains inscriptions, statues, etc., the result of excavations made here. An amphitheatre has also been recently discovered.

Civita Castellana is the best starting-point for the Soracte; there and back about 7 hrs. A good road (one-horse carriage 6-8 fr.; about 2 hrs.) leads to *S. Oreste*, formerly called *S. Rest(i)o* and in the 10th cent. *S. Edistio*, a village about $\frac{1}{2}$ hr. from the summit.

**Soracte*, mentioned by Horace (Carm. i. 9: *Vides ut alta stet nive candidum Soracte*) and Virgil (Æn. xi, 785: *Summe deum sancti custos Soractis Apollo*), is a limestone-ridge, descending precipitously on both sides, extending 3-4 M. from N.W. to S. E., and culminating in several peaks of different heights. On the central and highest summit (2260 ft.) stands the church of *S. Silvestro*. On the slope which gradually descends towards the S. E. is situated the village of *S. Oreste*. Leaving the miserable village to the right, the path ascends gradually to the left, and in $\frac{1}{2}$ hr. reaches the monastery of *S. Silvestro* (2120 ft.), founded in 746 by Charlemagne, son of Charles Martel and brother of Pepin. The summit, with the church and a small disused monastery, may now be reached in a few minutes. In ancient times a celebrated Temple of Apollo occupied this site. The view, uninterrupted in every direction, embraces several snow-clad peaks of the Central Apennines, the Volseian and Alban Mts., the sea (to the W.), and the Ciminian Forest (to the N.). — We may descend from *S. Oreste* to *Stimigliano* (see below) in about $2\frac{1}{2}$ hrs. (mule 5 fr.)

The Borghetto and Civita Castellana road next leads to ($7\frac{1}{2}$ M.) *Nepi* (p. 74). Halfway a track diverges on the right to *Caprarola* (p. 73).

Beyond Borghetto, to the right, Civita Castellana (p. 67) becomes visible for a short time. The train crosses to the left bank of the Tiber. 160 $\frac{1}{2}$ M. *Stimigliano*, and 165 M. *Poggio Mirteto*, both situated in the mountainous district of the *Sabina*, where olive-trees abound. 172 M. *Passo di Correse*. The name is a corruption of *Cures*, the ancient Sabine town, where Numa Pompilius was born, the ruins of which are in the vicinity.

The line follows the left bank of the Tiber to (180 M.) *Monte Rotondo*. The village, to the left, 2 M. higher (fine view of the Sabine Mts.), has an old castle of the Orsini, now belonging to the Piombino family. It was stormed by Garibaldi on 26th Oct., 1867. About 1 M. to the S.E. is *Mentana* (p. 343), where he was defeated on 3rd Nov. by the Papal and French troops, and forced to retreat.

From Monte Rotondo to Rome, a journey of $\frac{3}{4}$ hr., the line follows the direction of the ancient *Via Salara*. At (186 $\frac{1}{2}$ M.) *Castel Giubileo* (p. 341) we catch our first glimpse of the dome of St. Peter's at Rome, which vanishes again as we approach the *Anio* (p. 341). To the left are the Sabine and Alban mountains; then Rome again, with the dome of St. Peter, becomes visible to the right. A wide circuit round the city is described, and near the *Porta Maggiore* (p. 180) the so-called temple of *Minerva Medica* (p. 180) is passed.

195 M. *Rome*, see p. 111.

10. From Attigliano to Viterbo.

The Etruscan Towns in the neighbourhood of Viterbo.

FROM ATTIGLIANO TO VITERBO, 25 M., railway in $1\frac{1}{4}$ - $1\frac{1}{2}$ hr. (fares 4 fr. 55, 3 fr. 20, 2 fr. 5 c.).

Attigliano, see p. 66. — The train crosses the *Tiber*, passes ($3\frac{1}{2}$ M.) *Sipiniano* and ($10\frac{1}{2}$ M.) *Grotte S. Stefano*, and reaches — $16\frac{1}{2}$ M. *Montefiascone*. The station, at which omnibuses and carriages meet the trains, lies on the Viterbo road, nearly 3 M. from the high-lying town. Shortly before we reach the latter, we pass **S. Flaviano*, a church of 1030, restored by Urban IV. in 1262, in the Gothic and circular styles combined. The subterranean chapel contains the tomb of the Canon *Johannes Fugger* of Augsburg, with the inscription —

*Est, Est, Est. Propter nimium est,
Johannes de Fuc., D. meus, mortuus est.*

It is recorded of this ecclesiastic, that, when travelling, he directed his valet to precede him and to inscribe the word 'Est' on the doors of the hosteleries where the best wine was to be had. On the door of the inn at Montefiascone ('bottle mountain') the 'Est' was written three times, and the good canon relished the wine here so highly that he never got any farther. The best muscatel of the district is still known as Est Est (1 fr. per 'fiaschetto').

The little town (2010 ft.; *Albergo Garibaldi*, new), with 7500 inhab., commands a magnificent view: N. the lake of Bolsena as far as the chain of M. Amiata, E. the Umbrian Apennines, S. as far as the Ciminian Forest, W. as far as the sea. The extensive plain of ancient Etruria with its numerous villages may be surveyed from this point; and it has therefore been reasonably conjectured that the celebrated *Fanum Voltumnae*, the most sacred shrine of the Etruscans, once stood here. The uncompleted *Cathedral of S. Margareta*, with an octagonal dome, was one of the earliest works of *Sammicheli*.

To ($7\frac{1}{2}$ M.) *Bolsena*, see pp. 66, 65. The direct road to Orvieto does not touch Bolsena, but remains on the height to the E. A branch to the right leads to (3 M.) *Bagnorea* (the ancient *Balneum Regis*), picturesquely situated on a hill surrounded by ravines, and interesting to geologists.

The railway to Viterbo runs to the S. through a bleak and unattractive plain. Midway between Montefiascone and Viterbo, $\frac{3}{4}$ M. to the E. of the high-road, near the *Casale del Fontanile*, are the ruins of *Ferento*, the Etruscan *Ferentinum*, birthplace of the Emperor Otho. In the 11th cent. it was destroyed by the inhabitants of Viterbo on account of its heretical tendencies, for the Ferentines represented the Saviour on the cross with open eyes, instead of closed, as was thought more orthodox. Such at least is the account of the chroniclers. Among the extensive mediæval, Roman, and Etruscan remains, a *Theatre* of peculiar and primitive construction, with later additions, deserves notice. To the W. of the high-road lies part of the ancient *Via Cassia*.

25 M. *Viterbo*. — Station to the N. of the town, outside the *Porta Fiorentina*.

Hotels. *ALBERGO GRANDORI*, at the *Porta Fiorentina*, R. from $1\frac{1}{2}$ fr.,

also restaurant and café; ANGELO (tolerable, R. 1½ fr.). TRE RE, both in the Piazza; adjacent, ALBERGO & TRATTORIA SCHENARDI; ALBERGO PICCOLO PARIGI, near the station. — *Schenardi's* is the best café.

Post Office, Piazza del Plebiscito. — PHOTOGRAPHS at *Leonardo Primi's*, S. Giovanni in Zoccoli 7, and *Polozzi's*, Vicolo della Ficunaccia.

Viterbo, an episcopal residence with 16,000 inhab. (commune 19,000), surrounded by ancient Lombard walls and towers, is situated in a plain on the N. side of the Ciminian Forest, 1210 ft. above the sea-level. It was the central point of the extensive grant called the 'patrimony of St. Peter', made by the Countess Matilda of Tuscany (d. 1115) to the papal see, and is frequently mentioned in history as a residence of the popes, and as the scene of the papal elections in the 13th century. *Viterbo*, called by old Italian authors the 'city of handsome fountains and beautiful women', still presents an abundance of fine architectural details and picturesque points.

The centre of the town is occupied by the *Piazza del Plebiscito*, in which rises the *PALAZZO PUBBLICO, with a beautiful portico of the 15th century. The court contains an elegant fountain and six large Etruscan sarcophagus-lids with figures and inscriptions. To the right is the entrance to the *Museo Municipale*.

This contains Etruscan and Roman antiquities; also the 'Decree of Desiderius, king of the Lombards', and the Tabula Cibalensis, forgeries of the notorious *Annius* of *Viterbo*, a Dominican monk who died at Rome in 1502; mediæval sculptures, including a *Sphinx from S. Maria in Grado (1285); portrait-bust in terracotta (1510); an Aquamanile of the 12th cent.; and a few paintings (*Pietà from the church of S. Francesco, painted by *Seb. del Piombo* under the influence of Michael Angelo; an ancient but ruined replica of the Scourging of Christ, by the same; and a Madonna, by *Lorenzo da Viterbo*).

Opposite the Palazzo Pubblico, to the left, is the small church of *S. Angelo*, on the façade of which is a Roman sarcophagus, with the Hunt of Meleager; above is a 16th cent. inscription in honour of the beautiful *Galiana* (1138), on whose account, like Helen of old, a war was once kindled between Rome and *Viterbo*, in which the latter was victorious.

Opposite, at the corner of the *Via dell' Indipendenza*, are a lion and a palm-tree, corresponding to a similar group at the other corner of the Piazza, whence the *Via S. Lorenzo* leads to the cathedral. Before reaching the latter we cross a square, with a mediæval fountain, and a large bridge.

In the piazza in front of the cathedral is the spot where in July, 1155, Pope Hadrian IV. (Nicholas Breakspeare, an Englishman) compelled the Emp. Frederick I., as his vassal, to hold his stirrup. Among the mediæval buildings to the left is the dilapidated *Episcopal Palace* of the 13th cent., in which, by order of Charles of Anjou, the Conclave elected Gregory X. pope in 1271, John XXI. in 1276, and Martin IV. in 1281.

THE CATHEDRAL OF *S. LORENZO*, a handsome basilica of the 12th cent., was restored in the 16th century.

INTERIOR. The fantastic capitals of the columns should be noticed. At the end of the right aisle is the new tomb of Pope John XXI.; the

ancient tomb of 1277 is opposite, in the left aisle, behind the door. In the sacristy is a fresco, Christ with four saints, ascribed to *Lorenzo da Viterbo* (1472). — At the high-altar of this church, in 1279, Count Guido de Montfort, the partisan of Charles of Anjou, assassinated Henry, son of Count Richard of Cornwall, King of the Germans and brother of Henry III., in order thereby to avenge the death of his father, who had fallen at the battle of Evesham in 1265 when fighting against Henry III. Dante mentions this deed and places the assassin in the seventh region of hell (*Inf.* XII, 120). Other versions of the story mention the church of S. Silvestro (now del Gesù) as the scene of the crime.

Passing through the archway to the right of the Palazzo Pubblico (p. 70), we reach in a few yards the elegant portal of the church of the *Madonna della Salute* (13th cent.). — Some of the oldest houses in the town are to be found in the Vicolo del Pellegrino, between the Piazza del Plebiscito and the gate leading to Vetralla.

In the market-place rises the *Fontana Grande*, begun in 1206. The *Via Vittorio Emanuele* and the *Via Margherita* lead hence to the Porta Fiorentina, in the direction of the railway-station. At the end of the former we ascend to the right to the church of S. Rosa, which contains the blackened mummy of that saint, who was born here in the 13th century. She urged the people to rise against the Emp. Frederick II., and was expelled by the Ghibellines. Her festival is Sept. 3rd. — The Vicolo della Ficunaccia and the following street lead to the little Romanesque church of S. Giovanni in Zoccoli (11th cent.) and thence through the Porta S. Matteo to —

S. Maria della Verità, in which the chapel to the right is adorned with *Frescoes by *Lorenzo da Viterbo* (1469), representing the Marriage of the Virgin, the Annunciation, the Nativity, the Ascension, saints, and prophets, with numerous portraits. The tiled floor in front of the altar dates from the 15th century. Fine monastery-court. The foundations of a palace built by Frederick II. have been excavated between S. Maria della Verità and the station.

Near the Porta Fiorentina, in the Piazza della Rocca, stands a fountain of 1566, ascribed to *Vignola*, adjacent to which is the Gothic church of S. Francesco. In the right transept of the latter are the tombs of Pope Clement IV. (d. 1268), to the right, and Hadrian V. (d. 1276), to the left; to the left of the high-altar is a cardinal's tomb of 1536, and in the left transept another of 1445.

Outside the Porta Fiorentina lies the *Giardino Pubblico*, with its gay flower-beds, and busts of Victor Emmanuel, Cavour, and Garibaldi.

Excursions. About 1¼ M. to the N.E. of Viterbo, towards Orte (one-horse cab ½ fr.), is the handsome pilgrimage-church of S. Maria della Quercia, the façade of which is said to have been designed by *Bramante*. One of the two courts of the adjoining Dominican monastery has a Renaissance loggia supported on Gothic foundations; both courts have interesting fountains. — About 1¼ M. farther on is the small town of *Bagnaia*, with the charming **Villa Lante*, built in the 15-16th cent., the summer-residence of the ducal family of that name (visitors admitted; carr. to the Quercia and Bagnaia and back, with stay at both places, 2 fr.).

About 2 M. to the W. of Viterbo is *Bulicame*, a warm sulphurous spring, mentioned by Dante (*Inf. xiv*, 79) and still used for baths. The attractive road thither ($\frac{3}{4}$ hr.; turn to the right behind the Palazzo Pubblico) commands a fine view of Viterbo.

Several expeditions interesting both to antiquarians and to lovers of the picturesque may be made from Viterbo to the surrounding ruins of ancient ETRUSCAN CITIES. The volcanic nature of the district, indicated by the profound ravines and fissures of the surface, and the dreary desolation which prevails, combined with the proximity of graves of 2000 years' antiquity, impart an impressive sadness to the scene. — The inns are generally very unpretending.

A Vettura-Corriera, which takes passengers, leaves Viterbo daily for Toscanella, 12 $\frac{1}{2}$ M. to the W., on the road to Corneto (p. 4), and a diligence also plies thither thrice a week in 3 hrs.

Toscanella (625 ft.; *Mancinelli*), the ancient *Toscana*, is a small and mediæval-looking town of 4000 inhab., with walls and towers. Outside the Viterbo gate is a picturesque ravine, with several Etruscan tombs. Amidst the ruins of the ancient *Arx*, on the height to the right, is the Romanesque church of **S. Pietro*, dating from the 9th cent., and restored in 1039, though part of the florid façade is later. In the interior are a tabernacle of 1093, choir-screens from the original church, and (to the right of the choir) frescoes of the 11th century. The crypt is ancient. The custodian lives adjacent, in the dilapidated bishop's palace. — The somewhat later church of **S. Maria*, in the valley, is essentially an edifice of the close of the 11th cent., but the picturesque façade dates from the following century. The pulpit has been put together out of ancient and modern fragments. Custodian at the Palazzo Comunale. Both churches are now disused. — The small *Garden of the Countess Campanari*, in the lower part of the town, containing several sarcophagi with lifesize portraits of the deceased on the lids and an imitation of an Etruscan tomb, is interesting. *Signor Carlo Campanari*, late husband of the proprietrix, and his father conducted many of those extensive excavations which have filled the museums of Europe with Etruscan vases, goblets, mirrors, etc.

Castel d'Asso, popularly known as *Castellaccio*, 5 M. to the W. of Viterbo, may be visited on horseback or on foot (guide necessary; lights should not be forgotten by those who intend to explore the tombs). Passing the *Bulicame* (see above), the road traverses a moor and leads to the valley, which contains a succession of *Etruscan Tombs*, hewn in the rock. The fronts of these are architecturally designed, and bear some resemblance to the rock-tombs of Egypt; numerous inscriptions. On the opposite hill are the picturesque ruins of a mediæval castle and the scanty remains of an ancient village, probably the *Castellum Axia* of Cicero.

About 9 M. to the S.W. of Viterbo, with which it is connected by diligence, lies **Vetralla**, near the Roman *Forum Cassii*. At the entrance to the little town, near the Osteria (bargaining advisable), is *S. Francesco*, a basilica of the 12th cent., with a tomb of the 14th. From Vetralla a visit may be paid (with guide) to the **Ne-*

cropolis of Norchia. We follow the road to Corneto for about $2\frac{1}{4}$ M., and then a rough track over a bleak moor for 3 M. more. The valley of graves here is similar to that of Castel d'Asso, but more imposing. Two of the tombs are Greek in style. On the other side of the valley a town named *Orle* stood in the 9th cent., of which only the ruins of the castle and church now remain. — *Bieda*, the ancient *Blera*, now a poor village, $4\frac{1}{2}$ M. to the S. of Vetralla, possesses similar rock-tombs and two ancient bridges. The scenery is striking.

The high-road from Viterbo forks at Vetralla: the W. branch proceeds viâ *Monte Romano* to Corneto (diligence on fixed days; see p. 4), the S.E. to (11 M.) Sutri (see below).

The high-road from Viterbo to Rome (47 M.) is now rarely traversed by tourists. It gradually ascends the wooded height of *Mons Ciminus*, once considered the impregnable bulwark of central Etruria, until the Consul Q. Fabius, B.C. 308, successfully traversed it and signally defeated the Etruscans. The culminating point of the pass (2850 ft. above the sea), on which lies an old post-station, commands an admirable view. To the right, below, lies the small, round *Lago di Vico*, the *Lacus Ciminus* (1700 ft.), an extinct crater surrounded by woods.

About 9 M. from Viterbo a road diverges to the left from the road to Rome, and leads in $\frac{1}{2}$ hr. through wood to the little hill-town of *Caprarola* (about 6000 inhab.). The lofty **Palazzo Farnese* here, built about 1547-49 by *Vignola* for Cardinal Alexander Farnese, nephew of Paul III., is one of the most magnificent châteaux of the Renaissance.

The château is the property of the ex-king Francis of Naples, whose steward, *Dr. K. Ohlsen*, has carefully maintained the building and filled the rooms with works of art. The ground-plan is pentagonal, with a central rotunda; the round central court, with its arcades, is adjoined by five wings of equal size. The chief façade looks towards the town (N.E.). The saloons and other apartments are adorned with frescoes of scenes from the history of the Farnese family, allegories, etc., by *Federigo*, *Giovanni*, and *Taddeo Zuccaro* and *Antonio Tempesta*. The fine view ranges across the hilly country with the ancient Etruscan cities of Nepi, Sutri, and Falerii, to the Soracte; in the distance rise the dome of St. Peter's and the Volscian hills, to the E. the Apennines, and to the S.E. the Abruzzi. The beautiful gardens are embellished with fountains and statues, and with the charming *Palazzina*, also designed by Vignola. — The fruit-trees cultivated by Dr. Ohlsen enjoy a wide reputation.

Farther on, on the road to Rome, about $12\frac{1}{2}$ M. from Viterbo, is *Ronciglione*, a beautifully situated little town, commanded by a ruined castle.

About $2\frac{1}{2}$ M. to the S. of Ronciglione, on the road from Vetralla (p. 72), picturesquely situated on the crest of an isolated volcanic hill, is *Sutri*, the ancient Etruscan *Sutrium*, frequently mentioned in history as the ally of Rome in the wars against the Etruscans, from whom it was wrested by Camillus in B.C. 389 (*Claustra Etruriae*). In 383 it became a Roman colony. The deep ravine contains numerous Etruscan tombs, and, on the S. side,

fragments of the ancient walls. Three of the five gates are ancient, two towards the S., and the *Porta Furia* on the N. side (said to be so named because once entered by M. Furius Camillus), now built up. Outside the *Porta Romana*, at the foot of an eminence near the *Villa Savorelli*, is situated an admirably preserved **Amphitheatre*, hewn in the rock, dating from Augustus, erroneously regarded by some as Etruscan (axes 55 and 44 yds. respectively). The rocks above contain numerous tomb-chambers, one of which has been converted into a *Church, where, according to various local traditions, the early Christians used to celebrate divine service. A legend attaching to the *Grotta d'Orlando*, near the town, describes it as the birthplace of the celebrated paladin of Charlemagne.

A bridle-path leads in 2 hrs. from Sutri to the *Lake of Bracciano* and *Trevignano* (p. 391).

The road from Vetralla intersects the road to Rome, $5\frac{1}{2}$ M. to the E. of Sutri and $12\frac{1}{2}$ M. to the S.E. of Ronciglione, and reaches, 3 M. farther to the E., the little town of —

Nepi, the Etruscan *Nepete* or *Nepet*, afterwards *Colonia Nepensis*, now an episcopal seat and surrounded by mediæval walls and towers. The elegant Renaissance *Palazzo Municipale*, in the market-place, contains a few Roman sculptures and inscriptions. The *Cattedrale* dates from the 11th cent., but its crypt is older. The picturesque ruined *Castello*, to the E. of the town, occupies the site of an ancient castle rebuilt by Pope Alexander VI., and restored by Paul III. Lucretia Borgia resided here in 1500 after the death of her first husband. Below the castle, near the *Porta Romana*, are some squared blocks of tufa belonging to *Etruscan Walls*.

A road, beginning beside the imposing aqueduct which crosses the *Rio Falisco* at the entrance to the town, leads to the right to ($\frac{3}{4}$ M.) *Castel S. Elia*. The ancient church of **S. Elia*, built about 1000, containing numerous frescoes of the 11th cent., an old pulpit, and crypts, is now preserved as a 'monumento nazionale' (key at the sindaco's). The view from the *Campo Santo* is strikingly beautiful.

From Nepi a high-road runs to ($7\frac{1}{2}$ M.) *Cività-Castellana* (p. 67).

11. From Perugia to Foligno and Orte (*Rome*).

77 M. RAILWAY in $3\frac{3}{4}$ - $4\frac{1}{4}$ hrs. (fares 14 fr. 5, 9 fr. 75, 6 fr. 90 c.; express 14 fr. 95, 10 fr. 55 c.). — The most interesting points are *Assisi*, *Spoleto*, and *Terni*. It is sometimes advisable to exchange the railway for the road; in this way the Tomb of the *Volumnii* may be visited by driving from Perugia to Assisi, and the temple of *Clitumnus* between Foligno and Spoleto (pp. 80, 84). — FROM PERUGIA TO ROME, 128 M., in $5\frac{3}{4}$ - $7\frac{3}{4}$ hrs.

Perugia, see p. 46. The train descends, passing through several tunnels. To the left we obtain a glimpse of the tomb of the *Volumnii* (p. 55). 7 M. *Ponte S. Giovanni*. The train crosses the *Tiber*, the ancient frontier between Etruria and Umbria, and the *Chiuscio*. 13 M. *Bastia*.

15 M. *Assisi*. The town lies on a hill to the left (omn. $\frac{1}{2}$ fr.).

Before ascending to Assisi the traveller should visit the magnificent church of *S. MARIA DEGLI ANGELI, about $\frac{1}{4}$ M. to the W. of the station, on the site of the original oratory of St. Francis. It was begun in 1569 by *Vignola*, after whose death in 1573 it was continued by *Galeazzo Alessi* and completed by *Giulio Danti*. The nave and choir were re-erected after the earthquake of 1832, but the dome had escaped injury.

The INTERIOR contains, below the dome, the Oratory of the saint (called *Portiuncula*), the cradle of the Franciscan order, on the façade of which is the "Miracle of Roses", a vision of St. Francis, a fresco by *Fr. Overbeck* (1829); built in on the other side, to the left, is part of an altar of the 9th century. — In the *Cappella di S. Giuseppe* in the left transept is an altar with terracotta reliefs by *Andrea della Robbia* (Coronation of the Virgin, St. Francis receiving the stigmata, St. Jerome). — To the E. of the sacristy is a little garden in which the saint's thornless roses bloom. Adjacent are the *Cappella delle Rose*, containing frescoes from the life of the saint by *Tiberio d'Assisi* (1518), and the hut of St. Francis, over which an oratory was erected by Bonaventura and adorned with frescoes by *Lo Spagna*.

A beautiful path leads from S. Maria degli Angeli to Assisi in $\frac{3}{4}$ hr. The services of the guides who importune travellers at S. Maria degli Angeli and at Assisi are quite superfluous.

Assisi. — **Hotels.** *ALBERGO DEL SUBASIO (Pl. a; C, 3), with a fine view, adjoining the monastery of S. Francesco, R., L., & A. $2\frac{1}{2}$, B. 1, luncheon $2\frac{1}{2}$, D. $3\frac{1}{2}$ fr.; *LEONE (Pl. b; D, 3), near the Piazza; MINERVA, near the Porta S. Pietro (Pl. C, 3), unpretending.

Photographs from Giotto's frescoes sold by *P. Lunghi*, in the Piazza near S. Francesco, and by *G. Carloforti*, Via Portica 8.

Assisi (1050 ft.), a small town and episcopal see (pop. 3200), the ancient Umbrian *Assisium*, where in B.C. 46 the elegiac poet *Propertius*, and in 1698 the opera-writer *Pietro Metastasio* (properly *Trapassi*, d. at Vienna in 1782) were born, stands in a singularly picturesque situation.

It is indebted for its reputation to *St. Francis*, one of the most remarkable characters of the middle ages, who was born here in 1182. He was the son of the merchant Pietro di Bernardone, and spent his youth in frivolity. At length, whilst engaged in a campaign against Perugia, he was taken prisoner and attacked by a dangerous illness. Sobered by adversity, he soon afterwards (1208) founded the monastic order of *Franciscans*, which speedily found adherents in all the countries of Europe, and was sanctioned in 1210 by Innocent III., and in 1223 by Honorius III. Poverty and self-abnegation formed the essential characteristics of the order, which under different designations (Seraphic Brethren, Minorites, Observantes, and Capuchins, who arose in 1526) was soon widely diffused. St. Francis is said to have been favoured with visions, the most important of which was that of 1224, when Christ impressed on him the marks of his wounds (stigmata). From the 'apparition of the crucified seraph' the saint is also known as *Pater Seraphicus*. St. Francis died on 4th Oct., 1226, and in 1228 was canonised by Gregory IX. He wrote several works. Dante (*Paradiso* 11, 50) says of him that he rose like a sun and illumined everything with his rays. In the 18th cent. the Franciscan Order possessed 9000 convents with 150,000 monks.

Having reached the town, we proceed to the left to the conspicuous old *MONASTERY OF THE FRANCISCANS on the brow of the hill, which was finished soon after 1228 upon massive substructures. It was suppressed in 1866, but a few monks have been allowed to

remain here till their death. Part of the building has been converted by government into a school for the sons of teachers. Visitors are admitted by the iron gate to the left of the entrance to the lower church. An official acts as guide. Besides several frescoes of the 16th and 17th cent. in the refectories, the *Choir-Stalls by *Domenico da S. Severino*, brought from the upper church, dating from 1500, and adorned with admirable carving and inlaid figures of saints, are particularly worthy of attention. From the external passage a magnificent *View of the luxuriant valley is enjoyed.

The two *CHURCHES, erected one above the other, are objects of great interest. The *Crypt*, with the tomb of the saint, was added in 1818, when his remains were re-discovered.

The *LOWER CHURCH, still used for divine service, is always accessible; entrance by a side-door on the terrace (best light in the forenoon). It was begun in 1228, according to Vasari, by *Jacopo Tedesco*; but after 1232 *Filippo da Campello* appears as the architect in charge. Originally the church consisted of a nave of four bays with groined vaulting supported by wide circular arches, a W. transept, and a semicircular apse. About 1300 the Gothic chapels and the E. transept were added, while the S. portal dates from about the same period, though the vestibule in front of it, with its rich Renaissance decoration, was not erected till the 15th century.

To the right of the entrance is a tomb of the 14th cent., with an urn of porphyry, beside which is the magnificent 'Tomb of the Queen of Cyprus', of the close of the 13th cent., the recumbent figure on which probably represents *Jean de Brienne*, king of Jerusalem and Byzantine emperor (d. 1237). — The adjoining CAPPELLA DI S. ANTONIO ABBATE contains the tombs of a count of Spoleto and his son (14th cent.). — Opposite the entrance is the CAPPELLA DEL CROCEFISSO, with some unimportant frescoes; by the pillar to the left, consecration as cardinal of Egidius Alborno (d. 1367), founder of the chapel, who is buried here. Fine stained-glass windows of the 14th century.

The NAVE was painted by predecessors of Cimabue. The hexagonal CAPPELLA DI S. MARTINO, the first on the left, is adorned with frescoes of scenes from the life of the saint, by *Simone Martino* of Siena. — Above the pulpit: Coronation of the Virgin, by *Giottino*. — To the right of the nave are (1) the CAPPELLA DI S. STEFANO, with frescoes from the life of the saint, by *Dono dei Doni* (1560); (2) CAPPELLA DI S. ANTONIO DA PADOVA, the frescoes in which have been repainted; and (3) the CAPPELLA DI S. MADDALENA, adorned with frescoes, representing scenes from the life of the saint and of Maria *Aegyptiaca*, by a *Pupil of Giotto*, who did not scruple to paint copies here of his master's pictures at Padua.

The RIGHT TRANSEPT contains on its right wall *Scenes from the life of Jesus, by *Giotto*, assisted by his pupils. Adjacent, *Madonna with angels and St. Francis, by *Cimabue*. — On the left wall the series of frescoes from the life of Jesus is continued: Flight into Egypt, Massacre of the Innocents, Jesus in the Temple; St. Francis, and Death as Conqueror. — On the N. transverse-wall: Miracles of St. Francis and the Annunciation, by *Giotto*; Saints and Madonna, by *Simone Martino*. — At the end of the S. transept is the CAPPELLA DEL SACRAMENTO, with frescoes from the life of St. Nicholas, by a *Pupil of Giotto*, and the tomb of Cardinal Gian Gactano Orsini (d. 1339), who is represented in the stained-glass windows.

The HIGH ALTAR occupies the spot where the remains of St. Francis once reposed. Above it are four triangular spaces on the groined vaulting, containing the famous *FRESQUES OF GIOTTO, illustrative of the vows of the Franciscan order: poverty, chastity, and obed-

ience; the fourth painting is an apotheosis of St. Francis. The first picture represents the nuptials of St. Francis with Poverty in rags; Hope, next to whom is Love, has handed the ring to the bride. In the next picture Chastity appears in a tower, while in the foreground a monk is being baptised by angels. Purity and Bravery are bestowing on him a banner and shield, while on the right angels, with penances as their weapons, are combatting the demons of lust. Obedience, enthroned between Prudence and Humility, is further symbolised by the laying of a yoke on a monk. Each scene, moreover, is replete with allegorical allusions (chiefly from Dante), most of which will be readily understood by those who are versed in the fanciful combinations of the period.

The LEFT TRANSEPT contains Scenes from the Passion, on the right wall, and in front, on the left wall, a *Madonna between SS. Francis and John, by *Pietro Lorenzetti*. — In the CAPPELLA DI S. GIOVANNI, to the left, is a Madonna with saints, by *Lo Spagna* (1516).

In the SACRISTY, over the door of the second apartment, is a portrait of St. Francis, dating from the close of the 13th century.

The CRYPT (p. 76) is approached by a double staircase, and is lighted with candles when visited by strangers. — Behind the tomb stand colossal statues of Popes Pius VII. and IX.

The *UPPER CHURCH (completed in 1253), the frescoes of which are undergoing restoration, is entered either by the principal portal, or (by applying to the sacristan) from the lower church. The church is in the form of a Latin cross, with fine Gothic windows. The E. side possesses a Gothic portal. The pulpit in the nave dates from the 14th century.

The W. end of the church is adorned with much-damaged frescoes by *Cimabue* (or according to some, by *Giunta Pisano*). In the S. TRANSEPT, as we enter from the lower church, are a Crucifixion, Scenes from the Apocalypse, angels, and saints; in the CHOIR, Assumption and Death of the Virgin, and a bishop's throne of 1260; in the N. TRANSEPT, a Crucifixion, and History of St. Peter. In the vaulting of the choir and nave are Evangelists and Church Fathers. — NAVE. In the upper section of the S. wall are sixteen scenes from Old Testament history, from the Creation of the world to the Recognition of Joseph by his brethren; on the N. side, sixteen scenes from the New Testament, from the Annunciation to the Descent of the Holy Ghost, by *Pupils of Cimabue*, showing gradual improvement in execution. The lower section contains twenty-eight scenes from the life of St. Francis, probably by *Giotto* and his contemporaries: 1. (at the right transept) St. Francis receives honour while a youth; 2. He clothes the poor; 3. His vision of a palace and weapons; 4. Warned by the crucifix in S. Damiano; 5. Restores his apparel to his father, and is enveloped in a bishop's cloak; 6. Appears to Pope Innocent III., supporting the Lateran; 7. Receives licence to preach; 8. Appears to his brethren in a fiery chariot; 9. Vision of his appointed seat in heaven; 10. Expels evil spirits from Arczzo; 11. Offers the ordeal of fire to the Sultan; 12. Hovers in the air while praying; 13. The infant Christ awakes in the saint's arms, as the latter is constructing a manger for the Christmas festival; 14. Miraculous production of a spring of water; 15. Sermon to the birds; 16. Predicts the death of a nobleman; 17. Preaches before Honorius III.; 18. Appears at the Council of Arles; 19. Receives the stigmata; 20. His death; 21. Appears to a dying man; 22. A doubter convinced by the stigmata; 23. Parting from St. Clara; 24. Canonisation; 25. Appears to Pope Gregory IX.; 26. Cures a wounded man in Spain; 27. Confesses a dead woman; 28. Frees a repentant heretic.

Quitting the upper church and emerging on the space in front of it, we may descend the steps to the right and follow the street ascending thence to the Via Principe di Napoli, which leads us to the CIVILE NOSOCOMIO (a hospital on the right, No. 11), the chapel

of which is adorned with frescoes by *Mezzastris* (p. 80) and *Matteo da Gualdo* (1468), representing the miracles of SS. Anthony and James the Great. Farther on, to the right of the fountain, is an arcade of the 13th cent., formerly the *Monte Frumentario*.

In the PIAZZA VITTORIO EMANUELE rises the beautiful portico of a TEMPLE OF MINERVA (Pl. 9; D, 3), with six columns of travertine, converted into a *Church of *S. Maria della Minerva*. Ancient inscriptions immured in the vestibule. Adjacent to the church is the entrance to the ancient *Forum*, which corresponded to the present Piazza, but lay considerably lower. In the forum a *Basement* for a statue, with a long inscription (fee $\frac{1}{2}$ fr.).

The *Chiesa Nuova* (Pl. D, 3), a small but tasteful edifice of 1615, reached by descending to the right, near the S.E. angle of the Piazza, occupies the site of the house in which St. Francis was born.

The PIAZZA S. RUFINO, in the upper town, is embellished with a *Statue of St. Francis*, by Giov. Dupré, erected in 1882.


The CATHEDRAL OF S. RUFINO (Pl. E, 3), named after the first bishop (240), was completed in 1140, and the crypt in 1228. The ancient façade is adorned with three fine rose-windows. The interior was modernised in 1572. In the nave, to the right, is a Madonna with four saints by *Niccolò Alunno*. *Choir-stalls by *Giovanni da Sanseverino* (1520).


From the cathedral an unpaved road descends to the left to the Gothic church of S. CHIARA (Pl. E, 4), near the gate, probably erected by *Fra Filippo da Campello* in 1257. The massive buttresses have been recently restored. Beneath the high-altar are the remains of S. Clara, who, inspired with enthusiasm for St. Francis, abandoned her parents and wealth, founded the order of Clarissines, and died as first abbess. A handsome crypt of different coloured marbles has recently been constructed about her tomb. On the arch above the high-altar, frescoes by *Giottino*; those in the Cappella di S. Agnese (right transept) are attributed to *Giotto*.

The *Giardino Pubblico* (Pl. F, 4), between the Porta Nuova and the Porta Cappuccini, was laid out in 1882; it contains some fine oaks and commands a good view of the town and its fertile valley. A little way beyond the Porta Cappuccini, at the E. end of the town, are the ruins of a Roman *Amphitheatre* (Pl. F, 3).

A magnificent *VIEW of the town and environs is obtained from the *Castello* or *Rocca Maggiore* (Pl. D, E, 2), above the town, reached from the piazza in about $\frac{1}{2}$ hr. The tower should not be ascended without the assistance of a guide, who is to be obtained, with ladders and lights, at the hotel.

In a ravine of the lofty *Monte Subasio* (3610 ft.), at the back of Assisi, is situated the hermitage *delle Carceri*, to which St. Francis was wont to retire for devotional exercises. Near the little chapel are a few apartments built in the 14th cent., and the rock-bed of the saint (on foot $1\frac{1}{2}$, with donkey 1 hr.).





From Assisi to Spello a very beautiful drive of 6 M. (one-horse carr. 4-5 fr.). By train it is reached in 13 minutes. To the right of the road as the town is approached are the ruins of an amphitheatre of the imperial period, but they are not visible from the railway.

22 M. **Spello**, with 5000 inhab., picturesquely situated on a mountain-slope, is the ancient *Hispellum* (*Colonia Julia Hispellum*). The gate by which the town is entered, with its three portrait-statues, as well as the Porta Urbana, the Porta Vencris, and portions of the wall, are ancient.

The **Cathedral of S. Maria Maggiore*, built in the 16th cent. by Rocca da Vicenza (façade later), contains good paintings.

The bénitier to the right of the entrance is formed of an ancient cippus. To the left the Cappella del Sacramento with *Frescoes by *Pinturicchio* (1501): on the left, the Annunciation (with the name and portrait of the painter); opposite to us the Adoration; to the right, Christ in the Temple; on the ceiling, four Sibyls. — The Choir contains a magnificent canopy in the early-Renaissance style. On the left a Pietà, on the right a Madonna by *Perugino*, 1521. — In the SACRISTY, a *Madonna by *Pinturicchio*.

S. Francesco (or *Andrea*), consecrated in 1228 by Gregory IX., contains in the right transept an altar-piece, Madonna and saints, by *Pinturicchio* (1508), with a copy of a letter by *G. Baglione* to the painter painted upon it.

Among other antiquities the 'House of Propertius' is shown, although it is certain that the poet was not born here (p. 75). In the *Pal. Comunale* and on the church-wall of *S. Lorenzo* are Roman inscriptions. The church of *S. Girolamo*, outside the town, contains an interesting Betrothal of the Virgin by *Pinturicchio*. The upper part of the town commands an extensive view of the plain, with Foligno and Assisi. Ruins occasioned by the earthquake of 1832 are still observed.

The train crosses the *Topino* and reaches —

25 M. **Foligno**, the junction of the Ancona line (R. 14).

Halt of 20 min.; mediocre Refreshment Room. — One-horse Carriage to the town (1/4 M.) 40 c. — Inns. **POSTA*, by the gate, R. from 2, D. 4, L. & A. 1 fr., with restaurant and café; *TRATTORIA FALCONE*, both in the main street, the Via della Fiera.

Foligno, near the ancient *Fulginium*, a town with 10,000 (incl. suburbs 23,000) inhab., and an episcopal residence, lies in a fertile district. In 1281 it was destroyed by Perugia, from 1305 to 1439 it was governed by the celebrated family of the Trinci, and in 1439 annexed to the States of the Church. The earthquake of 1832 occasioned serious damage.

At the entrance to the town a marble statue was erected in 1872 to the painter *Niccolò di Liberatore*, surnamed *l'Alunno*, the head of the school of Foligno (p. 48). Public grounds behind it.

The *Corso Cavour* leads straight to the Piazza Vittorio Emanuele.

The first side-street on the right conducts us to the PINACOTECA, in the old *Ospizio di Mendicità*, which contains a few Ro-

man sculptures (relief with circus games) and some paintings by Umbrian masters: *Pier Antonio Mezzastris of Foligno*, 1. Madonna and angels, 3. Madonna with SS. John and Dominic, 4. Crucifixion, 5. Madonna with SS. Francis and John; in the middle, 57. *Dono dei Doni*, St. Catharine. — Hence we follow the Via Umberto I., pass through the gate on the right, and turn once more to the left to the church of *S. Annunziata* (beginning of the 16th cent.), which contains a Baptism of Christ, by *Perugino*; in the sacristy is an *Entombment by *Montagna* (or *Lorenzo Lotto*?).

In the Piazza Vittorio Emanuele is the side-façade of the CATHEDRAL *S. FELICIANO*, with a Romanesque portal (1201). The interior was modernised in the 16th and 17th centuries. To the left of the choir is an octagonal chapel, by *Antonio da Sangallo* (1527); some of the columns in the crypt date from the 9th century. — Opposite the side-portal is the *Palazzo Orfini*, with a Renaissance façade, unfortunately much injured. On the E. side of the piazza rises the *Palazzo del Governo*, the seat of the Trinci in 1398-1439. The chapel on the upper floor (custode in the Municipio, at the other end of the market-place) contains frescoes by *Ottaviano Nelli* (1424; history of the Virgin, Joachim, and Anna; in the vestibule, Romulus and Remus).

The Via Salara, No. 64 in which, on the right, is the handsome *Palazzo Deli* (1510), leads to the Piazza S. Domenico. The old church of *S. Maria infra Portas*, in this piazza, with a portico of the 8th cent., contains numerous but mostly faded frescoes of the Umbrian school. The Gothic church of *S. Domenico*, opposite, is now a riding-school.

The *Scuola d'Arte e Mestieri*, in the street of that name diverging from the Via Salara, contains casts of many almost inaccessible monuments of Umbrian art, including the 'Temple of Clitumnus'. — In the Piazza S. Niccolò is the church of S. NICCOLÒ, the second chapel to the right in which contains a large *Altar-piece (Nativity) by *Niccolò Alunno* (1492); the chapel to the right of the high-altar is adorned with a Coronation of the Virgin, by the same master.

About 4 M. to the E. of Foligno, on the slope of the hills, is situated the *Abbadia di Sassovivo*, with cloisters built in 1229, resembling those of S. Paolo Fuori at Rome (p. 352).

About 5 M. to the W. of Foligno is *Bevagna*, on the *Clitumnus*, the ancient *Mevania* of the Umbri, celebrated for its admirable pastures, with remains of an amphitheatre and other antiquities. The little churches of *S. Silvestro* and *S. Michele*, dating from the 12th cent., have façades by *Binellus* (1195) and *Rodulfus* (1201) respectively. The former is undergoing restoration as a 'national monument'.

From Bevagna (or from Foligno direct, 6 M.) we may visit the lofty *Montefalco* (*Alb. dell' Orso*, poor; *Posta*, near the gate), probably on the site of the Umbrian *Urvinum Hortense*, one of the best places for the study of Umbrian painting. The church of S. LEONARDO, by the Porta di Spoleto, contains a Madonna and saints by *Francesco Melanzio* of Montefalco (1515). In S. AGOSTINO are a Madonna, St. James, and St. John of the *Umbrian School* (1522; left wall), and God the Father, Madonna, Apostles, and Saints by *Benozzo Gozzoli* (right wall). — The church of *S. FRANCESCO, built in

the 14th cent., with a portal of 1585, contains numerous interesting paintings. On the entrance-wall, Annunciation and Nativity, by *Perugino*; wall of left aisle, Madonna and saints by *Tiberio d'Assisi* (1510); Crucifixion, Miracles of St. Anthony, *School of Benozzo Gozzoli*; Madonna, an archangel, four saints, *Umbrian School* (1506); last chapel in the left aisle, Crucifixion and Christ appearing to Mary Magdalene, *School of Giotto*. The choir is adorned with *Frescoes by *Benozzo Gozzoli* (1452), representing the legend of St. Francis, with portraits of popes, cardinals, and church-fathers; below the window, portraits of Dante, Petrarch, and Giotto. The frescoes on the wall of the right aisle are still partly concealed by the whitewash; the most important are those by *Benozzo Gozzoli* (1452; Crucifixion, Christ blessing, four church-fathers, Madonna and four saints). — The PINACOTECA, in the principal piazza, adjoining the Municipio, contains three saints by *Lo Spagna* (?), a Madonna by *Benozzo Gozzoli* (?), and numerous other unimportant works. — The church of S. FORTUNATO, 1 M. beyond the Porta di Spoleto, also possesses several interesting paintings. In the Cappella di S. Francesco (to the left in the court), Legend of St. Francis, by *Tiberio d'Assisi* (1512); in the nave, seven angels by *Benozzo Gozzoli*; in the choir, Madonna and saints, by *Franc. Melanzio* (1528); right aisle, *Madonna adoring the Holy Child, Angel with a musical instrument, by *Ben. Gozzoli* (1450). — A walk round the walls of the town affords magnificent *VIEWS of the Umbrian plain.

The RAILWAY traverses the luxuriant, well-watered valley of the *Clitumnus*, whose herds of cattle are extolled by Virgil, to —

30 M. Trevi (*Locanda*, near the Porta del Lago, poor). The small town, the ancient *Trebia*, lies picturesquely on the steep slope to the left. The *Pinacoteca* in the Municipio contains three works by *Lo Spagna* (1. Coronation of the Virgin, 61. St. Cecilia, 65. St. Catharine). The church of *S. Emiliano*, of the 12th cent., possesses an interesting portal (St. Æmilian between two lions) and three richly-ornamented *Altars by *Rocco da Vicenza* (1521).

About 1/2 M. beyond the Porta del Lago lies the church of S. MARTINO (key at the Café Cecchini). In the outer chapel is a *Madonna in glory, surrounded with four saints, by *Lo Spagna* (1512); above the entrance, Madonna and two angels, by *Tiberio d'Assisi*; in the interior, St. Martin by *Lo Spagna* (? to the left), and Madonna, St. Francis, and St. Anthony, of the *School of Foligno* (to the right). — The church of S. MARIA DELLE LAGRIME, 3/4 M. from the Porta del Cieco, on the way to the railway-station, was built in 1487 by *Antonio da Firenze* and possesses a fine portal by *Giovanni di Gian Pietro da Venezia*, added in 1511. In the 1st chapel to the left is a Resurrection, by an *Umbrian Painter*; in the transept, to the left, *Entombment by *Lo Spagna*; 2nd chapel to the right, Adoration of the Magi, by *Perugino*; 1st chapel to the right, Annunciation, *Umbrian School*.

The small village of *Le Vene*, on the *Clitumnus*, is next passed. Near it, to the left, we obtain a glimpse of a small ancient *Temple, usually regarded as that of *Clitumnus* mentioned by Pliny (Epist. 8, 8), but probably not earlier than the fifth cent., as the Christian emblems, the vine and the cross, on the façade testify. The temple, now a church of *S. Salvatore*, lies with its back towards the road, about 2 1/2 M. from Trevi. Near *Le Vene* the abundant and clear *Source of the Clitumnus*, beautifully described by Pliny, wells forth from the limestone-rock, close to the road. On the height to the left is the village of *Campello*. On the way to Spoleto, to the left, in the village of *S. Giacono*, is a church the choir of which is adorned with frescoes by *Lo Spagna* (Coronation of the Virgin,

Legend of St. James of Compostella; 1526). Beautiful road through richly cultivated land.

40½ M. **Spoleto**. The town is ¾ M. distant; one-horse carr. ¼ fr.

***ALBERGO & RISTORAZIONE DI FILIPPO LUCINI**, in the upper town, near the theatre, R., L., & A. 2½, luncheon 2½, D. 3 fr.; **POSTA**, in the lower part of the town, near the railway-gate. — *Trattoria della Ferrovia*, to the right of the gate. — **Caf  della Nazione* and *Birreria*, Corso Vitt. Emanuele. — *Baths*, Piazza S. Luca.

Spoleto, the ancient *Spoletium*, the seat of a bishop as early as A.D. 50, now an archiepiscopal see, is a busy town, beautifully situated, and containing some interesting objects of art. The chief occupations of its 11,000 inhab. (commune 21,600) are the gathering of truffles in the surrounding woods and the preparation of preserved meats, vegetables, and fruits. Mining is also carried on.

In B. C. 242 a Roman colony was established in the ancient Umbrian town, and in 217 it vigorously repelled the attack of Hannibal, as Livy relates (22, 9). It subsequently became a Roman municipium, suffered severely during the civil wars of Sulla and Marius, and again at the hands of Totila and his Goths, after the fall of the W. Empire, though Theodoric the Great favoured it. The Lombards founded a duchy here (as in Benevento) in 569, the first holders of which were *Faroald* and *Ariulf*. After the fall of the Carolingians, *Guido* of Spoleto even attained the dignity of Emperor, as well as his son *Lambert*, who was murdered in 898. In 1155 the then prosperous town was destroyed by Frederick Barbarossa; and in the beginning of the 13th cent. it was incorporated with the States of the Church. The *Castle* of Spoleto, known as *La Rocca*, originally founded in pre-Roman times, was rebuilt in 1364 by Cardinal Alborno , and completed by Pope Nicholas V. In 1499 it was inhabited by Lucretia Borgia. It fell into the hands of the Piedmontese on 18th Sept., 1860, after a gallant defence by Major O'Reilly, an Irishman.

Entering by the town-gate and following the main street which traverses the lower part of the town, we reach (5 min.) a gateway of the Roman period, called the *Porta d'Annibale*, or *Porta della Fuga*, in allusion to the above-mentioned occurrence.

We may continue to follow the *Strada Umberto*, ascending the hill in a wide curve, or take one of the direct but steep side-streets. Inclining towards the left, near the top, we come to the —

***CATHEDRAL OF S. MARIA ASSUNTA**, raised to its present dignity in 1067 and restored in the 12th century. On each side of the portico, added in 1491, is a stone pulpit. Above, Christ with Mary and John, a large mosaic by *Solsernus* (1207). The richly ornamented portal, of the 11th cent., bears on the left the name of *Gregorius Meliorantius*. The lower part of the tower contains many ancient fragments.

To the right of the vestibule is a **BAPTISTERY** (Cappella Erolti), containing frescoes in the style of *Giulio Romano*; the travertine font, with sculptures from the life of Christ, is of the 16th century.

The **INTERIOR** of the cathedral was restored in 1644. In the chapel immediately to the right of the entrance are some fragments of frescoes by *Pinturicchio* and a Crucifixion (1187), from SS. Giovanni e Paolo. — The **CHOIR** contains *Frescoes by *Fra Filippo Lippi*, completed after his death by *Fra Diamante* in 1470, Annunciation, Birth of Christ, and *Death of Mary; in the semicircle her Coronation and Assumption (unfortunately damaged). At the entrance to the chapel on the left of the choir, to the left, is the *Tomb of Fra Fil. Lippi* (d. 1469). The monument was

erected by Lor. de' Medici; the epitaph is by Poliziano. Opposite is the monument of an Orsini, by *Ambrogio da Milano* (1499). — The WINTER-CHOIR, in the left aisle, contains good carving of the 15th cent., and a Madonna by *Lo Spagna*.

In the Piazza del Duomo, in front of the cathedral, probably stood the palace of the Lombard dukes. Adjacent is the tasteful *Chiesa della Manna d'Oro*, founded in 1527. — On leaving the cathedral we proceed in a straight direction, slightly ascending, to the *Palazzo Arroni* (on the left) with a fine portal and Graffiti of mythological scenes (16th cent.) and to the PALAZZO PUBBLICO, containing several inscriptions and the small *Pinacoteca*.

On the entrance-wall, early mediæval sculptures. — Room II. Entrance-wall, Handsome chimney-piece of the beginning of the 16th cent.; centre, Archaic inscription regulating the felling of timber in a sacred grove. — R. III. Entrance-wall, *Madonna with saints, by *Lo Spagna*; right wall, Virtues and Putti, by *Lo Spagna*. — R. IV. Right wall, Madonna, by *Bern. Campello* (1502); Adoration of the Holy Child, by *Lo Spagna* (?).

On the other side of the Palazzo Pubblico, and in some of the neighbouring houses, Roman foundations have been brought to light.

The half-sunken **Triumphal Arch* of Drusus and Germanicus stands in the narrow street which leads to the S. from the PIAZZA DEL MERCATO, the ancient Forum. The small staircase adjoining it leads to a picturesque monastery court. — From this point we may enter the lower church of *S. Ansano*, with its damaged frescoes of the 11th cent., formerly dedicated to St. Isaac, who founded the hermitages on the Monte Luco. — Farther on traces of Roman construction have been discovered in *S. Agata*, now a prison, and its little piazza. — The small church of *SS. Giovanni e Paolo*, generally difficult of access, has a subterranean oratory, with 11th cent. frescoes. — Outside the Porta S. Luca, to the right, are the church and convent of *S. Paolo* (13th cent.), now a poorhouse; adjacent is *S. Madonna di Loreto*, founded in 1572, with a later façade.

The broad street in front of the Porta S. Luca leads to the left to the church of *S. Pietro*, the cathedral until 1067, restored after its destruction in 1329. The reliefs on the façade are of different dates: the representations from the bestiaries (the wolf preaching; the fox feigning death) at the central portal are the oldest, and may date from the 11th or 12th cent.; those above (deaths of the righteous and of the sinner) are later. — At the top of Monte Luco is the small church of *S. Giuliano*, where St. Isaac, a Syrian monk, founded a monastery about 500.

A road issuing from the Porta S. Gregorio on the other side of the town and skirting the river to the right, then turning to the left to the new *Campo Santo*, with its conspicuous arcades, brings us to the church of **S. Agostino del Crocifisso*, formerly *S. Salvatore*. This church was erected in the 5th or 6th cent. on the site of a Roman temple, and was destroyed at an early date. The fine ancient Roman doors have been preserved, but the ivy wreaths and consoles with which they are adorned and also the three magnificent windows

which pierce the façade are the work of the Christian architects. In the interior the nave was separated by twenty Doric columns from the aisles, which were built up on the conversion of the church into a monastery. Six antique columns with a Doric entablature are still preserved in the choir; and the octagonal dome rests upon eight gigantic columns, with curious imposts. — In the neighbourhood is the small 13th cent. church of *S. Ponziano*.

The *Conte Francesco Toni*'s valuable Collection of Petrefactions, in the Palazzo Toni, Piazza S. Luca, is of great interest to geologists (visitors readily admitted).

Travellers should not omit to extend their walk beyond the cathedral and the Palazzo Pubblico as follows. Continuing to ascend, after a few minutes we cross the Piazza Brignone in a diagonal direction, where a memorial slab commemorates the capture of the fortress in 1860. Passing the fountain, we leave the upper part of the Piazza by a street to the right, which passes immediately below the lower entrance of the fortress of *La Rocca*, now a prison. A little farther on, near a gate which here forms the entrance to the town, we perceive, to the left, polygonal foundations, being remains of the ancient castle-wall. Outside the wall is a profound ravine, spanned by the imposing aqueduct **Ponte delle Torri*, built of brick, which is used as a viaduct, uniting the town with Monte Luco. It rests on ten arches, and is 290 ft. in height, and 231 yds. in length. Its construction is attributed to Theodelapius, third duke of Spoleto (604). The ground-plan is apparently Roman, while the pointed arches indicate a restoration in the 14th century. A window midway affords a view. To the left on the height is perceived the monastery of S. Giuliano; below is S. Pietro (see p. 83). Beyond the bridge we turn to the left, generally following the direction of the aqueduct. After 10-15 min. a more unbroken *Prospect is obtained, embracing the fortress and town, and the spacious valley.

The ascent of *Monte Luco*, $1\frac{1}{2}$ hr., is somewhat fatiguing. Refreshments at the Franciscan convent near the top (adequate remuneration expected). The hermitages are now used as summer-dwellings. The 'Fra Guardiano' conducts visitors to the best points of view. To the N. and E. lies the valley of the Clitumnus with Trevi, Foligno, Spello, and Assisi; then Perugia and the Central Apennines near Città di Castello and Gubbio. In the other directions the view is intercepted by the mountains in the vicinity. Towards the E. these are overtopped by the rocky peak of the Sibilla, snow-clad until late in the summer. — Returning to the right we pass the former Capuchin monastery of *S. Maria delle Grazie*, an ancient resort of pilgrims.

The RAILWAY now ascends for $\frac{3}{4}$ hr. to its culminating point on *Monte Somma* (2230 ft.). — Passing through a long tunnel, it reaches (51 M.) *Giuncano*.

58 $\frac{1}{2}$ M. **Terni.** — The town is about $\frac{1}{4}$ M. from the station. The hotel-omnibuses meet the trains; a seat in a carriage ('un posto') to the piazza 30-50 c., box 20 c.

Hotels. *EUROPA & INGHILTERRA, in the piazza, with restaurant, R. from 2, A. $\frac{1}{2}$, B. $1\frac{1}{4}$, d \acute{e} j. $2\frac{1}{2}$, D. incl. wine 5 fr.; ITALIA; ALB. NUOVO, with trattoria. — *Caf  Elvezia*, near the Europa.

CARRIAGE to the Waterfalls ($\frac{3}{4}$, back $\frac{1}{2}$ hr.): 1 person 5, 2 pers. 7, 3 pers. 9 fr., etc. (bargaining advisable); or at the hotels 7, 10, and 15 fr. respectively, besides which a fee of 1- $\frac{1}{2}$ fr. is expected. — GUIDE (quite unnecessary) 3 fr. — The traveller should be abundantly provided with copper coins. At the different points of view contributions are levied by the custodians (3-4 soldi); flowers and fossils from the Velino are offered for sale, also for 3-4 soldi; besides which the patience is sorely tried by the importunities of a host of beggars and guides.

Terni, situated in the fertile valley of the *Nera*, with 15,900 inhab. (incl. villages) and several manufactories, is the ancient *Interamna*, where, it is believed, the historian Tacitus and the emperors Tacitus and Florianus were born. Remains of an amphitheatre (erroneously styled a '*Temple of the Sun*') in the grounds of the episcopal palace, Roman inscriptions in the *Palazzo Pubblico*, palaces of the Umbrian nobility, etc., are objects of interest. Pleasant walk on the ramparts, whence the beautiful *Nera Valley* is surveyed: to the left Collescipoli, to the right Cesi, opposite the spectator Narni.

The WATERFALLS OF TERNI may be reached on foot in $1\frac{1}{2}$ hr.; the whole excursion, including stay, requires about 4 hrs. (by carriage 3 hrs.). Pedestrians may return by railway. Carriages and fees, see above.

The RAILWAY to Rieti (see *Baedeker's Southern Italy*) gradually ascends to the S., across the plain of the *Nera*, to ($5\frac{1}{2}$ M.) *Stroncone*, the station for a village of the same name on the hill. Thence the line ascends rapidly in curves, threading six tunnels. As the train emerges from the last two, we catch fine glimpses of the upper valley of the *Nera*. — 10 M. *Marmore* (50 min. from Terni, in the reverse direction 40 min.; fares 1 fr. 85, 1 fr. 30, 85 c.), about $\frac{1}{2}$ M. from the waterfalls. The railway now ascends the valley of the *Velino*. — 11 M. *Piediluco* (55 min. from Terni; fares 2 fr. 5, 1 fr. 45, 95 c.), on the W. bank of the lake, opposite the village of that name (p. 86). A boat for the transit ($\frac{1}{2}$ hr.; $\frac{1}{2}$ -1 fr.) is not always to be had without delay. A road (2 M.) is being made.

To reach the WATERFALLS from the station of *Marmore* (*Rail. Restaurant*) we turn first to the right, and 80 paces beyond the pointsman's hut No. 214, cross the railway. Paying no attention to the 'Custodi delle Cascate' here lying in wait, we keep to the left, passing some cottages. We then pass through the gate on the right (when closed, fee of 2-3 soldi), and still keep on to the left till we reach (6 min.) the upper fall (p. 86).

Two carriage-roads lead from Terni to the waterfalls. The NEW ROAD ($4\frac{1}{2}$ M.), following the right bank of the *Nera*, and flanked with poplars, leaves the town near the *Porta Spoletina*, and crosses the plain in a straight direction. On the right rises a government manufactory of weapons; on the left an armour-plate factory. We now approach the stream, the valley of which contracts. On each side tower lofty rocks, to which the luxuriant vegetation of the slopes forms a beautiful contrast. — The OLD ROAD is reached from the piazza at Terni by passing the *Albergo Europa* and descending the *Strada Garibaldi*. We at first follow the Rieti and *Aquila* road, which crosses the *Nera* just outside the gate, traversing gardens and olive-plantations; after 2 M. (near a small chapel on the right), a

broad road to the left descends into the valley of the Nera, while the high-road ascends gradually to the right. The former descends in windings past the village of *Papigno*, picturesquely situated on an isolated rock, ($3\frac{3}{4}$ M.) crosses the Nera, and on the right bank, near the villa of Count Castelli-Graziani, reaches the new road mentioned above ($1-1\frac{1}{4}$ M. to the falls).

The celebrated falls of the *Velino* (which here empties itself into the Nera), called the **Cascate delle Marmore**, are about 650 ft. in height, and have few rivals in Europe in beauty of situation and volume of water. The rivulet is precipitated from the height in three leaps of about 65, 330, and 190 ft. respectively, the water falling perpendicularly at some places, and at others dashing furiously over rocks. The spray of the falls is seen from a considerable distance.

The *Velino* is so strongly impregnated with lime that its deposit continually raises its bed; and the plain of Rieti (1400 ft.) is therefore frequently exposed to the danger of inundation. In ancient times Manius Curius Dentatus endeavoured to counteract the evil by the construction of a tunnel (B. C. 271), which, though altered, is to this day in use. The rising of the bed of the river, however, rendered new measures necessary from time to time. Two other channels were afterwards excavated, the *Cava Beatina* or *Gregoriana* in 1417, and the *Cava Paolina* by Paul III. in 1546; these, however, proving unserviceable, Clement VIII. re-opened the original 'emissarium' of Dentatus in 1598. In 1787 a new cutting was required, and another has again become necessary. The regulation of the *Velino* fall has long formed the subject of vehement discussions between Rieti and Terni, as the unrestrained descent of the water in rainy seasons threatens the valley of Terni with inundation.

Fine views of the falls are obtained from several points. Before reaching the falls, we may ascend a rough path to the left, leading in 10 min. to the finest view of the upper and central falls. — We now return to the road, retrace our steps (80-90 paces) to the path on the left, and cross the Nera by a natural bridge, below which the water has hollowed its own channel. Where the path divides, we ascend gradually to the left. The surrounding rocks (in which there is a quarry) have been formed by the incrustations of the *Velino*. The channel on the right (*Cava Paolina*) is full in winter only. In 12-15 min. we come to a point, where the division of the cascade is surveyed; the central fall, in the spray of which beautiful rainbows are occasionally formed, may be approached more nearly. A farther steep ascent of 15-20 min. leads to a small pavilion of stone on a projecting rock, affording a beautiful view of the principal fall and the valley of the Nera. We next ascend a flight of steps (4 min.), and soon reach another point of view on the left, in the garden of the first cottage (20 c.). — Following the same path for a few minutes more, we turn to the right and come to a small house; passing through its garden (10-15 c.), and between several houses, we reach in 10 min. the road to Rieti and Aquila (see above), and, after crossing the railway, a good osteria (No. 153). The station of *Marmore* (p. 85) is seen to the left.

If time permit, the excursion may be extended to the beautiful

**Lake of Piediluco*, $1\frac{1}{2}$ M. farther on. Following the road, which skirts the indentations of the lake, we arrive at the village of *Piediluco*, with its ruined castle, in $\frac{1}{2}$ hr. (tolerable inn). On the opposite (S.W.) bank lies the railway-station mentioned at p. 85.

The RAILWAY intersects the rich valley of the Nera. To the right on the hill lies *Cesi*, 5 M. to the N.W. of Terni, to the right of the S. Gemine and Todi road (p. 55), with remains of ancient polygonal walls and interesting subterranean grottoes. To the left, *Collescipoli*.

$66\frac{1}{2}$ M. **Narni** (*Angelo*, tolerable), the ancient Umbrian *Narnia* (originally *Nequinum*), birthplace of the Emperor Nerva, Pope John XIII. (965-72), and Erasmus of Narni, surnamed Gattamelata, the well-known 'condottiere' of the 15th century. It is picturesquely situated, $\frac{3}{4}$ M. from the station, on a lofty rock (1190 ft.) on the *Nar*, now *Nera*, at the point where the river forces its way through a narrow ravine to the Tiber. The old castle is now a prison. — The *Cathedral*, erected in the 13th cent., with a vestibule of 1497, and dedicated to St. Juvenalis, the first bishop (369), is architecturally interesting. — The *Town Hall* contains the Coronation of Mary by *Ghirlandajo* (formerly in the monastery of the Zoccolanti, the strictest branch of the Franciscans), spoiled by retouching.

From Narni viâ Perugia by Todi, see pp. 56, 55.

From Narni a road leads to the N.W. to the (6 M.) venerable and finely situated Umbrian mountain-town of **Amelia**, Lat. *Ameria* (inn outside the gate), mentioned by Cicero in his oration *Pro Roscio Amerino*, with admirably preserved *Cyclopean Walls and other antiquities (1390 ft.).

The train turns towards the narrowing valley of the Nera, and passes close to the **Bridge of Augustus* (on the left), which spanned the river immediately below Narni in three huge arches, and belonged to the *Via Flaminia* (p. 101), leading to Bevagna (p. 80). The arch next to the left bank, 60 ft. in height, alone is preserved, while of the two others the buttresses only remain.

The train continues to follow the valley of the Nera, with its beautiful plantations of evergreen oaks. Beyond (71 M.) *Nera Montoro* we pass through two tunnels, and then (near the influx of the Nera) cross the *Tiber*, which in 1860-70 formed the boundary between the Kingdom of Italy and the Papal States. — Near —

77 M. **Orte** (**Rail. Restaurant*) we reach the main line from Chiusi to Rome (see p. 67).

12. From Bologna to Rimini, Falconara (*Rome*), and Ancona.

127 M. RAILWAY in 5-7 $\frac{1}{2}$ hrs. (fares 23 fr. 10, 16 fr. 15, 10 fr. 40 c.; express 25 fr. 40, 17 fr. 80 c.) — Beautiful views of the sea between Rimini and Cattolica, and beyond Pesaro. A seat on the *left* should therefore be secured. — From Bologna to Rome, 300 M., express in 13 $\frac{3}{4}$ hrs. (viâ Florence in 13 hrs.). This train diverges to the S.W. at *Falconara*, the last station before Ancona.

The towns on the coast of the Adriatic are far inferior in attraction to those in the W. part of the peninsula (Tuscany and Umbria); but without a visit to them the traveller's acquaintance with Italy would be but imperfect. The views of the Adriatic to the E., and of the Apennines to the W. are often charming, and the situation of some of the towns, especially Ancona, is strikingly beautiful. *Rimini*, an ancient Roman colony and frontier fortress, possesses several fine monuments of antiquity, and its church of S. Francesco is an admirable Renaissance work. Roman triumphal arches are also preserved at *Ancona* and *Fano*; and *Loreto* boasts of valuable sculptures in the Renaissance style (p. 106). *Urbino*, too, the birthplace of Raphael, lies within a short distance of this route. Many of the towns now have galleries of pictures collected from the suppressed monasteries, but of second-rate importance. The provinces of *Pesaro-Urbino*, *Ancona*, *Macerata*, and *Ascoli* are called the *MARCHES* (*Le Marche*). In Roman times the S. part as far as Ancona was called *Picenum*, while the N. part belonged to *Umbria* (comp. p. 92).

From *Bologna* viâ (22 M.) *Imola* to (26 M.) *Castel Bolognese*, junction for the branch-line to *Ravenna*, see *Baedeker's Northern Italy*. The line follows the ancient *Via Æmilia*, which ran from *Placentia* to *Ariminum*.

We cross the river *Senio*, the ancient *Sinnus*.

31 M. **Faenza** (**Alb. Firenze, Corona*, near the *Piazza Maggiore*; *Tre Mori*), a pleasant town with 14,500 inhab. (commune 36,100), on the *Amone* (ancient *Anemo*), the *Faventia* of the Boii, was the scene of Sulla's victory over Carbo. In the middle ages it witnessed numerous feuds, and in 1509 it was annexed by Julius II. to the States of the Church. The town was famous in the 15th cent. for its pottery, the manufacture of which has lately been revived ('faïence'), and contains considerable silk and weaving factories. Faenza was the birthplace of Torricelli, the inventor of the barometer in 1643, to whose memory a monument has been erected in front of the church of S. Francesco, to the left as we enter the town.

The main street leads direct to the *Piazza Maggiore*, which is surrounded by arcades. In this square, to the left, is the CATHEDRAL OF S. COSTANZO, a handsome basilica of the 15th cent., named after Constantius, the first bishop of Faventia (313). It contains the tombs of Giov. Bosi (d. 1542; 1st chapel to the right) and Africano Severoli (d. 1522; 5th chap. on the right), both by *Bariloto*; a Holy Family by *Innocenzo da Imola* (4th chap. on the right); and the tomb of St. Savinus, by *Benedetto da Majano*, 1472 (chap. on left of high-altar). In the *Piazza Maggiore* are also the *Palazzo Municipale* and the *Torre dell' Orologio*; the fountain in the centre, embellished with bronzes, dates from 1621.

The street at the end of the piazza, adjoining the post-office, leads to the right to the gymnasium, on the first floor of which is the municipal PINACOTECA.

At the end of the VESTIBULE: Colossal group of Mary with the two SS. John, by *Alfonso Lombardi*. — ROOM I. To the right: *Pace da Faenza*, Madonna with saints (14th cent.); **Lionardo Scaletti*, Madonna with angels and saints (1484); Crucifixion, St. Dominic and St. Peter; *Giambattista Bertucci*, Madonna with saints (1506); *Bagnacavallo*, Betrothal of St. Catharine; *Palmezzano*, Madonna with saints (1495); *Palmezzano*, Bearing of the Cross (1535); *Dosso Dossi*, Two heads. — ROOM II. *Giacomo Bertucci*

the Younger, Madonna with saints (1565), Descent from the Cross; *Cotignola*, Baptism of Christ; *Michele Manzoni*, Martyrdom of St. Eutropius; *Tiepolo*, Judith; *Ferrari Fenzoni*, Bethesda; *Massimo d'Azeglio*, Landscape; *Guido Reni*, Madonna, with SS. Francis and Christina; *Van Dyck*, Two royal portraits. — In the SMALL ROOMS: Two fine 'cassoni', formerly belonging to the Manfredi, and a wax-mask of the Dominican Paganelli. — In the ROOM TO THE RIGHT OF THE ENTRANCE: Marble *Bust of John the Baptist, and wooden statue of St. Jerome, both by *Donatello*; terracotta bust of the 16th cent., and a Madonna of the school of the *Robbia*.

In the Via Torricelli, at the end of the piazza, to the left, lie the old *Palazzo Manfredi* and, opposite, the church of *S. Michele*, with tasteful brick ornamentation.

The street beside the clock-tower crosses the bridge to the Borgo. The second church in it, to the right, *La Maggione*, contains a fine fresco by *Girolamo Pennacchi da Udine* (1533), representing the Madonna and saints (in a recess in the choir).

Beyond Faenza the train intersects the plain in a straight direction. It crosses the *Amone*, then the *Montone*, which, united with the *Ronco (Bedesis)*, falls into the Adriatic near Ravenna.

40 M. **Forlì** (*Alb. Masini*, tolerable; *S. Marco*, small, good cuisine; *Vapore*, unpretending but well spoken of), the ancient *Forum Livii*, founded by M. Livius Salinator after the defeat of Hasdrubal, is a well-built provincial capital with 16,000 inhab. (including suburbs 44,000).

Forlì, where in 410 the marriage of *Althaulf*, king of the Visigoths, with *Galla Placidia*, sister of the Emp. Honorius was solemnised, was long an independent state in which the Guelphs retained their ascendancy down to 1315. The *Ordellaffi* then usurped the supreme power, which they retained till 1480, when they were succeeded by *Girolamo Riario*, a favourite of Sixtus IV. This prince was assassinated in 1488, and his widow *Caterina Sforza*, was afterwards banished by *Cesare Borgia*. At length, in 1504, Pope *Julius II.* annexed the city to the States of the Church. — Forlì was the birthplace of the poet *Cornelius Gallus* (d. B.C. 27), of the historian *Flavio Biondo* (15th cent.; p. 128), and of the talented painter *Melozzo da Forlì* (end of 15th cent.), who was closely allied to Piero della Francesca, was recognised by his contemporaries as a master of perspective, and was afterwards engaged at Rome.

The *Piazza Vitt. Emanuele*, the principal square (comp. Plan, p. 90) is enclosed by handsome palaces. Here, too, is the church of —

S. MERCURIALE (so named after the first bishop of Forlì). In the 3rd chapel to the right, *Palmezzano*, Crucifixion, with saints and the donor; 5th chap. to the right, *Palmezzano*, Madonna with saints; 4th chap. to the left, the decoration in which is by *Giov. Veneziano* (1536), the Conception by *Palmezzano*; in the choir, carved stalls by *Alessandro de' Bigni* (1535); in the sacristy, *Tura*, Visitation. — Opposite the church is the restored *Municipio*, with a tasteless tower of the 18th century.

Proceeding southwards from the piazza, we reach the CATHEDRAL OF **S. CROCE**. In the left transept is the Chapel of the Madonna del Fuoco, the dome of which was adorned in 1686-1706 with frescoes of the Assumption by *Carlo Cignani* of Bologna. The painter is buried in the chapel. At the end of the S. aisle, to the left, is a St. Seb-

astian by *Rondinelli*. A reliquary of the 14th cent., and the sculptures of the principal door (15th cent.) also deserve notice.

SS. Biagio e Girolamo contains in the double chapel (1st & 2nd) on the right *Frescoes by *Melozzo* and *Palmezzano*: History of St. James and (in the dome) prophets and angels. To the left is the tomb of Barbara Manfredi (15th cent.). In the 3rd chapel on the right is an Immaculate Conception, by *Guido Reni*. In the 4th chapel: **Palmezzano*, Madonna and saints, with Girolamo Riario and Catharina Sforza and their sons (1486). The frescoes in the dome are also by *Palmezzano*.

The *Pinacoteca* and other municipal art-collections are preserved in the GINNASIO COMUNALE, in the Piazza di S. Pellegrino. The school of Forlì is represented in the Pinacoteca by *Melozzo* and *Palmezzano*, and also by *Agresti*, *Menzocchi*, *Morolini*, and *Cignani*. The names of the artists are attached to each painting.

In the COURT: Monument to the anatomist *Morgagni* (d. 1771), unveiled in 1875. On the STAIRCASE: Sarcophagus of the 14th cent.; Sarcophagus of St. Marcolinus, by *Antonio Rosellini* (1458). Fine door-frame and lunette, Madonna with angels (formerly in the cathedral), by *Simone di Giov. Ghini*.

Pinacoteca. Passing through a corridor with engravings we enter ROOM I. To the left: 5. *Marcello Venusti*, Resurrection (restored); 20. Tapestry from the design of a Lower Rhenish master (ascribed to *Perugino*); 35. Tapestry from the design of a South German master (ascribed to *Wohlgemuth*); 34. *Cigoli*, St. Francis; *Fra Angelico*, 43. Christmas night, 45. Christ on the Mount of Olives; 44. *Simone Memmi*, Two saints; 54. *Bassano*, Adoration of the Shepherds. In the middle: Hebe, by *Canova*. — LARGE ROOM. To the right: 77. *Cagnacci*, St. Valerian; 86. *Guercino*, Annunciation; 90. *Rondinelli*, Madonna; *92. *Francia*, Adoration of the Child; 93. *Agostino Carracci*, St. Francis; 96. *Palmezzano*, Portrait; 103. *Cignani*, Portrait of himself; **Melozzo*, 'Pestapepe', an apprentice with pestle and mortar (a fresco, formerly used as a shop sign); 113. *Morolini*, Annunciation; 115. *Palmezzano*, Crucifixion (1492); 117. *Cotignola*, God the Father with saints (1513); *126. *Melozzo*, S. Antonio Abbate, John the Baptist, and St. Sebastian; 127. *Melozzo*, God the Father; 128. *Palmezzano*, Annunciation; *147. *Palmezzano*, Institution of the Eucharist (1501); 148. *Palmezzano*, Portrait of himself in his 80th year (1536); 151. *Rondinelli*, Portrait said to be of Cæsar Borgia; 163. *Cagnacci*, S. Mercuriale. — In the SMALL ROOMS: Medals (among which is the portrait of Catharine Sforza), fayence, Pre-Roman and Roman antiquities, marble bust of Pino Ordelaffi (15th cent.).

The church of *S. Pellegrino*, opposite the Ginnasio, to the right, contains a fine tomb of the 15th century.

The *Citadel*, constructed in 1361 by Cardinal Alborno, and enlarged by the Ordelaffi and Riarii, is now used as a prison.

A diligence-route leads from Forlì through the Apennines viâ *Rocca S. Cesariano* and *S. Benedetto* to Florence.

THE RAILWAY TO RIMINI crosses the *Ronco* and passes (45 M.) *Forlimpopoli*, the ancient *Forum Popilii*; to the right, on the hill. *Bertinoro*, with its productive vineyards. It then passes *Polenta* and crosses the *Savio* (the ancient *Sapis*).

52 M. *Cesena* (*Leon d'Oro*, R. 2½ fr.; *Cappello*), with about 10,000 inhab. (incl. villages 38,300), is surrounded by beautiful meadows and hills, and boasts of several interesting palaces.

1. S. Filippo
2. S. Jacopo dei P.
3. Predicatori
3. S. Maria in S. Francesco
4. S. Sebastiano
5. Il Suffragio
6. Palazzo del Municipio
7. Posta delle lettere
8. Tribunale

1. S. Filippo
2. S. Jacopo dei P.
3. Predicatori
3. S. Maria in S. Francesco
4. S. Sebastiano
5. Il Suffragio
6. Palazzo del Municipio
7. Posta delle lettere
8. Tribunale


A B C D E

Chiese:

- | | |
|---|--------|
| 1. Misericordia | B.4. |
| 2. S. Antonio | C.5. |
| 3. S. Francesco (Tempio dei Mulatesta) | C.5. |
| 4. S. Francesco di Paola | C.5. |
| 5. S. Girolamo | C.4.5. |
| 6. S. Giuliano | A.3.4. |
| 7. S. Martino | B.4. |
| 8. Ginnasio & Biblioteca | C.5. |
| 9. Palazzo del Comune | B.5. |
| 10. Teatro Vittorio-Eman. | B.5. |
| 11. Vescovado | C.4.5. |

RIMINI.
1:15.500

300 200 100
Metri



Caesena is one of the most ancient episcopal sees in Italy, where St. Philemon is said to have held the office as early as the year 92. During the middle ages it was at first an independent state, then became subject to the Ghibelline family of Montefeltro, and shortly afterwards to the Malatestas, who were partizans of the Guelphs. This rapid change of rulers is alluded to by Dante, *Inf. xxvii, 52*:

*Così com' ella sie' tra il piano e il monte,
Tra tirannia si vive e stato franco.*

On 1st Feb., 1377, the town was cruelly sacked by Cardinal Robert of Geneva, and subsequently by Cesare Borgia after which it was incorporated with the States of the Church.

In the *Piazza* is the handsome *Palazzo Pubblico*, with a statue of Pius VI., who was born at Cesena in 1717, as well as his successor Pius VII. in 1742. — The *Cathedral* contains two marble altars of the 15th and 16th centuries. — The *Library*, built in 1452 by *Matteo Nuzio* for Domenico Malatesta Novello, contains 4000 MSS., many of them written for the founder, and afterwards used by the learned Aldus Manutius in preparing his famous editions of the classics. — The *Pinacoteca* contains a good *Presentation in the Temple* by *Franc. Francia*. — In the *Giardino Bufalini* is a statue erected in 1883 to the physician Maurizio Bufalini of Cesena.

On an eminence, $\frac{3}{4}$ M. distant, stands the handsome church of **S. Maria del Monte*, a work of *Bramante*. Productive sulphur-mines in the vicinity, towards the S.

The train crosses the stream *Pisciatello*, the upper part of which, called *Urgone*, is identical with the *Rubicon* of the ancients, the boundary between Italy proper and the province of Gallia Cisalpina, and memorable for its passage by Cæsar at the beginning of the civil war between him and Pompey, B.C. 49.

The most recent investigations tend to show that the Rubicon has entirely quitted its ancient course. It appears originally to have fallen into the *Fiumicino*, farther S., while at the present day its upper part (*Urgone*) unites with the *Pisciatello*. Most of the towns and villages of this district have in turn laid claim to the distinction of possessing the Rubicon within their territory. Nor did they rest satisfied with a mere literary feud in order to gain the object of their ambition. An action involving this question was instituted at Rome, and in 1756 the 'Rota' decided in favour of the claim of the *Uso* (see below), beyond the small town of *Savignano*. On the road between Cesena and Savignano stands a column bearing a decree of the Roman senate, which threatens to punish those who should without authority trespass beyond the Rubicon. Montesquieu regarded this as genuine, but it is an obvious imposition and not the only one connected with the interminable dispute regarding the Rubicon.

56 M. *Gambettota*; 60 $\frac{1}{2}$ M. *Savignano*. The train crosses the *Uso*. 63 M. *S. Arcangelo*, where Pope Clement XIV. (Ganganelli) was born in 1705 (d. 1771). The *Marecchia* is next crossed.

69 M. **Rimini**. — **AQUILA D'ORO*, in the Corso, R. & A. 2 $\frac{1}{2}$, luncheon 2 $\frac{1}{4}$, omn. from station $\frac{3}{4}$ fr.; *ALBERGO NUOVO*, also with omnibus at the station; *ITALIA*, at the *Pescheria*, fair. — *Trattoria d'Europa*, *Piazza Cavour*; *Caffè della Speranza*, *Piazza Giulio Cesare*. — *Railway Restaurant*, good wine of the country.

Carriage from the station to the *Piazza*, with one horse 1 fr., with two horses 1 fr. 20 c. — *Tramway* to the bathing-place on the beach.

Rimini, beautifully situated on the Adriatic at the mouth of the

Ansa and *Marecchia*, with 11,000 inhab. (incl. villages over 37,000), and extensive fisheries and silk manufactories, has of late come into notice as a sea-bathing place. Handsome public rooms with a café and restaurant, and numerous lodging-houses have been erected on the pleasant promenade on the beach.

Rimini, the ancient *Ariminum*, a town of the Umbrians, became a Roman colony in B.C. 269, and formed the frontier-fortress of Italy in the direction of Gaul, and the termination of the *Via Flaminia* from Rome, constructed in 220. The town was extended and embellished by Julius Cæsar and Augustus. During the Exarchate, it was the northernmost of the *Pentapolis Maritima*, or 'Five Maritime Cities', which were ruled over by one governor. The other four were *Pesaro*, *Fano*, *Sinigaglia*, and *Ancona*. In 260 Ariminum became an episcopal see, and in 350 a council against Arianism was held here. The town afterwards belonged to the Lombards.

In the course of the 13th cent. the Malatesta made themselves masters of the city. In 1285 *Giovanni il Sciancato* ('the lame'), surnamed also *Lancilotto*, put to death his wife, *Francesca Polenta* of Ravenna, and his brother, *Paolo il Bello* (an event from which Dante derived the episode of 'Francesca da Rimini' in the 5th canto of the *Inferno*, and Leigh Hunt the materials for his 'Story of Rimini'). During the following century this family ruled the greater part of the Romagna, and also, for a time, the mark of Ancona. Under Lewis the Bavarian they became vicegerents of the emperor, but Cardinal Albornoz afterwards succeeded in reducing them under the power of the pope. The Malatesta family, divided into the Pesaro and Rimini branches, distinguished themselves as condottieri, but also as patrons of learning. The most famous scion was *Sigismondo*, son of Pandolfo (1417-68), who united the gifts of a great military leader with the most violent passions. He attracted painters and scholars to his court, in order to secure immortality for himself and his mistress (afterwards his wife), the clever *Isotta*. — In 1528 the people revolted against the Malatesta and placed themselves under the authority of the pope.

A broad road leads from the *Station* (Pl. D, 4) to the gate, within which it is called the *Via Principe Umberto*. After 4 min. we follow the *Via al Tempio Malatestiano* to the left.

*S. FRANCESCO (*Duomo*, *Tempio dei Malatesta*; Pl. 3; C, 5), originally a Gothic edifice of the 13th cent., was magnificently remodelled in the early-Renaissance style in 1447-55 by *Sigismondo Malatesta* from designs by *Leo Battista Alberti* and under the superintendence of *Matteo da Pasti*. The windows of the original building are retained. Of the façade unfortunately the lower part only has been completed, while the dome intended by Alberti to surmount the choir is wanting. The choir itself dates from 1709. On the cornice are the initials and arms (the elephant and rose) of *Sigismondo* and *Isotta*.

The vaults on the S. side contain the sarcophagi of the poets and scholars whom *Sigismondo* entertained at his court. In the first four are the remains of *Basinio*, the Parmese poet; *Giusto de' Conti*; *Gemisthius Plethon* (d. 1451), a Greek philosopher whose corpse *Sigismondo* brought hither from his campaigns in Greece; and *Roberto Volturio* (d. 1489), the learned engineer. In the others repose several physicians and a bishop of the 16th century.

The INTERIOR was said by Pope Pius II. to resemble a heathen temple rather than a Christian church. To the right of the entrance is the *Tomb of Sigismondo* (d. 1463). Most of the plastic ornamentation of the chapels was executed by *Agostino di Duccio* of Florence; a few works are by *Piero Bernardo Ciuffagni*. — 1st CHAPEL on the right: above the altar, St. Sigismund of Burgundy, patron-saint of the founder; by the pillars,

allegorical figures of the virtues. — 2ND CHAPEL OF THE RELICS ('Santuuario', shown by the sacristan), containing a (restored) 'Fresco by *Piero della Francesca* ('*Petri de Burgo opus 1451*') : Sigismund Malatesta kneeling before his patron St. Sigismund, with La Rocca, built by him, on the right. In the CAPPELLA DI S. MICHELE, the 3rd to the right, is the *Tomb of Isotta* (d. 1470), erected in 1450, with the motto 'tempus loquendi, tempus tacendi'. The archangel on the altar, by *Guffagni*, is a portrait of Isotta. By the pillars, angels playing on musical instruments. — 4TH CHAPEL on the right: by the pillars, the planets and other fantastic representations from a poem by Sigismondo in honour of his mistress. — 4TH CHAPEL on the left: by the pillars, allegorical figures of the sciences. — 3RD CHAPEL on the left: Children's games, probably by *Simone Ferrucci*, a pupil of Donatello. — The 2ND CHAPEL on the left is closed. — The 1ST CHAPEL on the left, restored in 1868, is named the Cappella dell' Acqua from an ancient statue of the Madonna, represented as sending rain. On the left is a sarcophagus for the reception of the ancestors of the founder, with two reliefs, representing the House of Malatesta in the Temple of Minerva and the Triumph of Sigismondo. By the pillars, above the elephants, two portrait-medallions of Sigismondo.

From the small piazza in front of the church, the Via Patara leads S. to the PIAZZA GIULIO CESARE (Pl. C, 5), the ancient forum. A stone *Pedestal* here, erected by Sigismondo and restored in 1500, commemorates Cæsar's passage of the Rubicon. Near it is a chapel, on the spot where St. Anthony once preached, and another on the canal is said to mark the spot where the saint preached to the fishes because the people refused to hear him. — The Corso d'Augusto, which intersects this piazza, leads to the S. to the Porta Romana, and to the N. to the Piazza Cavour and the bridge of Augustus.

The *PORTA ROMANA or *Arco d'Augusto* (Pl. D, 6) is a triumphal arch of travertine, of simple design, erected to Augustus in B.C. 27 out of gratitude for the restoration of the Via Flaminia, as the inscription records (which, however, has been inaccurately restored; the letters to the right outside the gate also belong to it). Above are medallion figures, on the outside those of Jupiter and Minerva, on the inside those of Neptune and Venus.

Near the town-wall, beyond S. Marino, are the scanty remains of an *Amphitheatre* (reached by the Via dell' Anfiteatro, the second side-street of the Corso from the Porta Romana), which, however, scarcely merit a visit.

The PALAZZO DEL COMUNE (Pl. 9; B, 5), in the Piazza Cavour, contains a small picture-gallery, comprising: *Domenico del Ghirlandajo* (school-piece), SS. Vincenzo Ferrerio, Sebastian, and Rochus; *Giovanni Bellini*, Pietà (early work); *Perino del Vago*, Madonna; *Tintoretto*, S. Domenico. — In front of it rises a bronze *Statue of Pope Paul V.* (inscription on the pedestal obliterated). Beyond the *Teatro Vittorio Emanuele* (Pl. 10), erected in 1857, is the ancient *Palace of the Malatesta*, now a prison, and in a very dilapidated condition. Their arms are still to be seen over the entrance. The town-wall, to the right of the palace, commands a fine view of the mountains.

The *Library* (Pl. 8; C, 5), in the Via Gambalunga to the E. of the Piazza Cavour, founded in 1617 by the jurist Gambalunga, contains

23,000 vols. and several MSS. The small *Museo Archeologico* here contains the *Tomb of a woman, a herma of Pan and other antique sculptures, and tombstones of the 10-11th centuries.

At the end of the Corso the *Marecchia* (the ancient *Ariminus*) is crossed by the five-arched *PONTE D'AUGUSTO (Pl. A, B, 4), one of the finest ancient structures of the kind. It leads to the Borgo S. Giuliano, where the Via Æmia united with the Via Flaminia, which led to Rome. Here, too, is situated the church of —

S. Giuliano (Pl. 6; A, 3, 4), containing the Martyrdom of St. Julian, an altar-piece by *Paolo Veronese*, and an old picture by *Lattanzio della Marca* (1357), the Life of the saint.

In the *Castello di S. Leo*, 18 M. to the W. of Rimini, the notorious impostor *Cagliostro* (Giuseppe Balsamo) died in confinement in 1794. From S. Leo a bridle-path, much frequented by fishermen, leads viâ *Camaldoli* and *Vallombrosa* to *Florence*.

About 12 M. from Rimini is situated the ancient republic of *San Marino*, the smallest in the world (32 sq. M. in area, with 8000 inhab.), said to have been founded in an inaccessible wilderness by St. Marinus at the time of the persecutions of the Christians under Diocletian. This diminutive state braved all the storms of mediæval warfare, and even the ambition of the popes. It retained its ancient constitution till 1847, when its senate was converted into a chamber of deputies. The precipitous rock in a bleak district on which the town (*Albergo Bigi*) is situated is reached by one road only from Rimini. The village of *Borgo* at the base is the residence of the wealthier inhabitants. The celebrated epigraphist and numismatist *Bartolommeo Borghesi*, born at Savignano in 1781, was from 1821 until his death in 1860, a resident at S. Marino, where he arranged and described his admirable collections, and received visits from foreign savants.

FROM RIMINI TO RAVENNA, 31 M., narrow-gauge railway along the coast in 1½ hr. (fares 5 fr. 70, 4 fr., 2 fr. 60 c.).

Beyond Rimini the line skirts the coast, crosses the streams *Marano* and *Conca* (the *Crustumius Rapax* of *Lucan*), and reaches (75 M.) *Riccione*. 81 M. *Cattolica*, so called from having been the residence of the Roman Catholic bishops during the Council of Rimini in 359. A chain of hills descends here to the sea; the train ascends for some distance, and then passes through them by means of a long tunnel. It crosses the *Tavollo* and passes the *Villa Vittoria*, situated on the left, on the road to Rimini. We then cross the *Foglia*, the ancient *Isaurus* or *Pisaurus*.

90½ M. **Pesaro**. — *ALBERGO ZONGO, near the Piazza, with restaurant; starting-point of the diligence to Urbino (see p. 96). — *Caffè della Piazza*, in the piazza, next door to the Urbino diligence-office (4 fr.); *del Commercio*, in the Corso. — *Carriage* from the station to the town, one-horse 80 c., two-horse 1 fr.; one-horse carr. to Urbino about 12 fr.

Pesaro, with 11,000 inhab. (with suburbs 21,000), the ancient *Pisaurum*, is the capital of the united provinces of Pesaro and Urbino, and formerly belonged to the Pentapolis Maritima (p. 92).

Pesaro, first inhabited by the Scoli, then by the Umbrians and Etruscans, and a Roman colony as early as B.C. 184, was destroyed by *Vitiges* the Goth, and rebuilt by *Belisarius*. In the 13th cent. it passed to the *Malatesta* family, in 1445 to the *Sforza*, and in 1512 to the *Rovere*, dukes of Urbino, under whom, chiefly through the influence of *Lucrezia d'Este*, consort of Francesco Maria II., it became a centre of art and literature, and was visited by *Bernardo* and *Torquato Tasso*. The former of these

authors completed his 'Amadis' here. In 1631 the town was annexed to the Papal States. — The figs of Pesaro are excellent.

The Via Branca, to the left in which is the *Teatro Rossini*, leads to the Piazza, just on this side of which a side-street diverges on the left to the Alb. Zongo, while on the right is the handsome portal of the former church of *S. Domenico* (1395).

In the PIAZZA, which is adorned with a large fountain, rises the imposing *Prefettura*, the ancient ducal palace, built by the Sforza in 1455, and completed by the Rovere. The architects were probably *Girolamo Genga* and his son *Bartolommeo*. The banquet-hall, 132 ft. long and 48 ft. wide, still contains a painted wooden ceiling dating from the latter half of the 16th century. In 1474 this hall was the scene of the marriage of Constanzo Sforza and Camilla d'Aragon.

Opposite is situated the more modern *Palazzo dei Pagi*. Between the palaces, to the right, is a façade erected in 1848, with marble statues of the composer *Gioachino Rossini* (b. 1789; d. at Paris 1868), the 'Swan of Pesaro', and the author *Count Giulio Perticari* (1779-1822), by P. Lorandini. — At the other angle of the piazza is the *Palazzo del Municipio*, the vestibule and entrance of which face the Piazza Mamiani. It temporarily (until completion of the Ateneo, see below) contains an admirable *Majolica Collection* (550 pieces; many from Pesaro, Urbino, Castel Durante, and Gubbio, by *Maestro Giorgio*), two pictures by *Zoppo* (a Pietà and a head of John the Baptist), and a marble bust of Napoleon by *Canova*.

To the N. of the Piazza, in the Via Mazza (formerly *Posta Vecchia*), is the *Palazzo Almerici*, with the ATENEIO PESARESE.

In the VESTIBULE are votive stones of the matrons of Pisaurum, among the most ancient Latin monuments extant. In the court and on the staircase are Roman and Christian inscriptions and sculptures; high up two reliefs with representations of ships, dating from about 1000 B. C. — Here is the entrance to the Museum and to the BIBLIOTECA OLIVIERI. The latter contains 36,000 volumes and 1400 MSS., amongst which are letters of Tasso and others. — In the MUSEUM are ancient clay images and lamps; ivory carvings (early Christian reliefs of the Expulsion from Paradise and the Stoning of Stephen, and a slab from the throne of Maximian in Ravenna); early Italian bronzes and coins (*aes grave* from Ve-tulonia); an image of Mithras in vitreous paste.

In the *Palazzo Machirelli* (first turning to the left from the Albergo Zongo) is the *Liceo Comunale*, in which is a sitting figure of Rossini by Marochetti, erected in 1864 by two admirers, Baron Salamanca of Madrid and G. Delahante of Paris.

In the Via Rossini, in which stands the small house where Rossini was born, is the old *Cathedral* (closed at present). Close by, in the hall of the *Vescovado*, is an early-Christian Nymphæum.

The present cathedral, *S. Francesco*, in the Via Roma, has a Gothic portal. It contains a Madonna enthroned, with four saints, by *Giovanni Bellini* (1495). — **S. Giovanni Battista*, in the Via Passeri, was begun by *Giovanni Genga* in 1515, and finished by

Barlolummeo in 1543. — *S. Agostino*, in the Corso, has a Gothic portal of 1413.

On the N. side of the town stands the *Rocchetta* (now a powder-magazine), built by Giovanni Sforza. — Opposite the spacious *Lunatic Asylum* (*Manicomio* or *Ospizio degli Incurabili*) are the small *Orti Giuli*, where a bastion of the town-wall commands a fine view of the *Foglia* (once crossed by a Roman bridge) and of *Monte S. Bartolo*.

About $1\frac{1}{2}$ M. from Pesaro rises *Monte S. Bartolo*, where the Roman dramatist L. Attius is said to have been interred. On the top lies the *Villa Imperiale*, belonging to the *Principe Albani*, at whose town-house entrance-tickets may be obtained. Alessandro Sforza built a country-house on this site, the foundation-stone of which was laid by the Emperor Frederick III., on his journey to Italy in 1469. The upper rooms were adorned by the Rovere with stucco-work, majolica-plaques, and frescoes. In the 1st Room is the triumphal procession of Duke Francesco Maria of Urbino, accompanied by Alfonso of Ferrara, by *Genga*. The 2nd Room was decorated as an arbour, with figures of Daphne and landscapes, by the brothers *Dossi*; on the ceiling is the duke with his army. In the 3rd Room are the Coronation of Charles V., and allegories after designs by *Angelo Bronzino*. The frescoes in the following rooms represent the duke being appointed commander-in-chief by Cardinal Alidosi, Pope Leo X., and the doge of Venice. The last room, which has a fine stucco ceiling, is embellished by paintings by *Raffaellino del Colle*, representing the duke being crowned with a garland, Calumny (after Apelles), and the Christian virtues. — Eleonora Gonzaga caused *Girolamo Genga* to erect a new palace about 1530, near the old house, with an inscription on the façade to the effect that it was built for her husband Francesco Maria 'a bellis redeunti animi ejus causa'. It was unfortunately never completed, but even in its present dilapidated condition, it retains much beauty; fine view from the terrace. — In the neighbourhood is the church of the *Girolamitani*; one of the finest. Views in the environs is obtained from an eminence behind the monastery.

The *Municipio* of the little coast-town of *Gradara*, 7 M. to the N.W. of Pesaro, contains a Madonna and saints by *Giovanni Santi* (1484); in the *Rocca* is a terracotta altar by *Andrea della Robbia*.

AN EXCURSION TO URBINO is best made from Pesaro. Diligence twice daily (fare 4 fr.), ascending in 5, and descending in 4 hrs. The road leads through the valley of the *Foglia*, which falls into the sea at Pesaro, and then ascends, passing several unimportant villages. At the inn 'del Cappone', halfway, the horses are changed. Beyond *Moline* the road ascends in windings. Above, to the right, is the ducal palace, with three loggie flanked by round towers. The diligence stops in the main street, flanked on the left by arcades, in which the inn and café are situated.

Urbino (**Albergo dell' Italia*), the ancient *Urvinum Metaurense*, celebrated as the birthplace of the greatest painter of all ages, *Raphael Santi* (b. 28th March, 1483; d. at Rome, 6th April, 1520), lies on an abrupt hill, surrounded by barren mountains. The town, with narrow, crooked streets and 16,900 inhab. (incl. villages), has a university with as many professors as students, and merits a visit for the sake of its monuments and historical associations. The situation is picturesque.

In the 13th cent. the town came into the possession of the *Montefeltro* family, and under FEDERIGO MONTEFELTRO (1444-82) and his son *Guidobaldo* (1482-1508) attained to such prosperity as entirely to eclipse the neighbouring courts of the Malatesta at Rimini and the Sforza at Pesaro. Federigo Montefeltro, who distinguished himself as a condottiere in the feuds of the 15th cent., married his daughter in 1474 to Giovanni della Rovere, a nephew of Sixtus IV., and was in consequence created Duke of Urbino. His court was regarded as a model among the princely courts of that period. It was visited for shorter or longer periods by numerous scholars and artists, amongst whom the prince was pre-eminent for learning. His son, Guidobaldo, in spite of ill health and other misfortunes, zealously followed his example, with the able assistance of his beautiful and talented wife *Elizabeta Gonzaga*. A famous description of the court of Urbino under Guidobaldo, depicting it as the most refined social school of the day, is given by *Count Baldassar Castiglione* in his 'Cortigiano', the ideal of a courtier. In 1497 Guidobaldo was expelled by *Cesare Borgia*, the son of Alexander VI., after whose death, however, he returned to Urbino in 1503. He died in 1508 and bequeathed his dominions to his nephew *Francesco Maria della Rovere*, the favourite of Pope Julius II. In 1626 the duchy was incorporated with the States of the Church, when Urban VIII. persuaded the last and childless Duke *Francesco Maria II.* to abdicate.

Amongst the most distinguished ARTISTS employed at the court of Urbino, during the zenith of its splendour under Federigo and Guidobaldo, were *Paolo Uccelli*, *Piero della Francesca*, and *Melozzo da Forlì*. Even foreign painters, like *Justus van Ghent*, a picture by whom is still preserved in the gallery (see p. 98), were attracted to the court. The peculiar bond of union which existed here between the interests of science and art is chiefly exhibited in the library pictures or ideal portraits of scholars painted by Melozzo da Forlì and others, but which have been removed from Urbino together with the library. TIMOTEO VITI, or DELLA VITE, of Ferrara (1467-1523), the best pupil of Francesco Francia, spent the greater part of his life in Urbino; he was the first painter who exercised an influence on Raphael, but at a later period he himself became subject to that great master's magic spell. — The master, however, in whom we are now specially interested, is GIOVANNI SANTI of Urbino (? 1450-94), the father of Raphael, whose frescoes at Cagli (p. 101) and Fano (p. 100) show considerable power and a keen sense of the graceful. As Giovanni died when Raphael was in his 11th year, his son can hardly have had the benefit of his instruction. After his father's death, Raphael remained in Urbino till 1500, but under what tuition is unknown. Another native of Urbino was FEDERIGO BAROCCO (1528-1612), some of whose works are able, while others display the customary affectation of the post-Raphaelite period.

In the centre of the town is the PIAN DEL MERCATO, or marketplace, where the Corso Ducale, in which the inn is situated, ends. — The Via Pucinotti ascends hence to the right in a few minutes to a somewhat dull piazza, with the cathedral and ducal palace.

The Cathedral contains some interesting pictures.

To the right of the entrance, St. Peter, a replica of the statue in St. Peter's at Rome. In the 2nd chapel to the right: St. Sebastian by *Federigo Baroccio*; to the left of the high-altar, the Lord's Supper, also by *Fed. Baroccio*. In the sacristy: SS. Martin and Thomas à Becket, with a portrait of Duke Guidobaldo, the master-piece of *Timoteo Viti* (1504); Adoration of the Magi, by the same; and a Scourging of Christ by *Piero della Francesca*, elaborately executed in the miniature style. — The CHURCH (entered from the right corner of the small piazza between the cathedral and the palace) possesses a Pietà by *Giov. da Bologna*.

The **DUCAL PALACE, erected by *Luciano Laurana* of Dalmatia in 1468 by order of Federigo Montefeltro, and completed by *Baccio Pintelli*, is now used as a 'Residenza Governativa', and contains the archives. The requirement of strength, coupled with

the unevenness of the ground, has given rise to the irregularity of the building, but at the same time has enhanced its picturesqueness. The palace has always been much admired, and was regarded by the contemporaries of the founder as an embodiment of their ideal of a princely residence. According to modern standards, however, its dimensions are not grand, and even the court by Baccio, the entrance to which is opposite the cathedral, is pleasing rather than imposing. In the latter, to the right, are mediæval tombstones and a relief (Pietà) of the 14th century. The staircase to the upper rooms is on the left, with a statue of Duke Federigo, by *Girol. Campagna* (1606). The ornamentation of the doors, windows, and chimney-pieces here and in the apartments is by *Ambrogio da Milano*, etc. The corridors and rooms contain a collection of inscriptions from Rome and the Umbrian municipia, early-Christian and mediæval sculptures, and a small *Picture Gallery*.

The *Collection of Inscriptions* was made by the epigraphist *Fabretti*. — Of the *Sculptures* the chief are 72 reliefs with representations of engines of war (after *Francesco di Giorgio*), by *Ambrogio da Milano* (1464), which formerly decorated the outside of the palace. Farther on in Room I. are four chimney-pieces and a marble 'Lavatoio'. Room II. *Fr. Zuccherò*, Pietà; two crucifixes of the 13th cent.; St. Clara (14th cent.). Room III. Tapestry worked in Urbino by masters from Flanders; to the right, *Palmerini*, Madonna; stucco-reliefs by *Brandano*. Farther on is the SALA DEGLI ANGELI, with five beautiful doors and dancing angels, and a room with a portrait in relief of Ariosto. In the CHAPEL is a plaster-cast of Raphael's skull. The studio of Duke Federigo should be visited for the sake of the intarsias, which formerly also covered the upper part of the walls, and the fine ceiling. From the balcony a beautiful view is obtained. — The celebrated library collected by Federigo has been removed to Rome.

Picture Gallery. To the right: 38. *Baroccio*, Madonna, with saints; 25. *Viti*, St. Sebastian; 23. *Paolo Uccello*, Legend of the desecrated Host. Fine chimney-piece. — 22. *Giuliano da Rimini*, Madonna, with saints; *2. *Giovanni Santi*, Madonna with SS. John the Baptist, Sebastian, Jerome, and Francis, and the Buffi family; Pietà; 18. *Piero della Francesca*, Architectural piece; *1. *Justus van Gent*, Holy Communion, with numerous portraits, including Duke Federigo and Caterino Zeno, the Persian ambassador (to the right of the table; 1474); 60. *Tim. Viti*, S. Apollonia; 53. *Sassoferrato*, Madonna; 52. *Fra Carnevale*, Madonna; *Titian*, Last Supper (damaged), and the Resurrection (late works).

Opposite the palace rises an Obelisk, facing which is the church of *S. Domenico*, with a pleasing portal and a terracotta relief of the Madonna, with SS. Dominic and Peter Martyr, by *Luca della Robbia* (1449). — The street contracts; to the right is the *University*, with armorial bearings over the door. Farther on is the *Istituto di Belle Arti*, which contains sculptures and some fine majolicas.

In the market-place (p. 97) is the loggia of *S. Francesco*, a church of the 14th cent., with a handsome campanile. The portal of the chapel to the right of the high-altar is by Bartol. Centogatti (15th cent.).

The Contrada Raffaello leads hence to the Fortezza. No. 278 on the left is the house in which *Raphael* was born. It was purchased in 1873 at the suggestion of Count Gherardi, aided by a donation

from Mr. Morris Moore, and now belongs to the 'R. Accademia Raffaello'.

The rooms are adorned with engravings from Raphael's pictures. In one of the rooms is a fresco of the Madonna (removed from the court; entirely repainted), by *Giovanni Santi*, possibly representing Magia Ciarla, Raphael's mother (fee $\frac{1}{2}$ fr.).

From the beginning of the Contrada Raffaello the Via Bramante leads to the church of *S. Spirito*, containing a **Pietà* and **Descent of the Holy Ghost* by *Luca Signorelli*, originally a church-banner, of 1495.

Returning to the market-place, and descending the Via Balbona, we follow the Via della Posta Vecchia, the first side-street to the right, and then the Via S. Giovanni, the first street to the left, which leads straight to the *Oratorio della Confraternità di S. Giovanni*. The walls of the interior are covered with scenes from the history of the Virgin and John the Baptist, by *Lorenzo da S. Severino* and his brother, of the school of Giotto (1416). — The neighbouring church of *S. Giuseppe* contains a Nativity by *Fed. Brandano*.

In the *Theatre*, once famous for its decorations by *Girolamo Genga*, the first Italian comedy was performed. This was the 'Caulandra' of Cardinal Bibbiena (1470-1514), the friend of Pope Leo X. and patron of Raphael.

The hill of the old *Fortezza* (ascend the Contrada Raffaello, at the top take the Via dei Maceri to the left, and knock at No. 1461; fee 25-50 c.) commands an interesting *Survey of the barren chain of the Apennines. A powder-magazine now stands at the top.

About 1 M. to the E. of Urbino, to the left of the Pesaro road, are situated the conspicuous old monastery and church of *S. Bernardino*, with the new cemetery of Urbino. This spot commands a fine view of the town. The church contains the tombs of the Dukes Federigo and Guidobaldo, with their busts.

FROM URBINO TO FOSSOMBRONE (p. 101) $11\frac{1}{2}$ M.; no regular communication (carriage 10 fr.). The 'Corriere del Furlo' passes through Fossombrone at 11 a.m. Carriage from Urbino to Gubbio 40 fr.

THE RAILWAY FROM PESARO TO ANCONA skirts the coast, occasionally approaching close to the sea, of which a pleasant view is afforded.

98 M. **Fano** (**Albergo del Moro*), the *Fanum Fortunae* of antiquity, is indebted for its origin to a temple of Fortune, a fact commemorated by a modern statue of fortune on the public fountain. It afterwards prospered, and is now a pleasant little town (20,000 inhab., incl. suburbs), surrounded by ancient walls and a deep moat. The once celebrated harbour is now unimportant. Pope Clement VIII. (Aldobrandini) was born at Fano in 1536. The first printing-press with Arabic type was set up here in 1514 at the cost of Pope Julius II. As a sea-bathing place Fano is less expensive than Rimini.

In the centre of the town is the PIAZZA, in which (in the mediæval *Palazzo della Ragione*) is the *Theatre*, formerly one of

the most famous in Italy, rebuilt by *Torelli*, a native architect, and decorated by *Bibbiena* (d. 1774). One of the rooms contains (temporarily) a David with the head of Goliath, by *Domenichino* (formerly in the Collegio Nolfi), which unfortunately was much injured by thieves in 1871. — The old *Palazzo del Municipio* is seen through the arches to the right of the market-place.

The S. side of the Piazza, which is enlivened by a fountain of flowing water, is skirted by the Corso. Following the latter to the right, we reach the Via dell' Arco d'Augusto, the second cross-street to the left. In a small piazza here rises the CATHEDRAL OF S. FORTUNATO, the four recumbent lions in front of which formerly supported the pillars of the portico. The portal dates from the 13th century.

In the INTERIOR the chapel of S. Girolamo (the 2nd to the left) contains a monument of the Rainalducci family; nearly opposite (4th to the right) is a chapel adorned with sixteen frescoes by *Domenichino*, once admirable, now disfigured by restoration. — In the chapel of the sacristy, a Madonna with saints, by *L. Carracci*. — In the court of the *Vescovado*, behind the cathedral, are some sculptures of the 13th century.

Farther on we come to the *ARCH OF AUGUSTUS, which spans the street, a structure of simple design, to which a second story was added in the 4th cent., when it was re-dedicated to Constantine. It once had three openings, as is shown by a view of it on the adjacent church of S. Michele, adjoining the handsome Renaissance portal. — On the side of the arch next the town is the *Spedale degli Esposti*, a pleasing edifice with loggie.

Returning to the piazza, we follow the Via Boccaccio opposite the fountain, and then take the Via Bonaccorsi, inclining to the left, to the church of S. MARIA NUOVA, with portico.

INTERIOR. 1st chapel on the left: *Giov. Santi*, Visitation; 2nd chapel: *Perugino*, Annunciation, 1498. 3rd chapel on the right: **Perugino*, Madonna and saints, 1497; admirable predelle, recalling Raphael's style.

S. Croce, the hospital-church, contains a *Madonna with four saints, by *Giovanni Santi*. — *S. Paterniano*, dedicated to the first bishop of Fano, a handsome structure, possesses a Betrothal of the Virgin, by *Guercino*. — *S. Pietro* is an imposing and richly-decorated church, with frescoes by *Viviani*; in the chapel of the Gabrielli (1st on the left) an Annunciation by *Guido Reni*. — In *S. Agostino* is a painting of S. Angelo Custode, by *Guercino*. — In the vestibule of *S. Francesco* (closed) are the monuments of Pandolfo III. Malatesta (d. 1427; to the right), perhaps by *L. B. Alberti*, 1460, and his wife Paola Bianca (d. 1398; left).

Interesting excursion to the *Monte Giove*, by a good road (4 M.). At the top is a monastery, where visitors are lodged. Splendid view of the Adriatic.

FROM FANO TO FOSSATO VÎA FOSSOMBRONE AND THE FURLO PASS, corriere daily: to Fossombrone 2½, to Cagli 6½, to Scheggia 10, and to Fossato 12½ hrs., including halts for meals. The road is identical with the ancient *Via Flaminia*, constructed in B.C. 220 by the Censor C. Flaminius (who fell at the Battle of the Trasimene Lake, see p. 46), in order to secure possession of the district of the Po which had been recently wrested from the

Gauls. The road quits Fano by the Arch of Augustus and the Porta Maggiore, and skirts the N. bank of the *Metaurus*, the fertile valley of which is well cultivated. About 1 M. from Fossombrone, near the church of *S. Martino at Piano*, was once situated the Roman colony of *Forum Sempronii*, of which but scanty remains now exist. After its destruction by the Goths and Lombards, the modern Fossombrone sprang up.

15½ M. **Fossombrone** (*Tre Re; Pavone*), long in possession of the Malatesta family, accrued to the States of the Church under Sixtus IV. It is now a busy little town with 9000 inhab. and silk-factories, prettily situated in the valley, which contracts here, and commanded by a castle.

— From Fossombrone to *Urbino*, see p. 99.

The Via Flaminia about 2 M. from Fossombrone crosses the *Metaurus*, which descends from the valley near *S. Aneto in Vado* from the N., and follows the left bank of the *Candigliano*, which at this point empties itself into the *Metaurus*. The valley soon contracts; to the right rises the hill of *Pietratata*, occasionally named *Monte d'Asdrubale*. Here, according to the popular tradition, was fought the memorable battle of the *Metaurus* in which, B.C. 207, Hasdrubal, whilst marching to the aid of his brother Hannibal with 60,000 men, was signally defeated and slain by the consuls Livius Salinator and Claudius Nero. This was the great event which decided the 2nd Punic War in favour of Rome.

The valley now becomes still more confined and is bounded by precipitous slopes. At the narrowest part, where the rocky walls approach so near each other as to leave space for the river only, is the celebrated *Furlo Pass* (Furlo from *forulus* = passage, the ancient *petra intercisa*), a tunnel 17 ft. wide, 14 ft. high, and about 32 yds. in length. The founder of the work was the Emp. Vespasian (in A. D. 76), as the inscription preserved at the N. entrance records (*Imp. Caesar. Augustus. Vespasianus. pont. max. trib. pot. VII. imp. XVII. p(ater) d(atrix) cos. VIII. censor. faciund. curavit*). — A little beyond it is the small church *Badia del Furlo*. At the confluence of the *Candigliano* and *Burano*, 8 M. from Fossombrone, lies the village of *Acqualagna*. The road crosses the *Candigliano* and then follows the left bank of the *Burano*. At the foot of the hill on which *Cagli* is situated, an antique bridge, built of huge masses of rock, crosses a tributary brook.

31 M. **Cagli** (*Italia*, in the Piazza, charges according to bargain) occupies the site of the ancient borough of *Cates*, or *Calle*. *S. Domenico* contains one of the chief works of *Giovanni Santi*, Raphael's father, a Madonna with saints, *al fresco*. The angel on the right of the Madonna is said to be a portrait of the young Raphael. Also a *Pietà* with St. Jerome and Bonaventura, by the same master. *S. Francesco* and *S. Angelo Minore* also possess several pictures. — Travellers beyond Cagli are generally conveyed in smaller carriages. About 6 M. beyond Cagli is **Cantiano**, with 3000 inhab.; the church *della Collegiata* contains a Holy Family by *Perugino*. — The road ascends rapidly, and reaches the height of the pass, 2400 ft. above the sea. A little before arriving at *Schieggia* the road crosses a ravine by the curious *Ponte a Botte*, constructed in 1805.

43½ M. **Schieggia**, an insignificant place, lies at the junction of the roads to Fossato and Foligno, and to (6 M.) Gubbio (the latter leading over the pass of Monte Calvo; carriage 5-6 fr.). On *Monte Petrara*, in the vicinity, amid oak-plantations, stand the ruins of the celebrated temple of *Jupiter Apenninus*, whose worship was peculiar to the Umbrians. Several bronzes and inscriptions have been discovered in the environs.

The main road continues to descend the green valley of the *Chiascio*, and leads *vià Costacciaro* and *Sigillo* (stalactite caves) to —

55 M. **Fossato**, a station on the Ancona and Rome line, p. 109.

Beyond Fano the train crosses the river *Metaurus* (see above), celebrated as the scene of Hasdrubal's defeat (B.C. 207); then the *Cesano*, near (105 M.) stat. *Marotta*.

112 M. **Sinigaglia** or *Senigallia* (**Albergo Roma*, near the harbour; *Trattoria del Giardino*, near the Municipio), the ancient *Sena*

Gallica, with 22,500 inhab. (including villages), chiefly occupied in fishing. The town was destroyed by Pompey during the Civil War between Marius and Sulla. It was an episcopal see as early as the 4th cent., but was afterwards frequently devastated by fire and sword, so that it now presents quite a modern appearance. Pope Pius IX. (Conte Mastai-Ferretti) was born here on 13th May, 1792 (d. 1878). A fair, instituted in the 13th cent., is held here from 30th July to 8th Aug. annually; it was once the most frequented in Italy, but has long since lost its importance. In summer Sini-gaglia is a favourite sea-bathing place. — The monastery-church of *S. Maria delle Grazie* (2 M. distant) contains in the choir a picture by *Perugino* (retouched), and over the 3rd altar on the right a small Madonna by *Piero della Francesca*.

119¹/₂ M. *Montemarciano*. Pleasant view of the promontory of Ancona, rising from the sea. The train crosses the *Esino*. At (122 M.) stat. *Falconara* passengers for the line to Rome change carriages (see R. 14). The town lies on the hill to the right.

127 M. *Ancona*, see R. 13.

13. Ancona and its Environs. Osimo. Loreto.

Hotels. **VITTORIA* (Pl. b; C, D, 3), in the Corso Vittorio Emanuele, well fitted up, R. 2¹/₂, D. 5 fr.; *ALB. REALE DELLA PACE* (Pl. a; C, 3), with good restaurant, R. 3¹/₂, D. 4, omn. 1 fr.; **MILANO* (Pl. c; C, 4), Corso di Porta Pia, commercial, with restaurant and garden. Hotel-omnibuses at the station. — *Cafè. Stoppani & Leva*, in the Corso. — *Trattoria. Leon d'Oro*, in the Corso.

Post Office (Pl. 20; 8-8 o'clock), Piazza Roma. — **Telegraph Office**, Via del Porto.

Cabs. *One-horse* cab from station to town, incl. luggage, 1, at night 1¹/₂ fr.; *two-horse* 1¹/₂ or 2 fr. — For 1 hr. 1¹/₂-2 fr.; each ¹/₂ hr. more, 60-80 c. — Beyond the town, 2 fr. 50 or 3 fr. 60 c. for 1 hr.; each ¹/₂ hr. more, 1 fr. 15 or 1 fr. 70 c.

Tramway from the station through the Via Nazionale to the Piazza del Teatro and the Piazza Cavour.


Steamboats of the *Peninsular and Oriental Company* on Frid. mornings to Brindisi and Alexandria; on Sun. to Venice. *Società Riunite Florio-Rubattino*, on Mon. mornings to Zara in Dalmatia, in 9 hrs.; on Mon. afternoons to Tremiti, Viesti, Bari, Brindisi, the Piræus, and Constantinople; on Tues. nights to Venice, in 12 hrs. *Austrian Lloyd*, to Zara and Fiume every alternate Sat.; to Trieste every alternate Sunday.

Sea Baths, near the railway-station. *Warm Baths*, Piazza Stamura (Pl. E, 4).

British Vice-Consul, *Sig. Albert P. Tomassini* (also American Consular Agent).

Ancona, the capital of a province, with 28,000 inhab. (incl. suburbs 47,700), of whom upwards of 6000 are Jews, and possessing an excellent harbour, is beautifully situated between the promontories of *Monte Astagno* (Pl. C, 6) and *Monte Guasco* (Pl. C, 1). Since 1860 the government has improved the harbour and endeavoured to foster the trade of Ancona, but business has declined somewhat of late years. Silk and oil are largely manufactured here.

Ancona was founded by Doric Greeks from Syracuse, and thence named *Dorica Ancon* (i.e. 'elbow', from the form of the promontory). It was



ANCONA.

1. Arco Clementino
2. Arco Trajano
3. Arsenale

Chiese:

4. *Maz. d. Misericordia*
5. S. Bartolomeo
6. S. Ciriaco (Duomo)
7. S. Domenico
8. S. Francesco ad alto
9. S. Francesco della scale
10. S. Gesù
11. S. Maria della Piazza
12. S. Palazia

- B. 1. 13 S. Pellegrino
- B. 1. 14 Loggia de Mercanti
- C. 1. 15 Palazzo del Comune
- 16 di Giustizia
- C. 2. 17 Leuchtemberg
- D. 1. 18 Statua di Clemente VII.
- C. 1. 19 Teatro delle Muse
- D. 3. 20 Porta delle Lettere
- D. 4. 21 Monumento del Conte Carour
- D. 2 Alberghi:
- D. 2 a. Albergo della Pace
- C. 3 b. Vittoria
- C. D. 3 c. Milano
- D. 2 C. 4.

- C. 2.
- C. 3.
- C. 2.
- D. 2
- C. 3.
- D. 3.
- C. 3.
- D. 3.
- E. 4.
- C. 3.
- C. D. 3.
- C. 4.



300 500 Metri

Wagner & Debes, Leipzig



afterwards a Roman colony, and the harbour was enlarged by Trajan. In the middle ages it repeatedly recovered from the ravages of the Goths and others, and in 1532 was made over by Gonzaga to Pope Clement VII., who built a fort and garrisoned it. Ancona is also frequently mentioned as a fortress in modern history. Thus in 1796 it was surrendered to the French, in 1799 to the Austrians, in 1805 to the French again; and in 1815 it was ceded to the pope, to whom it belonged till 1860. In 1832-38 the citadel was garrisoned by the French, to keep in check the Austrians, who held Bologna and the surrounding provinces. In 1849 the town revolted, but on 18th June was re-captured by the Austrians. On 20th Sept., 1860, after the Battle of Castelfidardo (p. 105), it was finally occupied by the Italians.

The HARBOUR, an oval basin of about 990 by 880 yds. in diameter, is considered one of the best in Italy. A handsome quay, called the *Banchine*, has recently been completed. The N. pier is of ancient Roman origin. At the beginning of it rises the well-preserved marble ***Triumphal Arch** (Pl. 2; B, 1), erected A.D. 112 by the Roman senate in honour of Trajan on the completion of the new quays, as the inscription records. The holes to which its original bronze enrichments were attached are still observed. The new pier constructed by Pope Clement XII., a continuation of the old, also boasts of a *Triumphal Arch* (Pl. 1; B, 1), designed by *Vanvitelli*, but far inferior to the other. Its façade is towards the sea and has no inscription. At the S. angle of the harbour is the old Lazzaretto, built in 1732, now a bonded warehouse (*Magazzini Generali*, Pl. B, 5). The harbour is defended by several forts.

The ***Cathedral of S. Ciriaco** (Pl. 6; C, 1), dedicated to the first bishop of Ancona, stands on the *Monte Guasco* (Pl. C, 1), one of the above-named promontories, which shelters the harbour from the N.E., and an excellent point of view. The church occupies the site of a temple of Venus mentioned by Catullus and Juvenal, and contains ten beautiful columns which once belonged to the ancient temple. Like St. Mark's at Venice, it is in a mixed Lombard and Oriental style of architecture, and in the form of a Greek cross, each of the arms being flanked with aisles. The octagonal dome over the centre of the cross is one of the oldest in Italy. The façade (13th cent.), ascribed to *Margaritone d'Arezzo*, has a beautiful Gothic portico, the foremost columns of which rest on red lions.

In the LEFT AISLE, in front, is a handsome tomb of 1530. In the RIGHT TRANSEPT the semi-Byzantine capitals have been preserved; the railing of the steps to the choir dates from the 12th century. In the CRYPT, to the right, sculptures of the 13th cent.; relief of Christ between an ox and a lion, by *Philippus*; beneath, Head of Christ and St. George; tomb of the Franciscan B. Gabriel Ferretti (1456); in the corner, three statuettes (12th cent.); reliefs, probably from the ancient choir of the left transept; **Sarcophagus of Titus Fl(avius) Gorgonius*, Prætor of Ancona, with scenes from the life of Christ (the Nativity, Adoration, Baptism, Entry into Jerusalem, Christ before Pilate, Christ as Judge, Christ and the apostles with Gorgonius and his wife at the Saviour's feet; 4th cent.); farther on, Roman head; statue of St. Primianus; relief of Christ (12th cent.); sarcophagus of St. Marcellinus. — The CRYPT OF THE LEFT (modernised) TRANSEPT contains the tombs of SS. Cyriacus, Marcellinus, and Liborius, in the rococo style.

Pope Pius II. Piccolomini, while vainly endeavouring to organise

a crusade against the Turks, died in the *Episcopal Palace*, adjoining the cathedral, in 1464. — Within a house at the foot of the hill are scanty remains of a Roman *Amphitheatre*.

The *Palazzo Comunale* (Pl. 15; C, 2) has been frequently rebuilt; in the 13th cent. by *Margaritone d'Arezzo*, in the 15th by *Francesco di Giorgio*, and finally in the 17th century. The statues of Adam and Eve on the façade and the lower part of the rear date from the 13th cent. building. On the staircase in the interior is a statue of the law-giver Marco de' Rossi (14th cent.). — Close, by in the Via del Porto, is the church of *S. Maria della Misericordia*, with an elegant early-Renaissance portal.

The *Strada delle Scuole* descends from the Palazzo Comunale to the left, to the church of *S. Francesco* (Pl. 9; D, 3; now a barrack), resting on a massive substructure, with a rich Gothic portal by *Giorgio da Sebenico* (1455). — The street next leads (r.) to the *Prefettura*, the fine court of which is flanked by Gothic arcades, and has a fine Renaissance archway. We proceed through the court to the high-lying PIAZZA DEL PLEBISCITO (Pl. D, 3), adorned with a statue of Clement XII. (Corsini, 1730-40), by *Cornachini*. — Farther up is the church of *S. Domenico* (Pl. 7), which contains a Madonna and saints by *Titian* (in the 4th Chapel on the right), beautiful and imposing in its composition, though now much injured.

Adjoining the church on the right is the MUSEUM (*Civica Pinacoteca Podesti e Museo Archeologico delle Marche*).

VESTIBULE. Keystones from the doorways of houses and other reliefs of the 13th cent.; also large groups, Cain and Abel from the old Palazzo Comunale, etc. — ROOM I. Roman antiquities and coins. — ROOM II. Antique bronzes and vases; medals.

Upper Floor. ROOM I. Paintings and drawings by *Francesco Podesti*. — ROOM II. *1. *Carlo Crivelli*, Small Madonna; 8. *Titian*, Crucifixion (damaged); 9. *Pellegrino Tibaldi*, Baptism of Christ; 11. *Guercino*, Cleopatra; 13. *Lorenzo Lotto*, Assumption of the Virgin; 27. *Ciccarelli*, Relief of the Madonna; 30. *Guercino*, St. Pelagia; *37. *Lorenzo Lotto*, Madonna and saints.

The street descending to the right from the Prefettura leads to the *Loggia dei Mercanti* (Exchange, Pl. 14; C, 3), an early-Gothic edifice with a façade of 1459. In the interior are paintings by *Pellegrino Tibaldi* and stucco-work by *Varlè*. — Adjoining is the pretty *Palazzo Benincasa* (15th cent.). — Farther on to the right we reach the church of *S. Maria della Piazza* (Pl. 11; C, 3), with a rich *Façade of the beginning of the 13th cent.; the sculptures by *Filippus*. — We return through the Via della Loggia to the PIAZZA DEL TEATRO (Pl. C, 3), the centre of business, beyond which is *S. Agostino*, with a late-Gothic portal showing a Renaissance tendency.

From the Piazza del Teatro the well-paved CORSO VITTORIO EMANUELE (Pl. C, D, E, 4; tramway) ascends towards the E., through the new quarters of the town. At the end is the spacious PIAZZA CAVOUR, with a colossal statue of the minister in the centre (Pl. 21; E, 4).

EXCURSIONS FROM ANCONA.

The Province of Ancona, the ancient *Picenum*, is a remarkably fertile district, abounding in beautiful scenery. The Apennines send forth a series of parallel spurs towards the sea, forming a number of short, but picturesque valleys. The towns and villages are invariably situated conspicuously on the heights. To the W. the view is bounded by the *Central Apennines*, which here attain their greatest elevation in several continuous ranges, from the *Montagna della Sibilla* to the *Gran Sasso d'Italia* (9815 ft.), and are covered with snow till July. Towards the E. glitters the broad Adriatic, on which numerous sails are visible in clear weather.

On the coast, 9 M. to the S. of Ancona, rises the ***Monte Conero** (1760 ft.), with an old Camaldulensian monastery, commanding a superb panorama. The pedestrian follows a tolerable road over the coast-hills nearly as far as (7 M.) *Sirolo* (2000 inhab.), whence a path to the left ascends in $3\frac{1}{4}$ hr. to the top. A carriage (see p. 102) may be taken as far as the foot of the hill.

The ANCONA-FOGGIA RAILWAY (to Loreto, 15 M., in 36-55 min.; fares 2 fr. 70, 1 fr. 90, 1 fr. 20 c., express 2 fr. 95, 2 fr. 5 c.; to Porto Civitanova, 27 M., in 1 hr. 5 min. to $1\frac{3}{4}$ hr.) penetrates the heights enclosing Ancona by means of a tunnel. To the left, Monte Conero. 4 M. *Varano*.

10 M. **Osimo** (*Albergo della Corona*, in the market-place; omnibus from the station to the town, 3 M., 75 c.), the ancient *Aurimum*, colonised by the Romans B.C. 157, and mentioned by Cæsar, is now a country-town with 5000 inhab., and lies on a hill in a commanding position. The greater part of the **Town Wall*, dating from the 2nd cent. B.C., still exists. A walk round it affords a beautiful view. The *Palazzo Pubblico* in the large *Piazza* contains inscriptions and statues in Roman dress, found on the site of the ancient forum in the 15th cent., but barbarously mutilated on the occasion of the capture of the town by the Milanese in the 16th century. The *Cathedral* contains a fine bronze font of the 16th century.

Proceeding hence by railway, we perceive, to the right, *Castelfidardo*, where on 18th Sept. 1860, the papal troops under Lamoricière were totally defeated by the Italians under Cialdini.

15 M. **Loreto** (*Campanella*, or *Posta*, in the principal street; omnibus to the town 60 c.), situated on a hill at some distance from the line, and affording admirable *Views of the sea, the Apennines, and the province of Ancona, is a celebrated resort of pilgrims (nearly half a million annually). It consists of little more than a single long street, full of booths for the sale of rosaries, medals, images, etc., and is much infested by beggars.

According to the legend, the house of the Virgin at Nazareth became an object of profound veneration after the year 336, when the aged Empress Helena, mother of Constantine, made a pilgrimage thither, and caused a basilica to be erected over it. Owing to the incursions of the Saracens the basilica fell to decay, and after the loss of Ptolemais the *Casa Santa* was miraculously transplanted by the hands of angels in 1291 to the coast of Dalmatia (the precise spot being between Fiume and

Tersato), where it remained undisturbed during three years. For some unknown reason, however, it was again removed by angels during the night, and deposited near Recanati, on the ground of a certain widow *Laurela* (whence the name *Loreto*). A church was erected over it, and houses soon sprang up for the accommodation of the believers who flocked to the spot. In 1586 Pope Sixtus V. accorded to Loreto the privileges of a town.

Among the numerous pilgrims who have visited this spot may be mentioned Tasso, who thus alludes to it: —

*'Ecco fra le tempeste, e i fieri venti
Di questo grande e spazioso mare,
O santa Stella, il tuo splendor m'ha scorto,
Ch' illustra e scalda pur l'umane menti'.*

The *CHIESA DELLA CASA SANTA has been repeatedly restored since 1464. The handsome façade was erected under Sixtus V., a colossal statue of whom adorns the entrance flight of steps. Over the principal door is a life-size statue of the Madonna and Child, by *Girolamo Lombardo*, his sons, and his pupils; there are also three superb bronze-doors, executed under Pope Paul V., 1605-21. The campanile, designed by *Vanvitelli*, is a very lofty structure in a richly-decorated style, surmounted by an octagonal pyramid. The principal bell, presented by Pope Leo X. in 1516, weighs 11 tons.

In the INTERIOR, to the left of the entrance, is a beautiful *Font, cast in bronze by *Tiburzio Verzelli* and *Giambattista Vitale*, and adorned with bas-reliefs and figures of Faith, Hope, Charity, and Fortitude. On the altars and in the chapels of the nave are *Mosaics representing St. Francis of Assisi, by *Domenichino*, and the Archangel Michael, by *Guido Reni*; also a number of valuable pictures, frescoes, and sculptures.

In the centre of the church rises the '*Casa Santa*' (or '*Holy House*'), a simple brick-building, 13½ ft. in height, 28 ft. in length, and 12½ ft. in width, surrounded by a lofty *Marble Screen designed by *Bramante*, and executed by *Andrea Sansovino*, *Girolamo Lombardo*, *Giovanni da Bologna*, *Bandinelli*, *Tribolo*, *Guglielmo della Porta*, etc., with bronze doors by *Girolamo Lombardo*. This handsome work was begun under Leo X., continued under Clement VII., and completed under Paul III. It is adorned with statues of prophets and sibyls, and with reliefs, among which are: —

W. Side. Annunciation, by *Sansovino*, termed by Vasari, '*una opera divina*'; smaller representations by *Sangallo*, *Gir. Lombardo*, and *Gugl. della Porta*.

S. Side. Nativity, by *Sansovino*; David and Goliath, Sibyls, Adoration of the Magi, by other masters.

E. Side. Arrival of the Santa Casa at Loreto, by *Niccolò Tribolo*; above it, Death of the Virgin, by *Domenico Aimo* of Bologna.

N. Side. Nativity of the Virgin, begun by *Sansovino*, continued by *Baccio Bandinelli* and *Rafaele da Montelupo*. Bas-reliefs: Nuptials of the Virgin, by the same masters.

In a niche of the interior is a small black image of the Virgin and Child, in cedar, attributed to St. Luke. It is richly adorned with jewels, the lustre of which is enhanced by silver lamps always kept burning. In 1798 it was carried off to Paris by the French.

In the N. TRANSEPT is the entrance to the *Treasury (open to the public on Sun. till 11.30 a.m.; at other times fee 1 fr.), which contains valuable votive offerings and curiosities, the gifts of monarchs and persons of rank. Several of the treasures disappeared at the time of the Peace of Tolentino (1797). The ceiling-painting is by *Pomarancio*, who also painted the now damaged frescoes in the dome.

In the Piazza in front of the church are situated the *Jesuits' College* and the —

*PALAZZO APOSTOLICO, begun in 1510 from designs by Bra-

mante. It contains a small picture-gallery (*Titian*, Christ and the woman taken in adultery; *Vouet*, Last Supper; *Schidone*, St. Clara; *Guercino*, Descent from the Cross; *Ann. Carracci*, Nativity, etc.); a hall with *Tapestries after Raphael's Cartoons* (Paul at Lystra, Healing the Lame, 'Feed my Sheep', Elymas the Sorcerer, Holy Family, Miraculous Draught of Fishes, St. Paul's Speech); and a *Collection of *Majolicas*, chiefly from the well-known manufactory in Urbino (1 fr.).

The next station beyond Loreto is —

17½ M. **Recanati**, loftily situated at some distance from the line, and commanding charming views. It was a fortified and important place in the middle ages. A charter of municipal privileges accorded to it by Emp. Frederick II. in 1229 is shown at the *Palazzo Comunale*. The Cathedral of *S. Flaviano*, with a Gothic porch, contains the monument of Gregory XII., of 1417. Several of the palaces deserve notice, especially that of the *Leopardi*, containing the collections of the scholar and poet *Giacomo Leopardi* (d. 1837).

Excursion from Recanati to *Macerata* (see below), passing the ruins of *Helvia Ricina* (remains of an amphitheatre, bridge, etc., on the *Potenza*). Omnibus from Macerata to stat. Civitanova.

The train crosses the *Potenza*. 23 M. *Potenza Picena*, named after a Roman colony, the ruins of which have disappeared. On the hill, 4½ M. distant, lies *Montesanto*.

27 M. *Porto Civitanova*, at the mouth of the *Chienti*; the town of Civitanova lies 1 M. inland. — Thence to Pescara, Foggia, etc., see *Baedeker's Southern Italy*.

FROM PORTO CIVITANOVA TO FABRIANO, 59½ M., railway in about 4 hrs. — The line at first ascends the fertile valley of the *Chienti*. The principal stations are as under.

17½ M. **Macerata** (*Pace*; *Posta*), a flourishing town with 20,300 inhab., capital of the province of Macerata, picturesquely situated on the heights between the valleys of the *Chienti* and *Potenza*, possesses a university, an agricultural academy, etc. In the *Cathedrat* a Madonna with St. Francis and St. Julian, ascribed to *Perugino*. In *S. Giovanni* an Assumption of the Virgin, by *Lanfranco*. The *Palazzo Municipale* and the *Pat. Compagnoni* contain inscriptions and antiquities from *Helvia Ricina* (see above), after the destruction of which the modern towns of Recanati and Macerata sprang up. Macerata also has a modern triumphal arch, called the *Porta Pia*. The *Biblioteca Comunale* contains a small *Pinacoteca*, the chief treasures of which are a Madonna and SS. Julian and Anthony of Padua by *Gentile da Fabriano* (Nos. 35, 22), a Madonna by *Carlo Crivelli* (1470; No. 36), and a Madonna with saints by *Alegretto da Fabriano* (1368; No. 39). Outside the gate, ¾ M. from the town, is the church of the *Madonna delle Vergine*, ascribed to *Bramante*.

22 M. *Urbisaglia*, the Roman *Urbs Salvia*, with extensive ruins, amphitheatre, walls, baths, etc.

28½ M. **Tolentino** (*Corona*, tolerable), the ancient *Tolentinum Picenum*, prettily situated on the *Chienti*, with 12,000 inhab., was once strongly fortified. The *Palazzo Municipale* in the Piazza contains a few Roman antiquities, the most important of which is a female portrait-statue of the time of the Flavian emperors. The *Basilica di S. Niccolò* possesses a court of the 13th cent. and a Gothic **Portal*, presented to his native town by Niccolò Mauruzzi, the celebrated condottiere (1435). A chapel in the interior is adorned with frescoes from the life of St. Nicholas, by *Lorenzo* and *Jacopo da San Severino*, and another contains two paintings of the

Venetian school (the Fire at St. Mark's at Venice, and the Plague in Sicily). The church of *S. Francesco*, dating from the 13th cent., contains a fresco of the Crucifixion executed in 1360 (chapel to the right of the high-altar) and another of 1475, representing the Madonna and S. Amicone healing the infirm (chapel to the left). The church of *S. Catero*, on the E. side of the town, possesses an early-Christian sarcophagus, embellished with reliefs (Adoration of the Magi, Christ as the Good Shepherd) and containing the remains of St. Catervus, who is highly revered in the Marches. The frescoes of the Crucifixion and the Evangelists date from the 15th century. The *Pal. Gentiloni* contains the proceeds of the excavations carried on by Count Silveri Gentiloni since 1880 in the Picene necropolis surrounding the town (adm. by visiting-card). The tombs, dating from c. 525-350 B.C., yield numerous weapons and amber ornaments. The learned *Francis Philelphus*, one of the first students and disseminators of classical literature, was born at Tolentino in 1388. — The picturesque environs command fine views of the mountains.

The railway now quits the Chienti and enters the valley of the *Potenza*. — 35 M. **San Severino delle Marche**, 6 M. to the N.W. of Tolentino and about as far S. of Castel-Raimondo (see below), in the valley of the Potenza, arose from the ruins of the ancient *Septempeda*. In the church *del Castello*, frescoes by *Diotisalvi d'Angeluzzo*, and an altar-piece by *Niccolò da Foligno* (1468); in the sacristy of the *Duomo Nuovo* a Madonna by *Pinturicchio*. *S. Lorenzo* stands on the site of an ancient temple. Inscriptions and antiquities in the town-hall, and at the residence of the Conte Servanzi-Collio.

From (42 M.) *Castel-Raimondo* a road leads to the S. to (6 M.) **Camerino**, the ancient *Camerinum Umbrorum*, once the capital of the Umbrian Camertes, who during the Samnite wars allied themselves with Rome against the Etruscans. It is the seat of a bishopric (founded in 252). The cathedral of *S. Savino* occupies the site of a temple of Jupiter; in front of it is a bronze Statue of Pope Sixtus V., of 1587. The painter *Carlo Maratta* was born here in 1625 (d. at Rome in 1713).

47 M. **Matelica**, a town with 4000 inhab., possessing pictures by Palmezzano and Eusebio di S. Giorgio in the church of S. Francesco, and a small picture-gallery in the *Pal. Piersanti*. — 54 M. *Albacina*. — 59½ M. *Fabriano*, see p. 109.

14. From Ancona to Foligno (*Orte, Rome*).

80 M. RAILWAY in 4-5½ hrs. (fares 14 fr. 60, 10 fr. 25, 6 fr. 60 c.; express 16 fr. 5, 11 fr. 25 c.). To Rome (183 M.) in 8½-12 hrs. (fares 33 fr. 35, 23 fr. 30, 15 fr. 5 c.; express, 36 fr. 70, 25 fr. 65 c.).

The train runs on the rails of the Bologna line, which with the old road skirts the coast (to the right a retrospect of the town and harbour), as far as (5½ M.) *Falconara* (p. 102).

Here the train diverges to the S.W. into the valley of the *Esino* (Lat. *Æsis*), which it soon crosses at (10½ M.) *Chiaravalle*, a small town with a Cistercian monastery.

17½ M. **Jesi** (**Alb. & Trattoria della Speranza; Corona*), with 20,000 inhab. (incl. villages), now one of the most prosperous manufacturing towns of the province, was the ancient *Æsis*, where the Emp. Frederick II., the illustrious son of Henry VI. and Constantia of Sicily, and grandson of Frederick Barbarossa, was born on 26th Dec. 1194. The picturesque town-walls, dating from the middle ages, are in good preservation. The *Cathedral* is dedicated to the martyr St. Septimins, the first bishop of Jesi (308). The *Palazzo Pubblico*, now the Prefettura, bears the town-arms within

an elaborate Renaissance border. Jesi was also the birthplace of the composer G. Spontini (1778-1851).

The valley contracts, and the train crosses the river twice. 26 M. *Castel Planio*. Beyond (30½ M.) *Serra S. Quirico*, near *Monte Rosso*, the valley narrows to a wild ravine, endangered by falling rocks. Long tunnel through the *Monte Rosso*. 39½ M. *Albacina*, junction for Porto Civitanova (p. 107).

44½ M. **Fabriano** (*Leon d'Oro; Campana*), a prosperous town with 18,000 inhab. (incl. suburbs), noted since the 14th cent. for its paper-manufactories, lies near the sites of the ancient *Tuficum* and *Attidium*. The *Town Hall* contains ancient inscriptions and a small collection of pictures. The *Campanile* opposite bears a bombastic inscription about the unity of Italy. The churches of *S. Niccolò*, *S. Benedetto*, *S. Agostino*, and *S. Lucia*, and the private houses *Casa Morichi* and *Fornari*, contain pictures of the Fabriano school, of which *Gentile da Fabriano* (?1370-1450; p. 48) was the head. — Railway to Porto Civitanova, see p. 107.

From Fabriano a mountain-road (9 M.) leads viâ the picturesque *La Genga* to the lofty **Sassoferrato**, situated in a fertile valley, consisting of the upper and lower town, with 2000 inhab., and possessing interesting churches and pictures. *Giambattista Salvi*, surnamed *Sassoferrato*, was born here in 1605; he was especially noted for his *Madonnas*, and died at Rome in 1685. *S. Pietro* contains a *Madonna* by him. In the vicinity are the ruins of the ancient *Sentinum*, where, B. C. 296, the great decisive battle took place between the Romans and the allied Samnites, Gauls, Umbrians, and Etruscans, in which the consul Decius heroically sacrificed himself. The Roman supremacy over the whole of Italy was thus established.

Beyond Fabriano the train skirts the brook *Giano*, and penetrates the central Apennine chain by a tunnel 1¼ M. long.

At (54½ M.) *Fossato* (junction of the line from Arezzo to Fossato, pp. 56-59) we enter the plain of the *Chiascio*. To the left on the hill, *Palazzolo*; to the right, *Pellegrino*; to the left, *Palazzo* and *S. Facondino*.

58 M. **Gualdo Tadino**, a small town with 7000 inhab., lies about 2 M. from the railway (cab 40 c.), near the insignificant ruins of the ancient *Tadinum*. In 552 Narses defeated and slew the Ostrogothic king Totila here, and owing to this victory, soon gained possession of Rome. In the *Palazzo Comunale* is a small picture-gallery with a *Pietà* by Niccolò Alunno (1471) and works by native artists; in the corridor are an ancient sarcophagus and a few inscriptions. The church of *S. Francesco* contains an altar-piece by Niccolò Alunno (1471). The *Cathedral* has a fine rose-window; in the sacristy, pictures by Niccolò Alunno.

The train gradually descends to (68 M.) **Nocera**, an episcopal town, on the site of the ancient *Nuceria*, a city of the Umbri (3 M. from the station; omn.). The *Cathedral* and the church of the *Maddernina* contain a few tolerable paintings. Some admirable frescoes of 1434 were discovered in 1877 on the organ-screen of *S. Francesco*, and others of less importance (c. 1500) in the nave and choir,

The *Orfanotrofeo (Vescovado Antico)* contains portraits of the bishops of Nocera from the 1st cent. of our era(?), painted in 1659. Near the town are mineral springs, known since 1510.

The train now enters the narrow *Val Topina*, crosses the brook several times, passes through a tunnel, and descends by *Ponte Centesimo* to —

80 M. *Foligno*; thence to *Rome*, see pp. 79-87 and 66-68.

SECOND SECTION.

R O M E.

Arrival. At the railway-station (Plan I, 25) numerous hotel-omnibuses are in waiting, for the use of which a charge of 1-1½ fr. is made in the bill. *Open one-horse Cab* for 1-2 pers., 1 fr.; at night 1 fr. 20 c.; *Closed one-horse Cab* 1-2 pers. 1 fr. 20 c., at night 1 fr. 30 c.; each additional pers. 20 c., at night 40 c.; *Two-horse Carriage*, for 1-4 pers., 2 fr., at night 2½ fr.; each addit. pers. 20 c., at night 40 c.; small articles of luggage free, each small box 20 c., trunk 50 c. *Porter (facchino)* 25-60 c. — **POLICE OFFICE (Questura):** Via SS. Apostoli 17 (Pl. II, 16). — Railway enquiry and ticket offices in the town, Via della Propaganda 8 and Corso 218; also *Thos. Cook & Son*, Piazza di Spagna 2.

Embassies and Consulates. There are two classes of diplomatic agents at Rome, those accredited to the Italian government, and those accredited to the Papal court. The offices of two of the former class alone need here be mentioned: **ENGLISH EMBASSY**, *Marquis of Dufferin*, Via Venti Settembre, near Porta Pia; **AMERICAN LEGATION**, *Hon. Albert G. Porter*, Via Nazionale 13 (office-hours 10-1). — **ENGLISH CONSULATE:** *A. Roesler Franz, Esq.*, consul, Piazza S. Claudio 96. **AMERICAN CONSULATE:** *Hon. Augustus O. Bourn*, consul-general, Via Nazionale 13 (office-hours 10-2).

Hotels (comp. pp. vi, xx). The best and most expensive are in the *Strangers' Quarter*, between the Porta del Popolo and the Piazza di Spagna, and also between the latter and the railway-station (some of them inconveniently situated). Several are closed during summer.

***HÔTEL QUIRINALE** (Pl. I, 25, *h*), Via Nazionale, a large hotel in the Swiss style, with lift, R. & L. 4-6, B. 1½, lunch 3, D. 5-6, A. 1, omn. 1, 'pension' 12 fr. and upwards; ***HÔTEL DE LONDRES** (Pl. I, 17, *c*), Piazza di Spagna 13, with lift, D. excl. wine 6 fr.; ***BRISTOL** (Pl. I, 22, *x*), Piazza Barberini, with lift; ***RUSSIA** (Pl. I, 18, *b*), Via del Babuino 9, near the Piazza del Popolo, with a lift and a pleasant garden, R. from 3, B. 1½, lunch 3, D. 5, 'pension' 10 fr. and upwards; **ROMA** (Pl. I, 17, *i*), Corso 128, with lift, R. 4, D. 5, B. 1½ fr.; **EUROPA** (Pl. I, 20, *d*), Piazza di Spagna 35. After these rank the ***HÔTEL CONTINENTAL**, Via Cavour 5, near the station, with lift; **HÔTEL DE LA VILLE** (Pl. I, 18, *o*), Via del Babuino 196; **HÔTEL DE PARIS** (Pl. I, 23, *z*), Via S. Nicola di Tolentino, with lift; ***INGHILTERRA** (Pl. I, 17, *f*), Via Bocca di Leone 14, B. 1½, D. 5 fr.; ***HÔTEL ROYAL**, Via Venti Settembre, opposite the Finance Ministry (p. 168), new, with lift; **HÔTEL MARINI**, Via del Tritone 17, with lift. At all these, 'pension' for a prolonged stay, 10-12 fr. per day, and upwards.

Somewhat less expensive: **MINERVA** (Pl. II, 16, *m*), Piazza della Minerva 69, in the interior of the city, well spoken of, with lift, R. 3, B. 1¼, D. with wine 5 fr.; ***HÔTEL HASSLER** (Pl. I, 17, *w*), Via Bocca di Leone 68, 'pension' from 11½ fr., without lunch from 9 fr. (Feb. 1st-June 1st, 12 and 9½ fr.), frequented almost exclusively by Germans, with restaurant; **EDEN HOTEL** (same proprietor), Via Ludovisi 49, with lift; **ALLEMAGNE** (Pl. I, 17, *k*), Via Condotti 18, well spoken of; **MOLARO** (Pl. I, 19, *w*), Via Gregoriana 56, R. from 4, A. 1, L. ¾, B. 1½, lunch 3, D. 5 fr.; **HÔTEL-PENSION DU MIDI**, Via delle Finanze; **ANGLO-AMERICANO**, Via Fratina 128; **VITTORIA** (Pl. I, 19, *l*), Via Due Macelli 24; **LAURATI**, Via Na-

zionale 153-155, not far from the Piazza Venezia, with lift, R. 3½, L. ¾, A. ¾ fr.; MILANO, Via Colonna 22 and Piazza di Monte Citorio (Pl. I, 16), frequented by the Italian deputies, with a restaurant; ALIBERT (Pl. I, 17, q), Vicolo d'Alibert, quiet, R. 2½, A. ½ fr.; CESARI (Pl. I, 16, v), Via di Pietra; ITALIA (Pl. I, 22, aa), Via Quattro Fontane 12, with lift; POSTA, Via della Vite 29 (Pl. I, 16, 19), R. from 2 fr.; HÔTEL ET PENSION CENTRALE (Pl. I, 16, ad), Piazza della Rosa 9; CAVOUR, Via S. Chiara 5 (Pl. II, 13, 16), R. from 2, 'pension' from 7 fr.; ORIENTE (Pl. I, 19, ab), Via del Tritone 80, R. from 2, 'pension' from 7½ fr.; HÔTEL DU SUD (Pl. I, 19, v), Via Capo le Case 56; HÔTEL DU CAPITOLE, Corso 286-291, corner of the Piazza Venezia, 'pension' 8 fr., well spoken of, with a café-restaurant; COLONNA, Piazza Colonna; SENATO, Via delle Coppelle 16, with restaurant; ALBERGO S. CHIARA, Via S. Chiara 18, R. 2½ fr. — 'Pension' at all these hotels, except the smaller ones last mentioned, with or without luncheon. The price of the room is generally raised for those who do not take full 'pension', except in the last-named houses, where the visitor can arrange to be perfectly free. It is advisable to come at once to a distinct understanding as to the price of the room, including light and attendance.

Pensions. TELLENBACH, Via Due Macelli 66, near the Piazza di Spagna, with lift, pens. 7-9 fr.; AVANZI, Via Capo le Case 75; MRS. MAY, Via Ludovisi 15; LERMANN, Via Cavour 71, 7-10 fr. according to the room; Miss SMITH, Piazza di Spagna 93; PENSION FRANÇAISE (Mme. Lavigne), Via del Tritone 36, with lift; BELLEVUE DI PINCIO, Via di Porta Pinciana 18, English hostess, 8-10 fr.; MRS. CHAPMAN, Via S. Nicola da Tolentino 76, American; PENSION UNIONE, Piazza Monte Citorio 121; MAD. MICHEL, Via Sistina 72; KRUEGER, Via Nazionale 181, frequented by Americans, from 8 fr. per day; PECORI, Via Quirinale 45, in the Palazzo Rospigliosi, with back entrance towards the Via Nazionale (7 fr.); BELVEDERE, Via Porta Pinciana 18 (8 fr.).

Private Apartments. The best are situated in the quarter bounded by the Corso on one side, and by the Via del Babuino, the Piazza di Spagna, and the Via Due Macelli on the other, and also in the Via Capo le Case, Via Sistina, Via Gregoriana, Piazza Barberini, and other streets on the Pincio. The most expensive, and often the least sunny, are in the Corso, Piazza di Spagna, and Via del Babuino. A northern aspect should be studiously avoided, and a stipulation made for stove, carpet, and attendance (stufa, tappeti, servizio). Rent of two well-furnished rooms in a good locality 150-250 fr., one room 40-80 fr. per month; for a suite of 3-5 rooms 300-500 fr. and even more. Artists generally reside in the Via Sistina, Via Quattro Fontane, and that neighbourhood. In the Forum of Trajan and the adjoining streets the visitor may obtain sunny apartments, conveniently situated with regard to the ancient part of the town. Rooms may be procured in almost every street in the strangers' quarter, where notices and placards are frequently observed; but, as they are seldom removed when the rooms are let, the traveller must be prepared for a number of fruitless enquiries. Those who engage apartments in the Corso should come to an understanding with regard to the windows for the Carnival. — House-agents: *Karl Pochalsky* (German), Corso 131; *Toti*, Piazza di Spagna 53; *Multon & Co.*, Via Frattina 104. — Firewood is kept stored in many houses (basket about 2½ fr.); it may be bought cheaper (20 fr. per 'passo', delivered free), at *Rotti's*, Via Monte Brianzo 33; *Gentili's*, Campo Marzio 24; and other large wood-stores.

Rome does not yet possess a complete DIRECTORY; but much information is afforded by the *Guida Commerciale della Città di Roma*, published by *Tito Monaci* (10 fr.). An unknown address may be ascertained at the *Ufficio di Anagrafe* on the Capitol, under the arches of Vignola, above the stairs leading to the Monte Caprino (p. 208).

Restaurants (those of more moderate pretensions are called *Trattorie*: comp. p. xxii). Handsomely fitted up and expensive (*D. à prix fixe* 6 fr. and upwards): — *Nazzarri*, Piazza di Spagna 81; *Spillmann & Co.*, Corso 164; *Renard*, Via Frattina 97; *Café di Roma* (p. 113); *Doney & Nipoti*, Via delle Convertite 19. — The following are somewhat less pretensions: *Milano* (see above), Monte Citorio 13; *Colonna*, Piazza Colonna, in the arcade to the

right; *Café di Venezia*, Corso 288, near the Piazza Venezia; *Birreria Morteo & Co.* (see below; lunch from 3, D. from 4 fr.).

Second class, with good French and Italian cuisine: *Ranieri*, Via Mario de' Fiori 26; **Corradetti*, Via della Croce 81, frequented by visitors of all nationalities; *Panelli*, Via della Croce 69; *Gran Cairo*, Via del Tritone 182; *Senato* (see p. 112), Via delle Copelle 16; *Al Fagiano*, Piazza Colonna, at the corner of the Via Colonna, often crowded (branch at Via Sistina 3); *Le Venete* (Venetian cuisine), Via Campo Marzio 69, with garden.

The TRATTORIE are recommended to those who have some acquaintance with the language and customs of the country: — *Cervigni*, Via Nazionale 246; *Pietro Micca*, Via S. Andrea delle Fratte 35 and Via Mercede 27 (Piedmontese cookery); *Rosetta*, Via Giustiniani 22 and Via Rosetto 1, nearly opposite the front of the Pantheon. — The cuisine and wine at the following are perhaps as good as at those just enumerated, but the rooms are not so clean: *Gabbione*, Via del Lavatore 40, by the Fontana Trevi; *Torretta*, Piazza Borghese; *Tratt. Europea*, Piazza Rusticucci 21 & 26, opposite St. Peter's; *Tratt. degli Artisti*, Via della Vite 68 (German cooking and beer; also a few beds); *Tre Re*, Via della Ripresa dei Barberi 16, first floor, near the Piazza Venezia; *Bucci*, Pescheria delle Copelle 54-57 (fish and 'zuppa alla marinara'). — Meals supplied to private houses by nearly all the Trattorie and by *Bricchi*, Via Capo le Case 71; *Giorgio*, Via Bocca di Leone 5. — Mention may also be made of the ROSTICCERIE, where freshly cooked meat and poultry may be bought by the pound for dinner or supper: *Canepa*, Via Venti Settembre 22; *Polotti*, Via Venezia 10; *Mei*, Tomacelli 158, and others.

Osterie (wine-houses, comp. p. xxiv). The ordinary wines of the environs of Rome (*Vino dei Castelli Romani*) are generally served in clear bottles containing one, a half, or a fifth litre (mezzo litro 30-50c.), and the better qualities in smaller bottles (fiaschetti). — The following have a good name for their wine at present: *Jacobini*, with buffet, Via di Pietra 66 and Via Quattro Fontane 114 (wine of Genzano); *Ostini*, Via delle Convertite 11 (Genzano); *Palombella* (Montefiascone, p. 69), Via della Palombella 2; *Santovetti*, Via del Quirinale 21 (Frascati); *Salvatori*, Via Uffici del Vicario 22; the *Osteria*, Via Belsiana 86 (Marino wine); *Bottiglieria Romana*, Via Umiltà 74. There are also favourite Osterie on the *Monte Testaccio* (p. 251) and by the *Ponte Molle* (p. 336).

The best TUSCAN WINE HOUSES are *Caselli*, Via dell' Impresa 25, with a branch at Via del Tritone 172 B; *Campagnoli*, Via della Missione 5, behind the Chamber of Representatives; *Fiaschetteria Toscana*, Piazza S. Lorenzo in Lucina 30; *Siccioli & Co.* (wine only), Palazzo Sciarra, Via Muratte. The Tuscan wine is generally served in large bottles (fiaschi) covered with basket-work, and payment is made according to the quantity consumed (about 50 c. per mezzo litro). Luncheons may also be obtained at these houses.

Foreign wines are sold at the restaurants (p. 112), and by *Presenzini*, Via della Croce 78; *Burnel & Guichard Aîné*, Via Frattina 116. Also by the LIQUORISTI: **Aragno*, Corso 237, Piazza Sciarra, and Piazza Monte Citorio 118-120; *Giacosa*, Via della Maddalena 17-19; *Vinc. Attili*, Via del Tritone 88 (open till 2 a.m.); *Morteo* (see above). — Mineral waters may be obtained from *Caffarel*, Corso 20, and *Manzoni*, Via Pietra 90.

Beer (*birra*). *Birreria Morteo & Co.*, Palazzo Ruspoli (p. 148), in the Corso, at the corner of the Piazza in Lucina, with a pleasant garden (Vienna beer 35 c.; good cuisine, see p. 112); branch-establishment, Via Nazionale 46-48; **Sav. Albrecht*, Via di S. Giuseppe a Capo le Case 24 (Munich beer); *Birreria Poli*, Via Poli 90-96; *Maranello*, Via del Gesù 59; *Gambrinus-Halle*, Corso 393, near the Piazza Colonna (Munich beer). — Roman beer is brewed and sold by Germans: Via di S. Giuseppe a Capo le Case 7; also at the cafés, etc.

Cafés. **Roma*, Corso 426-432, somewhat expensive; **Nazionale*, Corso 372, adjoining the Palazzo Chigi, and also at the corner of the Corso (179) and Via delle Convertite (excellent coffee at these two); *Venezia*, Corso 289; *Colonna*, *Café degli Specchi*, Piazza Colonna; *S. Chiara*, Via S. Chiara, adjoining the Piazza Minerva; *Capretari*, Piazza Capretari; *Castellino*, Via Nazionale 129; *Caffè Turco*, Piazza di Spagna 43 (also beer); *Greco*, Via

Condotti 86, and *Artisti*, Via Due Macelli 91, also restaurant, both frequented by artists; *Castellino*, Via Nazionale 134. — *Ices* in all the cafés; particularly good at the *Sorbetteria Napoletana*, Via dell' Impresa 22, to the N. of the Piazza Colonna, 50 c. per portion, 30 c. per half-portion.

Confectioners. *Ronzi & Singer*, in the Piazza Colonna, corner of the Corso (No. 349); *Pesoli*, Via del Tritone 58; *Ramazzotti*, Via Frattina 76, Corso 282, and Via Nazionale 195; *Nazzarri*, Piazza di Spagna (comp. p. 112). — **ENGLISH AND VIENNESE BAKERS:** *Colalucci*, Via della Croce 91; *Luis*, Via della Croce 49; *Perego*, Via Nazionale 143; *Valan*, Via del Babuino 100 and Via Condotti 79a; *Donati* (biscuits), Via Principe Umberto 145. — **VACCHERIE** (dairies; fresh milk, cream, butter, and eggs daily): Via Venti Settembre 141, with branch-establishment at Via Sistina 105; Via Muratte 14; Via del Tritone 14. — **GROCERS:** *Casoni*, Piazza di Spagna 32; *Castrati*, Piazza Trevi 89; *Parenti*, Piazza di Spagna 46; *Mansili*, Via Due Macelli 90; *Achino*, Monte Citorio 116. — **PRESERVED MEATS, etc.:** *Albertini*, Via Nazionale 65 and Via Crociferi 28; *Dagnino*, Via del Tritone 54-56; *Guerrini*, Via Frattina 109; *Valazza*, Via Muratte 11. — **FRUIT SMOORS:** *Gangalanti*, Piazza S. Lorenzo in Lucina 19; *Posidoro*, Via del Tritone 179; *Melano*, Via della Croce 9.

Tobacco (comp. p. xxiv) at the *Regia dei Tabacchi*, corner of the Corso and Piazza Sciarra; foreign cigars 25 c. and upwards.

Gratuities. As exorbitant demands are often made, the following averages are given. In the galleries for 1 pers. 10 soldi, for 2-3 pers. 15s., for 4 pers. 1 fr.; regular frequenters 5 soldi. To attendants who open doors of houses, churches, gardens, etc., 5s.; for other services (guidance, explanations, light, etc.), 1/2-1 fr. — It is also usual to give a trifle (1-2s.) to the waiters at the cafés.

Baths (1 1/2-2 fr.; fee 25 c.) at the hotels; also Vicolo d'Alibert 1, Via Belsiana 64, Via del Babuino 96. Via Ripetta 116; Via della Vite 29, opposite the post-office; Via Volturmo 37 (recommended in summer, from May onwards). — **Hydropathic Establishments:** Piazza Pia (Pl. I, 10); Via Crociferi 44.

HAIRDRESSERS: *Giardinieri*, Corso 423; *Lancia*, Via S. Giacomo 12; *Pasquali*, Via Condotti 11; all with ladies' rooms. — **Perfumers**, Corso 390, 342, 343; *Rimmel*, Corso 524; *Brugia*, Corso 344.

LIEUX D' AISANCE (10 c.): Vicolo dello Sdrucciolo, near the Piazza Colonna; Via dei Pianellari, adjoining the church of S. Agostino (p. 189); Via Belsiana; Via del Mancino, adjoining the Piazza Venezia (15 c.); Vicolo del Governo Vecchio; Vicolo Tata Giovanni; Vicolo Tribuna Tor de' Specchi; Via Alessandrina; Passeggiata di Ripetta; in the colonnade of the Piazza of St. Peter, on the side next the Porta Angelica; outside the Porta del Popolo, to the left.

Climate (comp. Intro.). The mean temperature at Rome is 60° Fahr.; the greatest heat in summer being about 100° in the shade, and the greatest cold about 21°. Snow falls rarely, and does not lie long. The average temperature in January is 45°, in July 75°. The pleasantest season is from the beginning of October to the end of May. In summer when the fever-laden *aria cattiva* prevails, all the inhabitants who can afford it make a point of leaving the city. The prevalent winds are the *Tramontana*, or north wind, which generally brings clear and bracing weather, and the *Scirocco*, or south wind, which is relaxing and rainy. As the temperature usually falls rapidly after sunset, and colds are very easily caught, the traveller should not dress too lightly. Invalids should of course consult their medical advisers before choosing rooms, but even persons in robust health will do well to remember the Roman proverb: '*Dove non va il sole, va il medico*'.

Physicians. English: *Charles*, Via S. Nicola da Tolentino 72; *Drummond*, Piazza di Spagna 3; *Gason*, Via S. Sebastianello 8; *Baldwin*, Piazza Trinità de' Monti 16; *Young*, Piazza di Spagna 20; *Spurcay*, Via Condotti 48; *Thompson* (American), Via Due Macelli 60. — German: *Erhardt* (physician to the German Embassy), Mario de' Fiori 16; *Erhardt jun.*, Piazza di Spagna 26; *Fleischl*, Corso 151 (3-4); *Kranichfeld*, Piazza di Spagna 44; *Prof. Molescholl*, Via Volturmo 58; *Neuhaus*, Via di Porta Pinciana 56;

Weber, Via Sistina 86; *Gottburg*, Piazza di Spagna 9 (at Kissingen in summer); *Bull* (Danish), Piazza di Spagna 20; *Wittmer*, Via delle Quattro Fontane 17; *Bosány* (physician to the Austrian Embassy), Corso 300; *Held* (homœopath), Corso 456. — Italian: *Galassi*, Piazza Capretari 70; *Manassei*, Via de' Lucchesi 9; *Nardini*, Pal. Doria, Via Plebiscito 112; *Occhini*, Palazzo Moroni, Via S. Nicola da Tolentino; *Liberati* (homœopath), Via S. Chiara 49. — SURGEONS: *Ceccarelli*, Via Leccosa 54; *Duranle*, Via S. Basilio 50. — OCULISTS: *Danlone*, Piazza Monte Citorio 121 (hours for consultation 11-1); *Businelli*, Piazza S. Lorenzo in Lucina 17 (consultations 2-4). — AURIST: *De Rossi*, Piazza di Spagna 71. — DENTISTS: *Chamberlain* (American), Piazza di Spagna 51; *Curtis* (American), Piazza di Spagna 93, 1st floor; *Galassi*, Piazza di Spagna 68; *Van Marter* (American), Via Nazionale 87; *Martin*, Corso 389; *Stehlin*, Via delle Carozze 3, 1st floor.

Chemists: *Sininberghi*, *Evans*, & Co., Via Condotti 64-66, patronised by the English and American embassies; *Roberts & Co.*, Piazza di S. Lorenzo in Lucina 36; *Baker & Co.* (proprietor *G. P. Passarge*), Piazza di Spagna 42, patronised by the German embassy; *Borioni*, Via del Babuino 98; *Garneri*, Via del Gambero 39; *Marignani*, Corso 435; other Italian chemists in every part of the town. — SURGICAL INSTRUMENTS AND BANDAGES: *Immelen*, Via Frattina 134. — SICK NURSES may be obtained at Via Palermo 35 (10 fr. per day; Roman Catholic) or on application to Miss Martin, Via Palestro 62 (5-7 fr.).

Bankers. English: *Macbean & Co.*, Piazza di S. Silvestro 51; *Maquay, Hooker, & Co.*, Piazza di Spagna 20; *F. Montague-Handley*, Piazza di Spagna 79; *Eddy*, Piazza S. Silvestro 62; *Plowden & Co.*, Piazza S. Claudio 166. — Italian: *Cerasi*, Via del Babuino 51; *Spada*, Via Condotti 20. — German: *Nast-Kolb & Schumacher*, Via della Mercede 9; *Schmitt & Co.*, Via della Vite 7; *Pucci, Noerrenberg, & Co.*, Palazzo Chigi, Piazza Colonna; *Roesler-Franz*, Piazza S. Claudio 96; *Fueter, Tognola, & Co.*, Via del Tritone 46; *Wagnière*, Piazza Capranica 78. — *Money Changers* in the Corso, Via Condotti, etc. (comp. Introd.).

Booksellers. *Piale*, Piazza di Spagna 1; *Loescher & Co.*, Palazzo Simonetti, Corso 307, entered from Via del Collegio Romano; *Spilhoever*, Piazza di Spagna 84; *Libreria Centrale*, Pal. Bernini, Corso 146; English, German, and French books at all these. *Fratelli Bocca*, Corso 217; *Fratelli Treves*, Corso 383; *Paravia*, Piazza SS. Apostoli 56-65. — Religious works and music, Via di Propaganda Fide 6. — MAPS at *Bossi's*, Corso 401, and at *Loescher's* (see above). — OLD BOOKS at *Rossi's*, Via Bocca di Leone 25, and *Bocca's*, Via del Giardino 110; also at *Loescher's* and *Spilhoever's*. — BOOKBINDERS. *Glügler*, Via della Mercede 36; *Olivieri*, Piazza di Spagna 87 and Via del Babuino 49; *Santlinelli*, Via Pié di Marmo.

Libraries. The principal libraries are the following:

1. BIBLIOTECA APOSTOLICA VATICANA, see p. 319. Permessi issued directly by the Cardinal-Secretary of State to the prefects of the library, see p. 124. Readers admitted from Oct. 1st to Easter 9-1, from Easter to 29th June 8-12 o'clock; the library is closed on Sun., Thurs., and holidays.

2. PUBLIC LIBRAIRIES, open on the days mentioned below from 9 to 3, with the exception of the Biblioteca Angelica, which is open from 9 to 2. Admittance without permessi according to the conditions set forth in the placard in the Bibl. Vittorio Emanuele. Books are lent out by the Bibl. Vittorio Emanuele only, on the security of the embassy or consulate (farther particulars in the Ufficio dei Prestiti, on the ground-floor of the library). *Biblioteca Alessandrina* in the Sapienza (p. 197), entrance Via dell'Università, 1st Nov.-30th June also open 7-10 p.m. — *Biblioteca Angelica* (p. 189), Sun. and Thurs.; closed in Oct. — *Biblioteca Casanatensis* (p. 196), daily, except Sundays. — *Biblioteca Centrale Vittorio Emanuele* (p. 156), from Nov. to May also 7-10 p.m., closed for a short time at midsummer (besides the large public reading-room there is a 'Sala Riservata' with an excellent reference-library, for the use of which a permesso is necessary).

3. PRIVATE LIBRARIES: *Biblioteca Barberina* (p. 171), open to the public on Thurs. 9-2; closed in Oct. — *Biblioteca S. Cecilia*, Via de' Greci 18, daily 9-3 (music). — *Biblioteca Chigiana* (p. 154), admission by permesso, ob-

tainable through the traveller's consul, 10-12; closed in summer. — *Biblioteca Corsiniana* (p. 325), open to the public daily, except Sun. and Wed., Nov. to March 1-4, Apr. to July 2-5. — *Biblioteca Sarti* (p. 238), in the Academy of St. Luke, daily except Sat. and Sun., in summer 8-2, in winter 9-3. — *Biblioteca Vallicellana* (p. 200), open on Tues., Thurs., and Sat., 10-3. — *Biblioteca Lancisiana* (p. 276; medical works), in the Hospital of S. Spirito, daily, 9.30-2.30.

Lending Libraries. English books at *Piale's* and at *Loescher's* (see p. 115; one book weekly 1, monthly 3 fr.). — **Reading Rooms.** *Piale*, Piazza di Spagna 1 (English and American newspapers).

Newspapers, very numerous, 5-10 c. per number. The most popular with visitors are: *Italie* (in French, containing a list of the sights of the day); *Fanfulla* (similar to the Paris Figaro); *Riforma*, *Capitan Fracassa*, and *Popolo Romano*, three government organs; *Diritto*, *Tribuna*, opposition journals; *Capitale*, *Messaggero*, and *Don Chichotte*, radical; *Osservatore Romano*, *Journal de Rome*, *Civiltà Cattolica*, and *Voce della Verità*, all clerical. *Rugantino* is a comic paper in the local dialect. — The *Italian Times* and *Roman Herald* (20 c.) are English papers published at Rome.

Guides to the Antiquities. *Mr. R. S. Forbes*, publisher of the 'Bulletin Commentarium Rerum Urbanarum' (fortnightly), Via del Babuino 93, and *Signor Olinto L. Spadoni*, editor of the 'Roman Herald', Piazza di Spagna 3, give peripatetic lectures on the site of ancient ruins and organise excursions to the environs.

Teachers of Italian (2-3 fr. per lesson): enquire at the booksellers'.

Music Sellers. *Successori Landsberg*, Via Condotti 85, 1st floor (pianos and music for sale or hire); *Bossola*, Corso 140; *Venturini & Co.*, Corso 387; *Ricordi*, Corso 392; *Bartolo*, Via Condotti 70. — Strings: *Berti*, Via Tor Argentina 19; *Rufini*, Piazza SS. Apostoli 49. — Teachers of music and singing may be heard of at the booksellers' or at the music-shops. As well-known composers and teachers of the piano may be mentioned: *M. Ravnkilde*, a Dane, Ripetta 39; *Alb. Cavanna*, Via dei Greci 10.

Studios. SCULPTORS: *Amici*, Passeggiata di Ripetta 20; *L. Ansiglioni*, Via Venti Settembre 116; *R. Cauer*, Via Brunetti 16; *Chiaradio*, Via Margutta 5; *Dausch*, Via S. Giacomo 18; *Ezechiël*, Piazza delle Terme 118; *Feuerstein*, Via Palestra 19; *Galletti*, Via Gesù e Maria 21; *Gerhard*, Passeggiata di Ripetta 33; *Prof. Guglielmi*, Via Babuino 155; *Hasselrits* (Dane), Via Margutta 51; *Ives*, Via Margutta 33; *Jos. Kopf*, Via Margutta 59; *Macdonald*, Via S. Nicola da Tolentino 22; *Monteverde*, Piazza dell' Indipendenza; *F. Schulze*, Palazzo Barberini; *Simmons*, Via S. Nicola da Tolentino 73; *Sommer*, Monte Caprino 24a; *Spies*, Piazza S. Pietro in Vincoli 40a; *Story* (American), Via S. Martino a Macao 7; *Volkman*, Piazza Dante 5.

PAINTERS: *Aerni*, Via Margutta 48; *Alvarez*, Via S. Martino 9; *Brandt*, Via di Ripetta 39; *Brioschi*, Palazzo Venezia; *Coleman* (American), Via Margutta 33; *Corrodi* (water-colours), Via del Tritone 62; *H. Corrodi*, Via degli Incurabili 8; *Effenberger*, Vicolo S. Nicolo da Tolentino 13; *Ferrari*, Via Margutta 33; *Glennie*, Piazza Margana 17; *Griswold* (English), Via del Basilio 46; *Hébert*, director of the French Academy (p. 149); *Knüpfer*, Palazzo Venezia; *Koelman*, Via dell'Olmato 46 (miniatures); *Kronberg* (Swede), Via Margutta 33; *Lindemann-Frommel* (landscape), Via del Babuino 39; *Löwenthal*, Via Margutta 33; *Mario de Maria*, Pal. Lanza Vecchio, outside the Porta Pia; *Martens*, Via Flaminia 44; *Navone*, Passeggiata di Ripetta 35; *Nerly* (landscapes and sea-pieces), Piazza S. Bernardo 109; *Podesty*, Palazzo Doria, Circo Agonale 13; *Pradilla* (Spaniard), Via Sistina 75; *Schlösser*, Via Venti Settembre 4; *Schwarzer*, Piazza S. Salvatore in Lauro 13; *Sciuti*, Piazza Mattei 10; *L. Seitz*, Piazza Cappuccini 6; *Shade*, Via Sistina 123; *Siemiradski* (Pole), Via Gaeta 7; *Strutt*, Via della Croce 81; *Tilton*, Via S. Basilio 20; *Vannutelli*, Via Margutta 51a; *Vedder* (American), Via S. Basilio 20; *Villegas*, Pal. Villegas, Viale Parioli; *Weckesser*, Piazza Barberini 43; *Zielke*, Via de' Maroniti 4.

INTERNATIONAL ASSOCIATION OF ARTISTS, Via Margutta 53. President: *Jacovaeci* (painter). — **BRITISH ACADEMY**, Via S. Nicolo da Tolentino 22 A.

— BRITISH AND AMERICAN ARCHÆOLOGICAL SOCIETY, Via delle Croce 76, with a good library. — VEREIN DEUTSCHER KÜNSTLER, Palazzo Serlupi, Via del Seminario 13.

Works of Art, both ancient and modern, are liable to government inspection on exportation. — **GOODS AGENTS:** *C. Stein*, Via di Mercede 42; *Giordani & Ferroni*, Piazza Colonna 370a; *Roessler, Franz, & Co.*, Via Condotti 6; *Tombini*, Via del Gambero 6. — **PACKER** ('Incassatore'): *Ferroni*, Ripetta 228; *Vincenzo Giorgini*, Via Mororiti 31.

Shops. **ANTIQUITIES:** *Augusto Castellani*, Piazza di Trevi 86 (see below); *Martinetti*, Via Bonella 74; *Bernard*, Via Sistina 21; *Innocenti*, Piazza Trinità de' Monti 13A; *Noci*, Via Fontanella Borghese 29.

ART, WORKS OF. *Società Artistica*, Via del Babuino 136; *D'Atri*, Via Condotti 7; *Pisani*, Piazza di Spagna 23 (these chiefly for pictures); *Andreoni*, Piazza del Popolo 17 (marble and alabaster sculptures). See also Cameos, Casts, Copies of Bronzes, Engravings, etc.

ARTISTS' MATERIALS. *Corteselli*, Via Sistina 150; *Juliana*, Via Babuino 147; *Zecca*, Via Margutta 53a.

ARTICLES OF VOYAGE: *Barfoot* (English saddlery), Via del Babuino 150D and 152; *Chiara*, Via Giustiniani 17; *De' Angeli*, Via Sistina 28; *Old England*, Via Nazionale 115.

CAMEOS: *Sautini*, Via del Babuino 96; *Angelici*, Via Sistina 19; *Pianella*, Via de' Maroniti 4, fourth floor; *D'Estrada*, Via Sistina 26; *Rosi*, Piazza di Spagna 86, second floor.

CASTS: *Marsili*, Via Frattina 16; *Leopoldo Malpieri*, Corso 54; *Padovelli*, Via Due Macelli 85; *Lucignani*, Via Sistina 111.

CLOTHING. FOR GENTLEMEN: *Guastalla*, Corso 335 (large shop); *Savonelli & Co.*, Corso 300; *Fratelli Bocconi*, Corso, adjoining the Piazza Colonna; *Old England*, Via Nazionale 115. See Tailors. — **LADIES' DRESS AND MILLINERY:** *Fraletti Ponlecorvo*, Corso 172; *Massoni*, Corso 307; *Compagnie Lyonnaise*, Corso 473; *Catarina Tua*, Corso 526; *Madame Boudrot*, Via Condotti 81; *Mauro-Giubergia*, Corso 60; *Antonia Lupa*, Corso 28; *Ville de Lyon*, Via dei Prefetti 48-52; *Costanza Federico*, Via S. Nicola da Tolentino 26 (for moderate requirements). — See Haberdashery.

COPIES OF ANCIENT BRONZES AND MARBLES: *Boschetti*, Via Condotti 74; *Röhrich*, Via Due Macelli 62; *Nelli*, Via del Babuino 139; *Rainaldi*, Via del Babuino 51A (large stock, fixed prices).

DRAPERS: *Todros*, Corso 418; *Schoslal*, Corso 158; *Oussel*, Corso 244; *Guastalla*, Via Colonna 20.

DRESSMAKERS: *Caterina Tua*, Corso 526; *Antonia Lupa*, Corso 28; *Massoni*, Corso 307; *Costanza Federico*, Via S. Nicola da Tolentino 26, I. (for moderate requirements).

ENGRAVINGS at the *Regia Calcografia*, formerly the Stamperia Camerale (moderate prices), Via della Stamperia 6 (Pl. I, 19, 7).

FURNITURE (carved). *Barberito*, Via Sistina 130; *Noci*, Via Fontanella Borghese 29-34. — **INTARSIA:** *Zuccarelli*, Via del Babuino 34.

GLOVES, COLLARS, AND NECK-TIES: *Chanal*, Corso 143; also at Corso 227; Piazza S. Lorenzo in Lucina 39; Via della Vite 10; Via Frattina 15; Via di Pietra 77.

GOLDSMITHS: **Castellani*, Piazza di Trevi 86, who also possesses an interesting collection of ancient golden ornaments, and executes imitations from Greek, Etruscan, and Byzantine models; *Marchesini*, corner of the Corso and Via Condotti; *Boni*, Piazza S. Carlo, in the Corso; *Ansorge, Fasoli, Pierret*, Piazza di Spagna 72, 95, & 20; *Freschi*, Via Condotti 56; *Calvi*, Via Sistina 15 (silver ornaments after ancient patterns).

HABERDASHERY: *Masini*, Corso 309; *Carsana*, Corso 136; *Borgia*, Via dei Prefetti 19. See also Clothing, Dressmakers, Roman Shawls.

HATTERS: *Bessi*, Via Nazionale 137; *Miller*, Via Condotti 16; *Vigano*, Via Monte Catini 4; *Monti* (straw-hat warehouse), Piazza Fireuze 29.

JEWELLERY, see Goldsmiths, Roman Pearls.

LAMPS, etc.: *Faucillon*, Via di Propaganda 23.

MARBLE-CUTTERS: *Orlandi*, Via Sistina 75C; *Fabbi*, Via Sistina 94; *Piermattei*, Via Sistina 81,

MILLINERS, see Haberdashers, Dressmakers, etc.

MOZAICS: *De Felici*, Piazza di Spagna 99; *Roccheggiani*, Via Condotti 14. Mosaics and cameos, at moderate prices, in the Stabilimento, Piazza Borghese 106.

OPTICIANS: *Hirsch*, Corso 402; *Priotti*, Corso 419; *Suscipi*, Corso 157.

PHOTOGRAPHS: *Loescher* (p. 115); *Spithoever* (p. 115; Braun's photographs, Anderson's views of Rome); *Libreria Centrale* (p. 115; Brogi's photographs); *Molins*, Via Condotti 28 (views of the Parker Collection, for archaeologists); *Casali*, Via Sistina 119; *Hefner*, Via Frattina 133 (Semelli's photographs); *Alinari & Cook*, Corso 90; *Moscioni*, Via Condotti 10a; *Olivieri*, Piazza di Spagna 87 and Via Babuino 49; *Piale*, Piazza di Spagna 1.

Photographs for artistic purposes (reproduction of sketches, pictures, etc.): *Vasari*, Via Poli 25. — Portraits: *Alessandri*, Corso 12; *Le Lieure*, Vicolo del Mortaro 19; *Montabone*, Piazza di Spagna 9; *Schemboche*, Via di Mercede 54; *Fotografia Nazionale*, Via Gregoriana 20; *Suscipi*, Via Condotti 48; *Della Valle*, Via della Croce 67.

ROMAN PEARLS: *Rey*, Via del Babuino 122; *Bartolini*, Via Frattina 97; *Lacchini*, Piazza di Spagna 69.

ROMAN SHAWLS: *Agostini*, Campo Marzo 3; *Bianchi*, Piazza della Minerva 69 (also other Roman silk wares); *Amadori*, Corso 316; *Steffoni*, Piazza di Spagna 63.

SHOEMAKERS: *Berardi*, Via Fontanella di Borghese 36; *Giangrandi*, Via Frattina 79; *Jesi*, Corso 129; *Rubini*, Corso 223; *Renner*, Via delle Quattro Fontane 7; *Patetta*, Via Due Macelli 30; *Fratelli Münster*, Corso 162. Boots and shoes are generally dear in Rome.

SMALL WARES, etc.: *Merico Cagiati*, Corso 167-169; *Janetti*, Via Condotti 18; *A. Cagiati*, Corso 250; *Finzi & Bianchelli*, Corso 377; *Old England*, Via Nazionale 115; *Fil. Haas & Figli*, Via Condotti 46, at the corner of the Corso.

STATIONERS: *Calzone*, Corso, entrance in the Via Lata; *Ricci*, Corso 214, Piazza Colonna; *Brenta*, Pal. Odescalchi, Corso.

TAILORS: *Schraider*, Piazza di Spagna 5; *Mattina*, Corso 107, first floor; *Mons*, Via Due Macelli 48; *G. Sègre*, Piazza di Trevi 88; *Foa & Guastalla*, Corso 105.

UMBRELLAS, SUN-SHADES, AND FANS: *Gilardini*, Corso 409; *Motta*, Corso 334; *Guattari*, Corso 411.

UPHOLSTERERS: *Levera*, Via Corso 395; *Peyron & Co.*, Corso Vittorio Emanuele 53; *Fil. Haas & Figli*, Via Condotti 46.

WATCHMAKERS: *Kobell*, Via del Gambero 19; *Kolbauer*, Via Due Macelli 108; *Gondret*, Corso 144; *Hausmann*, Via Bocca di Leone 84; *Kohlmann*, Via Condotti 69; *Conti*, Piazza di Spagna 53.

WEAPONS (permesso necessary, see p. xvii): *Spadini*, Piazza Borghese 89.

Italian Alpine Club, Roman Section, Via Collegio Romano 26. (Members of foreign Alpine Clubs are readily afforded information about mountain-ascents in the Apennines.)

Theatres. Since the demolition of the Teatro Apollo, the first place is taken by the TEATRO ARGENTINA or *Teatro Comunale* (Pl. II, 13, 16), Via di Tor Argentina, near S. Andrea della Valle. — Then follow the TEATRO COSTANZI (Pl. I, 25), Via Firenze, and TEATRO VALLE (Pl. II, 13, 15), near the Sapienza, for dramas. — Besides these there are the smaller theatres: TEATRO METASTASIO (Pl. I, 13, 15), Via di Pallacorda, near the Via della Scrofa, for vaudevilles with 'Pulcinella' (performances about 6 and 9; for gentlemen only); TEATRO MANZONI, Via Urbana 153; TEATRO QUIRINO (Pl. II, 16, 19), Via delle Vergini, for small operettas and ballet.

The companies usually change three times a year, one performing in autumn and winter till Christmas, another till Lent, and a third after Lent. Boxes are generally let permanently, and visits paid and received there. Ladies frequent the boxes only, gentlemen the pit (*platea*). Particulars about admission, etc., are published in the hand-bills. Comp. p. xxiv.

Marionette Theatre: TEATRO GOLDONI, Via de' Soldati. — *Cafés Chantants*, numerous.

Cabs, Omnibuses, and Tramways, see Appendix.

Carriage Hirsers. *Belli*, Via Margutta 27; *Piscitelli*, Vicolò degli Avignonesi 7. Charges vary according to the season, but the average may be placed at 30 fr. a day. The best carriages are obtained at the larger hotels, where, however, the charge is sometimes as high as 50 fr. a day. Gratuity to the coachman extra. — **Saddle Horses.** *Cairolì*, Via Margutta 38; *Jarret*, Piazza del Popolo 3; *Francesangeli*, Via Principe Umberto 133; *Pieretti*, Via Firenze 43. Charge 10 fr. for half-a-day; ostler's fee 1 fr.

Porters (*Fattorini Pubblici*). The best are those of the *Impresa Romana*, Vicolò Sciarra 60, with the name on their caps and a brass number on their coats. Porter with letter or luggage under 33 lbs., 25-75 c. according to the distance. There are also three other companies.

Post Office (comp. *Introd.*, p. xxv), Piazza di S. Silvestro in Capite, a large new edifice, open from 8 a.m. to 9.30 p.m. (Pl. I, 16; also entered from the Via della Vite). *Poste Restante* letters ('ferma in posta') are delivered at several windows for the different initials under the arcades in the court, on the right. Under the arcades, on the left, is a writing-room (letter 10 c.). *Branch Offices*: at the railway-station (open till 10.30 p.m.), Piazza Barberini 10 (open till 10 p.m.), Via del Babuino 106, Borgo Nuovo 136, Corso Vittorio Emanuele 61, Via Alessandrina 100 (open 8-5). — *Parcel Post* at the general post-office and at Monte Citorio 132 (9-6).

Telegraph Office, open day and night, in the General Post Office building, Piazza di S. Silvestro in Capite. *Branch Offices*: Piazza Araceli 3, Via Venti Settembre 118, Borgo Nuovo 36 (in summer 7-9, in winter 8-9); also at the Railway Station (open night and day).

English Churches. *All Saints*, Via Babuino, Piazza di Spagna, designed by Street (superseding the old Anglican Church near the Porto del Popolo); services at 8.30 a.m., 11 a.m., and 3 p.m., in summer 9 a.m. and 5 p.m.; chaplain, *Canon Watson Wasse, M. A.*, Via della Croce 81. — *Trinity Church*, Piazza S. Silvestro, opposite the Post Office (p. 153); services at 11 a.m. and 3 p.m.: chaplain (1889-90), *Rev. A. C. Thiselton*. — *American Episcopal Church of St. Paul*, a handsome brick edifice by Street, Via Nazionale; services at 8.30 a.m., 11 a.m., and 4 p.m.; rector, *Rev. Dr. Nevins*, Via Nazionale 16. — *Scottish Presbyterian Church*, Via Venti Settembre 7, near the Quattro Fontane; services at 11 a.m. and 3.30 p.m.; minister, *Rev. Dr. Gray*, Via Venti Settembre 7, 2nd floor. — *Wesleyan Methodist Church*, Via della Scrofa 63; services on Sun. 11 a.m. and 7.30 p.m., on Thurs. 7.30 p.m.; minister, *Rev. Henry Piggott*, Via delle Copelle 28. — *American Baptist Church*, Via Teatro Valle.

Italian Protestant Churches. *Waldensian Church*, Via Nazionale 107. — *Free Italian Church* (Signor Gavazzi), Via Panico 43, opposite the church of S. Angelo. — *Military Church*, Via delle Copelle 28; service every evening at Ave Maria (1 hr. after sunset); chaplain, *Rev. Cav. Capellini*, Pozzo delle Cornacchie 14. — *Episcopal Methodist Church*, Piazza Poli. — *Baptist Chapel*, Piazza San Lorenzo in Lucina. — *Baptist Church*, Via Urbana 154.

Anglo-American Club, Via Condotti 21. — **English Club**, Via della Croce 78.

Church Festivals. Since the annexation of Rome to the kingdom of Italy on 20th Sept., 1870, the great ecclesiastical festivals have lost most of their splendour. The public ceremonies at which the Pope formerly officiated in person, such as those of the Holy Week, the benedictions, and the public processions including that of the Fête de Dieu, have been discontinued. The Pope still officiates on high festivals in the Sistine Chapel, but visitors are not admitted without an introduction from very high quarters. (Gentlemen are required to wear uniform or evening dress. Ladies must be dressed in black, with black veils or caps.)

The following enumeration of the various festivals, as they were celebrated prior to 20th Sept. 1870, will still be found useful in many respects. Details are contained in the *Diario Romano*, published annually. The best work on the ceremonies of the Holy Week and their significance is the *Manuale delle cerimonie che hanno luogo nella settimana santa e*

nell'ottava di pasqua al Vaticano (1 fr.; also a French edition), obtainable at the bookshops mentioned at p. 115.

The Pope used to officiate in person three times annually, on Christmas Day, Easter Day, and the Festival of St. Peter and St. Paul (29th June); and four times annually he imparted his benediction, on Holy Thursday and Easter Day from the balcony of St. Peter's, on Ascension Day from the Lateran, and on 15th Aug., the anniversary of the 'Assumption of the Virgin', from S. Maria Maggiore. The most imposing ceremonies were those of the *Holy Week*, from Palm Sunday to Easter Day, the most important of which took place in the Sistine Chapel, accompanied by the music ('lamentations', etc.) of Palestrina and other old masters, on which occasions the papal band (*cappella papale*) performed.

The following are the principal festivals: —

- January 1. Cappella Papale in the Sistine, 10 a. m.
 — 5. Cappella Papale in the Sistine, 3 p. m.
 — 6. Epiphany. Cappella Papale in the Sistine, 10 a. m.; at 4 p. m. procession in Araceli.
 — 17. S. Antonio Abbate (Pl. II, 25, near S. Maria Maggiore), benediction of domestic animals.
 — 18. Anniversary of foundation of the chair of St. Peter, Cap. Papale in St. Peter's, 10 a. m.
 — 21. S. Agnese Fuori (p. 342).
 February 1. Illumination of the lower church of S. Clemente (p. 260).
 — 2. Candlemas. Cap. Papale in St. Peter's, 9 a. m.
 — 7. Cappella Papale in the Sistine, in memory of Pius IX.
 — 20. Cappella Papale in the Sistine, to celebrate the anniversary of Leo XIII.'s election.

On Ash Wednesday and every Sunday during Lent, Cappella Papale in the Sistine at 10 a. m. The Lent sermons in Gesù (Pl. II, 16), S. Maria sopra Minerva (Pl. II, 16), and other churches are celebrated.

- March. 3. Cappella Papale in the Sistine, to celebrate Leo XIII.'s installation.
 — 7. St. Thomas Aquinas, in S. Maria sopra Minerva (Pl. II, 16).
 — 9. S. Francesca Romana (in the Forum).
 — 16. Festival in the chapel of the Palazzo Massimi (Pl. II, 17) in commemoration of a resuscitation by S. Filippo Neri (p. 199).
 — 25. Annunciation. Cap. Papale in S. Maria sopra Minerva (Pl. II, 16).

HOLY WEEK.

Palm Sunday. Cappella Papale in St. Peter's. Consecration of palms; then mass. At 2 p. m. confession in the Lateran (Pl. II, 30).

Wednesday. Cappella Papale in the Sistine, 3 p. m. Tenebræ, Miserere.

Holy Thursday. Cappella Papale in the Sistine, 10 a. m. Towards noon the benediction 'Urbi' from the loggia of St. Peter's. Then washing of feet in St. Peter's, immediately after a dinner to twelve pilgrims in the loggia of St. Peter's. Cappella Papale in the Sistine, 3 p. m. Tenebræ and Miserere.

Good Friday. Cappella Papale in the Sistine, 9 a. m. (music by Palestrina). At 3 p. m. Tenebræ and Miserere. Procession of Cardinals in St. Peter's.

Saturday. Cappella Papale in the Sistine, 9 a. m. (Missa di Papa Marcello, by Palestrina). Baptism of converts in the Lateran.

Easter Day. High Mass in St. Peter's, formerly celebrated by the Pope. The elevation of the host (about 11 a. m.) was accompanied by the blast of trumpets from the dome. The Pope was then carried in procession from the church, and about noon imparted the great benediction 'Urbi et Orbi' from the loggia of St. Peter's. After sunset, illumination of the dome of St. Peter's.

Easter Monday. Cappella Papale in the Sistine, 9 a. m.

Easter Tuesday. Cappella Papale in the Sistine, 9 a. m.

Saturday in Albis. Cappella Papale in the Sistine, 9 a. m.

April 25. Procession of the clergy from S. Marco (Pl. II, 16) to St. Peter's at 7. 30 a. m.

- May 26. S. Filippo Neri. Cappella Papale in the Chiesa Nuova, 10 a. m.
Ascension. Cappella Papale in the Lateran. Benediction from the loggia.
Whitsunday. Cappella Papale in the Sistine, 10 a. m.
Trinity. Cappella Papale in the Sistine, 10 a. m.
Corpus Domini (Fête de Dieu). Procession of the Pope and clergy round the piazza of St. Peter's, 8 a. m.
- June 24. John the Baptist. Cappella Papale in the Lateran, 10 a. m.
 — 28. Eve of SS. Peter and Paul. Cappella Papale, St. Peter's, 6 p. m.
 — 29. SS. Peter and Paul. — Forenoon, Cappella Papale, St. Peter's, celebration formerly by the Pope.
- July 14. S. Bonaventura, in S. S. Apostoli.
 — 31. S. Ignazio, in Gesù.
- Aug. 1. St. Peter in Vinculis, in S. Pietro in Vincoli (Pl. II, 23).
 — 5. S. Maria della Neve, in S. Maria Maggiore (Pl. II, 25).
 — 15. Assumption of the Virgin. Cappella Papale in S. Maria Maggiore (Pl. II, 25), 9 a. m.; great benediction from the loggia.
- Sept. 8. Nativity of the Virgin. Cappella Papale in S. Maria del Popolo (Pl. I, 18), 10 a. m.
 — 14. Elevation of the Cross, in S. Marcello (Pl. II, 16).
- Oct. 7. S. Marco, in the church of that saint (Pl. II, 16).
 — 18. S. Luca, in the church of that saint (Pl. II, 20).
- Nov. 1. All Saints' Day, Cappella Papale in the Sistine, 10 a. m. and 3 p. m.
 — 2. All Souls' Day. Cappella Papale in the Sistine, 10 a. m.
 — 3. Requiem for former Popes. Cappella Papale in the Sistine, 10 a. m.
 — 4. S. Carlo Borromeo. Cappella Papale in S. Carlo, 10 a. m.
 — 5. Requiem for deceased cardinals in the Sistine.
- On the four Sundays of Advent, Cappella Papale in the Sistine, 10 a. m. (On the first Sunday of Advent Procession of the Mass to the Cappella Paolina.)
- Nov. 22. St. Cecilia. Cappella Papale in S. Cecilia in Trastevere (p. 331). Illumination of the Catacombs of Callistus (p. 361).
 — 23. Illumination of the lower church of S. Clemente (p. 260).
- Dec. 8. Conception. Cappella Papale in the Sistine, 3 p. m. Procession from Araceli (Pl. II, 20).
 — 24. Christmas Eve. Cappella Papale in the Sistine, 8 p. m. Towards midnight, solemnities in Araceli, about 5 a. m. in S. Maria Maggiore (Pl. II, 25).
- Dec. 25. Christmas Day. Cappella Papale in St. Peter's, 9 a. m., celebration formerly by the Pope; elevation of the host announced by trumpets in the dome.
 — 26. St. Stephen's Day. Cappella Papale in the Sistine, 10 a. m.
 — 27. St. John the Evangelist. Cappella Papale in the Sistine, 10 a. m.
 — 31. Cappella Papale in the Sistine; after which, about 4 p. m., grand Te Deum in Gesù (Pl. II, 16).

Popular Festivals (which have lost much of their former interest): —
EPIPHANY (6th Jan.), celebrated in the evening in the Piazza Navona, since 1873 (formerly near S. Eustachio); array of booths and prodigious din of toy-trumpets.

THE CARNIVAL, which has of late regained a little of its former splendour, lasts from the second Saturday before Ash Wednesday to Shrove Tuesday, and consists in a daily procession in the *Corso*, accompanied by the throwing of bouquets and comfits (except on Sundays and Fridays, when a 'gala corso' generally takes place), and concluding with a horse-race. The last evening is the Moccioni (taper) evening, the tapers being lighted immediately after sunset. A window in the *Corso* is the best point of view. The liveliest scene is between the Piazza Colonna and S. Carlo. Balconies there are in great request (as high as 600 fr.); single places are let on stands fitted up for the occasion.

The OCTOBER FESTIVAL, in the vintage-season, once famous, is celebrated with singing, dancing, and earousals at the osterie outside the gates.

The FESTA DELLO STATUTO, or Festival of the Constitution, introduced since the annexation of Rome, is on the first Sunday in June. Military parade in the forenoon in the Piazza dell' Indipendenza or the Campo Militare (p. 169). In the evening fireworks ('Girandola') in the Piazza del Popolo and elsewhere. — On the anniversary of the FOUNDATION OF ROME (21st April), it has of late been usual to illuminate the Colosseum and the Forum with Bengal fire.

The opening of Parliament is also inaugurated with festivities.

Street Scenes. The top of the Scala di Spagna (Pl. I, 20) and the Via Sistina are the favourite haunts of artists' models, chiefly Neapolitans, whose costumes are a well-known subject of photographs and pictures.

The favourite haunts of the country-people are in front of the Pantheon (Pl. II, 16; especially on Sundays), the Piazza Montanara (Pl. II, 17), and the market-place of the Campo di Fiori (p. 204).

The **Garrison** of Rome consists of 4 regiments of *Infantry* (wearing the 'giubba', or dark blue coat common to the whole army, grey trousers, white leather belts, and caps); 2 regiments of *Granatieri* (or Grenadiers; infantry uniform, with a burning grenade on the cap to distinguish them); 1 regiment of *Bersaglieri* or rifleman (dark blue uniform with crimson facings, large plumed caps worn on one side, forming an élite corps like the Austrian Kaiserjäger); 1 regiment of *Cavalry* (dark blue uniform, light grey trousers, and helmets; the Lanzieri wear fur caps and trousers faced with black); 1 brigade of *Field Artillery* and 1 brigade of *Fortress Artillery* (dark blue uniform with yellow facings); and 1 brigade of *Engineers* (dark blue uniform with crimson facings). To these we may add the *Carabinieri*, or gendarmes (p. xvi).

Collections, Villas, etc.

Changes in the arrangements take place so frequently that the following data cannot long remain accurate. Even the lists of sights contained in some of the daily newspapers are not always trustworthy (best in 'L'Italie' and in the Anglo-American 'Roman Herald'). Intending visitors should therefore make additional enquiry at the hotels, booksellers, etc. The Villas Borghese and Doria Pamphilj are best visited by carriage. — Galleries and palaces within angular brackets in the following list are temporarily closed.

The '*Permessi*' necessary for visitors to the Vatican and several other collections may either be obtained personally in the ways described below or through the consuls (p. 111) or bankers. — *Fees*, see p. 114.

Accademia di S. Luca (p. 238), pictures: daily, 9-3; closed in July and August.

Albani, Villa (p. 338), antiquities and pictures: Tuesdays, except in wet weather, from 12 noon; admittance by permesso, obtainable at the office in the Palazzo Torlonia, Piazza Venezia 135, to the left on the ground-floor, on presenting a visiting-card.

Barberini, Palazzo (p. 170), picture-gallery and antiquities: daily, 10. 30-5 (Thurs. 2-5); library, Thurs. 9-2 (closed from the middle of Sept. to the end of Oct.).

**Borghese, Palazzo* (p. 184), pictures: Mon., Wed., and Frid., 9-3; admittance by permesso, obtainable at the Palace 10-12 a. m.

**Borghese, Villa* (p. 334), garden: Tues., Thurs., Sat., and Sun., after 1 p.m., cabs also admitted; the casino, with the antiquities, Sat. 1-3, admittance by permesso obtainable at the Palazzo Borghese.

- * *Capitoline Museum* (p. 216): daily, 10-3, 50 c.; on Sun., New Year's Day, Epiphany, Festival of the Constitution (p. 122), Ascension Day, Corpus Christi Day, Festival of SS. Peter and Paul, Aug. 15th, Sept. 8th, and Dec. 8th, 10-1, free; closed on Easter Day, Sept. 20th, Nov. 1st, and Christmas.
- Castello S. Angelo* (p. 274): daily at 9, 11, 1, or 3 o'clock by permesso, available for six persons, obtainable at the Comando di Divisione Territoriale di Roma, Via de' Burrò (a street connecting the Piazza di Pietra and Piazza S. Ignazio; Pl. I, II, 16), No. 147, second floor.
- * *Catacombs of St. Callistus* (p. 361): daily, see p. 356.
- * *Colonna, Palazzo* (p. 163), picture-gallery: Tues., Thurs., & Sat., 11-3.
- * *Colosseum* (p. 234): open at all hours; the galleries closed after 11 p. m. (comp. p. 236).
- * *Conservatori, Palace of* (p. 215), new collection, bronzes and pictures: times of admission same as for the Capitoline Museum (see above).
- Corsini, Palazzo* (p. 324), picture-gallery: Mon., Thurs., and Sat., 9-3, except on holidays.
- * *Doria, Palazzo* (p. 158), picture-gallery: Tues. and Frid. 10-2; or Wed. or Sat., if one of the usual days is a holiday.
- Doria, Villa*, see below (*Villa Pamphilj*).
- * *Farnesina, Villa* (p. 323): on the 1st and the 15th of each month; closed in midsummer.
- * *Forum Romanum* (p. 222): daily, till dusk, gratis; closed in midsummer, 12-3.
- * *Kircheriano, Museo* (p. 156): daily, except public holidays, 9-3 (1 fr.), Sun. free.
- * *Lateran, Collections of the* (p. 268): daily, 9-3; in spring 10-4, in summer 9-1.
- [*Ludovisi, ancient sculptures from the former Villa* (p. 172): closed at present.]
- Maltese Villa and S. Maria Aventina* (p. 253): Wed. and Sat., 9 to dusk.
- Mattei, Villa* (p. 259): Thurs., after 2. 30 p.m.; visitors write their names in a book.
- Medici, Villa* (p. 149), collection of casts: Wed. and Sat., 8-12, and afternoons till dusk.
- Museo Artistico Industriale* (p. 151), daily, 9-3, except Wed.
- Museo delle Terme* (p. 168), same as the Capitoline Museum.
- * *Palatine Excavations* (p. 242): daily, 9 till dusk; adm. 1 fr.; on Sun. and holidays gratis; closed in summer 12-3.
- * *Pamphilj, Villa Doria* (p. 355): Mon. and Frid., 1 till dusk, sometimes only from 4; two-horse carriages and one-horse carriages without numbers also admitted.
- * *St. Peter's, Dome of* (p. 285), daily 8-11, by permesso.

Quirinale, Palazzo del (p. 173), the residence of the King, daily, but part of it only is shown.

**Rospigliosi, Casino* (p. 175), pictures: Wed. and Sat., 9-3.

**Thermae of Caracalla* (p. 255): daily, 9 till dusk (1 fr.); Sun. after 10, gratis; closed from 12 to 3 in midsummer.

Thermae of Titus (p. 237): admission as to the preceding.

[*Torlonia, Museo* (p. 325), formerly by written application to the Palazzo Torlonia (p. 162), but closed at present.]

**Vatican Collections and Library* (p. 287) accessible on the days mentioned below (but always closed on Sat., Sun., and holidays), 10-3, gratis, by permessi, to be obtained through a consul, or by direct application at the Segreteria of the Maggiordomo (9-1 o'clock) in the Cortile di S. Damaso (p. 286).

Intending visitors apply to the Swiss guard (no gratuity) at the Portone di Bronzo, opposite the chief entrance to the Vatican (p. 286), and are conducted to the office, where they write their names in the permesso. The hotel-keepers also procure permessi for their guests, for which they sometimes charge 1 fr. each. On leaving the Vatican the visitor who intends to return should at once procure another permesso in the way above mentioned, or ask the custodian to give him back the old one (1/2 fr.).

Besides the permessi for artists and scientific men mentioned below, there are ordinary permessi available for 5 persons. For *Raphael's Stanzas and Loggie*, the *Picture Gallery*, and the *Sistine Chapel*, 9-3 o'clock on the first five week-days, festivals excepted. — For the *Museum of Statuary*, the *Etruscan Museum*, and the *Egyptian Museum*, Mondays, Tuesdays, Wednesdays, and Fridays, 9-3.

The *Vatican Library* is open on the same days as the Museum of Statuary (Mon., Tues., Wed., Frid., 8-12), no permesso being required; comp. p. 319.

Those who desire to study, draw, or copy in Roman museums or private collections must procure a *Permesso* through their consul. For the *Papal Museums* permission is granted by *Monsignor Macchi* (maggiordomo of the pope) at his office (see above), the written application having been left there a day or two previously. (Separate permessi required for the museums of the Vatican and Lateran, the Vatican picture-gallery, and Raphael's Loggie.) In the case of *Private Galleries*, application must be made to the proprietor in Italian or French, stating also which picture it is intended to copy, and the size and description of the copy. In some collections copies of the original size must not be made. As to this and similar regulations, information should be previously obtained from the custodian. The following form of application to the Monsgr. Maggiordomo, may be also addressed to a prince or marchese, the 'Revma' being in this case omitted.

Eccellenza Revma,

Il sottoscritto, che si trattiene a Roma con lo scopo di proseguire in questa capitale i suoi studj artistici (storici, etc.), si prende la libertà di rivolgersi con questa a Vra Eccellenza Revma pregando La perchè voglia accordargli il grazioso permesso di far degli studj (dei disegni, delle notizie, etc.) nel Museo (nella Galleria) Vaticano.

Sperando di essere favorito da Vra Eccellenza Revma e pregando La di gradire anticipatamente i più sinceri suoi ringraziamenti, ha l'onore di protestarsi col più profondo rispetto

*di Vra Eccellenza Revma
Umno Obbmo Servitore
N. N.*

Roma li . . .

*A Sua Eccellenza Revma
Monsignor Macchi*

Maggiordomo di Sua Santità.

Diary.

(To be compared with the preceding Alphabetical List).

Daily: Capitoline Museum (p. 216) and Palace of the Conservatori (p. 215), 9-3, adm. 50 c.; Sun., 10-1, gratis. — Collections in the Lateran (p. 268), 10-3, in summer 9-1. — Museo Kircheriano (p. 156), 9-3, adm. 1 fr.; Sun. gratis. — Forum Romanum (p. 222). Excavations on the Palatine (p. 242); adm. 1 fr.; Sun. gratis. Thermæ of Caracalla (p. 255); adm. 1 fr.; Sun. gratis; all three after 10 a.m., closed in summer from 12 to 3. — Dome of St. Peter's (p. 285) 8-11. — Catacombs of St. Callistus (p. 361), etc.

Daily, except Sundays and Holidays: Academy of S. Luca (p. 238) 9-3; closed in July and August. — Galleria Barberini (p. 170) 12-5.

Sundays: Villa Borghese (p. 334), after 1 p.m.

Mondays: Vatican Collections (Raphael's Stanze and Loggie, Picture Gallery, Sistine Chapel, and Museum of Statuary) 9-3 (Library 8-12). — Galleria Borghese (p. 184) 9-3. — Galleria Corsini (p. 324) 9-3. — Villa Pamphili (p. 355).

Tuesdays: Vatican Collections (Raphael's Stanze and Loggie, Picture Gallery, Sistine Chapel, and Museum of Statuary) 9-3 (Library 8-12). — Galleria Doria (p. 158) 10-2. — Galleria Colonna (p. 163) 11-3. — Villa Borghese (p. 334), in the afternoon.

Wednesdays: Vatican Collections (Raphael's Stanze and Loggie, Picture Gallery, Sistine Chapel, and Museum of Statuary) 9-3 (Library 8-12). — Casino Rospigliosi (p. 175) 9-3. — Galleria Borghese (p. 184) 9-3. — S. Maria Aventina (p. 253), from 9 a.m.

Thursdays: Vatican Collections (Raphael's Stanze and Loggie, Picture Gallery, Sistine Chapel, Egyptian and Etruscan Museums) 9-3. — Galleria Corsini (p. 324) 9-3. — Barberini Library (p. 171) 9-2. — Galleria Colonna (p. 163) 11-3. — Villa Borghese (p. 334) in the afternoon. — Villa Mattei (p. 259) after 2.30 p.m.

Fridays: Vatican Collections (Raphael's Stanze and Loggie, Picture Gallery, Sistine Chapel, and Museum of Statuary) 9-3 (Library, 8-12). — Galleria Borghese (p. 184) 9-3. — Galleria Doria (p. 158) 10-2. — Villa Doria-Pamphili (p. 355).

Saturdays: Casino Rospigliosi (p. 175) 9-3. — Galleria Corsini (p. 324) 9-3. — Galleria Colonna (p. 163) 11-3. — Villa Borghese (p. 334) and the Casino, in the afternoon. — S. Maria Aventina (p. 253) 9 till dusk.

Duration of Visit.

To become thoroughly acquainted with the matchless attractions of Rome, the traveller should spend a whole winter in the 'Eternal City', and even to obtain a hasty glimpse at them he must make a stay of 10-14 days at least.

Summary of Chief Attractions.

CHURCHES: St. Peter's (p. 277), S. Giovanni in Laterano (p. 265), S. Maria Maggiore (p. 176), S. Lorenzo fuori le Mura (p. 343), S. Paolo fuori le Mura (p. 352), Sistine Chapel (p. 287), S. Agostino (p. 189), S. Clemente (p. 260), S. Croce in Gerusalemme (p. 181), S. Maria degli Angeli (p. 167), S. Maria in Araceli (p. 209), S. Maria sopra Minerva (p. 195), S. Maria della Pace (p. 191), S. Maria del Popolo (p. 147), S. Maria in Trastevere (p. 330), S. Onofrio (p. 322), S. Pietro in Vincoli (p. 182), S. Prassede (p. 178).

PALACES: Palazzo della Cancelleria (p. 199), Farnese (p. 205), Giraud (p. 276), di Venezia (p. 162).

RUINS: Forum (p. 222), Colosseum (p. 234), Imperial Palaces (p. 241), Cloaca Maxima (p. 248), Thermæ of Titus and Caracalla (pp. 237, 255), Pantheon (p. 193), Theatre of Marcellus (p. 203), Forum of Trajan (p. 240), Temple of Neptune (p. 155), Pyramid of Cestius (p. 252). — Catacombs of St. Callistus (p. 361).

COLLECTIONS OF STATUES in the Vatican (p. 308), Capitol (p. 216), Lateran (p. 268), Villa Albani (p. 333), Borghese (p. 334), Ludovisi (p. 172).

PICTURES: Raphael's Loggie and Stanze (p. 292), galleries of the Vatican (p. 301), Palazzi Borghese (p. 185), Barberini (p. 171), Colonna (p. 163), and Doria (p. 158).

PROMENADES: *Monte Pincio* (p. 148), where a military band plays daily 2 hours before sunset (in summer in the Piazza Colonna), attracting a fashionable crowd both of Romans and foreigners. — The *Villa Borghese*, the most popular of the Roman villas (p. 334); the *Villa Doria-Pamphilj* (p. 355); and the *Via Appia* (pp. 254, 348). — The new *Passeggiata Margherita* (p. 330) and *Parco Regina Margherita* (p. 336).

POINTS OF VIEW on the left bank: The Pincio (Pl. I, 18; p. 148), Basilica of Constantine (Pl. II, 20; p. 232), Palatine (Pl. II, 21; p. 241); on the right bank: *S. Pietro in Montorio (Pl. II, 12; p. 328), and the adjoining **Passeggiata Margherita* (p. 330; at least 1/2 hr. before sunset).

A Fortnight's Visit.

The traveller who desires to see most of the above sights within a fortnight must economise time by drawing up a careful programme for each day before starting, or by following the plan suggested below. It is advisable to devote the early part of the forenoon to visiting the churches, which, with the exception of the largest, are closed from 12 to 4. With regard to meals, it is hardly necessary to say that the heavy 'déjeuner à la fourchette' in the middle of the day should be eschewed, as it encroaches on the most valuable part of the day, and that the usual English hours for a substantial breakfast, slight luncheon, and late dinner should be observed. One of the first things to be done is to secure 'permessi' (comp. pp. 122, 124).

1ST DAY. The first part of this had better be devoted to what may be called an '*Orientation Drive*'.

Engage a cab for 2-3 hrs. (tariff, see Appendix) and drive down the Corso as far as the Piazza di Venezia, then to the Foro Trajano and through the Via Alessandrina and Via Bonella to the Forum Romanum, past the Colosseum, through the Via di S. Giovanni in Laterano to the Piazza in front of the church, then through the Via Merulana, passing S. Maria Maggiore, through the Via Ag. Depretis (Quattro Fontane) and the Via Nazionale to the Piazza Venezia, then through the Corso Vittorio Emanuele to the Via Tor Argentina, through the last street to the Ponte Garibaldi, crossing it to Trastevere, passing S. Maria in Trastevere, and through the Lungara to the Piazza di S. Pietro; then through the Borgo Nuovo, across the Piazza Pia, past the Castle of S. Angelo, over the Ponte S. Angelo, and through the Via Baucò di S. Spirito, the Corso

Vittorio Emanuele, and the Via Aracœli to the Piazza in Aracœli at the foot of the Capitol, where the cab may be dismissed. Ascend to the *Piazza del Campidoglio* (p. 210), visit the *Capitoline Museum* (p. 216) and the *Forum Romanum* (p. 222), and lastly spend the evening on the *Pincio* (p. 148).

2ND DAY (Mon. or Wed.). *Galleria Borghese* (p. 185; Mon., Wed., Frid., 9-3); *Pantheon* (p. 193); *S. Maria sopra Minerva* (p. 195); *Cancellaria* (p. 199); *Pal. Farnese* (p. 205); *Ponte Sisto* (p. 327); *S. Maria in Trastevere* (p. 330); *S. Pietro in Montorio* (p. 328); then, if time permit, a walk in the new *Passeggiata Margherita* (p. 330), which may also be included in the programmes given below for the 3rd and 8th days.

3RD DAY (Mon., Tues., Wed., or Frid.). *St. Peter's* (p. 277) and the *Dome* (p. 285; 8-10); *Sistine Chapel* (p. 287; 9-3); *Antiquities* (p. 304; 9-3); *S. Onofrio* (p. 322).

4TH DAY (Mon., Thurs., or Sat.). *Raphael's Stanze and Loggie, Vatican Picture Gallery* (p. 293; Mon. to Frid. 9-3); *Galleria Corsini* (p. 324; 9-3); *Palatine* (p. 241).

5TH DAY (any week-day). *Museo Kircheriano* (p. 156); *Forum of Trajan* (p. 240); *Fora of Augustus* (p. 239) and *Nerva* (Colonnacce, p. 239); *S. Pietro in Vincoli* (p. 182); *Thermae of Titus* (p. 237); *Colosseum* (p. 234); *Arch of Constantine* (p. 236); walk over the *Caelius* (p. 258), if time permit.

6TH DAY (Tues.). *S. Maria del Popolo* (p. 147); *Gesù* (p. 197); *Galleria Doria* (p. 158; 10-2); *Galleria Colonna* (p. 163; 11-3); *Quirinal* (p. 174); *S. Maria degli Angeli* (*Thermae of Diocletian*, p. 167); *S. Agnese fuori le Mura* (p. 342), if time left.

7TH DAY (any day). *S. Clemente* (p. 260); *Lateran, Museum* (9-3), *Church and Baptistery* (p. 267); *S. Maria Maggiore* (p. 176); *S. Prassede* (p. 178); *S. Lorenzo fuori* (p. 343).

8TH DAY (any day). From the *Forum Romanum* to the *Janus Quadrifrons* (p. 248); *Cloaca Maxima* (p. 248); *Ponte Rollo* (p. 250); so-called *Temple of Fortuna Virilis* (p. 249) and that of *Hercules Victor* (p. 249); *S. Maria in Cosmedin* (p. 249); by tramway to *S. Paolo fuori* (p. 352) and back to the *Porta S. Paolo*; *Pyramid of Cestius* (p. 252); *Monte Testaccio* (251); over the *Aventine* (*S. Sabina*, p. 252).

9TH DAY (any day). *S. Agostino* (p. 189); *S. Maria dell' Anima* (p. 191); *S. Maria della Pace* (p. 191); second visit to *Sistine Chapel* and to *Raphael's Stanze and Loggie* or to the *Picture Gallery* (9-3). Excursion to *Ponte Molle* (pp. 334-336).

10TH DAY (any day). *S. Maria in Aracœli* (p. 209); collections in the *Palace of the Conservatori* (p. 211; 10-3); *Thermae of Caracalla* (p. 255); *Via Appia*, within and without the city (pp. 254, 348), and the *Catacombs of Callistus* (p. 361). Back by the tombs on the *Via Latina* (p. 346).

11TH & 12TH DAYS. Another day or two should be devoted to revisiting the collections of antiquities in the *Vatican* and the *Capitol* and the *Borghese Gallery*; a visit may also be paid to the *Villa Farnesina*, open only on the 1st and the 15th of each month.

13TH & 14TH DAYS. Lastly, a day should certainly be devoted to the *Alban Mts.* (p. 363), and another to *Tivoli* (p. 377). These excursions should not be postponed till the end of the visitor's stay at Rome. They may be made on a Sunday, which is not a good day for sight-seeing.

Bibliography.

The literature on the history and topography of Rome, especially of ancient Rome, is so extensive, that it is impossible to do more than indicate a few of the most useful works on the subject. At the revival of learning after the dark ages numerous scholars, such as Poggio (1440), Flavio Biondo, and Lucio Fauno, devoted themselves with enthusiasm to exploration in this field. The most important of the mediæval works on Rome is Nardini's *Roma Antica* (1666), edited by Nibby in 1818.

Among modern works we may mention the following:—

1. ITALIAN. *Nuova Descrizione di Roma Antica e Moderna 1820*, by C. Fea. *Indicazione Topografica di Roma Antica* (3rd ed., 1841) and other works by Canina.
Roma nell' Anno 1838, by Nibby (3 vols.; 1843).
2. FRENCH. *Rome, Description et Souvenir*, by Francis Wey, a handsome illustrated work, with 358 wood-cuts (3rd ed., Paris, 1875).
Rome au Siècle d'Auguste, by Decobry (1844).
Promenades Archéologiques, by Boissier (Paris, 1881).
Rome et ses Monuments, by Deblescr (1882; useful information about church services and other ecclesiastical matters).
Les Antiquités de la Ville de Rome au XIV^e, XV^e, et XVI^e siècles, by E. Müntz (Paris; 1886).
3. GERMAN. *Geschichte und Beschreibung der Stadt Rom*, by Sachse (1824).
Beschreibung Roms, by Niebuhr. Platner. Runsen. Ulrichs. and others. A learned and extensive work forming the basis for all subsequent exploration (6 vols., 1830-42). An abridgment of this work, in 1 vol., was issued by Platner and Ulrichs in 1845.
Handbuch der Römischen Alterthümer, by W. A. Becker, a useful supplement to the foregoing (numerous references to classical authors).
Topographie der Stadt Rom im Alterthum, by H. Jordan, with an account of the present state of the excavations (3 vols.; 1871-85).
Topographie der Stadt Rom, by O. Richter, an excellent and learned survey, though somewhat crowded owing to its conciseness (1889).
Die Ruinen Roms, by Reber (3rd ed., Leipsic, 1879).
Darstellungen aus der Sittengeschichte Roms in der Zeit von August bis zum Ausgang der Antonine, by L. Friedländer, a valuable contribution to the social history of the imperial era (5th ed., 1881-82).
Geschichte der Stadt Rom im Mittelalter, by Ferdinand Gregorovius, a history of Rome in the middle ages, closing in 1535 (1858-72).
Geschichte der Stadt Rom, by A. von Reumont, a history of Rome from its foundation to 1846 (3 vols.; Berlin, 1867-70).
4. ENGLISH. *Walks in Rome*, by Augustus J. C. Hare (12th ed., 1887). an admirable cicerone for the ordinary visitor to Rome (may be borrowed at Piale's library).
Rome, Ancient and Modern, by the Rev. Dr. Donovan (4 vols.; 1842), based on the works of Professor Nibby.
Transformation or The Marble Faun, by Nathaniel Hawthorne, contains much incidental matter of interest for the visitor to Rome. — See also Georges Sand's 'Daniella', Hans Andersen's 'Improvisatore', and Miss Roberts' 'Mademoiselle Mori'.
Archæology of Rome, by J. H. Parker, profusely illustrated.
Architectural History of Rome, by J. H. Parker (1881).
Romæ Antiquæ Notitiæ, or the Antiquities of Rome, by Basil Kennet (1731).
Rome under Pius IX., by S. W. Fullom (1864).
Rome Illustrated, translated from the French of Francis Wey (see above; new ed., 1887).
Architectural Antiquities of Rome, by Taylor & Cressy (new ed., 1874).
Rome and the Campagna, by Burn (London, 1870), the best English work of the kind.
Historic and Monumental Rome, by C. J. Hemans (1874).
Gallus, by W. A. Becker (English translation by Metcalfe).
Manual of Roman Antiquities, by Prof. Ramsay.
Topography of Rome and its Vicinity, by Sir William Gell (1846).
The Roman Catacombs, by the Rev. J. Spencer Northcole (new ed., 1859).
The City of Rome, by Dyer (1883).
Ancient Rome in 1885, by Prof. J. H. Middleton (Edinburgh, 1885).
Ancient Rome in the Light of Recent Discoveries, by R. A. Lanciani (illus.; London, 1888).

The reader need scarcely be reminded of the histories of Gibbon, Niebuhr, Mommsen, Merivale, Arnold, Duruy, and Ihne.

History of the City of Rome.

Difficult as it undoubtedly is to trace the career of the Eternal City throughout upwards of two thousand years, and to mark and appreciate the manifold vicissitudes which it has undergone, the traveller will naturally desire to form some acquaintance with the history of the ancient centre of Western civilisation, the city of the Republic and Empire, on the ruins of which the seat of a vast ecclesiastical jurisdiction was afterwards founded, and now the capital of an important and steadily progressing modern state. Wherever we tread, our thoughts are involuntarily diverted from the enjoyment of the present to the contemplation of the past; and the most careless of pleasure-seekers will find it difficult to withstand the peculiar influence of the place. The following sketch is merely designed to put the traveller in the way of making farther researches for himself, and deals exclusively with those leading and general facts with which he ought to be acquainted before proceeding to explore the city in detail.

As the more remote history of Italy is involved in much obscurity, so also the origin of the city of Rome is to a great extent a matter of mere conjecture. It was not till a comparatively late period that the well-known legend of Romulus and Remus was framed, and the year B. C. 753 fixed as the date of the foundation. In all probability, however, Rome may lay claim to far greater antiquity. We are led to this conclusion, not only by a number of ancient traditions, but also by the recent discovery in Latium of relics of the flint-period, an epoch far removed from any written records. The *Palatine* was regarded by the ancients as the nucleus of the city, around which new quarters grouped themselves by slow degrees; and it was here that Romulus is said to have founded his city, the *Roma Quadrata*, of which Tacitus (Ann. 12, 24) states the supposed extent. Modern excavations have brought to light portions of the wall, gateways, and streets which belonged to the most ancient settlement (see pp. 241, 242). After the town of Romulus had sprung up on the Palatine, a second, inhabited by Sabines, was built on the *Quirinal*, and the two were subsequently united into one community. Whilst each retained its peculiar temples and sanctuaries, the *Forum*, situated between them, and commanded by the castle and the temple of Jupiter on the *Capitol*, formed the common focus and place of assembly of the entire state, and the Forum and Capitol maintained this importance down to the latest period of ancient Rome. The rapid growth of the city is mainly to be attributed to its situation, the most central in the peninsula, alike adapted for a great commercial town, and for the capital of a vast empire. The advantages of its position were thoroughly appreciated by the ancients themselves, and are thus enumerated by Livy (5, 54): ‘flumen opportunum, quo ex mediterraneis locis fruges devehantur, quo maritimi commeatus accipiantur, mare vicinum

ad commoditates nec expositum nimia propinquitate ad pericula classium externarum, regionum Italiae medium, ad incrementum urbis natum unice locum'. The Tiber was navigable for sea-going ships as far as Rome, whilst its tributaries, such as the Anio, Nera, Chiana, and Topino, contained sufficient water for the river vessels which maintained a busy traffic between Rome and the interior of the peninsula. The state of these rivers has, however, in the course of ages undergone a complete revolution, chiefly owing to the gradual levelling of the forests on the mountains, and at the present day the lower part only of the Tiber, below Orte, is navigable.

Whilst the origin of the capital of the world is traditionally referred to Romulus, its extension is attributed with something more of certainty to Servius Tullius. Around the twin settlements on the Palatine and Quirinal, extensive suburbs on the *Esquiline* and *Caelius*, as well as on the lower ground between the hills, had sprung up; for not only were numerous strangers induced to settle permanently at Rome on account of its commercial advantages, but the inhabitants of conquered Latin towns were frequently transplanted thither. Out of these heterogeneous elements a new civic community was organised towards the close of the period of the kings, and its constitution commemorated by the erection of the *Servian Wall*. This structure included an external wall round the whole of the town, and also the fortifications of the Capitol and other heights within it. The outer wall led from the N. slope of the Capitol across what was later the Forum of Trajan, skirted the Quirinal, and turned to the S.E. at the gardens of Sallust (p. 173). For more than $\frac{3}{4}$ M. at this part of the circuit, where the artificial defences are not aided by nature, the wall was replaced by a rampart about 80 ft. in breadth, with a moat 100 ft. wide in front of it. Considerable remains of this rampart are extant near the railway-station. The wall recommenced on the E. side of the Esquiline, skirted the S. slope of the Caelius, enclosed the two summits of the Aventine, and ended at the Tiber (below St. Sabina's, p. 252). While care was taken thus to protect the city externally, the kings were not less solicitous to embellish the interior with handsome buildings. To this period belong the *Temple of Jupiter Capitolinus* (p. 208), the *Circus* in the valley between the Palatine and the Aventine (p. 250), the *Carcer Mamertinus* (p. 237), and above all the *Cloaca Maxima* (p. 248), destined to drain the swampy site of the Forum, and still admired for its massive construction. This energetic and brilliant development of the city under the kings of the Tarquinian family in the 6th cent. B.C. came to a close with the expulsion of the last king Tarquinius Superbus (509).

During the first century of the REPUBLIC the united efforts of the citizens were directed to the task of establishing themselves more securely in the enjoyment of their new acquisitions; and in this they succeeded, although not without serious difficulty. It

was a hard and bitter period of probation that the nation had to undergo in the first period of its new liberty, and it was not till the decline of the Etruscan power that Rome began to breathe freely again. After protracted struggles she succeeded in conquering and destroying her formidable rival *Veii* (396), a victory by which the Roman supremacy was established over the south of Etruria as far as the Ciminian Forest. Shortly afterwards (390) the city, with the exception of the Capitol, was taken and entirely destroyed by the *Gauls*. Although this catastrophe occasioned only a transient loss of the prestige of Rome, it produced a marked effect on the external features of the city. The work of re-erection was undertaken with great precipitation; the new streets were narrow and crooked, the houses poor and unattractive, and down to the time of Augustus, Rome was far from being a handsome city. Her steadily increasing power, however, could not fail in some degree to influence her architecture. During the contests for the supremacy over Italy, the first aqueduct and the first high-road were constructed at Rome by *Appius Claudius* in 312 (*Aqua* and *Via Appia*, p. 348); in 272 a second aqueduct (*Anio Vetus*) was erected. Down to the period of the Punic wars Rome had not extended beyond the walls of *Servius Tullius*; but, after the overthrow of Carthage had constituted her mistress of the world, the city rapidly increased. The wall was almost everywhere demolished to make room for new buildings, so that even in the time of Augustus it was no longer an easy matter to determine its former position, and new quarters now sprang up on all sides. During the last century B.C., after the Græco-Asiatic wars of the previous century had brought the Romans into contact with the civilisation of the East, the city began to assume an aspect more worthy of its proud dignity as capital of the civilised world. The streets, hitherto unpaved, were now converted into the massive lava-causeways which are still visible on many of the ancient roads (*e. g.* *Via Appia*). The highest ambition of the opulent nobles was to perpetuate their names by the erection of imposing public buildings. Thus in 184 *M. Porcius Cato* erected the first court of judicature (*Basilica Porcia*) in the Forum, and others followed his example. Speculation in houses was extensively carried on, and it was by this means that the *Triumvir Crassus*, among others, amassed his fortune; for rents were high, and the houses of a slight and inexpensive construction. These *insulae*, or blocks of houses erected for hire, contrasted strikingly with the *domus*, or palaces of the wealthy, which were fitted up with the utmost magnificence and luxury. Thus the tribune *Clodius*, the well-known opponent of *Cicero*, paid 14,800,600 sesterces (*i. e.* about 130,525*l.*) for his house. The ordinary building material consisted of sun-dried bricks (*lateres*), while the volcanic stone (*tufa* and *peperino*) of the neighbourhood was used for the more ambitious edifices. Among the comparatively few extant buildings

of the Republican period are the *Tabularium* of B. C. 78 (p. 221), the *Ionic Temple* at the Ponte Rotto (p. 249), and the tombs of the *Scipios* (p. 257), *Bibulus* (p. 163), and *Caccilia Metella* (p. 349).

The transformation of the republic into a MILITARY DESPOTISM involved the introduction of a new architectural period also. Usurpers are generally wont to direct their energies to the construction of new buildings, with a view to obscure the lustre of the older edifices, and to obliterate the associations connected with them. *Caesar* himself had formed the most extensive plans of this nature, but their execution was reserved for his more fortunate nephew. Of all the ruins of ancient Rome those of the buildings of *AUGUSTUS* occupy by far the highest rank, both in number and importance. The points especially worthy of note are the *Campus Martius* with the *Pantheon* (p. 193) and the *Thermae of Agrippa* (p. 195), the *Theatre of Marcellus* (p. 203), the *Portico of Octavia* (p. 203) and the *Mausoleum of Augustus* (p. 184), the *Basilica Julia* (p. 226), and the *Forum of Augustus* with the *Temple of Mars* (p. 239). No fewer than 82 temples were restored by Augustus ('templorum omnium conditorem ac restitutorem' as he is termed by *Livy*), who might well boast of having found Rome of brick and left it of marble. The wonderful fire-baked bricks, the time-resisting qualities of which excite our admiration in the Roman buildings of the next 500 years, now came into use, supplemented by the beautiful travertine from the vicinity of *Tivoli*, while the walls were lined with marble from *Carrara*, *Paros* and other Greek islands, *Numidia* ('giallo antico'), *Laconia* ('rosso antico'), and *Eubœa* ('cipollino'). The administration and police-system of the city were also re-organised by Augustus, who divided Rome into 14 quarters (*regiones*), adapted to its increased extent (p. 134). A corps of watchmen (*vigiles*), who also served as firemen, was appointed to guard the city by night. These and other wise institutions, as well as the magnificence attained by the city under Augustus, are depicted in glowing terms by his contemporaries. His successors followed his example in the erection of public edifices, each striving to surpass his predecessors. In this respect *Nero* (54-68) displayed the most unbridled ambition. The conflagration of the year 64, which reduced the greater part of Rome to ashes, having been ignited, it is said, at the emperor's instigation, afforded him an opportunity of rebuilding the whole city in a modern style and according to a regular plan. For his own use he erected the '*Golden House*', a sumptuous palace with gardens, lakes, and pleasure-grounds of every description, covering an enormous area, extending from the *Palatine* across the valley of the *Colosseum*, and far up the *Esquiline* (p. 234). These and other works were destroyed by his successors, and well merited their fate; the fragments which still bear the name of *Nero* at Rome are insignificant.

The FLAVIAN DYNASTY, which followed the Julian, has on the

other hand perpetuated its memory by a number of most imposing works, above all the *Colosseum* (p. 234), which has ever been regarded as the symbol of the power and greatness of Rome, the *Thermae of Titus* on the Esquiline (p. 237), the *Flavian Palace* on the Palatine (p. 244), and the *Triumphal Arch* (p. 233) erected after the destruction of Jerusalem. Under *Trajan*, architecture received a new impetus, and indeed attained the highest development of which the art was capable at Rome. To this the *Forum of Trajan* (p. 240), with the column, and the reliefs afterwards employed to decorate Constantine's arch, bear eloquent testimony. Under *Trajan* the culminating point both of art and of political greatness was attained. Thenceforward the greatness of the empire began gradually, but steadily, to decline. Although under the next emperor *Hadrian* this tendency was apparently arrested, yet the monuments of his reign, such as the *Temple of Venus and Roma* (p. 233), and his *Mausoleum* (p. 275), exhibit traces of degeneracy.

The same remark applies also to the time of the ANTONINES. These monarchs were remarkable for their excellent qualities as sovereigns, and their peaceful sway has frequently been regarded as the period during which mankind in general enjoyed the greatest prosperity. There is even a tradition that 'the good old times' will return when the equestrian statue of the worthy *Marcus Aurelius*, the gilding of which has almost entirely disappeared, shall resume its costly covering. This, however, was but the lull preceding a storm. The great plague under the latter emperor was the first of a series of fearful calamities which devastated the empire. Throughout an entire century civil wars, incursions of barbarians, famine, and pestilence succeeded each other without intermission. Although Rome was less affected by these horrors than the provinces, it is computed that the population of the city, which at the beginning of the 2nd cent. was about 1½ million, had dwindled to one-half by the time of *Diocletian*. A constant decline in architectural taste is traceable; but, as building always formed an important feature in the policy of the emperors, the number and extent of the ruins of this period are considerable. To this epoch belong the *Column of Marcus Aurelius* (p. 154), the *Arch of Sept. Severus* (p. 228), the magnificent *Baths of Caracalla* (p. 255), and the huge *Thermae of Diocletian* (p. 167).

After the Punic War the walls of the city had been suffered to fall to decay, and during nearly five centuries Rome was destitute of fortification. Under the emperor *Aurelian*, however, danger became so imminent that it was deemed necessary again to protect the city by a wall against the attacks of the barbarians. This structure is to a great extent identical with that which is still standing. The latest important ruins of antiquity bear the name of CONSTANTINE THE GREAT, viz. the *Basilica* (p. 232), *Baths* (pp. 165, 174), and *Triumphal Arch* (p. 236). The two former were, however, erected by his rival *Maxentius*. Constantine manifested

little partiality for Rome and ancient traditions, and the transference of the seat of empire to *Byzantium* (in 330) marks a decided turning-point in the history of the city, as well as in that of the whole empire. Rome indeed was still great on account of its glorious past and its magnificent monuments, but in many respects it had sunk to the level of a mere provincial town. No new works were thenceforth undertaken, and the old gradually fell to decay.

The city was still divided, in accordance with the *AUGUSTAN SYSTEM*, into fourteen regions, in enumerating which we shall name the principal ruins belonging to each: — 1. *Porta Capena*, *Via Appia*, within the city (p. 254); 2. *Caelimontium*, *Cælius* (p. 258); 3. *Isis et Serapis*, *Colosseum* (p. 234), *Baths of Titus* (p. 237); 4. *Templum Pacis*, *Venus et Roma* (p. 233), *Basilica of Constantine* (p. 232), *Temple of Faustina* (p. 231); 5. *Exquilie*, *Temple of Minerva Medica* (p. 180); 6. *Alta Semita*, *Baths of Constantine* (p. 174) and *Diocletian* (p. 167); 7. *Via Lata*, between the modern *Corso*, the *Quirinal*, and *Pincio* (p. 148); 8. *Forum Romanum*, the republican and imperial *Fora* (pp. 222, 237) and the *Capitol* (p. 208); 9. *Circus Flaminius*, *Theatres of Marcellus* (p. 203) and *Pompey* (p. 205), *portico of Octavia* (p. 203), *Pantheon* (p. 193), *column of Marcus Aurelius* (p. 154), and the *Temple of Neptune* (p. 155); 10. *Palatium*, *Palatine* (p. 244); 11. *Circus Maximus*, temple in the *Forum Boarium* (p. 250); 12. *Piscina Publica*, *Baths of Caracalla* (p. 255); 13. *Aventinus*, *Pyramid of Cestius* (p. 252); 14. *Transiberim*, *Trastevere* and the *Borgo*. According to the statistics of this period, Rome possessed 37 gates, from which 28 high-roads diverged, and 19 aqueducts; and although four only of these last are now in use, there is probably no city in the world which can boast of such an excellent supply of water as Rome. The banks of the *Tiber* were connected by 8 bridges. There were 423 streets, 1790 palaces, and 46,602 dwelling-houses. Among the public structures are mentioned 11 *Thermæ*, 856 baths, 1352 fountains in the streets, 36 triumphal arches, 10 basilicas, etc. When the grandeur and magnificence suggested by these numbers is considered, it may occasion surprise that comparatively so few relics now remain; but it must be borne in mind that the work of destruction progressed steadily during nearly a thousand years, and was not arrested till the era of the Renaissance, but for which even the monuments still extant would ere now have been consigned to oblivion.

The *Catacombs*, the earliest burial-places of the *CHRISTIANS*, illustrate the gradual progress of this interesting community, in spite of every persecution, from the 1st century downwards. At the beginning of the year 313 *Constantine* issued his celebrated decree from *Milan*, according to Christianity equal rights with all other religions. This was the decisive step which led to the union of the church with the state. In 325 the first œcumenical council was held at *Nicæa*, and in 337 the emperor caused himself to be baptised when on his death-bed. Tradition attributes the earliest ecclesiastical division of Rome into seven diaconates to *St. Clement*, the fourth bishop, and *St. Peter* is said to have founded the first place of worship in the house of the senator *Pudens*, now the church of *S. Pudenziana* (p. 175). To *Callistus I.* (217-22) is ascribed the foundation of the church of *S. Maria in Trastevere* (p. 330), and to *Urban*, his successor, that of *S. Cecilia* (p. 331). About the beginning of the fourth century *S. Alessio* and *S. Prisca* on the *Aventine* are supposed to have been founded. Of these churches, however, and also of the edifices erected by *CONSTANTINE*,

no trustworthy record has been handed down to us. To that monarch tradition attributes the foundation of the following churches — the *Lateran*, *St. Peter's*, *S. Paolo Fuori*, *S. Croce in Gerusalemme*, *S. Agnese Fuori*, *S. Lorenzo Fuori*, and *SS. Pietro e Marcellino* at Torre Pignattara (p. 345), — but probably erroneously, with the exception of the first, which was styled 'omnium urbis et orbis ecclesiarum mater et caput'. It is, however, noteworthy that the oldest and most important churches were generally outside the gates, or at least in their immediate vicinity; and this is accounted for by the fact that the Roman aristocracy at first clung tenaciously to the old traditions, and for a long period the city preserved its heathen character. The state at length overcame this antagonism. In 382 the altar of Victoria was removed from the senate-hall, and in 408 the ancient religion was at length deprived by a law of Honorius of all its temporal possessions, and thus indirectly of its spiritual authority also. The destruction of the ancient temples, or their transformation into Christian places of worship now began, and the churches rapidly increased in number. At this early period Rome possessed 28 parish churches (*tituli*), besides numerous chapels, and among them arose the five PATRIARCHAL CHURCHES, presided over by the pope, and forming a community to which the whole body of believers throughout the world was considered to belong. These five were *S. Giovanni in Laterano*, *S. Pietro*, *S. Paolo*, *S. Lorenzo*, and the church of *S. Maria Maggiore* founded by Liberius. Besides these, *S. Croce in Gerusalemme* and *S. Sebastiano*, erected over the catacombs of the Via Appia, enjoyed special veneration. These formed the 'Seven Churches of Rome' to which pilgrims flocked from every part of western Christendom. The number of monasteries now steadily increased, and at the same time the inroads of poverty made rapid strides.

In the 4TH CENTURY the cultivation of the Roman Campagna began to be seriously neglected, and in an official document of the year 395 it is stated that upwards of 500 square miles of arable land had been abandoned and converted into morass. The malaria at the same time extended its baneful sway from the coast into the interior of the country. The storms of the barbarian irruptions greatly aggravated the misery. Although the Vandals and Goths are often erroneously held responsible for the destruction of all the great monuments of antiquity, which, on the contrary, *Theodoric the Great* did his utmost to protect, Rome doubtless suffered terribly from having been the scene of their battles and pillagings. In 410 the city was plundered by Alaric, and in 445 by the Vandals, and in 537 it sustained its first siege from the Goths under *Vitiges*. They laid waste the Campagna and cut off all the supplies of water brought to the city by the aqueducts, but the skill of *Belisarius*, and the strength of the walls, particularly those of the Castle of S. Angelo, effectually repelled their attacks on the city. In March

538 they were at length compelled to abandon their designs, after having beleaguered the city for upwards of a year. In December 546, *Totila*, the king of the Goths, entered Rome, and is said to have found not more than 500 persons within the walls of the devastated city. Belisarius then repaired the walls, which had been partially destroyed, and in 547 he sustained a second siege. In 549 the city again fell into the hands of *Totila*, but in 552 it was recaptured by *Narses* and once more united with the Byzantine empire. About this period the city was reduced by war, pestilence, and poverty to a depth of misery which was never again paralleled, except during the absence of the papal court at *Avignon*. No thorough restoration was possible, for the Byzantine emperors cared nothing for Rome, and in the Lombards arose new enemies to their dynasty in Italy. In 663 *Constans II.* visited Rome, an interval of 306 years having elapsed since it had been entered by a Byzantine emperor, and availed himself of the opportunity to carry off the last remains of the bronze with which the ancient monuments were decorated. In 755 the Lombards under their duke *Aistulf* besieged Rome for two months and ruthlessly devastated the Campagna, which during the preceding interval of peace had begun to wear a more smiling aspect. A lamentation of that period begins thus: —

‘Nobilibus quondam fueras constructa patronis,
Subdita nunc servis, heu male Roma ruinis;
Deseruere tui tanto te tempore reges,
Cessit et ad Græcos nomen honosque tuus’.

and terminates with the words: —

‘Nam nisi te Petri meritum Paulique foveret,
Tempore jam longo Roma misella foret’.

It was in fact the tradition, indelibly attaching to Rome, of the great struggles and victories of Christianity which preserved the city from total destruction. The transformation of heathen into Christian Rome was accompanied by the gradual development of the PAPACY as the supreme ecclesiastical power in the West. *Leo the Great* (440-461) and *Gregory the Great* (590-604) may be regarded as the chief originators of this scheme of aggrandisement. These prelates and their successors were indefatigable in their efforts to realise their project, and under their auspices, notwithstanding the poverty and misery into which Rome had sunk, new churches and monasteries were constantly springing up among the ruins of the monuments of antiquity, and the last feeble spark of artistic taste which still survived was devoted to the decoration of these buildings. The objects at which they chiefly aimed were independence of Byzantium, the subjection of the Eastern church to the court of Rome, and the conversion of the heathen Germans, the accomplishment of which would materially pave the way for their ulterior ambitious schemes. In 727 the Lombard king *Luitprand* presented Sutri, which had been captured by him, to the pope, this being the first instance of a town being presented to the church, and this gift

constituted a basis for the subsequent formation of the States of the Church. In 755, on the invitation of the pope, the Frankish king *Pepin* proceeded to Italy and practically put an end to the Byzantine supremacy. It is not known whether that monarch absolutely made over the Exarchate of Ravenna and the other towns to the representative of St. Peter, or whether he granted them to him as a fief; but it is certain that the temporal power of the popes and their supremacy over Rome dates from the grants made by *Pepin* to the church. On Christmas Day, in the year 800, *Charlemagne* was crowned by *Leo III.*, and from that period dates the career of the 'Holy Roman Empire' and the MEDIEVAL HISTORY of Rome and the Roman Catholic Church.

A characteristic of this period is to be found in the numerous, many-storied towers of red brick which contrast so strongly with the monuments of ancient Rome. This style of architecture was developed in the Carlovingian epoch, although most of these towers now extant were not erected before the 12th or 13th century. In still greater numbers sprang up towers of a defensive character, a few only of which, such as the so-called *Torre di Nerone* (p. 169), are still preserved. The forest of towers, belonging to numerous different owners, which reared themselves over the ruins of the mistress of the world, affords at the same time a clue to the character of the whole epoch; for, in spite of the nominal sway exercised over the greater part of Europe by the pope and the emperor, continual feuds raged both at Rome and elsewhere between the temporal and spiritual powers, and between the nobility and the populace. The great monuments of antiquity were now doomed to utter destruction, and their fate is thus described by the historian *Gregovorius* (iii, 565): —

'Charlemagne had already set the example of carrying off ancient columns and sculptures to adorn his cathedral at Aix-la-Chapelle, and the popes, who regarded the greatest monuments of Rome as the property of the state, possessed neither taste, nor time, nor ability to take measures for their preservation. The plundering of ancient buildings became the order of the day. The priests were indefatigable in transferring antique columns and marbles to their churches; the nobles, and even the abbots, took possession of magnificent ancient edifices which they disfigured by the addition of modern towers; and the citizens established their workshops, rope-walks, and smithies in the towers and circuses of imperial Rome. The fisherman selling his fish near the bridges over the Tiber, the butcher displaying his meat at the theatre of *Marcellus*, and the baker exposing his bread for sale, deposited their wares on the magnificent slabs of marble which had once been used as seats by the senators in the theatre or circus and perhaps by *Cæsar*, *Mark Antony*, *Augustus*, and other masters of the world. The elaborately sculptured sarcophagi of Roman heroes were scattered in every direction and converted into cisterns, washing-vats, and troughs for swine; and the table of the tailor and the shoemaker was perhaps formed of the cippus of some illustrious Roman, or of a slab of alabaster once used by some noble Roman matron for the display of her jewellery. For several centuries Rome may be said to have resembled a vast lime-kiln, into which the costliest marbles were recklessly cast for the purpose of burning lime; and thus did the Romans incessantly pillage, burn, dismantle, and utterly destroy their glorious old city'.

Leo IV. encircled the 'LEONINE CITY' with a wall, and erected other useful structures, which indicate a renewed period of prosperity; but the ravages of the Saracens in the city and its environs soon prevented farther progress. When at length these barbarians were finally subdued by *John X.*, the city was repeatedly besieged and captured by German armies during the contest for the imperial supremacy; and subsequently, in consequence of incessant civic feuds, the whole city was converted into a number of distinct fortified quarters, with castellated houses, in the construction of which numerous monuments of antiquity were ruthlessly destroyed for the sake of the building materials they afforded. Every temporary re-establishment of peace was invariably followed by new scenes of devastation, as when the senator *Brancaleone* dismantled no fewer than 150 of the strongholds of the warlike nobles.

The constantly increasing civic and national dissensions at length compelled *Clement V.* in 1309 to transfer the seat of the pontifical government to Avignon, where it remained till 1377, whilst Rome was successively governed by Guelphs and Ghibellines, Neapolitans and Germans, Orsini's and Colonna's, and for a brief period (1347) *Cola di Rienzi* even succeeded in restoring the ancient republican form of government. This was an epoch of the utmost misery, when poverty, war, and disease had reduced the population to less than 20,000 souls.

A happier era was inaugurated by the return of *Gregory XI.* to the city (1377). After the termination of the papal schism (1378-1417), the new development of the city progressed rapidly, aided by the vast sums of money which flowed into the papal coffers, and by the revival of taste for art and science promoted by *Nicholas V.*, *Julius II.*, *Leo X.*, etc. In 1527 the city was devastated by the troops of Charles of Bourbon; but it gradually recovered from the blow, its population again increased, and many churches and palaces were restored by the popes, their cardinals, and favourites, especially during the pontificate of *Sixtus V.* (1585-90), to whom modern Rome is chiefly indebted for its characteristic features. Comp. p. lvii.

In 1798 a republic was established for a short period at Rome, and from 1809 to 1814 the city was under the supremacy of France. A republican form of government was again declared in 1849, in consequence of the events of 1848, but *Pius IX.* was restored by the French in 1850. The city was then garrisoned by 15,000 French troops, who were withdrawn in 1866, in accordance with the convention of 1864; but they were recalled after the Garibaldian hostilities of 1867, and were quartered in the environs until the breaking out of the Franco-Prussian war of 1870. On 20th Sept. of that year the Italian troops marched into the city, after a bombardment of five hours. The States of the Church are now incorporated with the kingdom of Italy, of which Rome is once more the capital. The population of the city in 1870 was about 215,000.

CHRONOLOGICAL TABLE.

| B.C. | Rom. Emp | Popes ^a . | A.D. | Rom. Emp. | Popes. |
|------|----------------------------|-------------------------|------|--|----------------------------|
| 44 | Julius Cæsar murdered. | | 238 | Gordian III. | |
| 28 | Cæsar Octavianus Augustus. | | 244 | Philip the Arabian. | |
| A.D. | | | 249 | Decius. | |
| 14 | Tiberius. | | 251 | Gallus and Volusianus. | Cornelius, 251-252. |
| 37 | Caligula. | | 252 | | Lucius I., 252-253. |
| 41 | Claudius. | | 253 | Æmilianus. | Stephen I., 253-257. |
| 54 | Nero. | | | Valerianus. | Sixtus II., 257-258. |
| 67 | | Martyrdom of St. Peter. | 257 | | Dionysius, 259-269. |
| 68 | Galba. | Linus, 67-79. | 260 | Gallienus. | Felix I., 269-274. |
| 69 | Otho. | | | | |
| | Vitellius. | | 268 | Claudius II. | |
| 69 | Vespasian. | | 270 | Aurelian. | |
| 79 | Titus. | Anacletus, 79-91. | 275 | Tacitus. | |
| 81 | Domitian. | Clement, 91-100. | 276 | Florianus. | Eutychianus. |
| 96 | Nerva. | | | Probus. | |
| 98 | Trajan. | | 282 | Carus. | |
| 100 | | Euaristus. | 283 | Carinus and Numerianus. | |
| 109 | | Alexander I. | | | |
| 117 | Hadrian. | | 283 | | |
| 119 | | Sixtus I. | 284 | Diocletian. | Cajus. |
| 128 | | Telesphorus. | 296 | | |
| 138 | Antoninus Pius | | 306 | Constantius | Marcellinus. |
| 139 | | Hyginus. | | Chlorus and | |
| 142 | | Pius I. | | Maximianus | |
| 157 | | Anicetus. | | Galerius. | |
| 161 | Marcus Aurelius. | | 306 | Constantine the Great (sole Emp. 324-337). | |
| 168 | | Soter. | | | |
| 177 | | Eleutherus. | | | |
| 180 | Commodus. | | 307 | Maximin II. | |
| 190 | | Victor I., 190-202. | | Severus. | |
| 193 | Pertinax. | | | Licinus. | |
| | Didius Julianus. | | | Maxentius. | |
| 193 | Septimius Severus. | | 308 | | Marcellus |
| | | | 309 | | Eusebius. |
| 202 | | Zephyrinus, 202-218. | 311 | | Melchiades. |
| | | | 314 | | Sylvester I. |
| 212 | Caracalla (Geta d. 212.) | | 336 | | Marcus. |
| | | | 337 | Constantine II. | Julius I. |
| 217 | Maerinus. | | | Constantius. | |
| 218 | Heliogabalus. | Callistus I., 218-222. | 352 | Constans. | Liberius. |
| 223 | Alexander Severus. | Urbanus I., 223-230. | 355 | | Felix II. |
| 223 | | Pontianus, 230-235. | 360 | Julian. | |
| 230 | | | 363 | Jovian. | |
| 235 | Maximinus. | | 364 | Valentinian I. and Valens. | } Partition of the Empire. |
| 236 | | Anterus, 235-236. | | | |
| 238 | Gordian I. & II. | Fabianus, 236-250. | | | |
| | Pupienus and Balbinus. | | | | |

(^a) The dates of the popes down to Constantine are uncertain, having been handed down by vague tradition only.

| A.D. | Rom. Emp. | Popes. | A.D. | Rom. Emp. | Popes. |
|------|--------------------------------|---------------------------|------|------------------------------------|------------------|
| 366 | | Damasus I. | 615 | | Deusdeditus. |
| 367 | Gratian. | | 619 | | Boniface V. |
| 375 | Valentinian II. | | 625 | | Honorius I. |
| 379 | Theodosius (sole Emp. 392-395) | | 640 | | Severinus. |
| 383 | Arcadius. | | 642 | | John IV. |
| 384 | | Siricius. | 649 | | Theodorus I. |
| 395 | Honorius a. | | 655 | | St. Martin I. |
| 398 | | Anastasius I. | 657 | | St. Eugene I. |
| 402 | | Innocent I. | 672 | | St. Vitalianus. |
| 417 | | Zosimus. | 676 | | Adeodatus. |
| 418 | | Boniface I. | 678 | | Donus I. |
| 422 | | Celestinus I. | 682 | | St. Agathus. |
| 425 | Valentinian III | | 684 | | St. Leo II. |
| 432 | | Sixtus III. | 685 | | St. Benedict II. |
| 440 | | Leo I., the Great. | 686 | | John V. |
| 455 | Petronius | | 687 | | Conon. |
| | Maximus | | 701 | | St. Sergius I. |
| 455- | Avitus. | | 705 | | John VI. |
| 475 | Majorianus. | | 708 | | John VII. |
| | Lib. Severus. | | | | Sisinianus. |
| | Anthemius. | | 715 | | Constantine I. |
| | Olybrius. | Hilarius 461-468. | 731 | | St. Gregory II. |
| | Glycerius. | Simplicius | 741 | | St. Gregory III. |
| | Julius Nepos. | 468-483. | 752 | | St. Zacharias. |
| 475 | Romulus Augustulus. | | | | Stephen II. |
| 476 | End of the W. Roman Empire | | 757 | | Stephen III. |
| 483 | | Felix III. | 767 | | St. Paul I. |
| 492 | | Gelasius I. | 768 | | Constantine II. |
| 496 | | Anastasius II. | | | Philip. |
| 498 | | Symmachus. | 772 | | Stephen IV. |
| 514 | | Hormisdas. | 795 | | Hadrian I. |
| 523 | | John I. | | <i>Rom. Emp. of Germ. origin c</i> | St. Leo III. |
| 526 | | Felix IV. | 800 | Charlemagne. | |
| 530 | | Boniface II. b | 814 | Louis the Pious | |
| 532 | | John II. | 816 | | Stephen V. |
| 535 | | St. Agapetus I. | 817 | | St. Paschalis I. |
| 536 | | St. Silverius. | 824 | | Eugene II. |
| 538 | | Vigilius. | 827 | | Valentinus. |
| 555 | | Pelagius I. | | | Gregory IV. |
| 560 | | John III. | 843 | Lothaire. | |
| 574 | | Benedict I. | 844 | | Sergius II. |
| 578 | | Pelagius II. | 847 | | St. Leo IV. |
| 590 | | St. Gregory I. the Great. | 855 | Louis II. | Benedict III. |
| | | Sabinianus. | 858 | | St. Nicholas I. |
| 604 | | Boniface III. | 867 | | Hadrian II. |
| 607 | | S. Boniface IV. | 872 | | John VIII. |
| 608 | | | 875 | Charles the Bald. | |

(a) From 395, the year of the death of Theodosius, the division of the Empire became permanent; in the above table the Emperors of the W. Roman Empire only are enumerated.


(b) Thus far all the popes have been canonised.

(c) The names of a few English sovereigns, especially those who appear most prominently in papal history, have been added to this column to facilitate realisation of contemporary history.

| A.D. | Rom. Emp. | Popes. | A.D. | Rom. Emp. | Popes. |
|------|--|-----------------|------|------------------------------------|------------------|
| 881 | Charles the Fat. | | | | (Hildebrand.) |
| 883 | | Marinus I. | 1087 | | Victor III. |
| 884 | | Hadrian III. | 1088 | | Urban II. |
| 885 | | Stepheu VI. | 1099 | | Paschalis II. |
| 887 | Arnulf. | | 1106 | Henry V. | |
| 891 | | Formosus. | 1118 | | Gelasius II. |
| 896 | [Alfred the Great of Eng-land, 871-901.] | Boniface VI. | 1119 | | Calixtus II. |
| 897 | | Stephen VII. | 1124 | | Honorius II. |
| | | Romanus I. | 1125 | Lothaire of Saxony. | |
| | | Theodorus II. | | | Innocent II. |
| 898 | | John IX. | | | |
| 900 | Louis the Child. | Benedict IV. | 1130 | | |
| 903 | | Leo V. | 1138 | Conrad III. of Hohenstaufen. | |
| | | Christophorus. | 1143 | | Cœlestine II. |
| 904 | | Sergius III. | 1144 | | Lucius II. |
| 911 | Conrad I. | Anastasius III. | 1145 | | Engene III. |
| 913 | | Landonius. | | | |
| 914 | | John X. | 1152 | Frederick I. Barbarossa. | |
| 919 | Henry I. | | 1153 | | Anastasius IV. |
| 928 | | Leo VI. | 1154 | [Henry II. of England, 1154-1189.] | Hadrian IV. |
| 929 | | Stephen VIII. | 1159 | | Alexander III. |
| 931 | | John XI. | 1181 | | Lucius III. |
| 936 | Otho I. | Leo VII. | 1185 | | Urban III. |
| 939 | | Stephen IX. | 1187 | | Gregory VIII. |
| 942 | | Marinus II. | 1187 | | Clement III. |
| 946 | | Agapetus II. | 1190 | Henry VI. | |
| 955 | | John XII. | 1191 | | Cœlestine III. |
| 963 | | Leo VIII. | 1198 | Philip of Swabia and Otho IV. | Innocent III. |
| 964 | | Benedict V. | | | |
| 965 | | John XIII. | | [Richard Cœur de Lion, 1189-1199.] | |
| 973 | Otho II. | Benedict VI. | | | |
| 974 | | Benedict VII. | | | |
| | | Boniface VII. | | | |
| 983 | Otho III. | John XIV. | 1212 | Frederick II. | |
| 985 | | John XV. | 1216 | [John Lack- | Honorius III. |
| 996 | | Gregory V. | 1227 | land, 1199- | Gregory IX. |
| 999 | | Sylvester II. | 1241 | 1216.] | Cœlestine IV. |
| 1002 | Henry II. | | 1243 | | Innocent IV. |
| 1003 | | John XVII. | 1250 | Conrad IV. | |
| | | John XVIII. | 1254 | Interregnum. | Alexander IV. |
| 1009 | | Sergius IV. | 1261 | | Urban IV. |
| 1012 | | Benedict VIII. | 1265 | | Clement IV. |
| 1024 | Conrad II. | John XIX. | 1271 | | Gregory X. |
| 1033 | | Benedict IX. | 1273 | Rudolph of Hapsburg. | |
| 1039 | Henry III. | | | | |
| 1045 | | Gregory VI. | 1276 | | Innocent V. |
| | | Clement II. | | [Edward I. of England, 1272-1307.] | Hadrian V. |
| 1048 | | Damasus II. | | | John XX. |
| 1049 | | St. Leo IX. | | | or XXI. |
| 1055 | | Victor II. | 1277 | | Nicholas III. |
| 1056 | Henry IV. | | 1281 | | Martin IV. |
| 1057 | | Stephen X. | 1285 | | Honorius IV. |
| 1058 | | Benedict X. | 1288 | | Nicholas IV. |
| 1059 | | Nicholas II. | 1292 | Adolph of Nassau. | |
| 1061 | [William the Conqueror, 1066-1087.] | Alexander II. | 1294 | | St. Cœlestine V. |
| 1073 | | Gregory VII. | 1295 | | Boniface VIII. |


| A.D. | Rom. Emp. | Popes. | A.D. | Rom. Emp. | Popes. |
|------|-----------------|--------------------|---------------|-----------------|--------------------|
| 1298 | Albert I. | | 1550 | England, 1553 | Julius III. (Joan. |
| 1303 | | Benedict XI. | -1553.] | | Maria de Monte). |
| 1305 | | Clement V. | 1555 | | Marcellus II. |
| 1308 | Henry VII. of | | | | Paul IV. (Gian |
| | Luxembourg. | | | | Pietro Caraffa |
| 1314 | Louis of Ba- | | 1556 | Ferdinand I. | of Naples). |
| | varia and | | 1559 | [Elizabeth of | Pius IV. (Joan. |
| | Frederick of | | England, 1558 | | Angelus Medici |
| | Austria. | | -1603.] | | of Milan). |
| 1316 | [Edward III. of | John XXII. | 1564 | Maximilian II. | |
| 1334 | England, 1327 | Benedict XII. | 1565 | | St. Pius V. |
| 1342 | -1377.] | Clement VI. | | | (Ghislicri of |
| 1346 | Charles IV. of | | | | Piedmont). |
| | Luxembourg. | | 1572 | | Gregory XIII. |
| 1352 | | Innocent VI. | | | (Ugo Buon- |
| 1362 | | Urban V. | | | compagni of |
| 1370 | | Gregory XI. | | | Bologna). |
| 1378 | Wenzel. | Urban VI. | 1576 | Rudolph II. | |
| 1389 | | Boniface IX. | 1585 | | Sixtus V. (Felix |
| 1400 | Rupert of the | | 1590 | | Peretti). |
| | Palatinate. | | | | Urban VII. |
| 1404 | | Innocent VII. | | | (Giambattista |
| 1406 | | Gregory XII. | | | Castagna of |
| 1409 | | Alexander V. | | | Rome). |
| 1410 | Sigismund. | John XXIII. | 1590 | | Gregory XIV. |
| 1417 | [Henry V. of | Martin V. | | | (Nic. Sfondrati |
| | England, 1413 | | | | of Milan). |
| 1431 | -1422.] | Eugene IV. | 1591 | | Innocent IX. |
| 1438 | Albert II. | | | | (Giannantonio |
| 1440 | Frederick III. | | | | Facchinetti of |
| 1447 | | Nicholas V. | | | Bologua). |
| 1455 | [Henry VI. of | Calixtus III. | 1592 | | Clement VIII. |
| 1458 | England, 1422 | Pius II. (Æneas | | | (Hippolyt. Aldo- |
| | -1461.] | Sylvius, Sicna). | | | brandini of |
| 1464 | | Paul II. | | [James I. of | Florence). |
| 1471 | | Sixtus IV. | 1605 | England, 1603 | Leo XI. (Alexan- |
| | | (Francis della | -1625.] | | der Medici). |
| | | Rovere of | | | Paul V. (Camillo |
| | | Savona). | | | Borghese). |
| 1484 | [Henry VII. of | Innocent VIII. | 1612 | Matthias. | |
| | England, 1485 | (Joann. B. Cibo | 1619 | Ferdinand II. | |
| | -1509.] | of Genoa). | 1621 | [Charles I. of | Gregory XV. |
| 1492 | | Alexander VI. | England, 1625 | | (Alexander Lu- |
| | | (Roder. Borgia). | -1649.] | | dovisi). |
| 1493 | Maximilian I. | | 1623 | | Urban VIII. (Maf- |
| 1503 | [Henry VIII. of | Pius III. (Fran- | | | feo Barberini). |
| | England, 1509 | cis Piccolomini | 1637 | Ferdinand III. | |
| | -1547.] | of Siena). | 1644 | [Common- | Innocent X. |
| 1503 | | Julius II. (Julian | wealth and | | (Giambattista |
| | | della Rovere). | Protectorate, | | Pamfilii). |
| 1513 | | Leo X. (John de' | 1649-1660.] | | |
| | | Medici). | | | Alexander VII. |
| 1519 | Charles V. | | 1655 | | (Fabio Chigi of |
| 1522 | | Hadrian VI. | | | Siena). |
| | | (of Utrecht). | 1658 | Leopold I. | |
| 1523 | | Clement VII. | 1667 | [Charles II. of | Clement IX. |
| | | (Julius Medici). | England, 1660 | | (Giul. Rospig- |
| 1534 | | Paul III. (Alex- | -1685.] | | liosi). |
| | [Mary I. of | ander Farnese).] | | | |

MARTINUS V.
1417 1431



COLONNA

EUGENIUS IV.
1431 1447



CONDOLMIERI

NICOLAUS V.
1447 1455




PARENTUCELLI

CALIXTUS III.
1455 1458



BORGIA

PIUS II. PIUS III.
1458 1464 1503




PICCOLOMINI

PAULUS II.
1464 1471




BARBO

SIXTUS IV.
1471 1484



DELLA ROVERE

INNOCENTIUS VIII.
1484 1492



CIBO

ALEXANDER VI.
1492 1503




BORGIA

JULIUS II.
1503 1513




DELLA ROVERE

LEO X. LEO XI.
1513 1521 1605




MEDICI

HADRIANUS VI. CLEMENS VII.
1523 1523 1523



(UTRECHT) MEDICI

PAULUS III.
1534 1549



FARNESE

JULIUS III.
1550 1555




DEL MONTE

MARCELLUS II.
1555




CERVINO

PAULUS IV.
1555 1559



CARRAFA

PIUS IV.
1559 1565



MEDICI

PIUS V.
1566 1572



GHISLIERI

GREGORIUS XIII.
1572 1585



BUONCOMPAGNO

SIXTUS V.
1585 1590



PERETTI

URBANUS VII. (CASTAGNA)
1590



GREGORIUS XIV. INNOCENTIUS IX.

CLEMENS VIII.
1592 1605



ALDOBRANDINI

PAULUS V.
1605 1621



BORGHESE

GREGORIUS XV.
1621 1623



LUDOVISI

URBANUS VIII.
1623 1644



BARBERINI

INNOCENTIUS X.
1644 1655



PAMFILI

ALEXANDER VII.
1655 1667




CHIGI

CLEMENS IX.
1667 1669



ROSPIGLIOSI

CLEMENS X.
1670 1676



ALTIERI

INNOCENTIUS XI.
1676 1689



ODESCALCHI

ALEXANDER VIII.
1689 1691



OTTOBONI

INNOCENTIUS XII.
1691 1700



PIGNATELLI

CLEMENS XI.
1700 1721



ALBANI

INNOCENTIUS XIII.
1721 1724




CONTI

BENEDICTUS XIII.
1724 1730




ORSINI

CLEMENS XII.
1730 1740



CORSINI

BENEDICTUS XIV.
1740 1758



LAMBERTINI

CLEMENS XIII.
1758 1769



REZZONICO

CLEMENS XIV.
1769 1774




GANGANELLI

PIUS VI.
1775 1795



BRASCHI

PIUS VII.
1800 1823



CHIARAMONTI

LEO XII.
1823 1829



DELLA GENGA

PIUS VIII.
1829 1830



CASTIGLIONE

GREGORIUS XVI.
1831 1846



CAPELLARI

PIUS IX.
1846 1878





MASTAI-FERETTI

LEO XIII.
1878



PECCI



| A.D. | Rom. Emp. | Popes. | A.D. | Rom. Emp. | Popes. |
|------|--|---|------|-------------------------------------|---|
| 1670 | | Clement X. (Emilio Altieri). | 1765 | Joseph II. | |
| 1676 | | Innocent XI. (Benedetto Odescalchi). | 1769 | | Clement XIV. (Giov. Ant. Ganganelli of Rimini). |
| 1689 | | Alexander XIII. (Pietro Ottobuoni). | 1775 | | Pius VI. (Giov. Ang. Braschi). |
| | [William III. and Mary II. of England, 1688-1702.] | | 1790 | Leopold II. | |
| 1691 | | Innocent XII. (Ant. Pignatelli). | 1792 | Francis II. | |
| 1700 | | Clement XI. (Giov. Franc. Albani). | 1800 | | Pius VII. (Gregorio Barnaba Chiaramonti of Cesena). |
| 1705 | Joseph I. | | 1823 | [George IV. of England, 1820-1830.] | Leo XII. (Annib. della Genga of Spoleto). |
| 1711 | Charles VI. | | 1829 | | Pius VIII. (Franc. Xav. Castiglione of Cingoli). |
| 1721 | | Innocent XIII. (Mich. Ang. de Conti). | | | Gregory XVI. (Mauro Capellari of Belluno). |
| 1724 | [George II. of England, 1727-1760.] | Benedict XIII. (Vinc. Maria Orsini). | 1831 | | Pius IX. (Giovanni Maria Mastai-Feretti of Sinigaglia). |
| 1730 | | Clement XII. (Lorenzo Corsini). | 1846 | | Leo XIII. (Gioachino Pecci of Carpineto, b. 2. March 1810, Cardinal 1853. Pope 20. Feb. 1878). |
| 1740 | | Benedict XIV. (Prosp. Lambertini). | 1878 | | |
| 1742 | Charles VII. of Bavaria. | | | | |
| 1745 | Francis I. | | | | |
| 1758 | [George III. of England, 1760-1820.] | Clement XIII. (Carlo Rezzonico of Venice). | | | |

Rome, the capital of the kingdom of Italy, with 345,036 inhab. (31st Dec., 1885; less than Naples), is situated (41° 53' 54" N. lat., 12° 29' E. long., meridian of Greenwich) in an undulating volcanic plain, which extends from Capo Linaro, S. of Cività Vecchia, to the Promontorio Circeo, a distance of about 85 M., and between the Apennines and the sea, a width of 25 M. The city is built on both banks of the Tiber, the largest river in the Italian peninsula, which intersects the city from N. to S. in three wide curves. The banks of the Tiber are connected by EIGHT BRIDGES: the *Ripetta Bridge*, the highest; the new *Ponte Umberto*; the *Ponte S. Angelo*, near the castle of that name; the *Ponte Leonino*, a suspension bridge, crossing from the Lungara; the *Ponte Sisto*; the new *Ponte Garibaldi*; a seventh traversing the island between the second and third bends of the river, called *Ponte S. Bartolommeo* (the ancient *Pons Cestius*) from Trastevere to the island, and thence to the left bank the *Ponte*

de' Quattro Capi (*Pons Fabricius*); finally, below the island, a new bridge near the old *Ponte Rotto*. Other bridges are projected. The water of the Tiber, is turbid (the '*flavus Tiberis*' of Horace). The average width of the river is about 65 yds. and its depth 20 ft., but it sometimes rises as much as 30-35 ft., as was the case during the great inundation of 1871. The construction of an artificial channel for the river has been undertaken. The navigation of the river, by means of which the commerce of imperial Rome was carried on in both directions, with transmarine nations as well as with the Italian provinces, is now comparatively insignificant.

The prospect from one of the hills of Rome — and no city is richer in ever-varying and delightful views — is bounded towards the E. by the unbroken chain of the Apennines, which rise at a distance of 10 to 20 M. In the extreme N. towers the indented ridge of Soracte (2260 ft.), occupying an isolated position in the plain, and separated by the Tiber from the principal range of the Apennines. Farther E., and still more distant, is the Leonessa group (7255 ft.), which approaches the Central Apennines. Considerably nearer lies the range of the Sabine Mts. The summit at the angle which they form by their abutment on the Campagna is M. Gennaro (4160 ft.), perhaps the *Lucretilis* of Horace; the village at the base is Monticelli (1295 ft.). Farther off, on the slope of the hill, lies Tivoli, recognisable by its villas and olive-gardens. More towards the S., on the last visible spur of the Sabine Mts. (2515 ft.), is situated Palestrina, the *Præneste* of antiquity. A depression 4 M. in width only, separates the Apennines from the volcanic Alban Mts., above which a few peaks of the distant Volscian Mts. appear. On the E. spur of the Alban Mts. lies the village of Colonna (1180 ft.). The following villages are Rocca Priora (2350 ft.) and Monte Porzio (1530 ft.); then the town of Frascati (2220 ft.), below the ancient Tusculum. The highest peak of the Alban Mts. is M. Cavo (3130 ft.), once surmounted by a temple of the Alban Jupiter, now by a Passionist monastery. On its slope lies the village of Rocca di Papa (2645 ft.), loftily and picturesquely situated, below which, towards the plain, is the town of Marino (1320 ft.). The village, with the castle farther to the W. on the hill, is Castel Gandolfo; the mountain then gradually sinks to the level of the plain. Towards the W. the sea is visible from a few of the highest points only. On the N. the eye rests on the Janiculus (280 ft.), a volcanic chain of hills approaching close to the river, beyond which the horizon is bounded by mountains also of volcanic formation: towards the sea, to the left, the mountains of Tolfa (2040 ft.), then the heights around the lake of Bracciano with the peak of Rocca Romana (2020 ft.), the Ciminian Forest (now generally called the mountains of Viterbo, 3465 ft.); the nearest point to the right is the crater of Baccano, with the wooded hill of M. Musino (1320 ft.). The plain enclosed by this spacious amphitheatre of mountains, and

intersected by the Tiber and the Anio, which descends from Tivoli and falls into the former $1\frac{1}{2}$ M. above Rome, contains a sprinkling of farms and villages, but is far more replete with witnesses of its former greatness and present desolation in the innumerable and extensive ruins which cover it in every direction.

The city proper lies on the LEFT BANK of the Tiber, partly in the ancient *Campus Martius*, a plain adjoining the river, and partly on the surrounding hills. Modern Rome is principally confined to the plain, while the HEIGHTS on which the ancient city stood were for centuries almost uninhabited, and have only recently again begun to be occupied by houses. These are the far-famed Seven Hills of Rome. The least extensive, but historically most important, is the *Capitoline* (165 ft.), which rises near the Tiber and the island. It consists of a narrow ridge extending from S.W. to N.E., culminating in two summits, separated by a depression. Contiguous to the Capitoline, in a N.E. direction, and separated from it by a depression, extends the long *Quirinal* (170 ft.). On the N. a valley, in which the Piazza Barberini is situated, separates the Quirinal from the *Pincio* (165 ft.), which, as its ancient name 'collis hortorum' indicates, was occupied by gardens, and not regarded as part of the city. To the E. of the Quirinal, but considerably less extensive, rises the *Viminal* (175 ft.). Both of these may be regarded as spurs of the third and more important height, the *Esquiline* (245 ft.), which, forming the common basis of these two, extends from the Pincio on the N. to the *Cælius*. Its present distinguishing feature is the conspicuous church of S. Maria Maggiore; while S. Pietro in Vincoli and the ruins of the *Thermae of Titus* mark the ancient quarters which stood on the hill where it approaches the Viminal, Palatine, and Cælius. To the S. E. of the Capitoline, in the form of an irregular quadrangle, rises the isolated *Palatine* (165 ft.), with the ruins of the palaces of the emperors, and on the low ground between these hills lies the ancient Forum. Farther S., close to the river, separated from the Palatine by the depression (70 ft.) in which the *Circus Maximus* lay, is the *Aventine* (150 ft.). Lastly, to the E. of the latter, is the long *Cælius* (165 ft.); in the low ground between the Cælius, Palatine, and Esquiline is situated the Colosseum; and farther E., by the city-wall, between the Cælius and Esquiline, is the Lateran.

On the RIGHT BANK of the Tiber lies the more modern and smaller part of the city, divided into two halves: on the N. the *Borgo* around the *Vatican* and *St. Peter's*, encircled with a wall by Leo IV. in 852 and erected into a separate town; and to the S., on the river and the slopes of the Janiculum, *Trastevere*, which from ancient times has formed a tête-de-pont of Rome against Etruria, and was a densely peopled suburb in the reign of Augustus. These two portions are connected by the long *Via della Lungara*, constructed by Sixtus V.

The wall enclosing this area, which was inhabited during the imperial epoch by $1\frac{1}{2}$ -2 million souls, has a length of about 10 M.

on the left bank and is pierced by 13 gates. It is constructed of brick, and on the outside about 55 ft. high. The greater part of it dates from 271 to 276. It was begun by the Emp. Aurelian, completed by Probus, and restored by Honorius, Theodoric, Belisarius, and several popes. The wall on the right bank dates mainly from the time of Pope Urban VIII. (comp. the Plan of 'Ancient Rome', p. 207). The Italian government has recently begun to fortify Rome by a series of detached forts forming a circle of about 30 M. in circumference round the city.

The following description of Rome is arranged in accordance with a division of the city into five districts, the extent of which is marked on the clue-map at the end of the Handbook.

I. Strangers' Quarter and Corso, the chief centre of business.

II. The Eastern Quarters, including the *Quirinal*, *Viminal*, and *Esquiline Hills*, anciently covered with houses, afterwards long given over to fields and vineyards, but now again becoming of importance in consequence of the municipal improvements inaugurated in 1870.

III. Rome on the Tiber (left bank), the closely packed and tortuous city of the middle ages, the abode of the poorer classes, recently much altered and broken up by the construction of new streets.

IV. Ancient Rome, to the S., containing the chief monuments of antiquity.

V. The Right Bank of the Tiber, including the Vatican, St. Peter's, and Trastevere.

I. Strangers' Quarter and Corso.

The N. entrance to Rome is formed by the **Porta del Popolo** (Pl. I, 18), not far from the Tiber, through which, before the construction of the railroad, most visitors approached the Eternal City. It lies at the beginning of the main highway which connects Rome with Tuscany, Umbria, and N. and E. Italy generally. The gate was constructed in 1561 by *Vignola*, and the side towards the town by *Bernini* in 1655, on the occasion of the entry of Queen Christina of Sweden. In 1878 it was enlarged by the addition of two side-portals. The gate is named after the adjoining church of S. Maria del Popolo. — Outside the gate, on the right, is the Villa Borghese, see p. 334.

Within the gate lies the handsome ***Piazza del Popolo** (Pl. I, 18), adorned with an *Obelisk* between four water-spouting lionesses, which was brought by order of Augustus from Heliopolis after the defeat of Antony, placed in the Circus Maximus, and, according to the inscription, dedicated to the Sun. It was removed to its present position by order of Sixtus V. in 1589. The shaft is 78 ft. in height, and the whole monument with the pedestal and cross 118 ft. — Towards the W. the Piazza is bounded by an arched wall with

figures of Neptune and Tritons, opposite which is a similar structure adorned with Roma between the Tiber and the Anio. On each side of the latter is an approach to the *Pincio* (p. 148).

Three streets diverge from the piazza on the S.: to the right the *Via di Ripetta* (p. 184), parallel with the river; in the centre the *Corso* (p. 152); and to the left the *Via del Babuino*, leading to the Piazza di Spagna (p. 150). — Between the two latter streets stands the church of *S. Maria in Monte Santo*, adjacent to which, on the right, is that of *S. Maria de' Miracoli*, both dating from the latter half of the 17th cent., with domes and vestibules, designed by Rinaldi, and completed by Bernini and Fontana.

***S. Maria del Popolo** (Pl. I, 18), said to have been founded by Paschalis II. in 1099 on the site of the tombs of the Domitii, the burial-place of Nero, which was haunted by evil spirits, was entirely re-erected by *Baccio Pintelli* (? or *Meo del Caprina*) under Sixtus IV. in 1477. The interior was afterwards decorated by *Bernini* in the rococo style. It consists of nave, aisles, transept, and octagonal dome, and contains handsome monuments of the 15th cent. (comp. p. xix) and other works of art. (The sacristan shows the choir and chapels; fee $1\frac{1}{2}$ fr.)

RIGHT AISLE. The 1st Chapel, formerly *della Rovere*, now *Venuti*, was painted by *Pinturicchio*: *Altar-piece, Adoration of the Infant Christ; in the lunettes, life of St. Jerome. On the left, the tomb of Cardinal della Rovere, right, that of Cardinal di Castro; on the pillar to the left, a bust of F. Catel, the painter (d. 1857) by *Troschel*. — In the 2nd Chapel: Assumption of Mary, altar-piece by *C. Maratta*. — 3rd Chapel, painted by *Pinturicchio*: above the altar, Madonna with four angels; on the left, Assumption of the Virgin; in the lunettes, scenes from the life of Mary; in the predelle representations of martyrs in grisaille; on the right, tomb of Giov. della Rovere (d. 1483); on the left, recumbent bronze figure of a bishop. — In the 4th Chapel marble sculptures of the end of the 15th cent. above the altar: St. Catharine between St. Anthony of Padua and St. Vincent; right, tomb of Marcantonio Albertoni (d. 1485); left, that of the Cardinal of Lisbon (d. 1508).

RIGHT TRANSEPT. On the right, tomb of Cardinal Podocatharus of Cyprus. Near it is a door leading into a passage, at the end of which is the sacristy, containing the former *Canopy of the high-altar of Alexander VI. of the year 1492, with an ancient Madonna of the Siennese school and the beautiful monuments of (left) Archbishop Rocca (d. 1482), and (right) Bishop Gomiel.

LEFT AISLE. 1st Chapel, on the left and right of the altar, two ciboria of the 15th cent.; left, tomb of Card. Ant. Pallavicino (erected 1507). By an adjacent pillar the rococo monument of a Princess Chigi, by *Posi* (1771). — The *2nd Chapel was constructed under the direction of Raphael by *Agostino Chigi* in honour of St. Mary of Loreto, in the form of a Greek cross, with a lofty dome, in the style affected for such structures in the 16th century. On the vaulting of the dome are eight *Mosaics by *Aloisio della Pace* (1516), from Raphael's cartoons: — 'Around the central circular scene, which represents the Creator surrounded by angels, are grouped seven planet symbols and a genius leaning on a globe, separated by ornamental divisions. Each planet is represented by an ancient deity: Diana, Luna, Mercury, Venus, Apollo, Mars, Jupiter, and Saturn. They are portrayed in half-figure with appropriate action, and each is enclosed within a segment of the zodiac, on which rests an angel, either pointing to the Creator above or in the act of adoration. This association of gods and angels recalls the prophets and sibyls of Michael Angelo, each of whom is also accompanied by a genius. But Raphael's composition is entirely independent, with a distinct significance of its own, and one of a kind which shows

the master's power in its highest manifestation'. — The altar-piece, a Nativity of the Virgin, is by *Sebastiano del Piombo*, the other pictures by *Salviati*. Bronze relief over the altar, Christ and the Samaritan woman, by *Lorenzetto*; in the niches four statues of prophets: over the altars (left) *Jonah, perhaps designed by *Raphael*, and (right) Habakkuk, by *Bernini*; at the entrance, (left) Daniel, by *Bernini*, and (right) Elijah by *Lorenzetto*.

LEFT TRANSEPT: Tomb of Cardinal Bernardino Lonati (15th cent.).

In the CHOR *Ceiling-frescoes by *Pinturicchio* (1479): Madonna, the Four Evangelists, and the Four Fathers of the church, Gregory, Ambrose, Jerome, and Augustine, in excellent preservation, and long deservedly admired for the skilful distribution of space. Beneath are the *Tombs of the cardinals Girolamo Basso della Rovere and Ascanio Sforza by *Andrea Sansovino*, erected by order of Julius II. (1505), 'the perfection of sculpture combined with decoration'. The same pope is said to have caused the two fine stained-glass windows to be executed by *Claudius* and *William of Marseilles*.

The church gives a title to a cardinal. In the adjacent Augustine monastery Luther resided during his visit to Rome (1510).

If we ascend the Pincio by the approaches named at p. 147 (gates closed one hour after Ave Maria), we observe in the first circular space two granite columns (*columnae rostratae*) from the temple of Venus and Roma (p. 233), adorned with the prows of ships (modern); in the niches three marble statues, and above them captive Dacians, imitations of antiques. Beyond these, a large relief. Half-way up are an antique granite basin, with a fountain, and an *Equestrian Statue of Victor Emmanuel II.*, under a loggia.

The ***Pincio** (Pl. I, 18), the *collis hortorum*, or 'hill of gardens', of the ancients, was probably called *Mons Pincius* from a palace of the Pincii situated here in the later period of the empire. Here were once the famous gardens of Lucullus, in which Messalina, the wife of Claudius, afterwards celebrated her orgies. A vineyard belonging to the monastery of S. Maria at the foot of the hill was converted by *Valadier*, during the Napoleonic régime, into beautiful pleasure-grounds. This is a fashionable drive in the evening, when the Italians frequently pay and receive visits in their carriages, presenting a gay and characteristic scene. A military band plays here several times weekly in the latter part of the afternoon (p. 126). The walks are shaded by plantations and groups of trees, and (as suggested by Mazzini in 1849) adorned with busts of celebrated Italians. — The projecting terrace at the summit (150 ft.) commands a magnificent *VIEW of modern Rome.

Beyond the Piazza del Popolo and the new quarter in the Prati del Castello, on the opposite bank of the Tiber, rises the huge pile of St. Peter's, adjoining which is the Vatican to the right, and near it the city-wall. Among the hills which bound the horizon, the point planted with cypresses to the right is Monte Mario. To the left of St. Peter's, close to the Tiber, which is not visible, is the round castle of S. Angelo, with the bronze angel which crowns it. The pines on the height to the left of the castle belong to the Villa Lante on the Janiculum, with the Passeggiata Marzherita. Farther to the left, on the height, the façade of the Acqua Paola, adorned with a cross. Between the spectator and the river is a labyrinth of houses and churches. The following points serve as landmarks. Of the two nearest churches that with the two towers to the right is S. Giacomo in the Corso, that with the dome to the left, S. Carlo in the Corso; between the two appears the flat dome of the Pantheon, beyond which a part of

the Campagna is visible. To the left of this, on the height in the distance, rises the long, undecorated side of the church of S. Maria in Araceli, and behind it appears the tower of the senatorial palace on the Capitol. On the right side of the Capitol lies the Palazzo Caffarelli (German embassy), in front of which the upper part of the column of M. Aurelius in the Piazza Colonna is visible. Adjacent to the Capitol, on the left, is the bright-looking Villa Mills, shaded by cypresses, on the Palatine. Farther to the left a low brick-built tower on the Quirinal, the so-called Torre di Nerone. To the extreme left, and less distant, is the extensive royal palace on the Quirinal.

The N. side of the Pincio is supported by lofty walls, opposite which are the grounds of the Villa Borghese. In a small round space near the middle of the hill, beside a *Caf  *, rises an *Obelisk*, which Hadrian once erected in Egypt to the memory of Antinous. It was afterwards brought to Rome, and erected here in 1822. To the right of the walk leading to the S. exit is a monument by *Ercol   Rosa*, erected in 1883 to the memory of the brothers *Cairol  * of Pavia, who fell in battle near Rome in 1867 and 1870. The monument to the left, in the form of a globe, commemorates *Galileo Galilei*, who was confined from 1630 to 1633, at the instance of the Inquisition, in the Villa Medici (see below). — The exit is closed by an iron gate.

Leaving the Pincio by the S. gate, we observe to the left the Villa Medici. In front of it is an avenue of evergreen-oaks and a fountain, whence a celebrated view of St. Peter's, most striking towards evening or by moonlight, is obtained.

The **Villa Medici** (Pl. I, 18), erected in 1540 by *Annibale Lippi* for Cardinal Ricci da Montepulciano, came into possession of Cardinal Alessandro de' Medici about 1600, and afterwards belonged to the grand-dukes of Tuscany. In 1801 the French academy of art, founded by Louis XIV., was transferred hither. The garden is open to the public, and is entered by the gate to the left, or by the staircase to the right in the house (25-30 c.).

Among the ancient reliefs built into the walls of the tastefully decorated fa  ade of the villa next to the garden is one of the 'Judgment of Paris', the subject of a famous engraving by Marc Antonio. The wing contains a COLLECTION OF CASTS (open on Wed. & Sat., 8-12, and for three hours in the afternoon before dusk; the keeper proffers a written catalogue, for the use of which 25-30 c. is given), comprising many from statues not preserved at Rome, e.g. from the Parthenon of Athens, and the museum of the Louvre, which are valuable in the history of art. Adjoining the wing is a terrace, the front-wall of which is adorned with casts. We ascend a flight of steps (fee of a few soldi to the gardener who opens the door) and traverse the oak-grove to the right. We next ascend 60 steps to the BELVEDERE, whence a fine view, now somewhat circumscribed, is enjoyed.

The street passing the front of the Academy ends in the PIAZZA DELLA TRINIT  , where to the left rises the church of S. Trinit   de' Monti. The *Obelisk* in front of it, a conspicuous object from many points, is an ancient imitation of that in the Piazza del Popolo, and once adorned the gardens of Sallust.

S. Trinit   de' Monti (Pl. I, 20), erected by Charles VIII. of France in 1495, and plundered during the French Revolution, was

restored by *Mazois* in 1816 by order of Louis XVIII. It is open on Sundays only, before 9 a.m., and in the evening at Vespers (1 hr. before Ave Maria), when the nuns, for whom Mendelssohn composed several pieces, perform choral service with organ-accompaniment. When the door is closed, visitors ascend a side-staircase on the left, and ring at a door under a metal roof.

LEFT, 1st Chapel: Cast of the Descent from the Cross, by *Achtermann*. 2nd Chapel: altar-piece al fresco, *Descent from the Cross, by *Daniele da Volterra*, his master-piece (much injured and freely restored); the excellence of the drawing and composition (still better seen in the study at the Lateran, p. 271) is attributed to the aid of Michael Angelo. 3rd Chapel: *Madonna, altar-piece by *Veil*. 4th Chapel: *St. Joseph, by *Langlois*. 5th Chapel: Christ, the Wise and Foolish Virgins, and Return of the Prodigal, an altar-piece by *Seitz*. — RIGHT, 3rd Chapel: Assumption of the Virgin, *Dan. da Volterra*. 5th Chapel: Presentation in the Temple, Adoration of the Magi, Adoration of the Shepherds, of the *School of Raphael*. 6th Chapel: Resurrection, Ascension, Descent of the Holy Ghost, *School of Perugino*. — In the TRANSEPT, which is supported by Gothic arches, paintings by *Perino del Vaga* and *F. Zuccaro*.

The convent connected with the church has been occupied by the Dames du Sacré Cœur (teachers of girls) since 1827.

We quit the piazza to the left by the *Via Sistina*, which leads in 5 min. to the Piazza Barberini (p. 171), and in 20 min. more to S. Maria Maggiore (p. 176). To the right is the small *Via Gregoriana*, which after 3 min. is intersected by the *Via Capo le Case*.

To the right, *Via Sistina* No. 64, is the *Casa Zuccari*, once the house of the family of the artists of that name (marked by a memorial-tablet in 1872; paintings by Federigo Zuccaro on the ground-floor). In 1816 it was occupied by the Prussian consul Bartholdy, who caused one of the rooms to be adorned with frescoes by German artists then at Rome, among whom were Cornelius, Overbeck, Veit, and Schadow. The frescoes, however, were removed to the National Gallery at Berlin in 1888.

The long *Scala di Spagna* (Pl. I, 20; 'Gradinata di S. Trinità de' Monti'), which descends from S. Trinità to the Piazza di Spagna by 135 steps, was constructed by Al. Specchi and De Sanctis in 1721-25. Models for artists with their picturesque costumes frequent its vicinity. To the left of the steps as we descend is the house where *John Keats* died in 1821 (marked by an inscription).

The **Piazza di Spagna** (Pl. I, 17; 82 ft.), the centre of the strangers' quarter, is enclosed by hotels and attractive shops. At the foot of the steps is *La Barcaccia* (barque), a tasteless fountain by Bernini. Towards the N. the *Via del Babuino*, containing the new English church of *All Saints*, in the Gothic style, by Street (p. 119), and also several hotels, leads to the Piazza del Popolo (see p. 146). *John Gibson*, the sculptor, died in 1866 at *Via del Babuino* 144. In the S. prolongation of the long Piazza di Spagna rises the *Column of the Immacolata* (Pl. I, 20, 1), erected by Pius IX. in honour of the 'Immaculate Conception of the Virgin', a dogma promulgated in 1854; on the top of the cipolline column stands the

bronze statue of Mary; beneath are Moses, David, Isaiah, and Ezekiel.

At the S. end of the piazza is the *Collegio di Propaganda Fide* (Pl. I, 19, 16), founded in 1622 by Gregory XV., and extended by his successor Urban VIII. (whence '*Collegium Urbanum*'), an establishment for the propagation of the Roman Catholic faith, where pupils of many different nationalities are educated as missionaries. The printing-office of the college was formerly celebrated as the richest in type for foreign languages. — On the right is the *Palazzo di Spagna*, or palace of the Spanish ambassador, whence the piazza derives its name. Opposite lies the small *Piazza Mignanelli* (Pl. I, 20), a station of the omnibuses to St. Peter's and the Piazza Montanara (Nos. 8 & 23, pp. 1, 2 of the Appx.).

Opposite the Scala di Spagna is the *VIA DE' CONDOTTI*, with its numerous shops of jewellery, mosaics, antiquities, and photographs. It terminates in the Corso (see p. 152).

To the S.E. from the Piazza di Spagna runs the *Via de' Due Macelli*, to the left of the Propaganda, and to the right the *VIA DI PROPAGANDA*. The latter leads to **S. Andrea delle Fratte** (Pl. I, 19) at the corner of the *Via di Capo le Case*, the next cross-street. This church was erected under Leo XI. by *La Guerra*; the tasteless dome and campanile are by *Borromini*; the façade was added in 1826 by *Valadier*.

The pictures in the INTERIOR are poor works of the 17th cent.: the two angels by the tribune, by *Bernini*, were originally destined for the bridge of S. Angelo. In the 2nd Chapel on the right is (on the right side) the monument of Mlle. Falconnet by *Miss Hosmer*; on the last pillar to the right, in front of the aisle, the monument of the artist R. Schadow (d. 1822), by *E. Wolff*. In the 3rd Chapel to the left, by the right wall, is the tomb of Angelica Kauffmann (d. 1807); adjacent, by the pillar to the right, lies 'Maler Müller' (d. 1825). The Danish archaeologist Zoëga and a converted prince of Morocco are also interred in this church.

In the *Via di Capo le Case* stands the church of *S. Giuseppe a Capo le Case* (Pl. I, 19), adjoining which is the *MUSEO ARTISTICO-INDUSTRIALE*, an unimportant collection of terracottas, majolica, glass, ivory and wood carving, and other products of the artistic industries of Italy (adm. daily except Wed., 9-3, 50 c.). Descriptive labels are attached to the articles exhibited.

We follow the *Via di Propaganda* towards the S., passing in front of S. Andrea delle Fratte, and turn to the right into the *Via del Pozzetto*, and then to the left into the *VIA POLI* (Pl. I, 19). The last, which is almost immediately intersected by the *Via dell' Angelo Custode* (p. 154), a new street connecting the Piazza Barberini and the Piazza Colonna, crosses the small Piazza Poli, skirts the *Palazzo Poli*, and leads to the Fontana Trevi.

The ***Fontana di Trevi** (Pl. I, 19), which vies in magnificence with the Acqua Paola, is erected against the S. side of the Palazzo Poli, and was completed from a design by *Nicc. Salvi* (1735) in

1762. In the central niche is a figure of Neptune, by *Pietro Bracci*; at the sides, Health (left) and Fertility (right); in front, a large stone basin.

The ancient *Aqua Virgo*, now *Acqua Vergine*, which issues here, was conducted by M. Agrippa from the Campagna, chiefly by a subterranean channel 14 M. in length, to supply his baths at the Pantheon (p. 195), in B.C. 19. It enters the city by the Pincio, not far from the Porta del Popolo. The name originated in the tradition that a girl once pointed out the spring to thirsty soldiers. The fountain was restored by Hadrian I., Nicholas V., and others. In 1453 the latter pope conducted hither the main stream of the aqueduct, and the fountain then exchanged its ancient name for its present name of Trevi (a corruption of 'Trivio'), which it derives from its three outlets. This aqueduct yields daily upwards of 13 million cubic feet of water, perhaps the best in Rome. The fountains in the Piazza di Spagna, the Piazza Navona, and the Piazza Farnese are supplied from the same source. — On quitting Rome, the superstitious partake of the water of this fountain, and throw a coin into the basin, in the pious belief that their return is thus ensured.

The busy *Via delle Muratte* (p. 155), leads to the W. from the Fontana Trevi to the Corso. Opposite the fountain is SS. *Vincenzo ed Anastasio* (Pl. I, 19, 3), erected in its present form, with a degraded façade, from designs by M. Lunghi the Younger, at the beginning of the 17th century.

The Via di S. Vincenzo, called farther on the Via de' Lucchesi, terminates in the little PIAZZA PILOTTA, in which, to the right, stands the *Palazzo Muti Papazzurri*, (Pl. II, 19, 9), built by Mattia de' Rossi in 1644. (From the Via de' Lucchesi the Via della Dataria leads on the left to the Quirinal; p. 174.) To the right of the Piazza Pilotta lies the Piazza SS. Apostoli (p. 160). The VIA DELLA PILOTTA, skirting the rear of the *Palazzo Colonna* (No. 17 is the entrance to the Galleria Colonna), and passing under the two arches which unite that palace with the Giardino Colonna (p. 163), leads to the *Via Nazionale* (p. 169).

The Corso.

The *Corso, which corresponds with the ancient *Via Flaminia* leading from the Capitol, extends from the Piazza del Popolo (p. 146), between the Via di Ripetta and Via del Babuino, to the Piazza di Venezia, and is now the principal street of Rome. It contains numerous shops and is enlivened, especially towards evening, by crowds of carriages and foot-passengers. Its length is 1650 yds., or nearly a mile.

The first part of the street as far as the Piazza S. Carlo is less frequented than the other portions. No. 518, to the right, between the first two cross-streets, is the *Pal. Rondinini* (Pl. I, 17, 18), the court of which contains an unfinished Pietà by *Michael Angelo*. No. 18, the house opposite, was once inhabited by *Goethe*; inscription: 'In questa casa immaginò e scrisse cose immortali Volfango Goethe. Il Comune di Roma a memoria del grande ospite pose 1872'.

On the right, beyond the third cross-street, is the church of

S. Giacomo in Augusta, or *degl' Incurabili* (Pl. I, 17, 2), with a façade by C. Maderna. It belongs to the adjoining surgical hospital, which extends to the *Via Ripetta* and accommodates 340 patients (founded 1338, enlarged 1600). Nearly opposite, on the left, is the small Augustine church of *Gesù e Maria*, with façade by Rinaldi. — [In the *Via de' Pontefici*, the third transverse street from this point to the right, is the Mausoleum of Augustus (p. 184).]

The Corso next leads to the *PIAZZA S. CARLO*, in which, on the right, is **S. Carlo al Corso** (Pl. I, 17), the national church of the Lombards, and the resort of the fashionable world, with a tasteless façade. It was erected in the 17th cent. by *Onorio Lunghi* and completed by *Pietro da Cortona*.

Ceiling-paintings in the INTERIOR by *Giacinto Brandi*. Over the high-altar is one of the finest works of *Carlo Maratta*: the Virgin recommending S. Carlo Borromeo to Christ. (The heart of S. Carlo is deposited under this altar.) Chief festival of the church, 4th Nov.

The busy *Via de' Condotti* and other streets to the left lead to the *Piazza di Spagna* (p. 150); the *Via della Fontanella di Borghese*, prolonging the *Via de' Condotti* towards the W., leads to the *Palazzo Borghese* (p. 184) and the *Ponte S. Angelo* (p. 274).

Farther on in the Corso, on the right, No. 418 A, is the spacious *Palazzo Ruspoli*, built by Ammanati in 1586, and now containing the Restaurant Morteo (p. 112).

To the left, at the corner of the *Via Frattina* (No. 151), is the *Palazzo Bernini*, the vestibule of which contains one of the most exaggerated specimens of Bernini's style, a group representing 'Time bringing the truth to light'.

In a small piazza on the right side of the Corso, opposite the *Via Frattina*, rises **S. Lorenzo in Lucina** (Pl. I, 16), a church of ancient origin, but frequently restored. The only old part is the campanile, the top of which is modern. The church and adjoining monastery have belonged to the Minorites since 1606.

The PORTICO is supported by four columns; at the door are two half-immured mediæval lions. — In the INTERIOR, by the 2nd pillar to the right, is the tomb of Nic. Poussin (d. 1665), erected by Chateaubriand; above the high-altar a Crucifixion by *Guido Reni*.

Farther on, to the right, a little back from the street and partly concealed by other houses, is the unfinished *Pal. Fiano* (Pl. I, 16, 8). The passage to the court, entered from No. 4, *Piazza in Lucina*, contains some good reliefs of figures and ornamental designs from the *Ara Pacis*, set up by Augustus in B.C. 9 (other remains in the *Villa Medici*, the Vatican, and the *Uffizi* at Florence). In front of this palace a triumphal arch of M. Aurelius stood until 1662 (see inscription opposite, No. 167, recording that Alexander VII. levelled and widened the Corso for the horse-races; reliefs, see p. 219).

The *Via delle Convertite* on the left leads to the *Piazza di S. Silvestro*, which is embellished with a monument to the poet *Pietro Metastasio* (b. at Rome 1693, d. at Vienna 1782), erected in 1886.

In the N.W. corner of the piazza rises the venerable church of *S. Silvestro in Capite* (Pl. I, 16), erected, together with a monastery, by Paul I. (757-67) on the site of his own house. The entrance-court has been preserved, but the church has been frequently rebuilt. The 'head of John the Baptist' has been preserved here since the 13th cent. (festival, 31st Dec.). Part of the monastery has been converted into the handsome **Post and Telegraph Office**, which has entrances from the piazza and the *Via della Vite*. Another part of the old monastery contains the ministerial *Offices of Public Works*. — Opposite *S. Silvestro* is the *English Church of the Trinity* (p. 119), erected in 1874, with a handsome façade in the early-Renaissance style. — At No. 11, *Via di Mercede*, which leads to the E. from the *Piazza di S. Silvestro*, is a tablet recording that *Sir Walter Scott* lived here when at Rome in 1832.

Farther on in the *Corso*, to the right, is the **PAL. VEROSPI** (No. 374), now **TORLONIA** (Pl. I, 16, 10), erected by *Onorio Lunghi*, and restored by *Alessandro Specchi*. A loggia on the first floor is adorned with pleasing mythological frescoes by *Fr. Albani*, recalling the famous *Farnesina* works (p. 323). — Opposite begins the wide *Via dell' Angelo Custode* (see p. 151), which leads past the church of *S. Maria in Via* (by *Mart. Lunghi*, 1594; façade by *Rainaldi*, 1600) and the N. front of the *Palazza Poli* (p. 151), to the *Piazza Barberini* (p. 171). The large establishment of the *Fratelli Bocconi*, at the corner, was built in 1886-87.

To the right, farther on, at the corner of the *Piazza Colonna*, is the extensive **Pal. Chigi**, begun in 1562 by *Giac. della Porta*, and completed by *C. Maderna*. It contains a few antiques and a small collection of pictures, but is not open to the public. The 'Bibliotheca Chisiana' contains valuable MSS. (adm., see p. 124).

The handsome ***Piazza Colonna** (Pl. I, 16) is bounded on the N. by the *Pal. Chigi*, and on the S. by the *Pal. Ferrajuti* (Pl. 20). In the *Corso*, to the E., is the *Pal. Piombino* (Pl. 22), and opposite the *Corso* the former post-office, with a portico of ancient Ionic columns from *Veii* (p. 389).

The ***Column of Marcus Aurelius**, rising in the centre of the piazza named after it, is embellished like that of *Trajan* with reliefs from the emperor's wars against the *Marcomanni* and other German tribes on the *Danube*.

The column consists of 28 blocks, besides the basement and capital, in all 95 ft. in height, and is approached by steps. In 1589 *Sixtus V.* caused it to be restored and crowned with a statue of *St. Paul*. At that period it was ascribed to *Antoninus Pius*, after whom it is still frequently named. — The *Piazza Colonna* is much frequented in the evening. Military music here in the height of summer (p. 126).

Adjoining the *Piazza Colonna* (beyond the old post-office) is the **PIAZZA DI MONTE CITORIO**, on the right side of which is the spacious **Camera de' Deputati** (Pl. I, 16, 24), begun for the *Lu-*

dovisi family by *Bernini* (1650), but finished under Innocent XII. by *C. Fontana* for the 'Curia Innocentiana', or papal tribunal. The court in the interior was roofed over in 1871, and fitted up for the use of the Italian parliament. The sittings usually take place in the afternoon. Entrance to the public seats at the back, No. 10. The door-keeper will sometimes provide visitors with better places (fee 1 fr.). — The rising of the piazza towards the N. is due to the buried ruins of what has been erroneously identified with the amphitheatre of *Statilius Taurus* (B.C. 31).

The *Obelisk* in the centre of the piazza, like that in the Piazza del Popolo (p. 146), was brought to Rome by Augustus, and used as the indicator of a sun-dial. It stood till the 9th cent., was afterwards damaged, but was restored and erected here in 1789 under Pius VI. It was originally erected in the 7th cent. B.C. by *Psammetichus I.* Height, including the globe and pedestal, 84 ft.

The Pantheon (see p. 193) may be reached hence by turning to the right at the foot of Monte Citorio (S.W.), and crossing the small Piazza Capranica (p. 195). We turn to the left and proceed to the PIAZZA DI PIETRA, in which is the **Dogana di Terra* (Pl. I, 16, 18), formerly a custom-house, now the exchange. Imbedded in the façade are eleven Corinthian columns, 41 ft. high, of a *Temple of Neptune*, built by Hadrian, which once possessed 15 in its length and 8 in its breadth. The three middle columns and a fragment of the wall of the cella have been lately brought to light. The pedestals here bore the statues, representing conquered provinces, now in the Palazzo de' Conservatori (p. 211).

The *Via de' Pastini* leads hence to the Pantheon (p. 193), while the Corso is regained by the *Via di Pietra* to the left.

Continuing to follow the Corso from the Piazza Colonna, we observe, to the left, opposite the above-named *Via di Pietra*, the *Via delle Muratte* (p. 152), leading to the Fontana Trevi.

Farther on, also on the left, where the Corso expands into the 'Piazza Sciarra', we reach the **Palazzo Sciarra-Colonna* (No. 239; Pl. I, 16), the handsomest palace in the whole street, erected in the 17th cent. by *Flaminio Ponzio*, with a portal of later date.

The PICTURE GALLERY in this palace is now shown only to visitors with a recommendation from high quarters. Principal works: *Raphael*, Violin-player, dated 1518; *Palma Vecchio*, Female portrait, signed 'Tambend'; *Bern. Luini*, 'Vanity and Modesty', half-figures; *Caravaggio*, Players; *Perugino*, St. Sebastian; *Guido Reni*, Magdalene.

Opposite is the imposing *Savings' Bank*, by *Cipolla* (1868).

The *Via del Caravita*, the first side-street on the right, leads to the PIAZZA DI S. IGNAZIO (Pl. II, 16), in which is the Jesuit church of *S. Ignazio*, designed by the *Padre Grassi*, with a façade by *Algardi*. The building was begun by Card. Ludovisi in 1626, after the canonisation of the saint, but not completed till 1675.

INTERIOR. The impression is marred by the bad taste of the decorations, which, however, are less obtrusive than in most Jesuit churches. The paintings on the vaulting, dome, and tribune, and the picture over the high-altar are by the *Padre Pozzi*, an able master of perspective, by whom the chapel of St. Lod. Gonzaga, in the aisle to the right, was also designed. The perspective of the paintings on the ceiling and dome is correctly seen from a circular stone in the centre of the nave.

On the front of this church is a *Time-Ball*, regulated from the Observatory (p. 157), the fall of which is the signal for the discharge of the time-gun at the Castello S. Angelo.

On the S. the choir of the church adjoins the old Jesuit **Collegio Romano** (Pl. II, 16), where the higher branches of classics, mathematics, philosophy, etc., were taught, and degrees conferred. The extensive building was erected at the end of the 16th cent., under Gregory XIII. and Sixtus V., by *B. Ammanati*. The massive principal façade looks towards the Piazza del Collegio Romano. A number of the rooms contain the *Biblioteca Vittorio Emanuele* (Director, Commendatore *D. Gnoli*) consisting of the old Library of the Jesuits, augmented by the libraries of many suppressed monasteries and constant new acquisitions (in all about 500,000 vols. and several thousand MSS.). This library is especially important on account of its richness in modern works, in which most of the other Roman libraries are deficient, and for its easy accessibility and convenient arrangements (comp. p. 115).—The building also contains the *Liceo Ennio Quirino Visconti* and several collections, the chief of which (on the second floor, up three flights of steps) is the —

Museo Kircheriano, founded by the learned *Athanasius Kircher*, born in 1601, a Jesuit and teacher at Würzburg in 1618, afterwards professor of mathematics at the Coll. Romano, and celebrated for his mathematical and scientific researches (d. 1680). In 1870 the museum was acquired by government, which has founded here an extensive ethnographical and pre-historical collection (adm. see p. 123). The director is *Commendatore Pigorini*.

We first turn to the left, and enter the CORRIDOR. The *Show-Cases* in the centre contain small articles in bronze, iron, ivory, and bone, with a large collection of antique Roman and Italian bronze coins (*aes grave*). The *Cabinets* by the walls contain terracotta figures (chiefly votive), lamps, clay vessels, and small objects in glass and ivory. *2nd Cab. to the left* (No. III): Silver goblets found in the miurel spring at Vicarello (p. 391), among which are three in the form of milestones and inscribed with the names of the chief stations on the route from Gades (Cadiz) in Spain to Rome; a book consisting of 7 plates of lead inscribed with mystical symbols (end of the 2nd cent. A.D.). *3rd Cab. to the right* (No. VIII): Large bronze tablet with a dedicatory inscription to Minerva in the Faliscan dialect; above, an iron ring with a bronze label bearing the inscription 'I have run away, catch me, and restore me to my master, who will reward you with a solidus', generally supposed to have been intended for a slave, but more probably a dog-collar.

I. ROOM. In the centre is the famous *'Ficoronian Cista'*, named after its first owner, dating from the 3rd cent. B.C., and found near Palestrina in 1744. It is a toilet-casket of cylindrical form, adorned with admirably-engraved designs, representing the arrival of the Argonauts in Bithynia, and the victory of Polydeuces over king Amycus. The feet and the figures on the lid are of inferior workmanship; on the latter the inscriptions: 'Novios Plantios med Romai (me Romæ) fecit', and 'Dindia Macolnia fileai

dedit' (comp. Introd.). — Also in the centre is an ancient *Bronze Chair*, inlaid with silver. By the windows are bronze figures of Bacchus and of a Youth intended for a pillar. The *Wall-Cases* contain Egyptian wooden and bronze statuettes, Etruscan idols, small bronze figures of the Roman period, weapons, candelabra, etc. — The —

II. Room, to the left, at the end of Room 1, contains early-Christian tombstones and sarcophagus-reliefs. In the centre is a piece of ancient wall, in a black frame, with a caricature of the Christians scratched upon it: a man with the head of an ass, affixed to a cross, with a man at the side, and the words Ἀλεξαμίνος σεβέτα θεόν (Alexamenos worships God), found in the Pædagogium on the Palatine (comp. p. 247). This probably represents the sarcastic wit of an imperial page at the expense of some Christian companion. — The *Cabinets* contain mediæval and Oriental curiosities forming part of the original Kircher collection.

The remaining rooms contain the *Ethnographical* and *Prehistoric Museum*. In the long *Corridor*, which we next enter, are objects from the Polar Regions and from N. and S. America (with explanatory labels). — *CABINET* at the end of the corridor: Embroidered mantle from Mexico, time of Fernando Cortez. — Then, to the right, are three parallel *Corridors*, devoted to Australia, Polynesia, India, Japan, and Africa. — We now turn to the right and enter the long *Corridor* parallel to the first-mentioned, containing the *Prehistoric Collections*. Objects of the stone period come first, followed by those from lake-dwellings and those of the bronze age. Among the most interesting objects are the cinerary urns in the shape of the primitive peasants' huts (from Corneto); the models of megalithic monuments (menhirs and dolmens) from Terra d'Otranto; a model of a Sardinian *Nurago*, or conical tower supposed to have been erected by the aboriginal inhabitants of Sardinia as a refuge in case of hostile attack. — Farther on are American antiquities, including some rare Mexican masks with mosaic work.

From the section with the model of the *Nurago* we turn to the right into the room which contains the *Treasure of Praeneste*, found at Palestrina (p. 383) in 1877 and purchased by Government. Next the door is a much patched antique vessel, ornamented with fantastic figures of animals. Under the windows are fragments of silver and bronze vessels. The chief objects are exhibited in the *Cabinet* in the centre: No. 1. Breast (or head) decoration, with 131 lions, horses, and various fantastic animals attached to it in rows, the details of which are most elaborately executed in granulated work; adjacent are two cylinders terminating in heads of animals, and enriched with the Grecian pattern in a similar style. Of the several adjacent golden cylinders, the finest is No. 4, embellished with two rows of figures of animals and exquisite arabesques. The small rod found in the cylinder lies alongside of it. No. 2. Golden fibula; 26. Fragments of a silver bowl, with representations of four boats, Egyptian symbols and figures, and a battle-scene (in the centre), and inscribed with a Phœnician name in small characters (above the wing of a hawk); 25. Elegant silver bowl, the interior adorned with a central figure and two rows of gilded reliefs (royal hunting-scenes, horses, and birds), and terminating in a snake. 23. Large round silver-gilt goblet, with six snakes forming the handles; the bowl is decorated with rows of figures of armed men, wild beasts, and birds. 24. Silver-gilt bowl, the interior of which is enriched with two rows of horses, oxen, birds, and trees; it was found adhering to an oxydised iron axe (No. 89, in Case V), which has taken the impression of part of it. The two-handled golden vessel (No. 20), the daggers numbered 27 and 28, and the ivory-reliefs, Nos. 45-49 and 51, are also fine. In *Case V* are the largest objects of the treasure of Praeneste: 75. Fragments of a large caldron with griffins' heads as handles; 72. Iron tripod, with bronze bowl, the margin of which is embellished with three human figures and three animals, in a very primitive style.

The *OBSERVATORY*, which acquired a European reputation under *Padre Secchi* (d. 1878), is shown in the forenoon to visitors with an introduction,

In the Corso, beyond the Piazza Sciarra, on the right, is the *Palazzo Simonetti* (No. 307). Opposite is **S. Marcello** (Pl. II, 16), in the small piazza of that name, a church mentioned as early as 499, re-erected by *Giacomo Sansovino* in 1519, and recently entirely modernised. The poor façade is by *Carlo Fontana*.

The 4TH CHAPEL on the right contains paintings by *Perino del Vaga*, completed after his death by *Dan. da Volterra* and *Pellegrino da Modena*, and the monument of the celebrated Card. Consalvi (d. 1824), minister of Pius VII., by *Rinaldi*. Paintings in the TRIBUNE by *Giov. Battista da Novara*; those of the 2ND CHAPEL to the left by *Fed. Zuccaro*.

On the right is the small church of *S. Maria in Via Lata*, mentioned as early as the 7th cent., but in its present form dating from the 17th; façade by *Pietro da Cortona*; from the vestibule a staircase ascends to an oratory (built by *Vignola*) in which St. Paul and St. Luke are said to have taught. The *Via Lata* (called *Via Flaminia* outside the town; p. 336) was the ancient main street of the city, nearly corresponding with the present Corso. Below this church and the Palazzo Doria lie extensive ancient walls, which once belonged to the *Septa Julia*, an edifice begun by Cæsar and completed by Agrippa, used for taking the votes of the national assembly, but converted into a market-place in the reign of Tiberius, when this practice had fallen into disuse.

Adjoining *S. Maria in Via Lata* is the ***Palazzo Doria**, formerly *Pamphylj* (Pl. II, 16), an extensive pile of buildings, and one of the most magnificent palaces in Rome; façade towards the Corso by *Valvasori*, that towards the Coll. Romano by *P. da Cortona*, and another towards the Piazza di Venezia by *P. Amati*. The handsome court, surrounded by arcades, is entered from the Corso (No. 305). To the left is the approach to the staircase ascending to the ***Galleria Doria** on the 1st floor (Tues. and Frid., 10-2; during the Easter fortnight, daily; catalogues in each room; fee 1½ fr.). In winter the galleries and other rooms are very cold. — The Doria Gallery resembles the other Roman collections in being devoted to no particular school, and in possessing examples of every different style, but the founders have perhaps shown a preference for works of the 17th century. The ante-chambers are badly lighted, so that the pictures are not seen to advantage, but most of the works here are hardly above mediocrity. The visitor should, however, note the predella of a now lost altar-piece by *Peselli* (II. Room, 29, 39), a good specimen of early-Florentine painting, and the Madonnas of *Niccolò Rondinello* (II. Room), a little known master, who has happily imitated the golden colouring of the old Venetians, and is one of *Giov. Bellini's* ablest followers.

The gems of the collection are in the three galleries. *Raphael*, the prince of cinquecentists, is represented by the portraits of two Venetian scholars, *Andrea Navagero* and *Agostino Beazzano*; but their authenticity has been questioned, and the touch is certainly somewhat different from *Raphael's* usual style, although the vigorous

tone and breadth of colouring may be accounted for by his habit of fresco painting. Johanna of Arragon is a copy only (II. Gallery, 53), and so too is *Titian's* Periods of Life (I. Gall. 20). *Porde-none's* Daughter of Herodias (II. Gall. 40), and *Lor. Lotto's* portrait of himself (II. Gall. 34), on the other hand, are admirable Venetian works. The portrait of Andrea Doria by *Sebastian del Piombo* is not Venetian in character, but is interesting from the faculty displayed by the master of imparting an air of dignity to a forbidding subject. With this work the visitor should compare the portrait of Pope Innocent X., by *Velazquez* (I. Gall. ; no number), and the coldly aristocratic portrait of Gianettino Doria by *A. Bronzino* (II. Gall. 31). The colouring of the former is strikingly rich, completely eclipsing *Piombo's* massiveness of style. The skilful manner in which the three shades of red are blended should be particularly noticed.

Garofalo (or *Ortolano*, to whom the picture has recently been ascribed), though not a master of the highest rank, has produced an admirable work in his Nativity of Christ (II. Gall. 61). The landscape-painters of the 17th cent. are also well represented. In the landscapes of *Annibale Carracci* (III. Gallery) we observe a conflict between historic and scenic imagination, and the obtrusion of the former at the expense of harmony of effect. The pictures by *Salvator Rosa* (VII. Room) are not among his best works, but *Claude Lorrain's* landscapes (III. Gall. 5, 13, 24, 34), are justly admired. His 'mill', and the landscape with the temple of Apollo, may be regarded as models of ideal landscape; the effect is produced by the skilful gradations of distance: the foreground is inclosed by trees on both sides, the middle distance gently softened off, and the background formed by mountain outlines. — The Netherlands School of the 15th and 17th cent. is scantily represented, but some of the pictures, as *Memling's* Descent from the Cross (corner-cabinet), and *Lievens' Sacrifice of Isaac* (II. Gall. 26), are worthy rivals of their Italian neighbours.

I. Room: also copying-room, to which the finest pictures in the collection are frequently brought. *Antiquities*: in the middle, a Centaur in pietra dura and rosso antico (freely restored); four Sarcophagi with (No. 1) the hunt of Meleager, (3) history of Marsyas, (6) Diana and Endymion, and (no number) procession of Bacchus. Two fine circular altars; 2. Duplicate of the so-called Diana of Gabii in the Louvre; 4. Archaic statue of the bearded Dionysus; and a number of statuettes, some of fine quality. *Pictures*: 21, 22, 24, 25, 27, 29, 30, 34. Landscapes by *G. Poussin* and his followers; on the entrance-wall, *Perino del Vaga*, Madonna; between the windows (no number), ***Velazquez*, Pope Innocent X. To the left we enter the —

II. Room. 10. *Franc. Francia*, Madonna; *17. *School of Guido Reni*, Judith with the head of Holofernes; *22. *Guercino*, John

the Baptist at the Jordan; 23. *Sassoferrato*, Mater Dolorosa; 24. *Rondinello*, Madonna; 28. *Pisanello*, Sposalizio; 29. *Pesetti*, St. Sylvester before Maximinus II.; *34. *Fra Filippo Lippi*, Annunciation; 38. *Pisanello*, Nativity of the Virgin; 39. *Peselli*, Leo IV. exorcising a dragon; *40. *Guercino*, St. Agnes at the stake; *41. *Rondinello*, Virgin and Child. Ascribed to *Holbein*, 42. Portrait of a man, with a carnation and a purse, signed 'at the age of 40, 1545'; 45. Portrait of a woman, signed 'at the age of 36, 1545'. 44. *Neapolitan School*, Mary Magdalene; 46. *Carlo Saraceni*, Juno placing the eyes of Argus in the peacock's tail; 47. *Giov. Bellini* (ascribed by Messrs. Crowe and Cavalcaselle to *Bissolo*), Presentation in the Temple; 55. *School of Mantegna*, St. Anthony; 96. (to the right of the entrance) *Marco Basaiti* (acc. to C. and C.; not *Perugino*), St. Sebastian. — In the centre, Jacob wrestling with the angel, a group in marble, of Bernini's school.

III. Room (closed).

IV. Room (very dark). To the right on entering: 33. *Caravaggio*, St. John; *17, 31. *P. Bril*, Landscapes. Over the door: 1. *Paris Bordone*, Mars, Venus, and Cupid. In the centre a recumbent river-god in pietra dura. On the left wall: 8. *Caravaggio*, Melon-seller; in two frames, antique bronzes and other objects. By the window a bronze vessel with graffiti in a peculiar style, of late origin. *19, *25. *Orizonte*, Landscapes; 32. *Scipio Pulzone* (generally called *Gaetano*), Betrothal of St. Catharine.

V. Room: 13. *G. Poussin*, Palazzo Salviati and the Janiculus (p. 327); 21. *Beccafumi*, Betrothal of St. Catharine; 22. Holy Family and St. Catharine (not by *Titian*); 25. *Guercino*, St. Joseph; 27. *Domenichino*, Landscape; 31. *Poussin*, Landscape.

VI. Room. Over the door: 5. *D. Ghirlandajo*, Holy Family; 15. *Maratta*, Madonna; *9. *Spanish School*, Portrait of a boy. To the right of the exit, 39. *School of Giov. Bellini*, Marriage of St. Catharine. — The raised passage-room contains several small landscapes by *Brueghel*, *Orizonte*, and others.

VII. Room: *Salv. Rosa*, 3. Landscape, 8. Belisarius; 19. *Mazzolini*, Massacre of the Innocents.

VIII. Room: *J. A. Borgognone* and *C. Maratta*, Capture of the town of Castro in 1649, one of the chief military exploits of Pope Innocent X.; *17. *Lod. Carracci*, St. Sebastian; opposite, 22. *Lod. Carracci*, Holy Family. In the corner a *Head of Serapis in marble.

IX. Room: Several interesting ancient portrait-heads; landscapes by *Momper*, *Tempesta*, and *Orizonte*; fruit-pieces by *Weenix*.

X. Room: Subjects from still-life.

We now enter the galleries. To the left is the —

I. GALLERY: 2. *Garofalo*, Holy Family; 3. *Ann. Carracci*, Magdalene; 8. *Quinten Massys*, Two male heads; 9. *Sassoferrato*, Holy Family; 11. *J. Miel*, Madonna; 13. *Padovanino*, Descent from the Cross; 14. *Titian*, Portrait (called Marco Polo); 15. *A. del*

Sarto (?), Holy Family; 16. *Honthorst*, Lot and his daughters; 20. *Titian*, The three Periods of Life, a copy of the original in London; *25. *Cl. Lorrain*, Landscape with the flight to Egypt; *26. *Garofalo*, Visitation; 32. *Saraceni*, Repose during the flight into Egypt; 36. *Brueghel*, Creation of the animals; 37. *Nic. Poussin*, Copy of the Aldobrandine Nuptials (p. 321); 49. *P. Veronese* (?), Angel; 50. *G. Romano*, Holy Family, after *Raphael*; 51. *Dosso Dossi*, Christ expelling the money-changers from the temple. Opposite, at the last window: 5. *School of Mantegna*, Bearing of the Cross.

II. GALLERY (chiefly remarkable for its admirable portraits): 3. *Giov. Bellini* (or *Rondinello*), Madonna; *6. *Fr. Francia*, Madonna; 11. *Pordenone*, Portrait; 13. *Mazzolini*, Christ in the Temple; 14. (not *Titian*), Portrait; 15. *Lor. Lotto*, St. Jerome; no number, *Quinten Massys*, Money-changers disputing; 19. *Rubens*, Portrait; 21. *C. Saraceni*, Repentant Magdalene; 22. *Van Dyck* (?), Portrait; 25, 32, 60, 67. *Brueghel*, The four elements; 26. *Jan Lievens*, Sacrifice of Isaac; 30. *Rembrandt*, Faun; *31. *Angelo Bronzino*, Gianettino Doria; *34. *Lor. Lotto*, Portrait of a bearded man; no number, ***Sebastian del Piombo*, Portrait of Andrea Doria; beneath, bust of Doria; *40. *Giov. Ant. Pordenone*, Daughter of Herodias with the head of the Baptist, a model of female vigour and dignity; 49. *Rubens*, Portrait of his confessor (an early work); 52. *Titian*, Portrait; 53. *After Raphael*, Johanna of Arragon, Netherlandish copy; 54. Portrait of a poet (not by *Titian*); *61. *Garofalo* (*Ortolano* ?), Nativity; 65. Old copy of *Giorgione's* Concert (in the Pitti Gallery); *69. *Correggio*, Allegorical representation of Virtue, unfinished dead-colouring in tempera; 78. *Morone*, Portrait; no number, ***Raphael*, Navagero and Beazzano; 77. *Titian* and his wife (according to C. & C., by *Sofonisba Anguissola*). — The adjacent room (generally closed) contains works by unknown masters of the 16th century. At the end of the gallery is a portrait-bust of Donna Olimpia Maidalchini-Pamfili, by *Algardi*.

III. GALLERY: 3, 8, 30, 35. *An. Carracci*, Landscapes with historical accessories; 5. *Claude Lorrain*, Landscape with Mercury's theft of the cattle; *11. *Bronzino*, Portrait of Macchiavelli; *13. *Cl. Lorrain*, Mill; *A. Carracci*, 14. Salutation, 15. Nativity; *Gerh. van der Meire*, 18. Madonna, 22. Hermit; 19. *A. Carracci*, Pietà; *24. *Cl. Lorrain*, Landscape with temple of Apollo; 25. *B. Schidone*, Angel healing St. Rochus; 26. *Mazzola*, Portrait; 27. *Giorgione* (?), Portrait; 28. *P. Veronese*, Portrait; 31. *Fra Bartolommeo* (?), Holy Family; 32. *Dosso Dossi*, Vannozza, mother of Cæsar and Lucrezia Borgia (?); 34. *Cl. Lorrain*, Landscape with Diana hunting.

Adjacent is a small CORNER-CABINET: **Memling*, Entombment; *Basaiti*, Holy Family; *Mostaert*, Girl reading; *Rubens*, Lady with a glove; *Teniers*, Rustic festival.

IV. GALLERY: Roman sculptures of little importance.

Opposite the Palazzo Doria rises the new *Palazzo Odiescalchi* (comp. p. 166), erected in 1887-88 in the Florentine style. Adjacent is the *Pal. Salviati*, built by Rinaldi and occupied from 1725 to 1800 by the French Academy of Art (p. 149).

On the S. the Corso is terminated by the **PIAZZA DI VENEZIA** (Pl. II, 16, 19; 48 ft. above the sea-level), to the right in which, at the corner, rises the *Pal. Bonaparte*, formerly *Rinuccini* (Pl. II, 16; 5), erected by De Rossi, where Madame Lætitia, mother of Napoleon I., died on 2nd Feb., 1836. The piazza is named after the imposing ***Palazzo di Venezia**, built (1455) in the Florentine style, in which the effect is produced by massiveness (p. xlix). The building was formerly attributed to *Giuliano da Majano*, but existing documents record that it was erected by *Francesco del Borgo di S. Sepolero* for Pope Paul II. (1455). To what extent *Bernardo di Lorenzo* participated in the work is uncertain. The palace was presented in 1560 by Pius IV. to the Republic of Venice, with which it subsequently came into the possession of Austria, and it is still the residence of the Austrian ambassador, as before the cession of Venetia. The large court with arcades is little more than begun; and so also is a second and smaller court to the left of the other. Many of the stones of this building are said to have been obtained from the Colosseum.

Opposite the side-entrance of the Pal. di Venezia is the **Palazzo Torlonia** (Pl. II, 19, 1), formerly *Bolognetti*, erected about 1650 by *C. Fontana*, occupying the block as far as the Piazza SS. Apostoli, and the property of the late banker Prince Torlonia, Duke of Bracciano (d. 1886). It is lavishly decorated, and contains numerous works of art, but is not shown to the public. *Permessi* for the Villa Albani (comp. p. 122) are procured on the ground-floor, to the left. — The N. corner of the palace has been removed to make way for the *Via Nazionale* (see p. 169), which is continued towards the W. by the *Corso Vittorio Emanuele* (pp. 197 *et seq.*).

From the Piazza Venezia we proceed straight through the narrow **RIPRESA DEI BARBERI**, so named because the 'Barbary' horses used in the races of the Carnival were stopped here. The first cross-street to the left leads to Trajan's Forum (p. 240).

To the right the *Via S. Marco* leads to the **PIAZZA DI SAN MARCO** (Pl. II, 16), laid out in promenades. Here, on the right, lies —

S. Marco, incorporated with the Pal. di Venezia. This church is very ancient, being supposed to date from the time of Constantine. It was re-erected in 833 by Gregory IV., and adorned in 1455 by *Giuliano da Majano* (? *Domenico di Francesco*) with a fine vestibule and probably with the coffered ceiling of the nave. The interior, dating from the 17th cent., was modernised by Card. Quirini in 1744. Festival on 25th April.

VESTIBULE. Roman and ancient Christian inscriptions, built into the walls. St. Mark in relief, above the handsome inner principal portal. The **INTERIOR** is approached by a descent of several steps. With the exception of the tribune and the beautiful ceiling, all the older parts have been

disfigured by restorations. The TRIBUNE, with its handsome pavement (opus Alexandrinum), lies a few steps higher than the rest of the church. The mosaics (in the centre Christ; left, the saints Mark, Agapetus, and Agnes; right, Felicianus and Mark escorting Gregory IV.) date from the most degraded period of this art (about 833) and have been justly described as 'utter caricatures'. In the RIGHT AISLE, 1st Chapel: altar-piece by *Palma Giovane*, the Resurrection. 3rd Chap.: Adoration of the Magi, *Maratta*. At the end; adjoining the tribune: *Pope Mark, an admirable old picture, perhaps by *Carlo Crivelli*. In the LEFT AISLE, 2nd Chap.: altar-relief, Greg. Barbadozi distributing alms, by *Ant. d'Este*. 4th Chap.: St. Michael, *Mola*.

In the Piazza, in front of the church, is the so-called *Madonna Lucrezia*, the mutilated marble bust of a colossal female statue (priestess of Isis) which carried on conversations with the Abbate Luigi near the Pal. Vidoni (p. 198; no longer extant), similar to those of Pasquin with the Marforio (comp. p. 201).

The Via di S. Marco terminates in the *Via Araceli*, which to the left leads to the Piazza Araceli (p. 209) and the Capitol, and to the right to the Piazza del Gesù (p. 197).

In the prolongation of the Ripresa de' Barberi, beyond the Via S. Marco, a whole block has recently been levelled to afford an unimpeded view of the large *Monument of Victor Emmanuel* (p. 210) and to make room for its substructure. — To the left diverges the *Via di Marforio* (Pl. II, 19, 20), leading to the Forum. The name is derived from Forum Martis (or Forum of Augustus). The famous statue of Marforio which once stood in this street, opposite the Carcer Mamertinus, is now in the Capitoline Museum (p. 216). At the beginning of this street, to the left, is the *Tomb of Caius Poblicius Bibulus* (Pl. I, 19, 2; now entirely built over), to whom the ground was granted by the Senate as a burial-place for himself and his family in recognition of his merits ('honoris virtutisque causâ', as the inscription records) towards the end of the republic. This point must therefore have lain outside the walls of Servius, which ran immediately below the Capitol, interments within their limits having been prohibited. — At the end of the Via di Marforio, to the right, are the church of *S. Giuseppe de' Falegnami* (Carcer Mamertinus; p. 237) and the *Forum Romanum* (p. 222).

To the E. of the Piazza di Venezia, at the bend of the Via Nazionale (p. 169), between the piazza in front of the SS. Apostoli (p. 165) and the Via della Pilotta (p. 152), rises the extensive *Palazzo Colonna* (Pl. II, 19), begun by Martin V., and afterwards much extended and altered. It is now in great part occupied by the French ambassador, and a number of rooms on the ground-floor, with interesting frescoes, are therefore closed. The **Galleria Colonna* on the first floor (adm., see p. 123; 1/2 fr. on leaving) is entered from the Via della Pilotta, No. 17.

I. Room. From right to left. *Tintoretto*, Narcissus; *Moroni*, Portrait; **Pietro Novelli*, Marcantonio Colonna; *Muziano* (of Brescia, an imitator of Michael Angelo), Vittoria Colonna, the friend of Michael Angelo; *Lor. Lotto*, Card. Pompeo Colonna (?), a genuine,

but much damaged work; *Giorgione* (?), *Giacomo Sciarra Colonna*; *Pourbus*, Franc. Colonna; *Tintoretto*, Angels in glory with four busts; *Morello da Brescia* (?), Portrait; *Ag. Carracci*, *Pompeo Colonna*; *Hieron. Bosc* (not *Cranach*), Temptation of St. Anthony; *Van Dyck*, *Lucrezia Colonna*; *Dom. Ghirlandajo* (?), Reconciliation between the Romans and Sabines; **Bonifacio* (not *Titian*), Madonna with saints; **Pietro Novelli*, *Isabella Colonna* and her infant son *Lorenzo Onofrio*, a good work, deserving notice apart from the rarity of the master; *Dom. Ghirlandajo* (or, according to C. & C., *Cosimo Rosselli*), Rape of the Sabine women; **Palma Vecchio*, Madonna with St. Peter and the donor, the effect of the group being tastefully enhanced by a background of bushes. In the centre a Renaissance column of red marble with scenes from a campaign in relief.

A staircase, on which is placed a cannon-ball fired into the city during the bombardment of 1849, descends to the —

II. GALLERY, with ceiling-paintings by *Coli* and *Gherardi* (Battle of Lepanto, 8th Oct. 1571, which *Marcantonio Colonna* at the head of the papal fleet assisted in gaining). On the walls mirrors painted with flowers (by *Mario de' Fiori*) and genii (by *C. Maratta*). The statues here are of no great value, most of them modernised. Reliefs built into the wall under the windows (left): Head of Pallas; Wounded man, borne away by his friends; *Selene* in the chariot (archaistic style). Right wall: **Rubens*, Assumption of the Virgin; **Suslermans*, Fed. Colonna; *Crist. Allori*, Christ in Hades; *Salviati*, Adam and Eve; **Van Dyck*, Don Carlo Colonna, equestrian portrait; *Guercino*, Martyrdom of St. Emmerentia; *S. Gaetano*, Family group of the *Colonnas* (1581). Left wall: *Tintoretto*, Double portrait; *N. Poussin*, Pastoral scene; *Niccolò Alunno*, Madonna rescuing a child from a demon.

III. Room. The great attraction here consists of eleven water-colour **Landscapes* by *Gaspard Poussin*, which are among his finest works and the most valuable in this gallery. Some of them are unfavourably hung, but every one of them will repay careful inspection. They represent a mountain-road close to a profound ravine, a bleak plain lashed by a storm, a calm lake enclosed by majestic trees, a riven rocky landscape with waterfall, and various other subjects. Notwithstanding the simplicity and uniformity of the materials used, these works will not fail to interest by the excellence of the composition and drawing. — Window-wall: *Berchem*, Huntsman; *Claude Lorrain* (?), Landscape; *Wouverman* (?), Chase and cavalry-skirmish; *N. Poussin*, Metamorphosis of *Daphne*; a large cabinet with ivory carving by *Franc.* and *Dom. Steinhard* (in the centre, the Last Judgment, after Michael Angelo). Opposite (exit-wall): *Canaletto*, Architectural piece; *Crescenzo d'Onofrio*, Landscape.

IV. Room. Ceiling-painting by *Battoni* and *Luti* (in honour of Martin V.). Entrance-wall: *P. Veronese*, Portrait of a man; *Holbein* (?), Lor. Colonna; over the door, *Bordone* (not *Bonifacio*),

Holy Family. Right wall: *Albano*, Rape of Europa; **Spagna*, St. Jerome; *Domenico Puligo*, Madonna; *Ann. Carracci*, Bean-eater; *Paris Bordone*, Madonna with saints. Exit-wall: *Giov. Bellini*, St. Bernhard; *Girolamo Trevisani*, Poggio Bracciolini; *Bronzino*, Holy Family; **Titian*, Onuphrius Panvinus, an admirable study of the master's best period (name arbitrary). Window-wall: *F. Mola*, Cain and Abel; *Sassoferrato*, Madonna; *Guido Reni*, St. Agnes

V. Room. Throne-room, with handsome old carpet.

VI. Room. Entrance-wall: *Parmeggianino*, Holy Family; *Innoc. da Imola*, Same subject; two **Madonnas* surrounded by smaller circular pictures, erroneously attributed to *Van Eyck*, but by a later Dutch master, interesting on account of their elaborate miniature-like execution. Right wall: *Fr. Albano*, Two landscapes; *Gentile da Fabriano* (or, according to C. & C., *Stefano da Zevio*), Madonna; **Giulio Romano*, Madonna (comp. p. LVII); *Jacopo d'Avanzo*, Crucifixion; *Giov. Santi* (father of Raphael), Portrait; *Luini*, Madonna (much damaged). Exit-wall: *Fr. Fil. Lippi* (?), Madonna; *Luca Longhi*, Same subject; *S. Botticelli*, Same subject.

The beautiful *Garden*, on the E. side of the *Via della Pilotta* (entered by *Via del Quirinale* 12; comp. p. 175), contains several antiquities, fragments of a colossal architrave, said to have belonged to Aurelian's temple of the sun, and considerable portions of the brick-walls of the *Thermae of Constantine* (?), which formerly extended over the entire *Piazza di Monte Cavallo* (p. 173). The terrace commands a good survey of the city.

On the N. the *Pal. Colonna* is adjoined by the church and convent of the SS. Apostoli, the latter now containing the offices of the *Ministry of War*.

The church of ***SS. Apostoli** (Pl. II, 19), facing the piazza of the same name, was founded by Pelagius I. in honour of SS. Philip and James, re-erected under Clement XI. in 1702, and restored after a fire in 1871. The vestibule by *Baccio Pintelli* (?), the only part of the building earlier than 1702, contains (on the left) the monument of the engraver *Giov. Volpato* by *Canova* (1807), and (on the right) an ancient **Eagle* with chaplet of oak-leaves, from *Trajan's Forum*. Chief festival on 1st May.

INTERIOR. Right Aisle, 3rd Chapel: St. Anthony by *Luti*. In the Left Aisle, 2nd Chapel: Descent from the Cross by *Franc. Manno*. At the end, to the left, over the entrance into the sacristy: **Monument of Clement XIV.* by *Canova*, on the pedestal *Charity and Temperance*. In the tribune, with altar-piece by *Muratori* (said to be the largest in Rome), are the monuments erected by Sixtus IV. to his two nephews, the Cardinals *Riario*, that of *Pietro* (d. 1474) on the left, and that of *Alexander* behind the altar, and partly concealed by the organ. On the vaulted ceiling of the tribune, *Fall of the Angels*, a fresco by *Giov. Odassi*, in the rococo style, but of striking effect. The older church was decorated by *Melozzo da Forlì*, a fine fragment of whose frescoes is now in the *Quirinal* (p. 175), and others are in the sacristy of St. Peter's (p. 284).

The passage in the monastery adjacent to the church contains a monument to *Michael Angelo*, who lived and died in the parish of SS. Apostoli, and the tomb of *Card. Bessarion* (d. 1472).

Opposite the front of the SS. Apostoli is the old *Pal. Odescalchi*, built by Bernini.

II. The Eastern Quarter.

Quirinal. Viminal. Esquiline.

On the Quirinal at a very early period lay a Sabine town, the union of which with that on the Palatine formed the city of Rome. The Servian Wall (p. 130) ran from the Capitol along the N. W. side of the Quirinal, and then to the E. behind the Baths of Diocletian and the church of S. Maria Maggiore, enclosing the *Quirinal*, *Viminal*, and a part of the *Esquiline*. According to the new division of the city by Augustus, this quarter comprised two districts, the *Alta Semita* (Quirinal) and the *Æsquiliae* (Esquiline). The building of Aurelian's wall shows that this quarter was afterwards extended. According to the mediæval division these districts formed a single region only, named the *Rione Monti*, the most spacious of the fourteen quarters in the city, as it extended from the Porta Pia to the now closed Porta Metrovia, below the Lateran, and to the Forum Romanum. Its inhabitants, called *Montigiani*, differ, like those of Trastevere, in some of their characteristics from the other Romans. Pius IV. constructed the long main street from the Piazza del Quirinale to the Porta Pia (*Via del Quirinale* and *Via Venti Settembre*). The second main street, intersecting this one and leading from the Pincio to S. Maria Maggiore (*Via Sistina* and *Via Quattro Fontane*), was made by Sixtus V., who also provided the hill with water. With the exception of these inhabited quarters almost the entire E. part of Rome was until lately occupied by vineyards and gardens. But the selection of the city as the capital of the kingdom of Italy gave a strong impulse to its extension, and a new quarter has sprung up here near the station, which already rivals the older districts in business activity and prosperity. The main artery of traffic here is the *Via Nazionale*, which runs from the Piazza delle Terme along the ridge of the Quirinal to the Piazza Venezia, a distance of nearly a mile. Beyond the Piazza Venezia it is continued by the Corso Vittorio Emanuele (p. 197).

On the E. side of the PIAZZA DELLE TERME (Pl. I, 25) is the handsome **Railway Station**, constructed by Mirière and Bianchi in 1872. Opposite the arrival-platform begins the wide *Via Cavour*, leading to the Piazza dell' Esquilino and the Forum (see p. 176). The main front of the station faces the Thermæ of Diocletian. The open space here, now called the 'Piazza del Cinque Cento', is embellished with a *Monument* to the 500 Italian soldiers who were surprised and slain at Dogali by the Abyssinians in 1886. A small obelisk found at the church of S. Maria sopra Minerva in 1882 has been incorporated in this monument. Adjacent is a copious fountain, fed by the *Acqua Marcia*, which has been recently restored. In the evening the piazza is lighted by electricity.

The **Thermæ of Diocletian** (Pl. I, 25), which give name to the piazza, were the most extensive thermæ in Rome, and were constructed by Maximian and Diocletian at the beginning of the 4th century. The principal building was enclosed by a wall, the outline of the round central portion ('exedra') of which, is preserved by the new houses at the beginning of the Via Nazionale (p. 169). The corners of the main building were occupied by two circular structures, one of which is now the church of S. Bernardo (p. 169), and the other belongs to a prison. The circumference of the baths is said to have been about 2000 yds., or half as much as that of the Baths of Caracalla (p. 255), and the number of daily bathers 3000. The front faced the E., and the circular part, mentioned above, was at the back. Tradition ascribes the execution of the work to condemned Christians, in memory of whom a church, no longer existing, was erected here as early as the 5th century.

Pius IV. entrusted *Michael Angelo* with the task of converting part of the Thermæ into a *Carthusian Convent*. A large vaulted hall was accordingly converted into the church of ***S. Maria degli Angeli** (Pl. I, 25), which was consecrated in 1561. The present transept was then the nave, the principal portal was in the narrow end on the right, and the high-altar placed on the left. In 1749 *Vanvitelli* entirely disfigured the church by converting the nave into the transept, blocking up the portal, and other injudicious alterations.

A small **ROTUNDA** is first entered. The first tomb on the right is that of the painter Carlo Maratta (d. 1713). The first tomb on the left is that of *Salvator Rosa* (d. 1673). In the Chapel, Christ appearing to Mary Magdalene, an altar-piece by *Arrigo Fiamingo*.

We next enter the great **TRANSEPT**. The niche on the right in the passage contains a colossal statue of St. Bruno, by *Houdon*; in the chapel on the left, the *Delivery of the Keys, an altar-piece by *Muziano*. The transept (formerly the nave) is 100 yds. long, 29 yds. wide, and 90 ft. high. Of the 16 columns, each 40 ft. in height, eight are antique, of oriental granite, which were barbarously painted by *Vanvitelli*, and the others were disengaged from the brick wall when the church was restored. — Most of the large pictures here and in the tribune were brought from St. Peter's, where they were replaced by copies in mosaic. In the right half (on the pavement the meridian of Rome, laid down in 1703): on the right, Crucifixion of St. Peter by *Ricciolini*; Fall of Simon Magus, after *F. Vanni* (original in St. Peter's); on the left, *St. Jerome among the hermits, *Muziano* (landscape by *Briù*); Miracles of St. Peter, *Baglioni*. At the narrow end: chapel of B. Niccolò Albergati. In the left half: on the left, Mass of St. Basil with the Emperor Valens, *Subleyras*; Fall of Simon Magus, *Pomp. Battoni*; on the right, Immaculate Conception, *P. Bianchi*; Resuscitation of Tabitha, *P. Costanzi*. At the narrow end: chapel of St. Bruno.

In the **TRIBUNE** (one of the monks acts as guide here, ½ fr.); right, *Romanelli*, Mary's first visit to the Temple; **Domenichino*, Martyrdom of St. Sebastian (fresco); left, *Pomarancio*, Death of Ananias and Sapphira; *Maratta*, Baptism of Christ. The choir contains two monuments (l. Pius IV., r. Ant. Serbelloni), designed by *Michael Angelo*.

The remaining buildings are still partly occupied by the Carthusians and partly by various charitable and educational institutions. A good view is afforded by the roof of the church, to which visitors may ascend with the permission of the Prior.

Passing through the arch with a cross, to the right of the church, and then through the door to the left in the court, with the inscription 'Ospedale Margherita per i Poveri Ciechi', we reach the new *MUSEO DELLE TERME, which occupies several small rooms detached from the convent-court and part of the cloisters (adm., see p. 124).

The following are among the chief treasures of this collection. *Female figure, a replica of the Barberini Juno (p. 309), found in 1878 on the Palatine (admirable in the treatment of the drapery, but inferior in general effect to other reproductions of the same type). — *Youthful Faun, with deer-skin, from Hadrian's Villa. — *Nude bronze figure of a youth leaning on a staff, with portrait-features pointing to the Hellenic epoch (found, like the following, in building the new theatre in the Via Nazionale). — **Bronze figure of a pugilist, evidently represented as conversing with a comrade or an umpire. The realism of this repulsive figure, extending to the marks of injury received in fighting, is masterly in execution. — *Bacchus, a youthful figure in bronze, with inlaid silver ornamentation, found in the Tiber in sinking the foundations of the Ponte Garibaldi. — Sleeping Hermaphrodite, found in building the Teatro Costanzi. — *Mural paintings and stucco ornamentation, from the house of a Roman citizen, found in the Tiber works at the garden of the Villa Farnesina (p. 323).

The central court, laid out as a garden, contains the larger sculptures and architectural fragments. The large cypresses here, said to have been planted by Michael Angelo, were blown down in 1888.

Adjoining the Piazza delle Terme is the *Piazza S. Bernardo*, with the FONTANONE DELL' ACQUA FELICE (Pl. I, 22), erected by *Domenico Fontana* under Sixtus V. The badly-executed copy of the Moses of Michael Angelo is by *Prospero Bresciano*, who is said to have died of vexation on account of his failure; at the sides Aaron and Gideon by *Giov. Batt. della Porta* and *Flam. Vacca*; in front four modern lions (originals in the Vatican). The *Acqua Felice* was conducted hither in 1583 from Colonna in the Alban Mts., a distance of 13 M., by order of Sixtus V. (Felice Peretti).

The VIA VENTI SETTEMBRE, the name of which refers to the entry of the Italians in 1870, unites the Porta Pia (p. 341) with the Quirinal, ending at the four fountains of the Via Quattro Fontane (p. 170). In this street, opposite the *Acqua Felice*, stands the church of *S. MARIA DELLA VITTORIA* (Pl. I, 23), so called from an image of the Virgin which is said to have been instrumental in gaining the victory for the imperial troops at the battle of the 'White Hill' near Prague, afterwards deposited here, but burned in 1833. The church, with the exception of the façade, was erected by *C. Maderna*.

In the 2nd Chapel on the right, an altar-piece (Mary giving the Infant Christ to St. Francis) and frescoes by *Domenichino*. In the left transept the notorious group of St. Theresa by *Bernini* (covered; 5 s.). In the 3rd Chapel on the left, the Trinity by *Guercino*, and a Crucifixion attributed to *Guido Reni*.

In the Via Venti Settembre, to the right, nearer the Porta Pia, is the *Finance Office* (Pl. I, 26), built by Canevari.

A little to the S.W. of S. Maria della Vittoria, also in the Piazza S. Bernardo, is the ancient church of S. SUSANNA (Pl. I, 22, 23), altered to its present form in 1600 by *C. Maderna*. Paintings on the lateral walls from the history of Susanna, by *Baldassare Croce*; those of the tribune by *Cesare Nebbia*. — Opposite, and standing a little

back, is the church of S. BERNARDO (Pl. I, 22), a circular edifice, originally one of the corners of the Thermæ of Diocletian (p. 167), and converted into a church at the end of the 16th century. The vaulting is ancient, but like the Pantheon was once open. — The *Via Torino* leads hence to the *Via Nazionale* (see below).

On the E. side of the station, opposite the departure-platform, the largest and best-preserved part of the **Wall of Servius** (Pl. I, 25, 28), which protected the city on this undefended side, has been exposed to view. The wall, which is supported by a strong embankment, with its broad moat and numerous towers, might until recently be traced to the arch of Gallienus (p. 179); but the only parts now extant are a fragment in the Piazza Manfredo Fanti and another by the so-called Auditorium of Mæcenās on the *Via Merulana* (see p. 181).

Towards the N.E., passing the new buildings now springing up in this quarter, we reach (10 min.) the **Campo Militare** (Pl. I, 29, 32), the camp of the Prætorians of imperial Rome, originally established by Tiberius, but destroyed by Constantine so far as it lay without the town-wall, from which it projects in a quadrangular form. At the end to the left, and on the side, traces of gates are still distinguished; the wall was skirted by a passage, under which are several small chambers. The Campo, which has been enclosed by a wall, is again devoted to military purposes.

Opposite the entrance of the church of S. Maria degli Angeli (p. 167), and through the middle of the circular wall of the Thermæ, runs the broad **Via Nazionale** (Pl. I, 22; II, 19, 16), now one of the busiest streets of the city, and during the season as thronged with passengers and vehicles as the Corso itself (Tramway, No. 1, see p. 3 of Appendix). On the right the *Via Torino* leads to S. *Bernardo* (see above). In the *Via Nazionale* stands the *Hôtel Quirinal* and, farther on, the new American Episcopal Church of St. Paul, a Gothic structure by *Street*, with chimes (p. 119). The most important cross-street is the *Via Agostino Depretis* (*Via Quattro Fontane*), which leads on the right to the Pal. Barberini (p. 170) and on the left to S. Maria Maggiore (p. 176).

To the left in the *Via Nazionale* (No. 154) is the *Galleria Tenerani* (Wed., 1-4; at other times, fee), a complete collection of the original models of the sculptor P. Tenerani (d. 1869). — To the right is the small church of S. Vitale, on a site considerably lower than the new street-level; and farther on the handsome *Palazzo delle Belle Arti*, built as an exhibition-building in 1880-83 by Piacentini, and the *Palazzo Hüffer*. Farther on, to the left, are the new building of the *Banca Romana* and the gardens of the *Villa Aldobrandini*.

At the beginning of the *Via del Quirinale* (p. 173), the *Via Nazionale* expands into a triangular piazza, in the middle of which, within a railing, is a fragment of the *Servian Wall* (see above), excavated in 1875. Another fragment, with a well-preserved gateway, has been built into the Pal. Antonelli, on the right (No. 158; staircase on the right of the court). To the S., behind the 17th cent. church of S. Caterina di Siena (Pl. II, 19, 14), rises the *Torre delle Milizie* (Pl. II, 19, 6), erected about 1200 by the sons of Petrus

Alexius, commonly called *Torre di Nerone*, because Nero is said to have witnessed the conflagration of Rome from this point (no admission). — To the right, at the corner of the *Via Magnanapoli*, is the church of *SS. Domenico e Sisto* (Pl. II, 19, 15), with its lofty flight of steps, built by Vincenzo della Greca about 1640.

The *Via Magnanapoli* is prolonged by the *Via S. Lorenzo* in Panisperna, leading to *S. Maria Maggiore* (comp. p. 176). At the beginning of this street, to the left, is the church of *S. Agata* in *Suburra* (Pl. II, 22), dating from the 5th cent., but restored in 1633, and now possessing 12 granite columns only of the original edifice. It belongs to the adjacent seminary for Irish priests. The left aisle contains the *Monument of Daniel O'Connell* (d. 1847; who bequeathed his heart to this church), with a relief by Benzoni, erected in 1856. To the right of the entrance is the tomb of *John Lascaris*, author of the first modern Greek grammar (d. 1535).

From the above-mentioned triangular space the *Via Nazionale* descends the slopes of the *Quirinal* (95 ft.) in a wide curve. The flight of steps on the left descends to *Trajan's Forum* (p. 240). Farther on, to the left, is a mediæval tower of the *Colonna*, with immured fragments from the *Forum of Trajan*. At the next corner, to the left, stands a new *Waldensian Church*, and to the right the new *Teatro Drammatico*. We then skirt the S. façade of the *Pal. Colonna* (p. 163) and proceed between the *Via della Pilotta* (p. 152) and the *Piazza SS. Apostoli* (p. 163) to the *Piazza di Venezia* (p. 162).

The *VIA AGOSTINO DEPRETIS* (Pl. I, 22), mentioned at p. 169, hitherto named the *Via Quattro Fontane*, forms a continuation of the *Via Sistina* (p. 150), like which it owes its construction to *Sixtus V.* Turning from the *Via Nazionale* to the right into the N. W. part of this street (which runs to the S. E. to *S. Maria Maggiore*; see p. 176), we soon reach (5 min.) the four fountains, from which it took its former name, at the point of intersection with the *Via del Quirinale* (p. 173) and the *Via Venti Settembre* (p. 168). To the left is the small church of *S. Carlo* or *S. Carlino* (Pl. I, 22, 2), built by *Borromini* in the most extravagantly 'baroque' style; to the right, in the *Via Venti Settembre*, is the *Pal. Albani*, originally built by *Dom. Fontana*, and afterwards inhabited by *Cardinal Al. Albani*, the friend of *Winckelmann*. [Hence to the *Porta Pia* (p. 341) we take about 20 min. more, passing the new *War Office*, the churches mentioned at pp. 167, 168, and the *Acqua Felice* (p. 163).]

The continuation of the street, leading to the *Piazza Barberini*, has retained the name of *VIA QUATTRO FONTANE* (Pl. I, 22). At the end of it, to the right, at the corner of the *Piazza Barberini*, lies the handsome —

**Palazzo Barberini* (Pl. I, 22), begun by *Maderna* under *Urban VIII.*, and completed by *Bernini* (p. lix). The court, laid out as a garden, contains a marble statue of *Thorvaldsen*, by *E. Wolff*, after a work by the master himself, erected here, near his studio, by his pupils and friends. — The principal staircase is to the left under

the arcades; built into it is a Greek *Tomb-relief; on the landing of the first floor, a *Lion in high-relief, from Tivoli. A number of mediocre ancient sculptures are distributed throughout the courts and other parts of the building. — At the right end of the arcades a winding staircase (13 steps, then to the right) ascends to the **Galleria Barberini** (admission, see p. 124; catalogues for the use of visitors). This is the gallery of disappointment. In *Raphael's* Fornarina we expect to find a beauty radiant with the charms of youth, whereas her features present an almost haggard appearance, to which the ill-preserved condition of the picture further contributes. In *Guido Reni's* Beatrice Cenci we hope to see a countenance Judith-like, and characterised by stern resolve, instead of which we encounter a pale, delicate face. Lastly, when we inspect *Dürer's* Christ among the Scribes, we are almost tempted to doubt its authenticity; the numerous heads are ungroupped, some of them resemble caricatures, and it is in the execution of the hands alone that the workmanship of the great master is apparent.

I. Room: 16. *Pomarancio*, Magdalene; 20. *Parmeggianino*, Betrothal of St. Catharine. — II. Room: 33. *After Raphael*, Madonna; 36. *Innocenzo da Imola*, Madonna; 38. *Titian*, Cardinal Bembo, painted about 1540 but retouched; 53. *Francia* (?), Madonna with St. Jerome; 59. *Sodoma*, Madonna; 64. *Giov. Bellini* (?), Madonna; 68. *Mengs*, Portrait of his daughter; 69. *Pontorno* (after Morelli), Pygmalion; 72. *Francia*, Madonna; 73. *Masaccio* (?), Portrait of himself. — III. Room: *76. *Titian* (? C. & C. ascribe it to *Palma Vecchio*), 'La Schiava', female portrait; 79. *Cl. Lorrain*, Castel Gandolfo; 81. *Bronzino*, Portrait; *82. *Dürer*, Christ among the doctors, painted at Venice in five days in 1506 ('opus quinque dierum'); *86. *Raphael*, Portrait of the so-called Fornarina, so frequently copied, unfortunately marred by restoration; 85. *S. Gaetano*, Lucrezia Cenci, stepmother of Beatrice; 87. *Spanish School*, Anna Colonna; *88. *Guido Reni*, Beatrice Cenci (p. 202); 90. *N. Poussin*, Death of Germanicus; 92. *Claude Lorrain*, Wharf; 94. *And. del Sarto*, Holy Family.

Ascending the spiral staircase 60 steps farther, we turn to the right into the *Principal Saloon*, with frescoes by *Pietro da Cortona*. A small door to the right leads hence into the *Sculpture Saloon*, containing, among a number of ancient and modern works, an admirable *Statue by a Greek master, near the wall opposite the entrance, representing a woman with one arm extended. It was formerly supposed to be a nymph, a Dido, or a Laodamia; but it more probably represents a suppliant for protection at an altar, grasping a twig (now broken off) in the right hand.

On the highest floor is the *Biblioteca Barberina* (Thurs. 9-2) which contains 7000 MSS., including those of numerous Greek and Latin authors, of Dante, etc., a number of ancient bronze cistas from Palestrina, miniatures by Giulio Clovio (a pupil of Raphael), etc. Librarian, the *Abbé Pieralisi*.

The Via Quattro Fontane, like the *Via Sistina* (p. 150) and the *Via del Tritone* (p. 154), ends in the PIAZZA BARBERINI (Pl. I, 19, 22). In the centre the ***Fontana del Tritone**, by Bernini, a Triton blowing on a conch. Ascending the Piazza, we come to the *Via di S. Nicola di Tolentino*, with several new hotels, which leads to the

picture painted by the Devil in
 this church

church of that name, and then, under the name of Via S. Susanna, turns to the right to the Fontana dell' Acqua Felice and the Piazza delle Terme (p. 166). — The second street to the left, on the N. side of the Piazza Barberini, is the *Via di S. Basilio*, which leads to the Villa Ludovisi (see below), and through the Porta Salara to the Villa Albani (p. 338; 1 M.).

To the left of the Piazza Barberini rises the Piazza de' Cappuccini, in which is situated the church of **S. Maria della Concezione** (Pl. I, 23), or *dei Cappuccini*, founded in 1624 by Card. Barberini.

In the INTERIOR, over the door, a copy of *Giotto's* Navicella (in the vestibule of St. Peter's, p. 281), by *Beretta*. 1st Chapel on the right: °*St. Michael*, a famous work by *Guido Reni*; in the 3rd, remains of frescoes by *Domenichino*. Over the high-altar a copy of an *Ascension* by *Lanfranco*, now destroyed. Beneath a stone in front of the steps to the choir lies the founder of the church, Card. Barberini ('hic jacet pulvis cinis et nihil'); on the left the tomb of *Alex. Sobiesky* (d. 1714), son of John III. of Poland. Last chapel on the left: Altar-piece by *Sacchi*; in the first, one by *Pietro da Cortona*.

Beneath the church are four BURIAL VAULTS (shown by one of the monks), decorated in a ghastly manner with the bones of about 4000 departed Capuchins. Each vault contains a tomb with earth from Jerusalem. In the case of a new interment, the bones which have been longest undisturbed are used in the manner indicated. The vaults are illuminated on 2nd Nov. (All Souls Day), after Ave Maria.

A little to the N.W. is *S. Isidoro* (Pl. I, 20), founded in 1622.

Behind, in the Corso di Porta Princiana is the *Villa Malta*, occupied by Lewis I. of Bavaria, before his accession. Opposite is the entrance to the Aurora Casino of the old Villa Ludovisi (see below). — The *Porta Pinciana* (Pl. I, 21, 24), after having been walled up for centuries, was re-opened in 1888 to facilitate communication with the new quarter outside the Porta Salara.

Leaving the Piazza Barberini, and following the VIA DI S. BASILIO (see above), we reach (5 min.) a corner from which the street to the right leads to the gate, and that to the left to the entrance of the former —

Villa Ludovisi (Pl. I, 23), the gardens of which have fallen a prey to the extension of the town. The villa was erected in the first half of the 17th cent. by *Card. Ludovisi*, nephew of Gregory XV., and was afterwards inherited by the *Princes of Piombino*, who sold the greater part of it in 1885. The magnificent **Collection of Ancient Sculptures* contained in one of the Casinos, is to be transferred to a new building erected for it close by. The two Casinos, however, have been retained, though that with the gallery of statues will only remain until a museum has been prepared to shelter its contents (the latter may therefore be temporarily inaccessible). From the gateway (1/2 fr. on leaving) we proceed to the right to the —

I. CASINO, containing a *Collection of valuable ancient sculptures.

Vestibule: 1, 3, 7, 8. Hermæ; by the entrance-wall, to the right, 20. Head of Juno, very ancient; 18. Candelabrum in the form of a twisted

tree; 15. Sitting statue of a Roman, by *Zenon*. To the left of the entrance: 25. Female draped figure; 31. Tragic mask, mouth of a fountain in rosso antico. — SALOON: *28. Group of a barbarian, who, having killed his wife, plunges the sword into his own breast (right arm improperly restored), a work of the Pergamenean school (the 'Dying Gaul' in the Capitol also belongs to this group; see *Intro.* p. xxxiii). To the right of the entrance: *55. Warrior reposing (Mars?), probably destined originally to adorn the paproch to a door; 51. Statue of Athene from Antioch; 47. Cast of the statue of Æschines at Naples; 46. Bust, name unknown; above it, *45. Head of a Medusa, of the noblest type; 43. Rape of Proserpine, by *Bernini*; above it, 42. Judgment of Paris, a relief, the right side restored according to Raphael's design; **41. The so-called 'Juno Ludovisi', the most celebrated, and one of the most beautiful heads of Juno; 30. Mercury, in the same position as the so-called Germanicus in Paris. Left of the entrance: *1. Mars reposing, of the school of Lysippus: *7. Theseus and Æthra (or Telemachus and Penelope commonly called Orestes and Electra), by *Menelaos*, pupil of Stephanus (p. xxxvi); *9. Youthful Satyr; 14. Dionysus with a satyr; 15. Head of Juno; 21. Bronze head of Marcus Aurelius.

The CASINO DELL' AURORA, to the W., which on the ground-floor contains a vigorous ceiling-fresco of *Aurora by *Guercino*, and on the first floor a *Fama by the same, is seldom open to visitors. The entrance is in the Corso di Porta Pinciana, opposite the Villa Malta (p. 172).

The prolongations of the Via di S. Basilio (p. 172) are the VIA SALLUSTIANA and the VIA DI PORTA SALARA, which lead in 8 min. from the Villa Ludovisi to the Porta Salara (p. 338). Here in ancient times lay the magnificent *Gardens of Sallust*, the historian, which afterwards became the property of the emperors.

We now enter the VIA DEL QUIRINALE at the four fountains of the Via Agostino Depretis (p. 170). To the right are buildings connected with the royal palace; to the left the church of *S. Andrea*, by *Bernini*. In a few minutes more we reach the *PIAZZA DEL QUIRINALE (Pl. II, 19), recently extended and levelled, in the centre of which is a *Fountain* with an antique granite basin. Adjacent to the fountain are an *Obelisk*, 48 ft. high, which once stood in front of the mausoleum of Augustus and was erected here in 1787, and the two colossal marble ***Horse Tamers* from which the piazza formerly derived its name (Piazza di Monte Cavallo). These admirable groups once stood in front, probably at the entrance, of the Thermæ of Constantine (p. 174), which were situated here. They are frequently mentioned in history, and have never been buried nor concealed from view. The inscriptions on the pedestals, *Opus Phidiae* and *Opus Praxitelis* are apocryphal, the groups being works of the imperial age (prob. 4th cent.), copied from originals of the school of Lysippus. In the middle ages these were supposed to be the names of two philosophers, who, having divined the thoughts of Tiberius, were honoured by the erection of these monuments in recognition of their wisdom.

Opposite the Royal Palace, on the left, is the *Pal. of the Consulta*, erected under Clement XII. by Del Fuga, formerly the seat of a tribunal of that name, charged with the internal administration of the Papal States. It is now occupied by the offices of the *Minister*

of the *Exterior*. On the S.W. side of the piazza, behind the obelisk, stands the *Palazzo della Dataria*, erected by Paul V. Farther on, to the left, is the Pal. Rospigliosi (see below).

The piazza commands a fine *VIEW of the town, with the dome of St. Peter's in the background. During the excavations preparatory to the construction of the steps and the road extensive fragments of the walls of the *Thermæ* of Constantine were found, and below them older walls of solid blocks, belonging apparently to the walls of Servius Tullius. The new *Via della Dataria* descends straight to the Corso, and the first transverse street to the right, the *Via di S. Vincenzo*, leads to the Fontana Trevi (p. 151).

The **Palazzo Regio**, formerly *Apostolico al Quirinale* (Pl. I, 19), begun in 1574 under Gregory XIII. by *Flaminio Ponzio*, continued under Sixtus V. and Clement VIII. by *Fontana*, and completed under Paul V. by *Maderna*, has frequently been occupied by the popes in summer on account of its lofty and healthful situation. The conclaves of the cardinals were at one time held here, and the name of the newly-elected pope was proclaimed from the balcony of the façade towards Monte Cavallo. Pius VII. died here in 1823. After 20th Sept. 1870, the palace was taken possession of by the Italian government, and being now the residence of the king, the greater part is seldom shown to the public.

From the principal entrance we pass between the sentinels, and ascend the broad staircase to the left at the end of the vestibule. At the top of the staircase we write our names in a book, and obtain an escort (1 fr.). Adjacent to the SALA REGIA, with frescoes by *Lanfranco* and *Saraceni*, is the CAPELLA PAOLINA, erected by *Carlo Maderna*, and decorated with gilded stucco-work and copies in grisaille of Raphael's Apostles in SS. Vincenzo ed Anastasio alle Tre Fontane (p. 354) and with tapestry of the 18th century. To the right lies a suite of DRAWING and RECEPTION ROOMS, newly fitted up, and adorned with pictures and tapestry, chiefly modern. The reception-room of the ambassadors, beyond the throne-room, contains a portrait of the Emperor William I., by *Karl Arnold*, presented in 1874. In the 10th room, mosaics on the floor from Hadrian's villa. In the 14th, a *Ceiling-painting by *F. Overbeck* (1859), to commemorate the flight of Pius IX. in 1848: Christ eluding the Jews who endeavoured to cast him over a precipice (Luke iv. 28, 29). In the 15th, views from the Vatican. Towards the garden are the ROYAL GUEST-CHAMBERS, once occupied by Napoleon I., Francis I. of Austria, and in 1861 by Francis II. of Naples. The frieze of the former audience-chamber here is a cast of *Thorvaldsen's* *Triumphal Procession of Alex. the Great, ordered by Napoleon I. for this saloon. After 1815 the original became the property of the Marchese Sommariva, and is now in the Villa Carlotta near Cadenabbia on the Lake of Como, formerly his residence. In the small Chapel dell' Annunziata an *Annunciation, an altar-piece by *Guido Reni*. — In the COURT a staircase ascends to the right under the arcades; on the landing, *Christ surrounded by angels, a fresco by *Melozzo da Forlì* (p. 89), transferred thither in 1711 from SS. Apostoli.

The Garden, which is rarely shown, was tastefully laid out by U. Maderna. It contains rare plants and several antiques, and commands a fine view. — [Omnibus from the Piazza del Quirinale to S. Agnese Fuori, see p. 2 of the Appx.]

The ***Palazzo Rospigliosi** (Pl. II, 19), erected in 1603 by *Card. Scipio Borghese*, nephew of Paul V., on the ruins of the *Thermæ*

of Constantine, afterwards became the property of the princes Rospigliosi, relations of Clement IX., of Pistoja. The palace contains frescoes from the Baths of Constantine, a beautiful *Cl. Lorrain* (Temple of Venus), and other treasures of art, but is only shown by special permission of the prince. The S.E. corner of the palace has been removed to make way for the new *Via Nazionale* (p. 169). Admission to the *Casino*, see p. 124 ($\frac{1}{2}$ fr.).

We enter the court by a gate in the *Via del Quirinale* and then ascend the steps to the left. Several small statues in the GARDEN.

Along the external wall of the *Casino* are placed ancient sarcophagus-reliefs (Hunt of Meleager, Rape of Proserpine, etc.). By the door to the right we enter the —

PRINCIPAL HALL. ** Ceiling-painting by *Guido Reni*: Aurora strewing flowers before the chariot of the god of the sun, who is surrounded by dancing Horæ, the master's finest work. The colouring deserves special notice. The strongest light is thrown upon the figure of Apollo, whose hair and flesh are of golden hue. Of a corresponding tint are the yellowish-red robes of the nymphs nearest to Apollo. The colours are then gradually shaded off from blue to white, and from green to white, while the dun-coloured horses accord with the clouds in the background (p. lix). Opposite the entrance is a mirror, in which the painting may be conveniently inspected. — On the frieze, landscapes by *Paul Bril*, and on the ends of the sides, Triumph of Fauna and Cupid (from Petrarch), by *Tempesta*. Right wall: Statue of Athene Tritogeneia with a Triton; **Van Dyck*, Portrait.

ROOM ON THE RIGHT. In the centre a bronze steed from the Thermæ of Constantine. Opposite the entrance, *Domenichino*, Fall of man. Left wall: **Lorenzo Lotto*, Vanità. Right wall: **Dutch School*, Portrait; *Domenichino*, Venus and Cupid; **Luca Signorelli*, Holy Family. Entrance-wall: *L. Carracci* (?), Samson. — ROOM TO THE LEFT: entrance-wall, over the door, *Passignano*, Pietà; *Guido Reni*, Andromeda; Portrait of *N. Poussin* (at the age of 56), a copy of the original in the Louvre. Left wall: *Dan. da Volterra*, Bearing of the Cross. In the corner a bronze bust of Sept. Severus. On these two walls and the following: Christ and the Apostles, thirteen pictures, attributed to *Rubens*, probably only partly by him; *Domenichino*, Triumph of David.

No. 12, opposite the Pal. Rospigliosi, is the entrance to the garden of the Pal. Colonna (p. 163). In the *Via del Quirinale*, farther on, to the right, is the church of —

S. Silvestro al Quirinale (Pl. II, 19), erected at the close of the 16th cent., and with the adjacent monastery belonging to the fraternity of St. Vincent de Paul since 1770.

In the DOME four oval frescoes by *Domenichino*: David dancing before the Ark, Solomon and the Queen of Sheba, Judith, Esther and Ahasuerus. In the 2nd Chapel to the left, two landscapes by *Polidoro Caravaggio* and his assistant *Maturino*: Betrothal of the Infant Christ with St. Catharine, and Christ appearing as the gardener to Mary Magdalene.

The *Via del Quirinale* ends, as mentioned at p. 169, at the *Via Nazionale*.

The S.E. PART OF THE *VIA AGOSTINO DEPRETIS* (Pl. I, 22, II, 25; p. 170) leads from the *Via Nazionale* (p. 169) directly to the choir of S. Maria Maggiore. We turn to the right before reaching the piazza in front of the latter, enter the *Via Urbana*, and in a few paces reach —

S. Pudenziana (Pl. II, 25; open till 9 a.m.; custodian, *Via*

Quattro Fontane 81, to be found from 1 to 4), traditionally the oldest church in Rome, erected on the spot where St. Pudens and his daughters Praxedis and Pudentiana, who entertained St. Peter, are said to have lived. The church, the earliest record of which dates from 499, has been frequently restored; it was much altered in 1598, and has recently been modernised in very bad taste. In the façade, lately adorned with mosaics (St. Peter with SS. Pudens and Pudentiana; on the left Pius I., on the right Gregory VII.), is an ancient portal borne by columns, which has also been restored. Pleasing campanile of the 9th century. Chief festival on 19th May.

INTERIOR. The nave and aisles are of unequal length. In the pillars are still to be seen the ancient marble columns which originally supported the wall. The *Mosaics* in the TRIBUNE (4th cent.), Christ with S. Praxedis and S. Pudentiana and the Apostles, and above them the emblems of the Evangelists on each side of the cross, are among the finest in Rome (p. xlv; several of those on the right are modern). The DOME above the high-altar was painted by *Pomarancio*. The AISLES contain remains of an ancient mosaic pavement. In the left aisle is the CAPPELLA CAETANI, over the altar of which is an Adoration of the Magi, a relief in marble by *Olivieri*. At the extremity of this aisle is an altar with relics of the table at which Peter is said first to have read mass. Above it Christ and Peter, a group in marble by *G. B. della Porta*.

Below the church are ancient vaults in a good style of architecture, which the custodian shows if desired.

On the summit of the Viminal, not far off, stands the church of **S. Lorenzo in Panisperna** (Pl. II, 22), on the spot where St. Lawrence is said to have suffered martyrdom, an old edifice, but frequently restored. — Hence to the Via Nazionale, see p. 170.

In the PIAZZA DELL' ESQUILINO, the square in front of the choir of S. Maria Maggiore, stands one of the two *Obelisks* which formerly rose in front of the mausoleum of Augustus, 48 ft. in height (the other is on the Quirinal, p. 173). It was erected here by Sixtus V. in 1587. — The piazza is intersected by the broad *Via Cavour* (p. 166), which is carried through the valley between the Esquiline and Viminal to the Forum Romanum.

The façade of the church overlooks the PIAZZA S. MARIA MAGGIORE, which is embellished with a handsome *Column* from the basilica of Constantine, 16 ft. in circumference, and 46 ft. in height, placed here and crowned with a bronze figure of the Virgin by Paul V.

****S. Maria Maggiore** (Pl. II, 25), also named *Basilica Liberiana*, or *S. Maria ad Nives*, or *S. Maria ad Praesēpe*, from the manger which it contains, derives its usual name from its being the largest of the eighty churches in Rome dedicated to the Virgin. It is also one of the oldest churches at Rome, and indeed in Christendom. This is one of the five patriarchal churches (p. 135), and has a special 'jubilee entrance'. The principal festivals are on Christmas Day, 5th Aug., and the Assumption (15th Aug.). According to a legend which cannot be traced farther back than the 13th cent., the Virgin appeared simultaneously to the devout Roman patrician Johannes and to Pope Liberius (352-66) in their dreams, commanding them to erect a church to her on the spot where they

should find a deposit of snow on the following morning (5th Aug.). The *Basilica Liberiana*, which they are said to have built in obedience to this vision, was re-erected by Sixtus III. (432-40), who named the church *S. Maria Mater Dei*, shortly after the Council of Ephesus had sanctioned this appellation of the Virgin (430). Of this edifice the nave with its ancient marble columns and mosaics is still preserved. In the 12th cent. the church was farther altered in the mediæval style. Eugene III. added a new porch, Nicholas IV. a new tribune adorned with mosaics, and Gregory XI. gave the campanile its present form and its pointed roof. About the end of the 15th cent. began a new period in the history of the church, when the irregularities of the mediæval additions were removed, and symmetrical lines were formed by the erection of accessory buildings and straight walls. The two large side-chapels, covered with domes, were added by Sixtus V. in 1586 and Paul V. in 1611. The exterior of the tribune was remodelled by Clement X., and the final restoration was entrusted by Benedict XIV. to *Fuga*.

The *Façade*, designed by *Fuga* in 1743, consists of a porch with a loggia above it, opening towards the piazza in three arches. The five portals in this porch correspond with four entrances to the church (the last of which on the left, the *Porta Santa*, is now built up), and with a niche on the right. To the right is a statue of Philip IV. of Spain. The loggia (staircase to the left in the vestibule; one of the vergers opens the door), from which the pope formerly pronounced his benediction on 15th Aug., contains mosaics from a façade of the 13th cent., restored in 1825.

Above, in the centre, Christ; on the left the Virgin, SS. Paul, John, and James; on the right SS. Peter, Andrew, Philip, and John the Baptist. Below, on the left, the vision of Pope Liberius and the Patrician Johannes; on the right, the meeting of the two, and the tracing of the site of the church on the newly-fallen snow.

The *Interior*, dating from the pontificate of Sixtus III., 93 yds. long and 19 yds. wide, and subsequently enlarged, produces a rich and imposing effect. The pavement of the NAVE dates from the 12th cent. (p. xlvii) and the handsome ceiling was executed from designs by *Giul. da Sangallo*. The architrave, adorned with mosaic, is supported by 42 Ionic columns, 33 in marble and 4 in granite, above which, and on the chancel arch, are **Mosaics* of the 5th cent., in the ancient style (p. xlv; good light early in the morning). Those on the arch represent events from the Life of Mary, Annunciation, Infancy of Christ, Slaughter of the Innocents, etc.; left wall, history of Abraham and Jacob; right wall, Moses and Joshua (several of the pictures were restored in 1825). In front of the chancel arch is the *High-Altar*, consisting of an ancient sarcophagus of porphyry, said to have been the tomb of the Patrician Johannes, and containing the remains of St. Matthew and other relics; the canopy is borne by four columns of porphyry. In the apse of the TRIBUNE are **Mosaics* by *Jacobus Torriti* (1292): Coronation of the Virgin, with saints, near whom are Pope Nicholas IV. and Card. Jac. Colonna (comp. p. xlviii).

At the beginning of the nave are the tombs of Nicholas IV. (d. 1292) on the left, and Clement IX. (d. 1669) on the right, erected by Sixtus V. and Clement X. respectively. RIGHT AISLE: First chapel: *Baptistery* with fine ancient font of porphyry. Farther on is the Cap. del Crocifisso with 10 columns of porphyry, containing five boards from the 'Manger of the Infant Christ' (whence termed *Cappella del Presepe*). — In the RIGHT TRANSEPT is

the sumptuous *SISTINE CHAPEL, constructed by Fontana, and of late gorgeously restored; in the niche on the left, an altar-piece (St. Jerome) by *Ribera*; on the right, occupying the whole wall, the monument of Sixtus V., with a statue of the Pope by *Valsoldo*; on the left, monument of Pius V. by *Leonardo da Sarzana*. Over the altar, a canopy in gilded bronze represents angels bearing the church; in the 'Confessio' under the staircase a statue of S. Gaetano, by *Bernini*, and by the altar a relief of the Holy Family, by *Cecchino da Pietrasanta* (1480). — At the end of the right aisle, the Gothic monument of Card. Consalvi (Gunsalvus, d. 1299) by *Giov. Cosmas*.

LEFT AISLE. 1st Chapel (of the Cesi): Martyrdom of St. Catharine, altar-piece by *Girol. da Sermoneta*; on the right and left two bronze statues to the memory of cardinals of the family. 2nd Chapel (of the Pallavicini-Sforza), said to have been designed by Mich. Angelo: Assumption of Mary, altar-piece by *Gir. Sermoneta*. — In the LEFT TRANSSEPT, opposite the Sistine Chapel, is the BORGHESE CHAPEL, constructed by *Flaminio Ponzio* in 1611, and also covered with a dome. Over the altar, which is gorgeously decorated with lapis lazuli and agate, is an ancient and miraculous picture of the Virgin (almost black), painted according to tradition by St. Luke, which was carried by Gregory I. as early as 590 in solemn procession through the city, and again by the clergy during the cholera in 1837 and in the war of 1860. The frescoes in the large arches are by *Guido Reni*, *Lanfranco*, *Cigoli*, etc. The monuments of the Popes (l.) Paul V. (Camillo Borghese, d. 1621) and (r.) Clement VIII. (Aldobrandini, d. 1605) are by pupils of *Bernini*. The crypt contains tombs of the *Borghese* family.

In the right corner of the Piazza S. Maria Maggiore is a side-entrance to the church of —

***S. Prassede** (Pl. II, 25), erected by Paschalis I. in 822, and dedicated to St. Praxedis, the daughter of St. Pudens with whom Peter lodged at Rome, and the sister of S. Pudentiana. It was restored by Nicholas V. about 1450, again in 1832, and finally in 1869. The church is generally entered by the side-door.

Interior. The nave is separated from the aisles by 16 granite columns (six others, bearing arches, having been replaced by pillars). The **Mosaics* (9th cent.; p. xlv) deserve special notice. On the triumphal arch the new Jerusalem guarded by angels, Christ in the centre, towards whom the saved are hastening; on the arch of the tribune the Lamb, at the sides the seven candlesticks and the symbols of the Evangelists; lower down the twenty-four elders (interesting as showing the mode in which the art accommodated itself to the spaces allotted to it; thus, in order to follow the curve of the arch, the arms of the foremost elders in the middle and upper rows gradually increase in length); in the round part of the apse, Christ surrounded with saints (on the left Paul, Praxedis, and Pope Paschalis with the church; on the right Peter, Pudentiana, and Zeno). On either side of the tribune are galleries. — RIGHT AISLE. The 3rd chapel is the *Chapel of the Column* (ladies admitted on the Sundays of Lent only; the sacristan opens the door when desired). At the entrance are two columns of black granite with ancient entablature. The interior is entirely covered with mosaics on gold ground (about the 10th cent.), whence the chapel is sometimes called *Orto del Paradiso*. On the vaulting a medallion with head of Christ, supported by four angels. Above the altar a Madonna between the saints Praxedis and Pudentiana. To the right in a niche, the column at which Christ is said to have been scourged. The 4th chapel contains the tomb of Card. Cetti (d. 1474). At the extremity of the right aisle the *Cap. del Crocifisso* contains the tomb of a French cardinal (d. 1286). — In the LEFT AISLE by the entrance-wall is a stone-slab, on which St. Praxedis is said to have slept. The 2nd *Cap. di S. Carlo Borromeo* contains a chair and table once used by the saint. The 3rd *Cap. Agiati* contains paintings by the *Car. d'Arpino*. — The marble spout of a fountain in the nave indicates the spot where St. Praxedis collected the blood of the martyrs.

The CONFESSIO (keys kept by the sacristan) contains ancient sarcophagi

with the bones of the sister saints Praxedis and Pudentiana on the right, and those of martyrs on the left. The altar is decorated with fine mosaic of the 13th century. Above it an ancient fresco of the Madonna between the sisters. — The SACRISTY contains a Scourging by *Giulio Romano*.

To the S. and S.E. of the Piazza S. Maria Maggiore run two new thoroughfares, the *Via Merulana*, on the right, leading to the Lateran (p. 267), and the *VIA CARLO ALBERTO*, on the left. In the latter, to the left, is the church of *S. Antonio Abbate*, with a portal of the 13th cent.; interior uninteresting. S. Antonio is the tutelary saint of animals, and in front of the church from 17th to 23rd Jan., domestic animals of every kind used to be blessed and sprinkled with holy water.

A cross-street leads to the right from the *Via Carlo Alberto* to the church of *S. Vito* and the *Arch of Gallienus* (Pl. II.; 25, 28). This honorary arch was erected in 262 in honour of the Emp. Gallienus 'on account of his bravery, surpassed only by his piety' by a certain M. Aurelius Victor. The architecture is simple, but in the degraded style of the age.

The *Via Mazzini* and *Via Rattazzi* lead to the left from the *Via Carlo Alberto* to the Piazza *Manfredo Fanti*, in which stands the handsome *Aquarium* (Pl. II, 28), built from a design by *E. Bernich* in 1885 (adm. from 9.30 a.m., 1 fr.; director, *Prof. Vinciguerra*).

The *Via Carlo Alberto* ends at the large PIAZZA VITTORIO EMANUELE (Pl., II, 29), which is embellished with flower-beds. Here, on the left, are considerable remains of a water-tower of the *Aqua Julia* (Pl. II, 28), in the niches of which the so-called trophies of Marius, now on the balustrade of the Capitol, were formerly placed (p. 210). The ruin, called *Trofei di Mario*, has been partly restored, and is under the care of a 'guardia degli scavi'. — At the N. angle of the piazza rises the church of *S. Eusebio*, re-erected in the 18th cent., with the exception of the campanile. The ceiling-painting, the glory of St. Eusebius, is one of the earliest works of *Raphael Mengs*; the high-altar-piece is by *Bald. Croce*.

Several new streets, not yet completed, lead from the Piazza *Vittorio Emanuele* to the church of *S. Bibiana* (Pl. II, 31), consecrated in 470, and rebuilt for the last time in 1625 by Bernini. It contains eight antique columns; above these are frescoes from the life of the saint, on the right by *Ciampelli*, on the left by *Pietro da Cortona* (modernised). The statue of St. Bibiana on the high-altar is by *Bernini*. To the left by the entrance is the stump of a column, at which the saint is said to have been scourged to death. — The *Via di S. Bibiana* leads to the new *Porta di S. Lorenzo* and the basilica of that name, which may be conveniently visited at this juncture (see p. 343). We may return by tramway-line No. 2 (p. 3 of the Appx.).

The wide VIALE PRINCIPESSA MARGHERITA leads hence to the Piazza *Guglielmo Pepe* (with remains of the above-mentioned *Aqua Julia*) and the (10 min.) *Railway Station* (p. 166). On the right

it leads in 5 min. to the so-called **Temple of Minerva Medica** (Pl. II, 32), the ruin of an ancient Nymphæum in the form of a decagon, 55 yds. in circumference, with deep niches in the walls, and originally covered with marble below and stucco above. This must have belonged to some splendid bath-establishment, as many ancient statues have been found in the vicinity. One of these, the Minerva Gustiniani of the Braccio Nuovo in the Vatican (p. 316), has given rise to the otherwise unfounded appellation of 'Temple of Minerva'. In the middle ages the ruin was called *Le Galluzze* a name which has been conjectured to be a corruption of (the Thermæ of) 'Gaius and Lucius Cæsar', of whose existence, however, there is no other hint. The vaulting existed down to 1828. The building, which is architecturally interesting, dates from about the 3rd cent. after Christ.

The dusty and unfinished *Via Conte Verde*, the middle street running from the S.E. side of the Piazza Vittorio Emanuele, leads to the church of *S. Croce in Gerusalemme* (see below); the *Via Emanuele Filiberto*, the street to the right, leads to the *Lateran* (p. 267); and the *VIA PRINCIPE EUGENIO*, on the left, to the *Porta Maggiore*.

The ***Porta Maggiore** (Pl. II, 35) was originally an archway belonging to the *Aqua Claudia*, above which the *Anio Novus* flowed through a second conduit. The inscriptions record the construction of both aqueducts by the Emp. Claudius, A.D. 52, the Claudia, 45 M. in length, bringing water from the neighbourhood of Subiaco, and the Anio Novus coming from the sources of the river of that name, a distance of 62 M.; and also their restoration by Vespasian in 71, and by Titus in 81. Aurelian converted the monument into one of the gates of his city-wall; and the Colonnas used it in the middle ages as the nucleus of a fortification. The gate derives its name either from its imposing dimensions, or from the church of that name. It was purged of the later additions by Gregory XVI. — Two roads diverged hence: to the left the *Via Praenestina*, and to the right the *Via Labicana*, now named *Via Casilina*.

Between the two roads, outside the gate, on the removal of the fortifications of Honorius, which have been re-erected by the wall to the right, was discovered the ***Monument of the Baker Eurysaces**, dating from the close of the republic; it is erected in imitation of grain-measures laid alternately in vertical and horizontal rows.

The monument was erected by the baker himself; and the principal inscription, repeated several times, is to the effect that — 'This is the monument of Marcus Vergilius Eurysaces, a public purveyor of bread and an official'. Some of the reliefs represent grinding, baking, and other parts of his trade, and others refer to his post of purveyor to the city.

From this point to the Amphitheatrum Castrense and the *Porta S. Giovanni*, see p. 273, to the Campagna, see p. 345.

From the *Porta Maggiore* a road leads to (5 min.) *S. Croce in Gerusalemme*, passing under the arch of the Claudian aqueduct, and

skirting the wall on the inside. From S. Maria Maggiore to this church by the Via Conte Verde is a walk of 20 minutes.

S. Croce in Gerusalemme (Pl. II, 36), one of the seven pilgrimage-churches, once named *Basilica Sessoriana*, because the *Sessorium*, perhaps an ancient court of judicature, formerly stood here, is said to have been erected by St. Helena in honour of her discovery of the Cross. As early as 433 a Council met here. The church was rebuilt by Lucius II. in 1144, and was modernised under Benedict XIV. in 1743, by *Gregorini*, who added the poor façade.

INTERIOR. The nave was originally borne by 12 antique columns of granite, of which 8 only are now visible. An ancient sarcophagus of basalt below the high-altar contains the relics of SS. Anastasius and Cæsarius. In the tribune are modernised *Frescoes of the Invention of the Cross, ascribed to *Pinturicchio* (according to C. & C., by *Fiorenzo di Lorenzo*). The church contains numerous relics, including the 'Inscription on the Cross'.

To the left of the tribune a staircase descends to the *Crypt*, where on the left is an altar with a marble relief (*Pietà*); at the sides are statues of Peter and Paul of the 12th century. On the right the chapel of St. Helena (to which ladies are admitted on 20th March only). On the vaulting are **Mosaics*, after *Bald. Peruzzi*, representing the Four Evangelists. In the centre, Christ. In the arch over the entrance, on the left St. Helena, right St. Sylvester; over the altar, on the left St. Peter, on the right St. Paul. The altar-statue of St. Helena is an exact copy of the Barberini Juno in the Sala Rotonda of the Vatican (p. 306), with a cross for the sceptre in the right hand, and a nail of the cross for the vase in the left.

The greater part of the old Cistercian monastery formerly belonging to the church is now used as a barrack.

On the other side of S. Croce is an apse with arched windows and the beginning of adjoining walls, which are supposed to have belonged to a *Temple of Venus and Cupid*, or a *Nymphæum* of Alexander Severus, or to the *Sessorium* mentioned above.

From S. Croce to the Lateran is a dusty and shadeless walk of 5 min. (p. 266).

From S. Maria Maggiore the VIA MERULANA (Pl. II, 26, 29, 30; omnibus No. 7 and tramway No. 3, see pp. 1, 3 of Appx.) leads to the right to the Lateran (in $\frac{1}{4}$ hr.; p. 265).

The first cross-street to the right is the *Via di S. Martino*, which, under different names, leads through a well-peopled quarter to the Forum. To the left is the *Via di S. Vito*, in which stands S. *Alfonso de' Liguori*, a Gothic church built by Wigley in 1855, at the cost of a Mr. Douglas. At the end of the street are the church of S. Vito and the *Arch of Gallienus* (see p. 179). The next cross-streets to the right are the broad new *Via dello Statuto*, which unites with the Via Cavour, and the *Via di S. Pietro in Vincoli* (see below).

In this neighbourhood, but scarcely accessible on account of the new streets in progress, are the so-called *Sette Sale* (Pl. II, 26), consisting of seven, or rather nine, parallel vaulted chambers, which appear to have been used as reservoirs for the Thermæ of Titus (p. 237).

Farther on in the Via Merulana, to the right, is the new and unfinished *Palazzo Field*. Adjacent is a small triangular space, where a building in 'opus reticulatum' was discovered in 1874. It is supposed to have belonged to the *Gardens of Maecenas* which lay here. The oblong chamber, now roofed in, has a number of steps rising at the N. end, like the seats in an amphitheatre. The walls were richly decorated with paintings, which are now rapidly fading. It is used as a storehouse for newly discovered sculptures and inscriptions and contains nothing of general interest. Outside the S. and E. walls are seen fragments of the Servian wall (p. 169). Adm. on Thurs., 9-11 and 2-5.

Still farther on in the Via Merulana, at the corner of the Via Labicana (by which we may reach S. Clemente and the Thermæ of Titus in 5 min.; see p. 237), is the small church of *S. Pietro Marcellino*, founded at a very early period and entirely renewed under Benedict XIV. Opposite is the imposing new *House of the Franciscans*, built in 1835-87. We then reach the Piazza del Laterano (p. 265).

From the Via Merulana diverges the VIA DI S. PIETRO IN VINCOLI to the W., leading to the church of —

S. Martino ai Monti (Pl. II, 26), erected by Symmachus about the year 500, adjacent to the Baths of Trajan and an old church of Pope Sylvester. It was rebuilt in 844 by Sergius II. and Leo IV., and handsomely modernised about 1650. Principal festival, 11th Nov.

The INTERIOR, a basilica with a roof of straight beams, contains 24 antique columns. In the S. aisle six *Frescoes by *G. Poussin*, from the life of Elijah, the patron of the order (marred by restoration). In the N. aisle six smaller *Frescoes. Also two pictures representing the interior of the old churches of the Lateran and of St. Peter. — The PRESBYTERIUM is eleven steps higher; below is the CHURCH. From the latter we enter a large vault, probably once belonging to Thermæ, but at an early period converted into a church. The vaulting bears traces of ancient painting. This is supposed to be the site of Pope Sylvester's church, of the period of Constantine.

In 5 min. more we reach the church of ***S. Pietro in Vincoli** (Pl. II, 23; 150 ft. above the sea-level), also named *Basilica Eudoxiana* after Eudoxia, wife of Valentinian III., who founded the church about the year 442, as a receptacle for the chains of St. Peter which had been presented by her to Pope Leo I. It was restored by Pelagius I. and Hadrian I., the vestibule added by Baccio Pintelli(?), and the whole is now modernised. Admission before 11 a.m. and after 3 p.m.; when closed, visitors ring at the adjacent door to the left, No. 4 (1½ fr.).

INTERIOR. The nave and aisles are separated by 20 antique Doric columns. To the left of the entrance is the monument of the Florentine painters Pietro and Antonio Pollajuolo (d. 1498). The fresco above it, representing the plague of 680, is attributed to the latter master. The LEFT AISLE contains the monument (in the corner) of the learned Card. Niccolaus Cusanus (from Cues on the Moselle, d. 1465). Above it a relief: Peter with keys and chains, on the left the donor (Nic. Cusanus), right an angel. — On the 3rd altar to the left a mosaic of the 7th cent. with St. Sebastian.

At the end of the RIGHT AISLE is the monument of Pope Julius II. (p. 71) with the ²²Statue of Moses by *Michael Angelo*, one of his most famous works. The monument was originally destined for St. Peter's, and intended to be a most imposing work, consisting of upwards of 30 statues. Owing to various adverse circumstances the portion preserved here was alone completed. (Two statues destined for this monument are at the Louvre.) The statues of Moses (who is represented by mediæval Christian artists with horns owing to an erroneous translation of Exodus xxxiv. 35), Rachel, and Leah (as symbols, on the left of meditative, on the right of active life) alone were executed by the great master, and even these were not entirely his own workmanship. The grouping only of the remainder was from his design. The figure of the pope (who is not interred here) by *Maso del Bosco* is a failure; the prophet and the sibyl at the side are by *Raf. da Montelupo*. — To the right of the choir is St. Margaret, an altar-piece by *Guercino*. — The Choir contains an ancient marble seat from a bath, converted into an episcopal throne. A cabinet under the high-altar, with bronze ²³Doors (by the *Pollajuoli*, 1477), contains the chains of St. Peter, which are exhibited to the pious on 1st August.

The adjacent monastery of the Canonici Regolari is now the seat of the physical and mathematical faculty of the university. The handsome old monastery-court, by *Giuliano da Sangallo*, planted with orange-trees, is embellished with a fountain by *Antonio da Sangallo*. (Entrance by No. 5, to the right of the church.) — Opposite the façade of the church is the *Collegium Maroniticum*, with an old tower commanding a fine view.

Proceeding to the left, and then, where the street divides, to the left again, we reach the *Thermae of Titus* (p. 237) in 5 minutes. — The street in a straight direction descends to the *Basilica of Constantine* (p. 232), which is conveniently visited after the church of S. Pietro. To the right of S. Pietro in Vincoli is the church of *S. Francesco di Paola*, with a monastery, now the *R. Istituto Tecnico*.

III. Rome on the Tiber (Left Bank).

That part of the city which extends to the W. from the Corso as far as the river was uninhabited in the most ancient times (*Campus Martius*), but was gradually covered with buildings as Rome extended her sway, and as far back as the Republic, but more particularly in the reign of Augustus, it became the site of many palatial edifices, and the new town of ancient Rome. This quarter, which is now densely peopled, and was till quite lately in the main mediæval in character, consists of a network of narrow and dirty streets and lanes, enlivened by the busy traffic of the lower classes, and containing many highly interesting churches and palaces of the middle ages and the Renaissance. The present government has undertaken the task of improving this quarter by the construction of new and broad streets. The following description begins with the N. side.

From the Piazza del Popolo the broad VIA DI RIPETTA (Pl. I, 15, 14), with its prolongation the Via della Scrofa, leads to the S. in 16 min. to S. Luigi de' Francesi and the Piazza Navona (Circo

Agonale). On the right, 4 min. from the Piazza del Popolo, is a modern building with a central part in the shape of a horseshoe (*Il Ferro di Cavallo*), erected by Gregory XVI., and now containing the *Direzione Centrale del Lotto*, and studios belonging to the *Accademia di Belle Arti*, or *di S. Luca* (p. 238).

In the Via de' Pontefici, a cross-street to the left, is the entrance (No. 57; on the right) to the **Mausoleum of Augustus** (Pl. I, 17), erected by that emperor as a burial-place for himself and his family, and in which most of his successors down to Nerva were interred. On a huge substructure, which contained the mortuary chambers, arose a mound of earth in the form of terraces, embellished with cypresses, surmounted by a statue of the emperor, and environed with a park. In the middle ages it was converted into a fortress by the Colonnas; and a theatre (*Anfiteatro Umberto I.*) is now fitted up within its precincts. A few of the tomb-chambers are still preserved. Fee 1½ fr. Generally closed at midday.

To the left in the Via di Ripetta we next reach the church of *S. Rocco* (Pl. I, 14), erected in 1657 by *De Rossi*, with a façade added by *Valadier* in 1834. Immediately beyond it, on the right, is the *Harbour of the Ripetta*, constructed by Clement XI. in 1707; the picturesque curving flights of steps (built in 1704 with stones from the Colosseum) have lost greatly in effect from the construction of the *Ponte di Ripetta*, a new iron bridge leading to the Prati di Castello (p. 275). To the left is the end of the *Palazzo Borghese* (see below).

A little farther on, the street takes the name of **VIA DELLA SCROFA** (Pl. I, 3; II, 3), which it retains as far as the Piazza of *S. Luigi de' Francesi* (see pp. 189 et seq.).

The Via della Scrofa is soon intersected (about 9 min. from the Piazza del Popolo) by an important street, the **VIA DELLA FONTANELLA** (Pl. I, 16), which diverges from the Corso opposite the Via Condotti. At the Via della Scrofa it assumes the name of *Via del Clementino*, beyond which it is continued, as the *Via di Monte Brianzo* and the *Via Tordinona*, to the Ponte S. Angelo. The church of *S. Trinità de' Monti* (p. 149) is visible the greater part of the way, forming the termination of the street. In the Piazza Nicosia, adjoining the Via del Clementino, is the new *Palazzo Galitzin* (Pl. I, 13, 13), an imitation of the Pal. Giraud (p. 276). In the Via Tordinona the houses on the river-side have recently been levelled with the ground. A spacious quay named the *Lungo Tevere*, and a new bridge named the *Ponte Umberto* are in progress.

Turning to the left from the Via della Scrofa into the Via della Fontanella, we reach the **PIAZZA BORGHESE**, with the celebrated —

***Palazzo Borghese** (Pl. I, 16), begun by order of Card. Deza

in 1590 by the architect *Mart. Lunghi the Elder*, and completed by *Flaminio Ponzio* by order of Paul V., through whom it came into the possession of the Borghese family. The principal façade is towards the Via della Fontanella; the more imposing lateral façade is towards the Piazza Borghese. On the ground-floor and first floor the *COURT is surrounded by arcades resting on clustered granite columns (permessi for the Gallery obtained to the left). Below these are three ancient colossal statues (a Muse, an Apollo Musagetes, and a portrait-statue); and at the end of the right passage a fragment of the statue of an Amazon. Behind lies the small garden, containing three rococo fountains by *Rainaldi*, and some trifling antiquities. In the centre of the left side of the arcades is the entrance to the ****Galleria Borghese** (admission, see p. 122; catalogues for the use of visitors), hitherto the most important in Rome next to that of the Vatican, but much weakened in 1888 by the removal of several of its greatest treasures. Other changes may be expected. The following account refers to the collection as it was in summer, 1889. — Among the works which have been removed were several paintings of the OLDER SCHOOL, but the 15th century, through the gallery was founded at a time when the works of that period were not generally appreciated, is still better represented here than in the other private galleries of Rome. Among these are an admirable Holy Family ascribed to *Lorenzo di Credi* (Room I, No. 54) and two good specimens of the Milanese School of Leonardo da Vinci (Christ imparting his blessing, a small work by *Marco d'Oggionno*, I. Room, No. 33; Christ bearing his Cross, by *Solario*, II. Room, No. 42).

Among the works ascribed to RAPHAEL the Entombment (II. Room, No. 38) alone is authentic. The picture is not well preserved, and is perhaps not entirely by Raphael's own hand. The impression produced by it is disappointing, the composition seems too studied, and the colouring cold (p. liii). The predelle belonging to it are in the Vatican (p. 301). The Fornarina (II. Room, No. 65), the Madonna d'Alba (II, 39), Pope Julius II. (II, 18), and others ascribed to Raphael are copies; the unknown Cardinal (II, 21) is by a somewhat later Florentine master, who for the colouring of the gown has used a different kind of red from Raphael. It is quite as improbable that the so-called Portrait of Cesare Borgia (II, 26) was executed by Raphael. Cesare Borgia died in 1507, whereas the costume of the portrait is in the style of the middle of that century. The painter of this unknown personage was perhaps *Angelo Bronzino*. The IX. Room contains several *Frescoes* transferred hither from the Villa of Raphael, and ascribed to that master; but they are unlike his workmanship, both in composition and execution.

The SCHOOL OF FERRARA of the 16th cent. is copiously and well represented. A fine example of *Mazzolini's* richness of colour-

ing is his Adoration of the Magi (II, 59). *Dosso Dossi's* Circe (III, 11) conducts us into a world of fancy, similar to that depicted by Ariosto in his Orlando. Lastly there are several excellent works by *Garofalo*, the Raphael of Ferrara (II, 9: Descent from the Cross).

THE COLOURISTS OF THE XVI. CENT. will not fail to attract the visitor. To *Sodoma* the gallery is indebted for a Pietà (I, 7) and a Holy Family (II, 44), in which the head of the Madonna is radiant with beauty. At a comparatively recent period (1824) an important work by *Correggio* was secured for the gallery. It represents Danaë with Cupids sharpening their arrows (III, 40). The figure of Danaë is rather graceful than strictly beautiful, but the Cupids are very charming, and the chiaroscuro masterly. — A whole room is devoted to the VENETIAN SCHOOL. *Titian's* so-called Earthly and Heavenly Love (X, 21) is one of those creations which produces an indelible impression on the beholder. The picture rivets the attention like a poetical dream, and after the eye has feasted on the charms of the colouring the composition still captivates the imagination. The Arming of Cupid (X, 2) is one of the finest mythological works by the same master. *Bonifacio* is another master who supplies us with examples of the richness of colouring of the Venetian School (XI, 16, being the finest). *Giorgione*, on the other hand, is not fairly represented by the only specimen of his handiwork which the gallery possesses (X, 13).

As it is generally the case in the Roman galleries, the painters of the later revival of art, the adherents of the *Carracci* and the *Naturalists*, figure very numerous here. *Domenichino's* Diana (V, 15) contains a number of nymphs with lifelike heads, and an excellent background of landscape; and *Albani's* Elements (V, 11-14) are superb decorative pictures. On the other hand, the works of *Caravaggio*, the chief of the naturalists (V, 26), are repulsive. The pictures by German and Netherlandish masters in the XII. Room are unimportant. — The apartments are artistically decorated.

I. Room. *Decorations in grisaille and gold, by *Carlo Villani*. Left: *1. *Sandro Botticelli*, Madonna; 2. *Sodoma*, Pietà, unfortunately darkened by age; 3, 5, 6, 7. *Pinturicchio* (?), History of Joseph, panel-pictures such as were used in Florence for the doors of cupboards, the lids and sides of 'cassoni', etc.; 8. *Luini* (a copy), Vanità; *13. *Solario* (?), Ecce Homo; *25. *School of Leonardo*, Madonna; 16. *Piero di Cosimo*, Madonna with the Child, St. John, and angels; 18. *Perugino*, St. Sebastian; 19. *Sodoma* (?), Leda and the swan, an excellent copy of a celebrated picture by Leonardo; 21. *Mazzolino*, Madonna; 24. Portrait of Petrarch; 32. *Luini* (a copy), St. Agatha; *33. *Marco da Oggionno*, Youthful Christ; 34. *Perugino*, Madonna (a copy), *35. *Ridolfo Ghirlandajo* (according to Passavant, by *Timoteo della Vite*), Portrait of a boy, erroneously called a portrait of Raphael by himself; 42. **Andrea*

Solario, Christ bearing the Cross; 43. *Fr. Francia* (?), Madonna; *53. *Ant. Pollajuolo*, The Nativity; *54. *Lorenzo di Credi* (?), Holy Family, a work of the highest rank; 55. *Fr. Francia* (?), St. Anthony; 57. *Fr. Francia*, Madonna; 67. *Garofalo* (?), Adoration of the Child.

II. ROOM. 6. *Garofalo*, Madonna with St. Joseph and St. Michael; *9. *Garofalo*, Christ mourned over by his friends; 18. *Raphael*, Portrait of Julius II., an admirable copy; 19. *Perugino*, Portrait of a woman (copy); *21. *Raphael* (?), Portrait of a cardinal; 22. Copy after *Raphael*, John in the wilderness; *26. *Raphael* (?), Portrait of Cæsar Borgia (?); 29. *Giulio Romano* (? more likely *Bald. Peruzzi*), Venus; 30. (?) Portrait of a woman; 34. *Andrea del Sarto* (?), Madonna; *38. *Raphael*, Entombment (1507), his last work before going to Rome, ordered by Atalanta Baglioni for her chapel in S. Francesco de' Conventuali at Perugia (p. 53), afterwards purchased by Paul V.; 39. *Raphael*, Madonna di Casa d'Alba, an old copy; 40. *Fra Bartolommeo*, Holy Family; *44. *Sodoma*, Holy Family; 53. *Raphael* (?), Portrait of Perugino; *54. *Antonello da Messina*, Portrait; 55, 56. *Garofalo*, Madonna and saints; 59. *Mazzolini*, Adoration of the Magi; 60. *Garofalo*, Madonna; *65. Portrait of the so-called Fornarina, a good copy of *Raphael's* original in the Pal. Barberini (p. 171), perhaps by Sassoferato.

III. ROOM. 1. *Garofalo*, Madonna; *11. *Dosso Dossi*, The Sorceress Circe; 13. *Solario* (?), Mater Dolorosa; 14. *Sofonisba Anguissola*, Portrait of a woman; 22. *School of Raphael*, Holy Family; 24. *Andrea del Sarto* (?), Madonna with angels; *28. Madonna with the Child and St. John, by the same (?); 35. *Andr. del Sarto* (?), Venus with two Cupids; *40. *Correggio*, Danaë, one of his finest easel-pieces; 41. *Luca Cambiasi*, Venus and Cupid on dolphins (unfinished); 42. *Bronzino* (?), Portrait of Cosimo de' Medici; 46. Mary Magdalene, after *Correggio's* original at Dresden; 47. *Ann. Carracci*, St. Francis; *48. *Sebast. del Piombo*, Scourging of Christ (the same piece is in S. Pietro in Montorio as a fresco, p. 328); 49. *And. del Sarto* (?), Mary Magdalene.

IV. ROOM. *2. *Domenichino*, Cumæan Sibyl; 4. *Lod. Carracci*, Head; 10. *Cav. d'Arpino*, Rape of Europa; 14. *Sch. of the Carracci*, Entombment; *15. *Guido Cagnacci*, Sibyl; 21. *Ag. Carracci*, Entombment; 33. *Luca Giordano*, Martyrdom of St. Ignatius; *Carlo Dolci*, 36. Madonna, 37. Mater Dolorosa, 34. Head of Christ; 38. *Sassoferato*, Madonna.

V. ROOM. *11, 12, 13, 14. *Francesco Albani*, The Four Elements, landscapes with mythological accessories; *15. *Domenichino*, Diana and her Nymphs practising with their bows; 25. *Fed. Zuccaro*, Christ bewailed by angels; 26. *Caravaggio*, Madonna with St. Anna and the Child Jesus; 27. *Varotari (il Padovanino)*, Venus; 28. *Cav. d'Arpino*, Battle.

VI. Room. 1. *Valentin*, Return of the Prodigal Son; *3. *Andrea Sacchi*, Orazio Giustiniani; 5. *Guercino*, Return of the Prodigal; 7. *Pietro da Cortona*, Giuseppe Ghislieri; 8, 10. *Caravaggio*, David; 11. *Baroccio*, Flight of Aeneas from Troy; *13. *Titian*, Three periods of life, a copy by *Sassoferrato* (original in London); 18. *Sassoferrato*, Madonna; 24, 25. Landscapes in the style of Poussin; 36. *Caravaggio*, Boy with fruit.

VII. Room. The lower part of the wall is adorned with mirrors, on which Cupids (by *Ciroferri*) and garlands (by *Mario de' Fiori*) are painted. Above, in small niches, are 16 ancient portrait-busts, some freely restored. In the centre is a table of mosaic composed of stones some of which are extremely rare.

VIII. Room, containing a number of small objects of art. 13. *Marcello Provenzate*, Madonna; 68. *P. Bril* (?), Orpheus with the animals in a landscape; 73. *Vanni*, The Graces; *75. Female head, a silver-point drawing of the *School of Leonardo*; *83. View of the Villa Borghese in the 17th century. — To the left a passage adorned with landscape-frescoes leads to the —

IX. Room. Three *Frescoes (under glass) from the so-called Villa of Raphael, which formerly stood within the grounds of the Villa Borghese, and was removed in 1849 (p. 334): 1. Marriage of Alexander and Roxana, from a drawing in the Albertina in Vienna, which bears the name of Raphael; 2. Nuptials of Vertumnus and Pomona, of inferior value; 3. The so-called 'Bersaglio de' Dei' (shooting contest of the gods), from a drawing in the Brera at Milan ascribed by Raphael to Mich. Angelo; this obscure composition is perhaps borrowed from Lucian (Nigrinus, C. 36). All three were probably executed by Raphael's pupils. — Returning to the mirror-room, and leaving it by the door to the left in the opposite wall, we enter the —

X. Room. Opposite the entrance: 1. *Moroni*, Portrait; *2. *Titian*, Cupid equipped by Venus and the Graces (c. 1560); 4. *Sch. of Titian*, or of *Giorgione*, Judith, said to have the features of Titian's wife; 6. *Sch. of Ferrara*, Cupid and Psyche; *9. *Lor. Lotto* Portrait; 13. *Giorgione* (or school of Ferrara?), David with the head of Goliath; 14. *Paoto Veronese*, John the Baptist preaching repentance; *16. *Titian*, St. Dominic; 20. *Paoto Veronese*, Venus with satyr and amorette. — ***21. *Titian*, 'Amor sagro e profano' or rather 'Artless and Sated Love', one of Titian's greatest works, representing a favourite allegory of 16th cent. painters; to the right is the charming figure of Artless Love, to the left Sated Love (see also p. 186). — 22. *Leonetto Spada*, Concert; 26. *School of Palma Vecchio*, Portrait; 30. *Leandro Bassano*, The Trinity; *36. *Giov. Bellini* (?), Madonna, an early work.

XI. Room. 2. *Paoto Veronese* (?), St. Anthony about to preach to the fishes; 5. *Palma Vecchio*, Lucretia; 14. *Andr. Schiavone*, Last Supper; 15. *Bonifacio Junr.*, Christ among his disciples;

*16. *Bonifacio*. Return of the Prodigal; 17. *Titian*, Samson (retouched); 18. *Bonifacio*, Christ and the adulteress; 19. *Palma Vecchio* (?), Madonna; *32. *Palma Vecchio*, Holy Family; 33. *Portenone*, Family-portraits.

XII. Room. Dutch and German masters. 1. *Van Dyck* (?), Crucifixion; *7. Entombment, by the same (?); 8. *D. Teniers*, Genre picture; 9. *A. Brouwer* (?), Genre picture; 10. *Dutch School* (*Pieter Codde*), Soldiers; 11. *Le Duc*, Conversation-piece; 15. *Brabant Sch.*, Mary's visit to Elizabeth; 17. *Gherardo della Notte* (*Hontorst*), Lot and his daughters; 25. *Dürer* (?), Portrait (said to be of Duke Louis VI. of Bavaria); 27. *Van Dyck* (?), Portrait; 44. *Lucas Cranach*, Venus and Cupid.

Among the pictures formerly in the Gallery, which have now been removed to the Prince's private rooms, the following may be mentioned: *Al. Allori*, Risen Christ; several portraits by *Giov. Bellini*; *Lor. di Credi*, Madonna with the flower-glass; *Fr. Francia*, St. Stephen; *Guercino*, Female half-figure, and a *Mater Dolorosa*; *Guido Reni*, St. Joseph; *School of Leonardo da Vinci*, Madonna; *Lor. Lotto*, Madonna with SS. Onuphrius and Augustine; *Perugino*, Portrait of himself; *Ribera*, St. Stanislaus with the Child Jesus; *Giulio Romano* and his scholars, frescoes from the Villa Lante; *Sassoferrato*, Madonna; *Titian*, Portrait of himself.

Following the Via della Scrofa (p. 184) from the Palazzo Borghese and after 5 min. taking the fourth cross-street to the right (in front, straight on, is S. Luigi de' Francesi, p. 193), we reach the PIAZZA DI S. AGOSTINO.

*S. Agostino (Pl. I, 13), erected by *Baccio Pintelli* (?) in 1483 by order of Card. d'Estouteville, the protector of the Augustinians, on the site of an old oratorium, was the first Roman church with a dome. The façade and the spacious flight of steps are said to have been constructed of stones from the Colosseum. The interior, in the form of a Latin cross, was restored in 1750, and again in 1860, when it was adorned with frescoes by *Gagliardi*.

INTERIOR. On the entrance-wall a *Madonna and Child, in marble, by *Jacopo Tatti*, surnamed *Jac. Sansovino* after his master Andrea Sansovino, surrounded by numerous votive offerings. In the 1ST CHAPEL on the right, St. Catharine by *Venusti*; in the 2ND, *Nucci's* free copy of the lost Madonna della Rosa of *Raphael*; in the 4TH, *Christ delivering the keys to Peter, a group by *Cotignola*. By the 5TH CHAPEL is the monument (the second to the left) of the learned Onofrio Panvinio (d. 1568). Adjoining the door of the sacristy is the monument of the learned Cardinal Noris. — The RIGHT TRANSEPT contains the chapel of St. Augustine with an altar-piece by *Guercino*: St. Augustine between John the Baptist and Paul the Hermit.

The HIGH ALTAR was decorated by *Bernini*; the image of the Madonna is said to have been painted by St. Luke, and brought from the church of St. Sophia at Constantinople. In the chapel on the left of this are preserved the remains of St. Monica, mother of Augustine; altar-piece by *Gottardi*.

The 2ND CHAPEL in the LEFT AISLE contains a *Group in marble (St. Anna, Mary, and Jesus) by *Andrea Sansovino* (1512). In the 4th, St. Apollonia, altar-piece by *Muziano*. In the NAVE, on the 3rd pillar to the left, **Raphael's* Prophet Isaiah, holding a scroll with the words from Is. xxvi, 2, painted in 1512, but unfortunately retouched by *Dan. da Volterra*, and now much injured. In the execution of this work the great master is said to have been influenced by that of M. Angelo in the Sistine Chapel.

To the right of the church is the entrance to the *Biblioteca*

Angelica, consisting of upwards of 100,000 vols. and 2945 MSS., (adm., see p. 116).

Proceeding from the Piazza S. Agostino straight through the archway, we reach the PIAZZA S. APOLLINARE (Pl. I, 13), in which are situated the *Seminario Romano*, a kind of grammar-school, and *S. Apollinare*, an old church, rebuilt in 1552 and 1750, and owing its present form to Fuga. To the left, over the altar in the inner vestibule, is a Madonna by Perugino (?). — Opposite the church is the *Pal. Attems*, of the 16th cent., completed by the elder Lungli, possessing a handsome double court with arcades, the lateral colonnades of which are built up, and containing a few ancient statues.

From the Piazza S. Apollinare the Via Agonale leads to the S. to the Piazza Navona (see below). In a straight direction we reach the *Piazza di Tor Sanguigna*, whence the narrow *Via de' Coronari* and the *Via di Panico* lead to the (10 min.) Ponte San Angelo.

The *Via della Maschera d'Oro*, No. 7 in which is adorned with a frieze with paintings from the myth of Niobe by Polidoro da Caravaggio (much damaged), leads to the **Palazzo Lancelotti** (Pl. I, 13, I), erected under Sixtus V. by *F. da Volterra*, and completed by *C. Maderna*, with a portal by *Domenichino*. The court contains ancient statues and reliefs. In the private apartments of Prince Lancelotti, shown by special permission only, stands the celebrated ***Discus Thrower*, found on the Esquiline in 1761, a marble copy of the bronze statue by *Myron* (p. 305).

The ***Piazza Navona** (Pl. II, 13), now officially named *Circo Agonale*, occupies, as its form still indicates, the *Circus* or *Stadium of Domitian*. The name 'Navona', which was used in the middle ages, is said to be derived from the *agones*, or contests which took place in the circus. It is embellished with three *Fountains*. That on the N. side, by Leon. della Bitta and Greg. Zappolà, erected in 1878, represents Neptune in conflict with a sea-monster (polypus); round the central group are Nereids and sea-horses. Not far from it, in the centre of a large ancient basin of Pentelic marble, rises a fountain erected by *Bernini* under Innocent X.; at the corners of the lofty mass of rock, the different parts of which represent the four quarters of the globe, are placed the gods of the four largest rivers, the Danube, Ganges, Nile, and Rio della Plata, executed by pupils of *Bernini*. The whole is surmounted by an obelisk, which was originally erected in honour of Domitian in the Circus of Maxentius (p. 352). The third fountain, at the S. end of the piazza, is adorned with masks, Tritons, and the statue of a Moor by *Bernini*.

On the W. side of the Piazza Navona stands the church of **S. Agnese**; the interior, in the form of a Greek cross, and the campanili, are by *C. Rinaldi*, and the tasteless façade by *Borromini*. The Romans used to maintain that the Nile on the great fountain veiled his head in order to avoid seeing this façade.

Over the principal door is the monument of Innocent X. by *Maini*; to the left, in the chapel of the transept, is a statue of St. Sebastian, adapted from an ancient statue by *Maini*. Beneath the dome are 8 columns of 'cotta-cello'. The old church was in the side-vaults of the Circus where the saint suffered martyrdom. Two subterranean chapels with ancient vaulting still remain, one of them containing a good relief of the Martyrdom of St. Agnes by *Algardi* (descent by a stair).

To the left of the church is the *Palazzo Pamphilj*, also erected by *Rinaldi*, now the property of *Prince Doria*. Opposite to it is the national church of the Spaniards, *S. Giacomo degli Spagnuoli* (Pl. II, 13, 23), erected in 1450, and recently restored.

On the S. side of the piazza is the *Pal. Braschi*, with the Pasquino (see p. 201). A little to the E. lie the *Pal. Madama* and the *Pantheon* (pp. 192, 193).

The *Via di S. Agnese*, to the right of the church, leads to the *Via dell' Anima* on the right, where on the left side is situated **S. Maria dell' Anima* (Pl. II, 13; open till 8½ a.m., on holidays till noon; when closed, visitors go round the church by the *Vicolo della Pace* on the right, and ring at the door of the Hospice, opposite *S. Maria della Pace*). The name is derived from a small marble-group in the tympanum of the portal: a Madonna invoked by two souls in purgatory. This is the German national church and was erected in 1500-14. Handsome façade by *Giuliano da Sangallo*. Part of the interior is said to have been designed by *Bramante*.

The Interior has lately been thoroughly restored. The central window of the entrance-wall formerly contained stained glass by *William of Marseilles*, now modern. The modern frescoes of saints on the ceiling are by *L. Seitz* (1875-82), and the stained-glass window over the chief portal was designed by him. — RIGHT AISLE. 1st Chapel: *St. Benno receiving from a fisherman the keys of the cathedral at Meissen (Saxony), which had been recovered from the stomach of a fish, altar-piece by *Carlo Saraceni*. 2nd Chapel: Holy Family, altar-piece by *Gimignani*; left, monument and bust of Card. Slusius. 4th Chapel: altered copy of *Michael Angelo's* Pietà in St. Peter's, by *Nanni di Baccio Bigio*. — LEFT AISLE. 1st Chapel: *Martyrdom of St. Lambert, *C. Saraceni*. 3rd Chapel: frescoes from the life of St. Barbara, *Mich. Cozzie*. 4th Chapel: altar-piece (Entombment) and frescoes by *Salviati*.

CHOIR. Over the high-altar, *Holy Family with saints, by *G. Romano*, damaged by inundations; on the right, *Monument of Hadrian VI. of Utrecht (preceptor of Charles V., d. 1523), with figures of justice, prudence, strength, and temperance, designed by *Baldassare Peruzzi*, executed by *Michelangiolo Sanese* and *Niccolò Tribolo*; opposite to it, that of a Duke of Cleve-Jülich-Berg (d. 1575) by *Egidius of Rivière* and *Nicolaus of Arras*. A relief in the ante-chamber of the sacristy (at the end of the N. aisle) represents the investiture of this prince by Gregory XIII. In the church, at the entrance to the sacristy, is the tomb of the learned Lucas Holstein of Hamburg, librarian of the Vatican (d. 1661).

The *German Hospice* connected with the church was under Austrian management from 1815 to 1863. Opposite the hospital rises the church of —

**S. Maria della Pace* (Pl. II, I, 13, 3), erected by Sixtus IV. (1484) and Innocent VIII., restored by Alexander VII., and provided by *Pietro da Cortona* with a façade and semicircular portico. The church consists of a domed octagon, with a short nave.

Over the 1st CHAPEL on the right are ****Raphael's* Sibyls: to the left the Sibyl of Cumæ; on the arch above, the Persian; then the Phrygian, and the aged Sibyl of Tibur, receiving from angels and recording revelations regarding the Saviour. They were painted in 1514 by order of Agostino Chigi, who erected the chapel, and skilfully freed from 'restorations' by *Palmaroli* in 1816 (best light, 10-11 a.m.; see also p. lvi).

'With perfect mastery of the art of utilising the space at his command, a talent admirably illustrated in the Stanze, Raphael has here filled up the segment of the arch so simply and naturally that the spectator is apt to overlook the consummate skilfulness of the grouping. Equally characteristic of Raphael are the rhythm of the composition, the display of spirited contrasts, and the delicate gradations and judicious dénouement of passionate emotions; while the gracefulness of the female forms and the sprightly beauty of the angel-boys are specially Raphaelesque. Michael Angelo's Sibyls are justly extolled as creations of a sublime imagination, striking the spectator with their supernatural majesty; but these female figures of Raphael are pre-eminently human and lovable'.

In the lunette above the Sibyls are the Prophets by *Timoteo Viti* (p. 97): on the right Jonah and Joshua, on the left Daniel and David.

At the sides of the 1st Chapel on the left are *Monuments of the Ponzetti family, of 1505 and 1509 (which should be compared with the heavy decorations of the 2nd chapel on the right, executed half-a-century later). *Altar-piece in fresco by *Bald. Peruzzi*: Madonna between St. Brigitta and St. Catharine, in front the donor Card. Ponzetti kneeling (1516). The vaulting above contains scenes from the Old and New Testament, in three rows, also by *Peruzzi*. — To the left, under the DOME, is the entrance to the sacristy and court (see below). Over the first altar on the left, Adoration of the Shepherds, by *Sermoneta*; above it, the Death of Mary, by *Moranda*. The second altar, with handsome marble-work, partly gilded, is of 1490. The high-altar is adorned with an ancient and highly revered Madonna; on the vaulting are pleasing 'putti' by *Albani*. Over the adjacent altar to the right, Baptism of Christ, by *Sermoneta*. Over the niche, Mary's first visit to the Temple, by *Bald. Peruzzi* (retouched). — Newly-married couples usually attend their first mass in this church.

The *MONASTERY COURT, constructed by *Bramante* (p. li) by order of Card. Caraffa in 1504, is interesting. On the ground-floor are arcades, above which runs a series of columns. By the right wall, the tomb of Bishop Boccaccio (d. 1437). Entrance through the church, or by *Via Arco della Pace* 5.

From the portal of the church the *Via della Pace* and the *Via in Parione* lead straight to the busy *Via del Governo Vecchio* (p. 201).

The *Via del Salvatore* leads to the E. from the Piazza Navona to the PIAZZA MADAMA, where, in front of us, rises the façade of the **Palazzo Madama** (Pl. II, 13), so called from Margaret of Parma, daughter of Charles V., by whom it was once occupied. Previously and subsequently it belonged to the Medicis, afterwards grand-dukes

of Tuscany, by whose orders *Marocelli* altered it to its present form in 1642. The Italian Senate now meets in this palace. One entrance is from the Piazza S. Luigi, the other from the Piazza Madama. The vestibule, court, and staircase contain antique statues, sarcophagi, reliefs, and busts. The large hall was adorned by *Maccari* in 1888 with frescoes representing Appius Claudius Cæcus, Regulus, Cicero, and Catiline.

Passing the left side of the palace (to the right to the Piazza S. Eustachio, p. 197), we reach the PIAZZA DI S. LUIGI DE' FRANCESI, to the right in which rises **S. Luigi de' Francesi** (Pl. II, 13), the national church of the French, consecrated in 1589, having been built on the site of several earlier churches. Façade by *Giac. della Porta*. It is one of the best buildings of its period, and the interior also is judiciously decorated. Some of the pictures are badly lighted.

RIGHT AISLE. 1st Chapel: St. John, altar-piece by *G. B. Natidini*. On the opposite pillar is a monument to French soldiers who fell at the siege of Rome in 1849. 2nd Chapel: *Frescoes from the life of St. Cecilia, one of the most admirable works of *Domenichino* (p. lix); on the right the saint distributes clothing to the poor; in the lunette above, she and her betrothed are crowned by an angel; on the left the saint suffers martyrdom with the blessing of the Pope; above, she is urged to participate in a heathen sacrifice; on the ceiling, admission of the saint into heaven; altar-piece, a copy of *Raphael's* St. Cecilia (in Bologna) by *Guido Reni*. 4th Chapel, of St. Remigius: altar-piece, the Oath of Clovis, by *Giac. del Conte*; frescoes on the right, Campaign of Clovis, by *Girot. Sicciotante (da Sermoneta)*; on the left, Baptism of Clovis, by *Pellegrino da Bologna*. 5th Chapel, del Crocifisso: on the left the monument of the painter Guérin (d. 1833), on the right that of Agincourt (d. 1814), the writer on art. — Over the high-altar: *Assumption, by *Franc. Bassano*.

LEFT AISLE. 1st Chapel: St. Sebastian, altar-piece by *Massei*; on the right and left modern frescoes; by the first pillar on the right the monument of Claude Lorrain, erected in 1836. 3rd Chapel, of St. Louis: altar-piece by *Plautilla Bricci*, who is said to have designed the architecture also; picture on the left by *Gimignani*. 5th Chapel, of St. Matthew: altar-piece and pictures on the right and left by *Caravaggio*, on the left the Evangelist's vocation to the apostleship, on the right his death.

From the Piazza S. Luigi to the N. to the Via della Scrofa and S. Agostino, see p. 189. In a straight direction we proceed through the *Via Giustiniani* to the PIAZZA DEL PANTHEON (Pl. II, 16). Above the large *Fountain*, erected by Lunghi under Gregory XIII., was placed the upper end of a broken obelisk by order of Clement XI. This piazza generally presents a busy scene (comp. p. 122).

On the S. side of the piazza rises the church of *S. Maria Rotonda*, or the ****Pantheon**, the only ancient edifice at Rome which is still in perfect preservation as regards the walls and the vaulting. The original statues and architectural decorations have long since been replaced by modern and inferior works, but the huge circular structure with its vast colonnade still presents a strikingly imposing appearance. The walls, constructed of admirable brickwork, 20 ft. in thickness, were originally covered with marble and stucco. The ground in the environs has gradually been so much raised that the pavement of the temple, to which five steps formerly ascended, now lies below the level of the piazza. Excavations made in 1875 in

front of the edifice, which led to the discovery of two fine marble reliefs, have been filled up again as they interfered with the street traffic.

The PORTICO (36 yds. wide, 14 yds. deep) is borne by 16 Corinthian columns of granite, 13 ft. in circumference, and 39 ft. in height; the tympanum formerly contained reliefs, and the roof was embellished by statues. Eight of the columns are in front; the others form three colonnades, originally vaulted over, terminating in niches, in which stood the colossal statues of Augustus and his son-in-law M. Agrippa. The latter, according to the inscription on the frieze (*M. Agrippa L. F. Cos. tertium fecit*), caused the edifice to be erected B.C. 27. Pope Urban VIII. (Barberini) removed the brazen tubes on which the roof rested, and caused them to be converted into columns for the canopy of the high-altar of St. Peter's and cannons for the defence of the castle of S. Angelo. This Vandalism gave rise to the epigram of Pasquin, '*Quod non fecerunt barbari, fecerunt Barberini*'. The two campanili, the 'ass's ears', as they were derisively termed, erected by Bernini under the same pope, were removed in 1883. — The central colonnade leads to the ENTRANCE, with its ancient door strongly secured by bronze plates, in order to diminish the weight of which the upper portion is replaced by a railing.

The INTERIOR, lighted by a single aperture in the centre of the dome, produces so beautiful an effect that it was currently believed at an early period that the temple derived the name of *Pantheon*, which was applied to it as early as A.D. 59, from its resemblance to the vault of heaven (comp. p. xxxvi). The height and diameter of the dome are equal, being each 140 ft. The diameter of the opening is 30 ft. The surface of the walls is broken by 7 large niches, in which stood the statues of the gods, including, as has been ascertained, those of Mars, Venus, and Cæsar. The architrave is borne by fluted columns of giallo antico or pavonazzetto in couples, the shafts being 26 ft. in height. Above the latter, and corresponding with the niches, formerly rose a series of round arches, borne by Caryatides, but they appear to have been removed during a very early restoration of the edifice. The white marble, porphyry, and serpentine decorations of the Attica or Attic story remained in part till 1747, when they were barbarously covered with whitewash. The coffered ceiling of the vault, which consists of concrete, was decorated with gold-leaf, and the whole roof was covered with gilded bronze tiles, which the Emp. Constantine II. removed to Constantinople in 655. Under Gregory III. these tiles were replaced by lead. The building has frequently been restored, as, for example, by Domitian, Trajan, Septimius Severus, and Caracalla. The names of the last two are recorded by an inscription on the architrave of the portico.

In 609 the Pantheon was consecrated by Pope Boniface IV. as a Christian church, under the name of *S. Maria ad Martyres* (p. 358),

and in commemoration of the event the festival of All Saints was instituted (13th May, but afterwards celebrated on 1st Nov.). A palace, a cathedral-chapter, and a cardinal's title were afterwards attached to the church, which is generally known as *S. Maria Rotonda*, or *La Rotonda*.

In the second recess to the right of the high-altar is the burial vault of king *Victor Emmanuel II.* (d. Jan. 9, 1878). In the first Chapel to the left of the high-altar stands the simple monument of *Card. Consalvi* (buried in S. Marcello, p. 157), by *Thorvaldsen*.

To the left of the 3rd altar is *Raphael's Tomb* (b. 6th Apr., 1483; d. 6th Apr., 1520). On the wall is the graceful epigram composed by *Card. Bembo*:—

Ille hic est Raphael, timuit quo sospite vinci

Rerum magna parens, et moriente mori.

The Italian translation runs thus:—

'Questi è quel Raffaele, cui vivo vinta

Esser temeava Natura, e morto estinta'.

A lengthy inscription beside it announces that Raphael's remains were placed in a new sarcophagus in 1833. The statue of the Madonna on the altar, by *Lorenzetto*, was executed in accordance with Raphael's last will.

The Pantheon is also the last resting-place of Ann. Carracci, Taddeo Zuccaro, Bald. Peruzzi, Perino del Vaga, Giov. da Udine, and other celebrated artists. The altars and recesses are adorned with paintings and sculptures of the 18th century.

A visit to the interior by *moonlight* is recommended, but for this, as for the ascent of the dome, a special permesso must be obtained.

At the back of the Pantheon lie the ruins of the *Thermae of Agrippa*, which, however, have no connection with it. A large part of these baths was exhumed in 1881-2; and the rear wall of a large hall, with recesses, was brought to light in the *Via della Palombella*. A fluted column and a finely executed frieze (shells and dolphins) have been found and placed in position. Along the E. side of the Pantheon extended a kind of colonnade, of which considerable remains are extant.

From the Piazza of the Pantheon the *Via de' Pastini* leads towards the E. to the Piazza di Pietra (p. 155); or we may turn to the left (N.), cross the *Piazza Capranica*, with the small theatre of that name, and reach Monte Citorio (p. 155); or, lastly, we may follow the *Via del Seminario*, also towards the E., to S. Ignazio (p. 155).

Behind the Pantheon lies the PIAZZA DELLA MINERVA (Pl. II, 16), where the church of S. Maria sopra Minerva lies on the left, and the Hôtel de la Minerve opposite to us. In the centre of the piazza is a marble elephant, on the back of which a small ancient Obelisk was placed by *Bernini* in 1667 (p. 196).

***S. Maria sopra Minerva**, erected on the ruins of a temple of Minerva founded by Domitian, the only ancient Gothic church at Rome, was probably begun about 1285 by the builders of S. Maria Novella at Florence (p. xlviii). It was restored and re-decorated with painting in 1848-55, and contains several valuable works of art.

Interior. By the entrance-wall, on the right, the tomb of the Florentine knight Diotisalvi (d. 1482). — **LEFT AISLE.** On the left, the tomb of the Florentine Franc. Tornabuoni, by *Mino da Fiesole*; above it the monument of *Card. Giac. Tebaldi* (d. 1466). To the right of the altar in the 3rd Chapel, ***S. Sebastian**, by *Mino da Fiesole* (?). Over the altar: head of Christ, by *Pe-*

rugino. In the 5th Chapel is (r.) the monument of the Princess Lante, by *Tenerani*. — **RIGHT AISLE.** By the pillar between the 3rd and 4th chapels is an egress (generally closed) with an ancient Greek sarcophagus (Hercules taming the lion). In the 4th Chapel, the "Annunciation, a picture on a golden ground (in the foreground Card. Giov. a Torrecremata recommending three poor girls to the Virgin), painted to commemorate the foundation of the charitable institution of S. Annunziata and erroneously attributed to *Fra Angelico*; on the left the tomb of Urban VII. (d. 1590), by *Ambr. Baonvicino*. The 5th Chapel (*Aldobrandini*) contains paintings by *Alberti*; over the altar the Last Supper by *Baroccio*; monuments of the parents of Clement VIII. by *Giac. della Porta*. — **RIGHT TRANSEPT.** A small chapel on the right is first observed, containing a wooden crucifix attributed to *Giotto*; then the "Caralla Chapel (recently restored), with a handsome balustrade, painted by *Filippino Lippi*; on the right Thomas Aquinas, surrounded by allegorical figures, defending the Catholic religion against heretics; in the lunette, St. Thomas and the Miracle of the Cross; on the wall at the back, the Assumption of the Virgin; altar-fresco, the Annunciation, with a portrait of the donor Card. Caralla; sibyls on the vaulting by *Rafaellino del Garbo*; on the left the monument of Paul IV. (d. 1559), designed by *Pirro Ligorio*, executed by *Giac. and Tom. Casignola*. By the wall, adjacent to the latter, the "Tomb of Bishop Guiliel. Durantus (d. 1296), with a Madonna in mosaic by *Johannes Cosmas*, one of the best works of that period. The first chapel by the choir contains an altar-piece by *C. Maratta*. The second is the Cappella del Rosario; altar-piece groundlessly attributed to *Fra Angelico*; on the right the tomb of Card. Capranica (about 1470). — The CHoir contains the large monuments of the two Medicis, (l.) Leo X. and (r.) Clement VII., designed by *Ant. da San Gallo*; that of Leo executed by *Raffaele da Monte Lupo*, that of Clement by *Giov. di Baccio Bigio*; on the pavement the tombstone of the celebrated scholar Pietro Bembo (d. 1547).

In front of the high-altar, to the left, is *Michael Angelo's* "Christ with the Cross, which was ordered by Metello Vari and P. Castellari in 1514, and erected in 1521. *Pietro Urbano*, an assistant of the great master, was entrusted with the touching up of the work after its erection, but as he acquitted himself badly of his task, the finishing strokes were given to it by *Roderigo Frizzi*. The nudity of the figure is justified by the master's intention to portray the Risen Christ, but it is now marred by a bronze drapery; the right foot also is protected against the kisses of the devout by a bronze shoe (comp. p. li).

On the left by the choir is a passage to the Via S. Ignazio; on the wall the tombstone (first on the left) of Fra Beato Angelico da Fiesole, who died in the neighbouring monastery in 1455, with his portrait and the inscription: *Hic jacet Venerabilis pictor Frater Joannes de Florentia Ordinis prae-dicatorum 14 LV.* — In the LEFT TRANSEPT is the Chapel of S. Domenico, with 8 black columns, and the monument of Benedict XIII. (d. 1730) by *P. Bracci*. Adjacent, to the right, is the entrance to the sacristy.

The adjoining Dominican monastery, formerly the residence of the chief of the order, now contains the offices of the *Minister of Education* and the *Bibliotheca Casanatensis* (entrance to the left by the church, first door to the right beyond the court; adm. see p. 116). The library is the largest in Rome after that of the Vatican, consisting of 200,000 vols. and 1000 MSS.

The space between the Piazza del Collegio Romano and the Piazza S. Ignazio was occupied in antiquity by a famous *Temple of Isis*, and the excavations on this site have brought numerous remains of antiquity to light. Among these are the lions, sphinxes, and canopi in the Capitoline Museum (p. 216), and the obelisks now in the Piazza della Rotonda (p. 193), the Piazza della Minerva (p. 195), and the Piazza Termini (p. 166).

The *Via de' Staderari* leads to the right from the Piazza Madama (p. 193), passing the palace, to the PIAZZA S. EUSTACHIO. Here stands the —

Università della Sapienza (Pl. II, 13, 25; entrance *Via della Sapienza* 71), founded in 1303 by Boniface VIII., and after a rapid decline re-established by Eugene IV. It attained its greatest prosperity under Leo X., and under Leo XII. and Gregory XVI. possessed five faculties, but there are now four only (law, medicine, physical science, and philology). It contains several natural history collections and the *Biblioteca Alessandrina*, a library of more than 10,000 vols., which is open daily (p. 116). The present building was designed by *Giac. della Porta*. The church (*S. Ivo*), with its grotesque spiral tower, was designed by *Borromini* in the form of a bee, in honour of Urban VIII., in whose armorial bearings that insect figures.

The *Via della Palambella* leads hence in a straight direction to the *Pantheon* (p. 193); the *Via della Valle*, to the right, leads to *S. Andrea* and the *Corso Vittorio Emanuele* (see below).

The wide **Corso Vittorio Emanuele** (Pl. II, 16, 13, 10), recently constructed through the most closely built quarters of mediæval Rome, is a continuation of the *Via Nazionale*, described at pp. 169, 170, and facilitates communication between the *Piazza Venezia* (p. 162), in the centre of the city, and the *Ponte S. Angelo*. On the left is the main façade of the *Pal. di Venezia* (p. 162), and on the right rise the *Palazzi Bonaparte* (p. 162), *Doria* (p. 158), and *Graziotti*. We next reach the *Pal. Altieri*, with its extensive façade, erected in 1670, bounding the N. side of the small PIAZZA DEL GESÙ (Pl. II, 16), which is called after the church of that name.

***Gesù**, the principal church of the Jesuits, is one of the most gorgeous in Rome. It was built by *Vignola* and *Giac. della Porta* by order of Card. Alessandro Farnese, in 1568-77. Comp. p. lviii.

In the NAVE is a *Ceiling-painting by *Baciccio*, by whom the dome and tribune were also painted, one of the best and most lifelike of the rococo works of that period. The walls were covered with valuable marble at the cost of the Principe Aless. Torlonia in 1860. On the high-altar, with its four columns of giallo antico: Christ in the Temple, by *Capatti*; on the left the monument of Card. Bellarmino with figures of Religion and Faith, in relief; on the right the monument of P. Pignatelli, with Love and Hope. — In the TRANSEPT, to the left: *Altar of St. Ignatius with a picture by *Pozzi*, under which a silver-plated relief, representing St. Ignatius surrounded by angels, is said to be concealed. The original silver statue of the saint, by *Le Gros*, which was formerly here, is said to have been removed on the suppression of the order in the eighteenth century. The columns are of lapis lazuli and gilded bronze; on the architrave above are two statues: God the Father, by *B. Ludovisi*, and Christ, by *L. Ottoni*, behind which, encircled by a halo of rays, is the emblematic Dove. Between these the globe of the earth, consisting of a single block of lapis lazuli (said to be the largest in existence). Beneath the altar, in a sarcophagus of gilded bronze, repose the remains of the saint. On the right and left are groups in marble; on the right the Christian Religion, at the sight of which heretics shrink, by *Le Gros*; on the left Faith with the Cup and Host, which a heathen king is in the act of adoring, by *Théodon*. Opposite, in the transept, on the right, the altar of St. Francis Xavier.

The church presents a most imposing sight on 31st Dec., on the festival of St. Ignatius, on 31st July, and during the *Quarant'ore* (two last days of the Carnival), on which occasions it is brilliantly illuminated in the evening. During Advent and Lent, and generally at other seasons also, sermons are preached here at 11 a. m., often by priests of great ability.

Adjoining the church is the former *Casa Professa* of the Jesuits, now a barrack, adjacent to which, *Via di Araceli* 1 A, is the entrance to the rooms of St. Ignatius (Mon., Wed., Frid., 9-11). On the opposite side of the street is the *Palazzo Bolognetti* (Pl. I, 16, 3). — Passing the monastery, and following the *Via di Araceli*, we reach (5 min.) the *Piazza di Araceli*, at the foot of the Capitol (p. 208). — From the opposite angle of the *Piazza del Gesù*, the *Via del Gesù* leads to the right in 5 min. to the *Piazza della Minerva* (p. 195).

The lofty dome in front of us in the *Corso Vittorio Emanuele* belongs to the church of S. Andrea della Valle (see below). A few hundred paces to the W. of the *Piazza Gesù* the *Corso* is crossed by the *Via di Tor Argentina*, leading on the right to the Pantheon (p. 193) and on the left to the new *Ponte Garibaldi* (p. 202).

The small *VIA DEL SUDARIO* (Pl. II, 13), diverging from the *Corso* to the left at this point, first passes the *Teatro Argentina* on the left, and then, at the corner on the right (No. 13), the *Palazzo Vidoni*, formerly *Caffarelli* and *Stoppani*, originally designed by Raphael. Charles V. resided here in 1536 as the guest of the *Caffarelli*. On the staircase is the so-called *Abbate Luigi*, a Roman figure in a toga, formerly placed at the N. angle of the palace, facing S. Andrea della Valle, and used as the bearer of lampoons and pasquinades (comp. p. 163). In one of the rooms is the *Calendarium Praenestinum* of Verrius Flaccus, being five months of a Roman calendar found by Card. Stoppani at Palestrina. Admission not easily obtained.

Farther on in the *Corso Vittorio Emanuele* is the church of *S. Andrea della Valle (Pl. II, 13), begun by P. Olivieri in 1591 on the site of several earlier churches, and completed by C. Maderna. Façade designed by Carlo Rainaldi. The interior is well proportioned, but part of it has been whitewashed. See p. lviii.

On the right the *2nd Chapel (Srozzini) contains copies in bronze of the *Pietà* (in St. Peter's) and the *Rachel* and *Leah* (in S. Pietro in Vinc.) of *Michael Angelo*, by whom this chapel itself was perhaps designed. — On the left the 1st Chapel (BARBERINI) is adorned with several marble statues of the school of Bernini: St. Martha by *Mocchi*, John the Baptist by *Pietro Bernini*, Mary Magdalene by *Stati da Bracciano*, and St. John by *Buonvicino*. — At the end of the NAVE are the monuments of the two popes of the Piccolomini family, brought here from the old church of St. Peter; on the left that of Pius II. (d. 1464), by *Nic. della Guardia* and *Pietro Paolo da Todi*; on the right that of Pius III. (d. 1503), executed somewhat later. — In the DOME: Glory of Paradise, by *Lanfranco*; below, the *Evangelists by *Domenichino*, one of his finest works. By the same master, *Paintings on the vaulting of the apse. In front, between the transverse ribs: John the Baptist, St. John, and St. Andrew pointing to Christ (Gospel of St. John, 1. 35); in the vaulting itself, on the left, the Scourging of St. Andrew; then the Vocation of Peter and Andrew by Christ; on the right, St. Andrew beholds and reveres the cross to which he is about to be affixed; below are six female figures representing the virtues (p. lix). The large lower frescoes by *Calabrese* (martyrdom of the saint) are of no great value.

Opposite this church opens the small *Piazza della Valle*, containing the *Palazzo Capranica*, which is occupied by the Prussian

envoy to the Vatican.¹ The *Via della Valle* leads to the Piazza S. Eustachio (p. 197).

No. 141 in the Corso Vitt. Emanuele, to the right, is the **Palazzo Massimi alle Colonne** (Pl. II, 13, 11), a fine structure by *Baldassare Peruzzi*, who, however, died in 1536 before its completion. The arc-shaped façade was skilfully adapted to the curve of the originally narrow street, but has lost its effect by the construction of the wide Corso. The glimpse obtained of the double court is strikingly picturesque. On the second floor is the *Chapel of S. Filippo Neri* (open on 16th March)¹, who is said to have here resuscitated a child of the family.

In 1467, within the buildings connected with this palace, the Germans *Pannartz* and *Schweinhelm*, who during the two previous years had found an asylum in the monastery of Subiaco (p. 381), established the first printing-office in Rome, from which they issued Cicero's epistles and other works, furnished with the name of the printers and the words '*In aedibus Petri de Maximis*'. — The Massimi family claims descent from the ancient Fabii Maximi, and their armorial bearings have the motto '*Cunctando restituit*'.

Farther on is the small PIAZZA DI S. PANTALEO (Pl. II, 13), containing (right) the small church of that name, with a façade erected by *Valadier* in 1806. The *Via Cuccagna*, to the right, ends at the Piazza Navona (p. 190). For the *Via di S. Pantaleo*, also diverging to the right from the Corso, and its continuation the *Via del Governo Vecchio*, see p. 201.

On the left side of the Corso Vitt. Emanuele, at the point where the *Via Baullari* diverges to the Palazzo Farnese (p. 205), is the little *Palazzo Linotta* or *Palazetto Farnese*, of which *Bald. Peruzzi* is said to have been the architect. Tasteful but sadly dilapidated court and staircase. — The Corso here bends a little to the N.W. and discloses a view of the dome of St. Peter's.

To the left lies the long and narrow PIAZZA DELLA CANCELLERIA (Pl. II, 13), with the palace of that name and the church of S. Lorenzo in Damaso.

The ***Palazzo della Cancelleria** (Pl. II, 13), an edifice of majestic simplicity, designed by *Bramante* in strict conformity with the ancient orders of architecture, is one of the finest palaces in Rome (p. li). The elegant FAÇADE is constructed of blocks of travertine from the Colosseum. The chief portal, in an inharmonious baroque style, was added by *Domenico Fontana*. It leads into the *COURT, in two stories, surrounded by arcades. The columns originally belonged to the ancient basilica of S. Lorenzo, from which they were removed by *Bramante* (see p. 200). The graceful capitals are decorated with roses, a flower which belonged to the armorial bearings of the founder Card. Riario. To the right is an archway leading to the church of S. Lorenzo. This is the only palace in the interior of the city which the Italian government still permits to be occupied by the ecclesiastical authorities.

The N. part of the Cancelleria is occupied by the church of **S. Lorenzo in Damaso**, which has the above-mentioned façade in common

with the palace. The handsome portal is by *Vignola*. The church was originally founded by Damasus I. (ca. 370) near the Theatre of Pompey, but it was taken down in 1495 at the instance of Card. Riario and rebuilt here from a design by *Bramante*. The internal decoration is quite modern, dating from the time of Pius VII. (1820) and Pius IX. At the end of the right aisle is the tomb of the papal minister Count Rossi, who was assassinated on the staircase of the Palazzo della Cancelleria in 1848 (bust by *Tenerani*).

From the Cancelleria to the *Campo di Fiori*, see p. 204.

We continue to follow the Corso Vitt. Emanuele. At the corner of the second street to the right is the *Palazzo Sora*, formerly erroneously ascribed to Bramante, and frequently altered. — To the right stands the —

Chiesa Nuova (Pl. II, 10), or *S. Maria in Vallicella*, erected by S. Filippo Neri (about 1550-1605) for the order of Oratorians founded by him. Architecture by *Giov. Matteo da Città di Castello*, interior by *Mart. Lunghi the Elder*, façade by *Rughesi*.

The Interior, which is dark and unfavourable for pictures, is richly decorated. The admirable stucco-work is by *Cos. Faniello* and *Ercole Ferrata*. The ceiling of the NAVE, the dome, and the tribune are painted by *Pietro da Cortona*. — On the right, 1st Chapel, Crucifixion, *Scip. Gaetano*; 3rd Chapel, dell' Ascensione, altar-piece by *Muziano*. — On the left, 2nd Chapel, Adoration of the Magi, *Ces. Nebbia*; 3rd Chapel, Nativity, *Durante Alberti*; 4th Chapel, Visit of Elizabeth, *Baroccio*. — LEFT TRANSEPT: Presentation in the Temple, *Baroccio*; Peter and Paul, statues in marble, by *Valsoldo*. Here also, adjoining the tribune, is the small and sumptuous CHAPEL OF S. FILIPPO NERI, beneath the altar of which his remains repose. Above is the portrait of the saint in mosaic, after the original of *Guido Reni* preserved in the adjoining monastery. — Over the HIGH ALTAR, with its four columns of porta santa, a Madonna by *Rubens*; on the right *SS. Gregory, Maurus, and Papia, on the left *SS. Nereus and Achilleus, also by *Rubens*, who painted these pictures during his second stay in Rome in 1606 for this church, which was then the most fashionable in the city. — RIGHT TRANSEPT. On the right, Coronation of Mary, *Cav. d' Arpino*; SS. John the Baptist and John the Evangelist, statues in marble by *Flaminio Vacca*.

The SACRISTY (entered from the left transept) was constructed by *Marucelli*. On the vaulting: Angel with instruments of torture, by *Pietro da Cortona*. Colossal statue of the saint by *Algardi*.

On 26th May, the festival of the saint, and after Ave Maria every Sunday from 1st Nov. to Palm Sunday, concerts of sacred music, to which men only are admitted, are given in the adjoining *Oratorium*, which derives its name from the oratories fitted up by S. Filippo Neri. The saint was fond of music and advocated a cheerful form of divine service.

The adjoining *Monastery*, erected by *Borromini*, is of irregular shape, but remarkably massive in its construction. It contains a room once occupied by the saint, with various relics. The *Corte di Appello*, the *Tribunale Civile e Correzionale*, and the *Tribunale di Commercio* are now established here. — The valuable *Bibliotheca Vallicellana*, founded by S. Filippo Neri, and gradually enriched by rare MSS., now belongs to the 'Società Romana di Storia Patria' and is accessible without special permission (p. 116; entr. in the court, to the left at the top of the great staircase).

Farther on, to the left, lies the small PIAZZA SFORZA (Pl. II, 10).

with the *Bohemian Hospital*, the façade of which is adorned with sgraffiti. — The Corso Vitt. Emanuele is being continued to S. Giovanni de' Fiorentini (p. 207). In the meantime we may follow the *Via de' Banchi Vecchi*, to the right, to the Ponte S. Angelo (p. 274).

From the Piazza S. Pantaleo (p. 199) the VIA S. PANTALEO (Pl. II, 13) runs towards the N.W. No. 9 in this street, on the right, is the spacious **Palazzo Braschi**, erected by *Morelli* at the end of last century, and now occupied by the *Minister of the Interior*. It contains a fine marble *Staircase and a few ancient statues. The back of the building looks towards the Piazza Navona (p. 190).

Passing the palace, we reach the PIAZZA DEL PASQUINO (Pl. II, 13), which derives its name from an ancient group of statuary placed at the obtuse angle of the Pal. Braschi. This was an admirable, but now sadly mutilated work of a good period of art, and is said to have been called *Pasquino* as early as the end of the 15th cent. after a tailor of that name who lived in the vicinity and was notorious for his lampooning propensities. It was once the custom to affix satires and ebullitions of malice to this statue, the answers to which used to be attached to the Marforio (p. 162, 216), and to refer them to the slanderous tailor, whose name is perpetuated in the word 'pasquinade'. Compositions of this kind have been much in vogue at Rome ever since that period, sometimes vying with the best satires of antiquity. The group represents Menelaus with the body of Patroclus, looking around for succour in the tumult of battle. Duplicates of the group are in the Loggia de' Lanzi and the Palazzo Pitti at Florence, and there are fragments in the Vatican (p. 309).

We follow the VIA DEL GOVERNO VECCHIO, in which, on the right, is the *Pal. del Governo Vecchio* (Pl. II, 13, 20), which for a time was occupied by the law and police courts. No. 124, opposite, is an elegant little house in Bramante's style, built in 1500 for the papal secretary J. P. Turcius.

We next pass the back of the *Philippine Convent* (now a court-house, p. 200) and cross the *Piazza dell' Orologio*, whence the *Via Monte Giordano* leads to the *Palazzo Gabrielli*, with a pretty fountain in its court. [Thence the *Via di Panico* leads to the Ponte S. Angelo.]

The *Via del Governo Vecchio* now takes the name of *Via de' Banchi Nuovi* and ends at the *Via del Banco di S. Spirito*, through which we may proceed to the Ponte S. Angelo (p. 274; 12 min. from the Piazza S. Pantaleo).

From the Corso Vitt. Emanuele the important VIA DI TOR ARGENTINA, mentioned at p. 198, leads to the S. to the Tiber. Following it from the *Via Nazionale* we reach in 5 min. the piazza and church of **S. Carlo a' Catinari** (Pl. II, 14), built by *Rosati* in 1612

in honour of S. Carlo Borromeo, in the form of a Greek cross, with a dome.

1st Chapel on the right: Annunciation, by *Lanfranco*. In the spaces below the dome are the four cardinal virtues, by *Domenichino*. In the transept to the right, Death of St. Anna, *Andrea Sacchi*. Over the high-altar, Card. Borromeo in the procession of the plague at Milan, *P. da Cortona*; tribune decorated by *Lanfranco*. The other paintings are inferior. Through the Via Giubbonari to *Pompey's Theatre*, see p. 205.

Beyond S. Carlo a' Catinari the Via di Tor Argentina (hitherto here called the *Via di Mortella*) leads to the S. to the new *Ponte Garibaldi* (p. 330). Two side-streets lead to the E. to the *Pal. Cenci-Bolognetti* (Pl. II, 14, 17) and to the old Ghetto (see p. 203). The *Pal. Cenci* was the home of ill-fated Beatrice Cenci, who was executed in 1599 for the murder of her father, a man of execrable character. Her portrait in the *Pal. Barberini* (p. 171) is frequently copied by Roman artists.

The *Via dei Falegnami* runs to the E. from S. Carlo a' Catinari to the small *PIAZZA TARTARUGA* (Pl. II, 17), named after the graceful **Fontana delle Tartarughe* (tortoises), erected by *Giac. della Porta* in 1585, and embellished with bronze figures of four youths, by the Florentine *Taddeo Landini*. This is the most charming fountain in Rome; the design was formerly attributed to Raphael.

Farther on, to the left, is the **Palazzo Mattei** (Pl. II, 17, 27), originally an aggregate of separate buildings which occupied the block between S. Caterina de' Funari and Via Paganica. Of these the handsomest is the present so-called palace (principal entrance, Via di S. Caterina de' Funari 32; side-entrance, No. 31), erected in 1616 by *Carlo Maderna*, and one of his finest productions.

In the passages of the entrance, in the arcades, and along the sides of the COURT, a great number of ancient reliefs are built into the walls. In the court are (r.) Mars with Rhea Silvia, and Apollo with the Muses; and (l.) the Calydonian hunt and Rape of Proserpine. In the portico, Sacrifice of Mithras, Apollo with the Muses, and a Bacchanalian procession, all from sarcophagi. The statues in the court and niches on the staircase, some of them much modernised, are of no great value. The stucco decorations of the ceiling on the staircases are well executed.

Farther on, in the Via de' Falegnami, we observe on the left, within the ancient *Circus Flaminius*, the church of **S. Caterina de' Funari** (Pl. II, 17), erected in 1564 by *Giac. della Porta*, with a singular-looking tower. It contains a few unimportant pictures by *A. Carracci* (1st chapel on the right), *Nanni*, *Venusti*, *Muziano*, and *Agresti*. The name of the church is derived from the rope-makers who in the middle ages plied their vocation within the circus. The adjoining Augustine nunnery contains a girls' school.

The Via de' Falegnami ends at the *Palazzo Righetti* (Strozzi, Pl. II, 17, 16), where the Via Delfini leads to the left to the Via di Araceli (p. 163), while the street to the right leads to the *PIAZZA CAMPITELLI*. Here, on the right, is **S. Maria in Campitelli** (Pl. II, 17), erected by *Rainaldi* under Alexander VII. for the reception of a miraculous image of the Virgin, to which the cessation of the plague

in 1656 was ascribed. A smaller church of the same name, mentioned in the 13th cent., formerly stood on this site.

The INTERIOR, with its handsome projecting columns, is effective. — Beneath the canopy over the HIGH-ALTAR is placed the miraculous Madonna. In the 2nd Chapel on the right, the Gift of Tongues, by *Luca Giordano*; in the 1st Chapel on the left, two monuments resting on lions of rosso antico. In the S. transept is the tomb of Card. Pacca by *Pettrich*.

From the S.E. end of the Piazza Campitelli the *Via di Tor de' Specchi*, skirting the foot of the Capitol, leads to the left to the Piazza Araceli (p. 209), while the *Via Montanara* runs to the right to the small but busy PIAZZA MONTANARA (Pl. II, 17), much frequented by the country-people, especially on Sundays (tramway to S. Paolo Fuori, see Appx.).

In the Piazza Montanara, to the right, stands the Theatre of **Marcellus** (Pl. II, 17, 5), which was begun by Cæsar, and completed in B.C. 13 by Augustus, who named it after his nephew, the son of Octavia. Twelve arches of the outer wall are now occupied by smiths and other artizans as workshops. The lower story, partly filled up, is in the Doric, the second in the Ionic style, above which, as in the Colosseum, a third probably rose in the Corinthian order. It is said to have accommodated 20,000 spectators. The stage lay towards the Tiber. In the 11th cent. the theatre was used by *Pier-leone* as a fortress. To his descendants succeeded the *Savelli*, whose palace stands on a lofty mound of debris within the theatre. In 1712 the palace was purchased by the *Orsini*, and in 1816-23 was occupied by the historian Niebuhr, when Prussian ambassador. — From the Piazza Montanara the busy *Via Bocca della Verità* leads to S. Maria in Cosmedin (p. 249).

To the W. of the Theatre of Marcellus, extending as far as the Pal. Cenci, lay the **Ghetto** (Pl. II, 17), the quarter allotted by Paul IV. to the Jews, who in ancient and mediæval times occupied a quarter in Trastevere. The quarter, which was formerly closed by gates, was, however, entirely pulled down in 1887. Along the N. edge of it runs the *Via della Pescaria*, in which, immediately to the N.W. of the Pal. Orsini and the Theatre of Marcellus, are the interesting remains of the **Portico of Octavia** (Pl. II, 17, 18), erected by Augustus on the site of a similar structure of Metellus (B. C. 149), and dedicated to his sister. Under Titus it was destroyed by a fire which raged in this quarter of the city, but it was restored by Sept. Severus and Caracalla in 203, as the inscription records. The principal entrance consisted of a vestibule with eight Corinthian columns, of which two in the inner, and three in the outer row are still standing. To the right and left of this were double rows of 14 columns each, while there were at least 40 columns in a row at the sides. The entire colonnade, with its 300 columns, enclosed an oblong space, within which stood temples of Jupiter Stator and Juno. Columns from this structure are frequently seen built into other edifices. It was adorned with many admirable works of art

which formed part of the Macedonian booty, and it was here that the Medici Venus was found. In 770 the church of *S. Angelo in Pescaria* was built on the ruins of the colonnade by Stephen III., but, having been frequently restored, it has lost its mediæval character. A papal bull, issued in 1584, formerly compelled the Jews to hear sermons here on their Sabbath, when the Old Testament was expounded to them in accordance with the doctrines of the church.

The new street to the S. of the Portico of Octavia and to the W. of the Pal. Orsini leads to the **Ponte de' Quattro Capi** (Pl. II, 17), the oldest bridge now in Rome, built in B.C. 62 by *L. Fabricius*, as the inscription records. The name is derived from the four-headed figures on the balustrades. It is now, however, sometimes called the *Ponte Fabricio*. Fine view.

On the island (*Isola Tiberina* or *di S. Bartolomeo*) to which the bridge leads is a small piazza, embellished in 1869 with a monument to SS. John, Francis, Bartholomew, and Paulinus. Here, perhaps on the site of an ancient temple of *Æsculapius*, is situated the church of —

S. Bartolomeo (Pl. II, 18), erected about the year 1000 by the Emp. Otho III. in honour of St. Adalbert of Gnesen, and erroneously named *S. Bartolomeo*. The emperor had desired the Beneventans to send him the relics of St. Bartholomew, but received those of St. Paulinus of Nola in their stead. The present church, with the exception of the campanile, is modernised and uninteresting; façade by *Lunghi*, 1625.

The INTERIOR contains fourteen ancient columns; in the choir, remains of an early mosaic. In the centre of the steps leading to the presbyterium is the mouth of a fountain of the 12th cent., on which a figure of Christ with a book in his hand, and the heads of two side-figures are alone distinguishable.

In the small GARDEN OF THE MONASTERY (visitors ring at the entrance to the right by the church) is seen part of the ancient bulwark of travertine which gave the island the appearance of a ship. An obelisk represented the mast. The figure of a snake hewn on the bow of the ship is a reminiscence of the story that the Romans, when sorely afflicted by the plague, sent for *Æsculapius* from Epidaurus in B.C. 293, and that a snake, a reptile sacred to the god, concealed itself in the vessel, and on reaching the harbour escaped to this island, which was dedicated to *Æsculapius* in consequence. That the god was worshipped here has been proved by the discovery in the island of limbs in terracotta, which were presented by sick persons as votive offerings.

The island was connected with Trastevere by the ancient *Pons Cestius* (*Gratianus*; Pl. II, 18), which was built by Augustus, and restored by the Emperors Valentinian and Gratian. This bridge is now being rebuilt, and the traffic is served by a temporary wooden structure at the S. end of the island (p. 331).

To the S. of the Pal. della Cancelleria (p. 199) lies the **PIAZZA CAMPO DI FIORE** (Pl. II, 13), an important centre of business, espe-

cially since the vegetable-market, with the picturesque country-people who frequent it in the morning, was transferred hither from the Piazza Navona. Heretics and criminals used to be put to death here. Among the former was the celebrated philosopher and free-thinker *Giordano Bruno*, whose death in this square on Feb. 17th, 1600, is now commemorated by a monument erected in 1889.

Between the Piazza Campo di Fiore and S. Andrea Valle once lay the Theatre of Pompey (Pl. II, 13, 14). In this piazza is the *Pal. Pio* or *Righetti* (entrance, Via del Biscione 95), in the court of which a bronze statue of Hercules (p. 306) and substructures of the theatre were discovered in 1864. Numerous fragments of the ancient walls are incorporated in the modern building. The semicircular bend of the street by *S. Maria di Grottapinta* (Pl. II, 13, 5) distinctly shows the form of the ancient theatre. The Via de' Giubbonari leads hence to S. Carlo a' Catinari (p. 201).

From the Campo di Fiore three parallel streets lead to the S.W. to the PIAZZA FARNESE, adorned with two fountains. Here is situated the —

***Palazzo Farnese** (Pl. II, 14), one of the finest palaces at Rome, begun by Card. Alex. Farnese, afterwards Pope Paul III. (1534-45), from designs by *Ant. du Sangallo the Younger* (p. lvii), continued after his death (1546) under the direction of *Michael Angelo* (who designed the beautiful cornicing), and completed by the construction of the loggia at the back, towards the Tiber, by *Giuc. della Porta* in 1580. The building materials were taken partly from the Colosseum, and partly from the Theatre of Marcellus. This palace was inherited by the kings of Naples, and from 1862 to 1870 was occupied by Francis II. It was purchased in 1874 by the French government, whose embassy to the papal court is now established here; on the second floor is the 'Ecole de Rome', or French archaeological institution, founded in 1875. The triple *Colonnade of the entrance and the two halls of the court were designed by *Sangallo*, in imitation of the Theatre of Marcellus. The court contains two ancient sarcophagi (that to the right from the tomb of Cæcilia Metella, p. 349). The celebrated antiquities once in this palace (Farnese Bull, Hercules, Flora) are now in the Museum of Naples.

A room on the 1st floor (no admission) contains *Frescoes by *Annibale Carracci*, his finest work, consisting of mythological scenes with rich architectural painting, executed in eight years by him, his brother *Lodovico*, *Domenichino*, and other masters. — The old banquet-hall has a *Ceiling in carved wood, designed by *Michael Angelo*.

From the Piazza Farnese a line of streets, called the VIA DI MONSERRATO and *Via de' Bunchi Vecchi*, leads to the N.W. to the Ponte S. Angelo (p. 274). On the left is *S. Maria di Monserrato* (Pl. II, 10, 3), the national Spanish church, with a hospice. It was erected in 1495 by *Ant. du Sangallo the Elder*, and afterwards restored. The altar-piece of the first chapel on the right is by *Ann. Carracci*.

To the S.E. of the Piazza Farnese the Vicolo de' Venti leads to the Piazza DI CAPO DI FERRO. Here, on the right, rises the —

Palazzo Spada alla Regola (Pl. II, 14), erected in the pontificate of Paul III. about 1540 by Card. Capodiferro, in imitation of a

house built by Raphael for himself. Since 1640 the palace has belonged to the Spada family. It contains an interesting collection of antiquities and pictures, but is now inaccessible to all except those provided with an influential introduction.

The most important **Antiquities** are collected in a 'Museo'. Opposite the entrance-wall: sitting *Statue of Aristotle, a copy of a celebrated Greek work; right arm and left leg modern. Then eight fine *Reliefs, found in 1620 in S. Agnese Fuori le Mura, where they formed part of the pavement, with their faces downwards. Beyond the Aristotle, to the left, 65. Dædalus and Pasiphaë; right, 72. Paris as a cowherd. Window-wall: 66. Wounded Adonis; 67. Ulysses and Diomedes carrying off the Palladium. Entrance-wall: Endymion; Perseus and Andromeda, casts from the originals in the Capitoline museum. Left wall: 68. Paris taking leave of Ceneone; 69. Hypsipyle finds Opheltis, who had been entrusted to her, killed by a snake; 70. Amphion and Zethus; 71. Bellerophon watering Pegasus. Also several busts, small statues, etc.

From the court a staircase to the right ascends to the UPPER FLOOR. In the ANTE-CHAMBER is a *Colossal Statue of Pompey*, found in the pontificate of Julius III. (1550) in digging the foundations of a house in the *Vicolo de' Leutari*. The body was in the ground of one proprietor, and the legs in that of another. As both parties claimed the statue, the judge ordered it to be divided; but the pope prevented this by purchasing it for 500 scudi, and presented it to Cardinal Capodiferro. The head, though of a separate block, belongs to the original statue. The workmanship is mediocre.

We now traverse a room adorned with unimportant frescoes to the **Picture Gallery**. I. Room, beginning opposite the entrance: 3. *Bolognese School*, Madonna; 7, 12. *French School*, Portraits; 10. *Camuccini*, Card. Patrizi; 22. *Caravaggio*, Portrait; 40. *Scipio Gaetano*, Julius III. — II. Room: 1. *Seb. del Piombo*, Astronomer; 6. *Baudin*, Still-life; 9. *Brueghel*, Landscape; 10. *Guido Reni*, Judith; 12. *G. Poussin*, Landscape; 16. *And. del Sarto*, Visitation of Elizabeth (seriously damaged); 43. *Leonardo da Vinci* (a copy of the original in England), Christ and the scribes. — III. Room: 2. *Caravaggio*, St. Anna and the Virgin; 4. *Raphael*, John the Baptist, a copy; 15. *Brueghel*, Landscape; 24. *Guercino*, Dido's death; 26. *Baciccio*, Design of the ceiling-painting in Gesù (p. 197); 29. *Salvator Rosa*, Landscape; 31. *Titian*, Portrait; *40. *Moroni*, Portrait; 48, *49. *Marco Palmezzano*, God the Father, and Bearing the Cross; 51. *Titian* (?), Card. Paolo Spada; 60, 70. *Salv. Rosa*, Landscapes; 63. *Guido Reni*, Abduction of Helen; 67. *Borgognone*, Cavalry-skirmish. — IV. Room: 4. *Guido Reni* (ascribed to Giulio Romano), Card. Bernardo Spada; 9. After *Titian*, Paul III.; 10. *German School*, Portrait (1511); 15. *Caravaggio*, Laughing angel's head; 18. *German School*, Portrait; 26. *Ger. Honthorst*, Christ in the garden; 30. *Caravaggio*, St. Cecilia; 31. *Maratta*, Card. Fabricius Spada; 44. *Andr. del Sarto* (?), Madonna; 54. *French School*, Portrait.

Pursuing the same direction beyond the Piazza Capo di Ferro, we next reach the small PIAZZA DE' PELLEGRINI. On the left is the back of the *Pal. Santacroce*, now a *Monte di Pietà* (Pl. II, 14), or pawn-office, founded in 1539, and established here in 1604. (Some of the numerous pictures pledged here are of considerable value.) On the right is the church of *S. Trinità de' Pellegrini*, erected in 1614; the high-altar is adorned with a Trinity, by *Guido Reni*. The neighbouring hospital for convalescents and pilgrims contains 488 beds, and can provide dinner for 944 persons at one time. Italian pilgrims are entertained here at Easter for three days, and foreigners for four.

The VIA DE' PETTINARI (Pl. II, 14) leads from the Piazza de' Pellegrini to the *Ponte Sisto* (see p. 327).





From the Ponte Sisto towards the N. W., parallel with the river, runs the VIA DEL FONTANONE, prolonged by the VIA GIULIA (Pl. II, 14, 10), which was built by Julius II., leading in 12 min. to the Ponte S. Angelo. To the left in the Via del Fontanone, is the *Pal. Falconieri*, built by Borromini, with hermæ on the façade in a baroque style, terminating in colossal falcons' heads; the court affords a good view of the opposite bank of the Tiber, the Villa Farnesina, and the Janiculum. In the Vicolo della Lunetta, the next cross-street to the left, is the church of *S. Eligio degli Orefici*, a graceful little circular structure, built in 1509 from a design by *Raphael* and renewed in 1601. Farther on in the Via Giulia, on the same side, the *Carceri Nuovi*, a prison founded by Innocent X.; then No. 66, the *Pal. Sacchetti* (Pl. II, 10), originally erected by Antonio da Sangallo the Younger as his private residence. The courses of rough rustica masonry in the lower stories of the houses on the left side of the street, formed the beginning of a large court of justice, projected by Julius II. and designed by Bramante, but never carried out.

At the end of the street, on the left, is *S. Giovanni de' Fiorentini* (Pl. II, 10), the handsome national church of the Florentines. The building was begun, by desire of Leo X., from a design by *Jac. Sansovino* (which was preferred to competing plans of *Raphael*, *Sangallo the Younger*, and *Peruzzi*); and the difficult task of completing the substructures on the river was executed by *Sangallo*, *Michael Angelo*, and on his death, *Giac. della Porta* were afterwards engaged in the work, and the façade was added by *Aless. Galilei* in 1725. The only object of interest in the church is a picture by *Salv. Rosa* in the chapel of the right transept (SS. Cosmas and Damianus at the stake).

Near the church a *Chain Bridge* (1 soldo), constructed in 1863, crosses the river to the Lungara (p. 322). The *Via Paola* leads from the church to the Ponte S. Angelo (p. 274).

IV. Ancient Rome.

This part of our description of Rome embraces the southern portion of the city, beginning with the Capitol, and extending eastwards as far as the Lateran: *i. e.* the hills of the Capitoline, Palatine, Aventine, Cælius, and the S. slope of the Esquiline. This was the most important quarter of the Republican and Imperial city, but lay waste and deserted from the early part of the middle ages [down to our own times. Recently it has lost much of its characteristic aspect owing to the construction of new quarters, consisting mainly of tenement houses of the most Philistine appearance. A considerable part of it, however, extending from the Forum Romanum and the Fora of the Emperors to the Circus Maximus, the Thermæ of Caracalla, and the Porta S. Sebastiano, is to be protected, under the name of *Passeggiata Archeologica*, from the hand of the modern restorer. A number of ancient churches, which are extremely interesting to students of Christian architecture, as well as the imposing collections of the Capitol and Lateran, also attract numerous visitors.

The Capitol.

This is the smallest, but historically the most important of the hills of Rome. It was originally merely the S. spur of the Quirinal, from which it was separated by a slight depression, but this hollow was greatly enlarged in consequence of the building operations of Trajan. The Capitol consists of three distinct parts: (1) the N. summit with the church and monastery of Aracœli (164 ft.); (2) the depression in the middle with the piazza of the Capitol (98 ft.); and (3) the S.W. point with the Pal. Caffarelli (156 ft.). It was on this piazza, the *Area Capitolina*, that Romulus is said to have founded his asylum; it was here that popular assemblies were afterwards held; and it was here, in the year B.C. 133, on the occasion of the suppression of the revolt of Tiberius Gracchus, that the blood of the citizens flowed for the first time in civil warfare. One of the peaks of the hill was occupied by the *Arx*, or citadel, with the temple of Juno Moneta, while the other was the site of the great *Temple of Jupiter*. The temple was built by Tarquinius Superbus, the last of the kings, and consecrated in B.C. 509, the first year of the Republic. It was 800 ft. in circumference, and possessed a triple colonnade and three cellæ, that of Jupiter being in the middle, and one for Juno and Minerva on each side. In the year B.C. 83, during the civil war, the temple was burned down, and the same fate overtook it in A.D. 69, on the occasion of the struggle between Vespasian and Vitellius. This most sacred shrine of ancient Rome was magnificently restored by Domitian, and was preserved down to the year 455, when it was plundered by the Vandals and robbed of its gilded bronze tiles. After that period there is no trace of it in history.

For nearly 500 years after the time of Cassiodorus, the minister and chronicler of Theodoric the Great (6th cent.), there is no mention of the Capitol in the annals of Rome. The hill was in the possession of the monastery of Aracœli, and the name of *Monte Caprino*, or hill of goats, which was applied to the S.E. height, bears testimony to its desertion. The glorious traditions, however, which attached to this spot, gave rise to a renewal of its importance on the revival of a spirit of municipal independence at Rome. In the 11th century it again became the centre of the civic administration. The prefect of the city resided here; among the ruins of the venerable citadel the nobility and the citizens held their public assemblies; and in 1341 Petrarch was crowned as a poet in the great senate-hall here. The hill could originally be approached from the Forum only, the N.W. side being precipitous and inaccessible, but in 1348 the latter side was connected for the first time with the new quarter of the city by the construction of the flight of steps of Aracœli, which was almost the only public work executed at Rome during the exile of the papal court at Avignon. About 1389 Boniface IX. converted the palace of the senate

into a kind of fortress, but its present form dates from the 16th century. Two new approaches from the city having been constructed in 1536, the Capitol has since formed a kind of termination of the modern part of the city in the direction of the ruins of ancient Rome.

From the PIAZZA ARACÆLI (Pl. II, 17) three approaches lead to the Capitoline Hill, that in the centre being the principal ascent for pedestrians. On the left a lofty FLIGHT OF STEPS (124), constructed in 1348, ascends to the principal entrance of the church of *S. Maria in Aracœli* (generally closed, see below). — On the right the VIA DELLE TRE PILE, recently converted into a handsome drive (on which occasion remains of the ancient Servian wall, enclosing the hill in the direction of the Campus Martius, and now seen behind the railings to the left, were brought to light), leads past the entrance of the *Pal. Caffarelli*, which was erected in the 16th cent. by Ascanio Caffarelli, a former page of Charles V., and is now the residence of the German ambassador. The principal approach and the Via delle Tre Pile lead to the Piazza del Campidoglio, see p. 210.

**S. Maria in Aracœli* (Pl. II, 20), a very ancient church, is mentioned in the 9th cent. as *S. Maria de Capitolio*. The present name, derived from a well-known legend (see p. 210), dates from the 14th century. The church, of which the Roman senate formerly enjoyed the patronage, has given a title to a cardinal since the time of Leo X. The façade is unfinished.

Visitors generally approach the church from the Piazza of the Capitol by the staircase to the left, at the back of the Capitoline Museum, and on the first landing turn to the left. Over the door an ancient mosaic, the Madonna between two angels.

The Interior is disfigured by modern additions. The nave is borne by 22 ancient columns, chiefly of granite, varying greatly in style and dimensions. The 3rd on the left bears the inscription '*A cubiculo Augustorum*'. The rich ceiling was executed to commemorate the victory of Lepanto in 1571.

By the wall of the principal ENTRANCE, to the left, is the tomb of the astronomer Lodovico Grato (1531), with a figure of Christ by *Andrea Sansovino*; on the right the "Monument of Card. Librettus or De Alibrettis (a member of the celebrated French family of d'Albret; 1465), with partly-preserved painting. RIGHT AISLE, 1st Chapel: "Frescoes from the life of St. Bernardino of Siena, by *Pinturicchio*, restored by *Camuccini*. Frescoes on the ceiling attributed to *Franc. da Città di Castello* and *L. Signorelli*. The 5th Chapel (of St. Matthew) contains good pictures by *Muziano*. — LEFT AISLE. In the 2nd Chapel a manger (*presèpe*) is fitted up at Christmas, i.e., a gorgeous representation of the Nativity in life-size, with the richly decorated image of *Il Santo Bambino*, or Holy Child, which forms the principal treasure of the church. This image is believed to protect persons in imminent danger, is frequently invoked and revered, and is sometimes conveyed to the houses of the sick, on which occasions passers-by kneel on its approach. During the week after Christmas, from 3 to 4 o'clock daily, a number of children from 5 to 10 years of age address their petitions to the bambino. At the end of the left aisle a tomb-relief of Msgr. Crivelli by *Donatello* (much damaged).

TRANSEPT. On the right and left, by the pillars of the nave, are two "Ambones from the old choir, by *Laurentius* and *Jacobus Cosmas*. The Chapel on the right belongs to the *Savelli*; on the right and left (the latter originally an ancient sarcophagus) are monuments of the family, of the 13th cent. (of the parents and a brother of Honorius IV.). The left transept contains a rectangular canopy, borne by 8 columns of alabaster, called

the CAPPELLA SANTA, or DI S. ELENA. Beneath the altar, which was destroyed during the French Revolution, but was restored in 1835, the remains of S. Helena are said to repose in an ancient sarcophagus of porphyry. The present altar also encloses an ancient altar, bearing the inscription *Ara Primogeniti Dei*, which is said to have been erected by Augustus. According to a legend of the 12th cent., this was the spot where the Sibyl of Tibur appeared to the emperor, whom the senate proposed to elevate to the rank of a god, and revealed to him a vision of the Virgin and her Son. Hence the name, 'Church of the Altar of Heaven'. At the end of the N. transept is the monument of Matthæus of Aquasparta (d. 1302), the general of the Franciscans, mentioned by Dante.

CHOIR. To the left, the *Tomb of Giov. Batt. Savelli (d. 1498). From 1512 to 1565 the high-altar was adorned with the Madonna of Foligno by Raphael, ordered for this church, afterwards at Foligno (p. 79), and now in the Vatican. The donor, Sigismondo Conti da Foligno, is interred here. The present altar-piece is an ancient picture of the Madonna, ascribed to *St. Luke*.

The Franciscan monastery belonging to the church was pulled down in 1888 to make room for the large *Monument of Victor Emmanuel II.*, which occupies the N. end of the Capitol.

The CENTRAL APPROACH, ascending in low steps paved with asphalte ('la cordonnata'), leads to the Piazza del Campidoglio. At the foot of the steps are copies of the Egyptian *Lions* mentioned at p. 216, and at the top a group of the horse-taming *Dioscuri* (Castor and Pollux), which are said once to have adorned the theatre of Pompey. In the pleasure-grounds to the left is a bronze statue of *Cola di Rienzi*, by Masini. The pedestal, formed of ancient architectural and inscribed fragments, is intended to suggest Rienzi's antiquarian studies.

The design of the present **Piazza del Campidoglio*, or Square of the Capitol (Pl. II, 20), is due to *Michael Angelo*, and its execution was begun in 1536 by Paul III. (comp. p. 224). The palaces of the Conservatori and Senators were already in existence, but their façades were altered. Michael Angelo caused the open space towards the slope of the hill to be widened, so as to impart to the piazza an appearance of greater size. — On the balustrade in front, at the sides of the *Dioscuri*, are the so-called *Trophies of Marius*, from the water-tower of that name of the Aqua Julia (p. 179), and the statues of the Emp. Constantine and his son Constans from the Thermæ of Constantine (p. 174), on the Quirinal. On the right is the first ancient milestone of the Via Appia, and on the left the seventh milestone of the same road, found at Torricola in 1660.

In the centre of the piazza rises the admirable **Equestrian Statue of Marcus Aurelius* (161-181), in bronze, once gilded, and originally placed in the forum near the arch of Sept. Severus. In 1187 it was erected near the Lateran, and, as the inscription records, transferred hither in 1538. It owes its excellent preservation to the popular belief that it was a statue of Constantine, the first Christian emperor (see pp. 133, xxxviii). The pedestal is said to have been designed by Michael Angelo. Owing to its moderate height, the head of the statue is distinctly visible, whereas modern figures of the kind are often perched so high as to be almost indistinguishable.

Beyond this monument rises the **Palazzo del Senatore** (Pl. II, 20, 2), which was re-erected by Boniface IX. in 1389 on the site of the ancient Tabularium, and provided with its handsome flight of steps by *Michael Angelo*, under whose directions it is probable that the façade was constructed by *Giac. della Porta*. The river-gods which adorn it are the Tiber (right) and Nile (left). In the centre a fountain, above which is a sitting statue of Rome from Cori (comp. p. 386). The palace contains a spacious senate-hall, the offices of the civic administration, and an observatory. The *Campanile* was erected by Gregory XIII. in 1572, to replace an older one, probably belonging (like the four corner-towers, one of which towards the Forum, on the left, is still recognisable) to the edifice of Boniface. The roof of the tower, which is adorned with a standing figure of Roma, commands an extensive view (entrance, see p. 221).

The two palaces at the sides were erected in the 17th cent. by *Giacomo del Duca*, with some deviations from the plans of Michael Angelo. On the right is the *Palace of the Conservatori* (Pl. I), or town-council, with its collections (see below; a fire-engine station on the ground-floor), and opposite is the *Capitoline Museum* (Pl. 12; p. 216). — The flights of steps and colonnades on the E. side of these palaces were erected by *Vignola* (ca. 1550); that to the left by the museum leads to the church of S. Maria in Araceli (p. 209); that to the right, on the opposite side, to Monte Caprino (p. 221).

On the right of the Palace of the Senators runs the *Via del Campidoglio*, and on the left the *Via dell' Arco di Settimio Severo* (p. 237), both descending to the Forum.

COLLECTIONS OF THE CAPITOL.

These are contained in the two side-palaces just mentioned, and are open daily, under the conditions mentioned at p. 123.

A. *Palace of the Conservatori.

(Comp. Plan, p. 216).

The principal door leads from the Piazza del Campidoglio into the Court. By the right wall of the court are the hands and limbs of a colossal figure in marble. In the middle is the cinerary urn of Agrippina, wife of Germanicus, which in the middle ages was employed as a measure for corn; inscription, *Ossa Agrippinae M. Agrippae f. divi Augusti neptis uxoris Germanici Caesaris Matris C. Caesaris Aug. Germanici principis*. By the left wall are alto-reliefs of Roman provinces, interspersed with barbaric trophies and weapons, which once adorned the lower part of the Temple of Neptune mentioned at p. 155; also a colossal head, perhaps of Domitian. — In the centre of the colonnade opposite the entrance, a statue of Roma; at the sides statues of barbarians in grey marble. To the left, in the corner, a colossal bronze head; right an antique

group, *Horse torn by a lion, said to have been restored by Michael Angelo.

In the ENTRANCE-HALL farther on, opposite the staircase, 30. Modern 'columna rostrata', with the genuine fragment of an inscription in honour of C. Duilius, the victor of Mylæ, B.C. 260, placed here in the reign of Claudius and composed in a purposely antiquated style. Below the window is a statue of Charles of Anjou, King of Sicily (formerly in the large Hall of the Capitol), who was Senator of Rome in 1263-66, 1268-78, and 1281-84. On each side of the STAIRCASE are Roman inscriptions built into the wall, most of which were found on the Esquiline. — On the landing of the staircase is a list of streets in the 1st, 10th, 12th, 13th, and 14th regions of ancient Rome, dating from 136 A.D. Built into the walls are four *Reliefs from a triumphal arch of M. Aurelius, found near S. Martina in the Forum: on the right, 44. Sacrifice in front of the Capitoline temple; on the long wall, 43. Entry of the emperor; 42. Pardon of conquered enemies; 41. His reception by Roma at the triumphal gate. On the walls are ancient inscriptions. — On the left, above the second landing, No. 43. Relief, Curtius on horseback leaping into the gulf (15th or 16th cent.). Opposite, inscription referring to Frederick II.'s victory over the Milanese. — In the passage above, two reliefs from the triumphal arch of M. Aurelius (p. 153), which was removed in 1653 by order of Alexander VII., representing an oration of Marcus Aurelius and the apotheosis of Faustina. On the left is the entrance to the Collections described below.

We traverse two Rooms with modern lists of Roman magistrates, and enter a long CORRIDOR containing the so-called PROTOMOTECA, founded by Pius VII., a collection of busts of celebrated Italians, including poets (such as Dante, Petrarch, and Ariosto), scholars, painters, architects, and sculptors. At the end of the corridor is a monument to Canova. Several eminent foreigners have also been admitted: (l.) Winckelmann, (r.) Poussin and Raphael Mengs. On the walls are several old plans and views of Rome. — The second door to the right in this passage is the entrance to the New Capitoline Museum (see below), while the last door but two leads to the picture-gallery (p. 214), and the last but one leads up two steps to the 7th, 6th, and 5th rooms of the New Capitoline Museum.

The *New Capitoline Collection contains chiefly the bronzes and the yield of recent excavations.

I. ROOM OF THE BRONZE UTENSILS. *Bronze Chariot*, with representations in relief; **Bronze Seat*, with a footstool, adorned with inlaid silver work, found at the ancient Amiternum; *Litter*, partly inlaid with silver. Along the walls are smaller bronzes, including a Hermaphrodite, from whose back springs an arabesque, designed as a bearer. The door in front of us leads to the —

II. ROOM, which contains the *Collection of Coins*. — The door to the left leads into the large octagonal —

III. DOME SALOON, lighted from above, and constructed of iron and wood in the Pompeian style, by Vespignani. In the Vestibule, to the right: 2. Tombstone of *Q. Sulpicius Maximus*, a boy of 11½ years, who, according to the Latin inscription, worked himself to death after having gained the prize over 52 competitors for extemporising in Greek verses, quotations from which are inscribed on each side of the statuette of the youthful poet. To the left: 8. Sitting figure of *Terra Mater* (Mother Earth), in a small temple with inscription. — Opposite the entrance is a beautiful fountain-spout in the form of a drinking-horn, found in the garden of Mæcenas (p. 182). 18. Youthful athlete pouring oil into his left hand; 14, 16. Tritons, forming part of the following group. *15. Half-figure of the *Emperor Commodus*, with the attributes of Hercules; the marble still displays its fine original polish; the pedestal is formed by two Amazons (one only preserved) bearing a shield enclosed by cornucopiæ, below which is a celestial globe. 19. Figure of *Bonus Eventus*, with a cornucopia. 21. Large Sarcophagus from Vicovaro (p. 380), with hunting scenes. 24. Terpsichore; 25, 27. Well-preserved youthful portrait-heads, found together on the Esquiline; *26. Venus in the act of loosening her hair (both arms missing). Then, two interesting statues of a post-Constantine period, each holding aloft a cloth in the right hand as the signal for starting in the chariot-race. Graceful seated figure of a young girl. 33. Statue of *Claudia Justa*, with attributes of Fortune; Replica of the so-called Eros of Praxiteles (Vatican Gallery, p. 308), wrongly restored as a lyre-player; in a niche behind it, to the right, interesting *Relief, representing Vulcan and three Cyclopes making the shield of Achilles; *36. Head of a Centaur (probably Chiron); 38, 42. Athletes; *46. Marsyas bound to a tree (the tree, hands, and feet modern restorations). Opposite, *59. Head of an Amazon. In the middle, between the pillars: 62-65. Caryatides in the archaic style; two large vases, the one with spirited Bacchic representations particularly fine. 35. Infant Hercules with the lion's skin, club, and quiver, in his left hand the apples of the Hesperides; 10. Old woman carrying off a lamb.

IV. GALLERY. To the right: 46. Colossal bust of Mæcenas; *75. Fighting Hercules, with a portrait-head; several fine ancient Greek tombstones with female figures; 70. Colossal foot in marble. with a Tyrrhenian sandal adorned with a pleasing composition of Tritons, Cupids, and Dolphins. — On the walls of the CORRIDOR: Priest's boy with a sucking-pig for sacrifice. 125. Boy (restored as Mercury) playing with a tortoise (fountain-figure); 124. Marble vase, richly adorned with acanthus leaves; 123. Boy with a small dog. On the sarcophagus to the right are several heads; that of Atthis (under glass) shows traces of painting and gilding. Bust of

Anacreon, the poet, found in the gardens of Cæsar, outside the Porta Portese. Adjacent, a torso of *Athena*, modelled after the *Parthenos* of *Phidias*; fragment of a marble shield with battle-scenes. To the left, 130. *Silenus* in a crouching attitude, a fountain-figure.

We traverse the corridor of the *Protomoteca* (passing the monument of *Canova* on the right), and enter the —

V. ROOM OF THE TERRACOTTAS, chiefly common domestic utensils (pitchers, lamps, jars, etc.) and terracotta reliefs used as mural decorations. In the corner to the left is a seated female figure. Reliefs with landscapes (views of the Nile) and mythological scenes (*Hercules* and *Telephus*), showing traces of colouring. Near the exit are an ivory diptych and a stilus,

VI. ROOM OF THE BRONZES. At the entrance, **Priest's Boy* (*Camillus*); *Ephesian Diana*, on a trilateral altar. By the window, the so-called **Capitoline Wolf*, with *Romulus* and *Remus*; possibly the same which the ædiles *Cneius* and *Quintus Ogulnius* erected in B. C. 296, though more probably of an early mediæval origin. An injury on the right hind-leg is supposed to have been caused by lightning, by which, according to *Cicero*, the figure was struck in B.C. 65, in the consulate of *Manlius* and *Cotta*; the twins are modern. This work, with other bronzes, stood near the *Lateran* as early as the 9th century. 36. Small three-bodied *Hecate*. The **Thorn Extractor*, a boy removing a thorn from his foot. Gilded *Statue of Hercules*. A *Horse*, sadly mutilated, but of excellent workmanship, found in 1849, together with the fragments of a *Bull*. Then a *Colossal Hand* and a *Colossal Foot*, found near the Pyramid of *Cestius* (comp. p. 252). To the left of the exit, an expressive **Bronze Head*, said to be that of *C. Junius Brutus*, who expelled the kings and became the first consul; eyes of coloured stone. *Vase*, found near *Anzio*, presented by King *Mithridates* to a gymnasium (foot and handles modern).

VII. ROOM OF THE ETRUSCAN TERRACOTTAS, or the so-called *Museo Italico*, a collection of vases, terracottas (including two sarcophagi with figures on the lids), bronzes, and various anticaglias from *Etruria* and *Latium*. Under glass: Silver cover of a cist with archaic figures of animals, found at *Palestrina*.

On quitting this collection we pass through the first door on the right in the corridor and ascend to the —

Picture Gallery ('*Pinacoteca*'), founded by *Benedict XIV.* In a straight direction we enter the first saloon. The names of the artists and the subjects are attached to the pictures.

I. FIRST SALOON. Entrance-wall, to the right of the door: *89. *Rubens*, *Romulus* and *Remus*. Right wall: 145. *Giorgione*, *Holy Family*; 6. *Romanelli*, *St. Cecilia*; 7. *Pietro da Cortona*, *Triumph of Dionysus*; 65. *Garofalo*, *Madonna* and saints; 127. *Lorenzo di Credi*, *Madonna* and Child; 13. *Guerchino*, *John the Baptist*; 14. *N. Poussin*, *Flora* (copy of the picture in the Louvre); 16. *Guido Reni*, *M. Magdalene*; 20. *Domenichino*, *Cumean Sibyl*. Narrow wall: 142. *Albani*, *Nativity of the Virgin*; 26. *Tintoretto*, *M. Magdalene*; 210. *Gaud. Ferrari*, *Madonna*; 27. *Fra Bartolommeo* (?), *Presentation*

in the Temple; 30. *Garofalo*, Holy Family; 34. *Guercino*, Persian Sibyl; 70. *Paolo Veronese*, Madonna and saints (copy); above, *Lo Spagna*, Two saints (fresco). Left window-wall: 9. *Albani*, Magdalene; 52. *S. Botticelli*, Madonna and saints; 55. *Ag. Carracci*, Holy Family; 196. *Cola dell' Amatrice*, Assumption; 51. *School of Raphael*, Holy Family; 195. *Paolo Veronese*, Ascension; 54. *Garofalo*, Coronation of St. Catharine; 2. *Guido Reni*, A glorified spirit (unfinished). Entrance-wall: 91. *G. Reni*, Sketch for No. 2; 76. *P. Caravaggio*, Meleager; 78. *Fr. Francia*, Madonna (1513). On the right window-wall, above: Ten frescoes attributed to *Lo Spagna*, representing Apollo and the Muses, formerly at La Magliana (p. 393).

II. SALOON. Entrance-wall: *Pietro da Cortona*, 58. Sacrifice of Iphigeneia, 190. Alexander and Darius. Right wall: 47. *P. da Cortona*, Rape of the Sabine women; 116. *Guido Reni*, St. Sebastian; 117. *Guercino*, Cleopatra and Octavian; 119. *Lod. Carracci*, St. Sebastian; 128. *Caravaggio*, Fortune-telling gipsy. Short wall: *143. *Guercino*, St. Petronella raised from her tomb and shown to her bridegroom. Left wall: 154. *Paolo Veronese*, Magdalene; 41. *N. Poussin*, Orpheus; 169. *Cignani*, Madonna; 164. *Garofalo*, Madonna; 180. *Titian*, Christ and the adulteress; *224. *Paolo Veronese*, Rape of Europa.

III. Room. *132. *Giov. Bellini*, Portrait; 87. St. Nicholas, by the same; 124. *Paris Bordone* (catalogued as *Titian*), Baptism of Christ; 136. *Gentile Bellini* (?), Petrarch; 129. *Giov. Bellini*, Portrait; 49. *Domenichino*, Landscape with Hercules; 103. *Domenichino*, St. Barbara; 66. *Bronzino*, Portrait of a lady; 137. *Domenichino*, Landscape with St. Sebastian; 98. *School of Bellini*, Holy Family. Right wall: 222. *Bassano*, Christ in the house of the Pharisee; also a few good landscapes.

IV. Room. 80. *Velazquez*, Portrait; *100. *Van Dyck*, Portraits of Thos. Killegrew and Henry Carew; *134. Portrait of *Michael Angelo*, probably by himself; *106. *Van Dyck*, Two portraits; *61. *Guido Reni*, Portrait of himself; *Garofalo*, 161. Annunciation, 201. Transfiguration, 204. Adoration of the Magi; 223. *Paolo Veronese*, Madonna with angels.

The *Sale dei Conservatori* (i.e. of the town-councillors) contain frescoes and other works of art, chiefly of the end of the 16th century.

We pass through a CORRIDOR, containing a collection of porcelain presented by Conte Cini, and the old CHAPEL, containing an altar-piece (Madonna) by *Agostino d'Ingegno*, formerly ascribed to Pinturicchio. We then reach the I. ROOM, the walls of which are frescoed by *Sodoma* with scenes from the Punic Wars. — II. ROOM (to the right): Frescoes by *Laureti*; statues of the generals Marcantonio Colonna, Alexander Farnese, Rospigliosi, Aldobrandini, and Barberini. — LARGE SALOON, with frescoes by the *Cavaliere d'Arpino*, representing the Combat of the Horatii and the Curiatii, and other scenes from the period of the Kings; it also contains a bronze statue of Innocent X. by *Algardi*, and a marble statue of Urban VIII. by *Bernini*. — We now return through R. II. into the IV. ROOM. Scenes from the Cimbric war, and several antique busts. — V. ROOM: Fragments of the **Fasti Consulares*, or lists of Roman consuls, found in the 16th cent. (and smaller fragments in 1818 and 1872), between the temples of Castor and Faustina. They were originally exhibited in the Regia, or official residence of the Pontifex Maximus (p. 231). The busts of *B. Borghesi* (by Tadolini) and *W. Henzen* (by Kopf), two scholars who explained the Fasti, were placed here in 1888. The ancient hermæ with modern inscriptions are unimportant. — VI. ROOM. Several antiques: jug in the form of a female head in bronze; two ducks; head of Medusa, by *Bernini*. — VII. ROOM, a small room, with relics of Garibaldi, weapons, garlands, banners, letters, etc. — VIII. ROOM, formerly the assembly-hall of the Senate. The frieze, representing scenes from the life of Scipio Africanus, is attributed to *Ann. Carracci*. On the walls is tapestry woven at S. Michele. Bust of Michael Angelo, attributed to himself. Also busts in marble of Victor Emmanuel, Cavour, and Mazzini.

B. **Capitoline Museum.

This museum was founded by Innocent X., and extended by Clement XII., Benedict XIV., Clement XIII., and Pius VI. The works carried off by the French were restored with few exceptions to Pius VII. The collection is much smaller than that of the Vatican, but is rich in admirable works. Catalogue, prepared for the *Commissione Archeologica Municipale* in 1882, sold at the entrance (3 fr.).

a. GROUND FLOOR.

COURT (Cortile). Above the fountain in the centre is the **Marforio*, a colossal river-god holding a shell, probably representing the Rhine or Danube, erected in the middle ages in the Via di Marforio opposite the Carcer Mamertinus, where it was employed as a vehicle for the sarcastic answers to the interrogatories of Pasquino (see p. 201). Among the other sculptures, most of which are unimportant, are the two **Egyptian Lions* of basalt (formerly at the foot of the steps of the Capitol), two *Granite Columns* with reliefs, and two large *Canopi* (dog-faced baboons), all from the Temple of Isis (p. 195).

CORRIDOR (Pl. 4), to the left of the entrance: 3. Colossal Minerva; 5. Bacchante; below, Sarcophagus with Bacchanalian representation, purposely mutilated. — On the left, at the end, is the entrance to the —

I. ROOM (Pl. 1). Sarcophagus with a lion-hunt. In the centre is an altar with a sacrificial relief, erected by the superintendents of a Roman district (Vicus Æsculati), found in 1888 near the Ponte Garibaldi. On the walls are several ancient mosaics, one of which (No. 27) seems to represent a vessel leaving port (found on the Quirinal in 1878). Above the door of the 2nd room: 20. Cupids binding a lion, with Hercules in female attire spinning in the background. By the door, under glass, is a mosaic representing the rising of the Nile. — The two following rooms (Pl. 2, 3) contain inscriptions, sarcophagi, etc., of little general interest.


We return to the CORRIDOR (Pl. 4). To the left: several mediocre female draped statues. — To the right of the principal entrance: (right) 25. Diana; 24. Hercules; 23. Luna; 21. Mercury; (left) 14. Cyclopean Polyphemus with one of his victims (erroneously restored); (left) 15. Hadrian as a priest; (right) 20. Jupiter; below. Sarcophagus with the Calydonian Hunt; (right) 19. Colossal Mars (legs modern); 17. Hercules with the Hydra, found in the 16th cent. near S. Agnese in the Via Nomentana and restored by Algardi (the parts originally missing, the Hydra and leg of Hercules, were afterwards discovered and are now exhibited beside the restored group). — Adjacent, to the right, is the entrance to three rooms containing inscriptions and several interesting sarcophagi.


I. ROOM (Pl. 5). In the centre: Ara, which stood in the market-

PALAZZO DEI CONSERVATORI

1^o PLAN 0.


Sale nuove, Prctomoteca, Sale dei Conservatori.





PRIMO PIANO.

MUSEO CAPITOLINO.



Ingresso

PIANTERRENO.

place of Albano till 1743, with archaic representation of the exploits of Hercules. Also a few insignificant busts. — II. Room (Pl. 6). *5. Sarcophagus with battle between the Romans and Gauls; the commander of the latter commits suicide (perhaps Aneroëstus, defeated B.C. 225 near Pisa); (left) 11. Cippus of T. Statilius Aper, the architect (*'mensor aedificiorum'*), with a wild boar (aper) at his feet and a measuring wand and other instruments at the sides. On the walls are inscriptions. — III. Room (Pl. 7). Large *Sarcophagus (formerly supposed to be that of Alex. Severus and his mother Mammæa), with scenes from the life of Achilles. Achilles among the daughters of Lycomedes, (left) farewell of Deidamia, (right) arming of Achilles; at the back, Priam begging for the body of Hector (found in 1594 with the Portland Vase of the British Museum on the Mte. del Grano, near the Porta Furba. p. 347). Left of the door: 15. Sitting statue of Pluto. — We now return to the hall, and ascend the staircase to the —

b. FIRST FLOOR.

STAIRCASE (Pl. 8). Into the walls are built the fragments of the marble *Plan of Rome*, an important topographic relic, executed under Sept. Severus, found in the 16th cent. near SS. Cosma e Damiano (p. 231). Portions of the pieces found have been lost, but supplemented from the extant drawings (these parts are indicated by asterisks). On the landing of the stair are two female statues, groundlessly designated as Pudicitia and Juno Lanuvina.

I. ROOM OF THE DYING GLADIATOR. In the centre: 1. ***Dying Gladiator*, found at Rome in the 16th cent. and originally preserved in the Villa Ludovisi. The trifling restorations (right arm and part of the base) are said to have been made by Michael Angelo.

The dying warrior, recognized as a Gaul by his twisted collar, short hair, and mustache, is sitting on his shield, while the blood pours from his wounded breast; he has evidently inflicted the fatal blow himself, having previously broken the crooked horn which lies on his shield. He has preferred death to captivity, and exhibits the same dignity of character as the Barbarian in the group now in the Villa Ludovisi (p. 173), which was probably found at the same time (comp. p. xxxiv). The visitor will readily recall the exquisite lines by Byron: *Childe Harold*, Canto iv., 140.

7. (right of the door) Apollo with lyre. Right wall: *5. Head of Dionysus, erroneously taken for a woman's (Ariadne's); 4. Amazon; 3. Alexander the Great; 2. Demeter. Wall opposite the entrance: 16. Head of M. Jun. Brutus, the 'tu quoque Brute' of Cæsar; 15. Priestess of Isis; 14. Flora from the villa of Hadrian. Left wall: *12. Antinous from Hadrian's villa (p. xxxvii); below, Tombstone erected by a freedman of Tiberius to his wife, with elegant Greek and Latin verses and tasteful ornamentation. *10. *Satyr of Praxiteles*, the best of the extant copies (p. xxxii).

This is the figure which suggested the title of Nathaniel Hawthorne's romance, *The Marble Faun* (see p. 123), in the opening pages of which occurs a fine description of the statue.

9. Girl protecting a dove; instead of the modern snake, there was probably a dog, or some other animal in the original. Entrance-wall: 8. Zeno, found in 1701 in a villa of Antoninus Pius at Civit  Lavinia.

II. STANZA DEL FAUNO. On the walls reliefs, inscriptions, etc., among them the *Lex Regia* of Vespasian (black tablet of bronze on the entrance-wall), whence Cola di Rienzi, 'the last of the Tribunes', once demonstrated to the people the might and liberty of ancient Rome. In the centre, 1. *Satyr (Fauno)* in rosso antico, raising a bunch of grapes to his mouth, from Hadrian's villa, placed on a remarkable altar, dedicated to Serapis. Window-wall: 26. Colossal head of Bacchus, on a circular ara with a rostrum, and the inscription *ara tranquillitatis*, found together with the Ara Ventorum and the Ara Neptuni at the harbour of Anzio (p. 397), where they were employed by sailors for offering sacrifices. Wall of egress: 4. Head of Mercury (?); 3. Sarcophagus with relief of Diana and Endymion; *6. Head of Juno Sospita; 8. Boy with mask of Silenus. Right wall: 10. Minerva; 12. Mars. Entrance-wall: 15. Bust of Hercules; 16. Boy struggling with a goose, copy of a statue by *Boethos*, excavated near the Lateran in 1741; *18. Sarcophagus with battle of Amazons, and, on its left corner, 21. Head of Ariadne crowned with ivy.

III. LARGE SALOON. In the centre: 1. *Æsculapius*, in nero antico, on an altar representing a sacrifice. *2, 4. Two Centaurs in bigio morato, by *Aristeus* and *Papias*, found in Hadrian's villa in 1736; 3. Colossal basaltic statue of the youthful Hercules, found on the Aventine; it stands on a beautiful altar of Jupiter, embellished with representations of his birth, education, etc.; 5. Jupiter, in nero antico, or black-marble, found at Anzio, on an altar adorned with Mercury, Apollo, and Diana, in the archaic style. — Window-wall to the left of the entrance: 29. Portrait-statue restored as Hygieia; 31. Apollo with lyre; 32. M. Aurelius; 33. Amazon; 34. Mars and Venus, with portrait-features; 36. Athena. — Wall of egress: 6. Satyr; 7. Apollo; 8. Minerva; 9. Colossal bust of Trajan with civic crown. — Right wall: 13. Hadrian as Mars, found near Ceprano. In the niche: *17. Athena, archaistic statue. 19. Amazon; 20. Apollo; 21. Mercury; 22. Old nurse, probably from a group of the Children of Niobe; 24. Ceres (?). — Entrance-wall: 25. Colossal bust of Antoninus Pius; 27. Hunter with a hare; 28. Harpocrates, god of silence, from Hadrian's Villa.

IV. ROOM OF THE PHILOSOPHERS. On the wall valuable **Reliefs*, six from the frieze of a temple of Neptune, with sacrificial implements and parts of ships (Nos. 99, 100, 102, 104, 105, 107). — In the centre (No. 98) the sitting consular *Statue of Marcus Claudius Marcellus (?), conqueror of Syracuse, B. C. 212, from the Giustiniani collection, formerly in the Museo Chiaramonti. Also 93 **Busts of Celebrated Characters of Antiquity*, to some of which arbitrary names are affixed. 1. Virgil (?); 4. *5, 6. Socrates; 9. Aristides the ora-

tor; 10. Seneca(?); 13. Lysias(?); 16. Marcus Agrippa; 19. Theophrastus; 20. Marcus Aurelius; 21. Diogenes the Cynic; 22. Sophocles (not Archimedes); 23. Thales; 24. Asclepiades; 25. Theon; 27. Pythagoras; 28. Alexander the Great(?); 30. Aristophanes(?); 31. Demosthenes; 33, 34. Sophocles; 35. Alcibiades (? certainly not Persius); 37. Hippocrates; 38. Aratus(?); 39, 40. Democritus of Abdera; 41, 42, 43. Euripides; 44, 45, *46. Homer; 47. Epimenides; 48. Cn. Domitius Corbulo, general under Claudius and Nero; *49. Scipio Africanus, recognisable by the wound on his head which he received when a youth at the battle of Ticinus, whilst saving his father's life; 52. Cato of Utica(?); 54. Minerva; 55. Cleopatra(?); *59. Arminius(?), erroneously named Cecrops; 60. Thucydides(?); 61. Æschines; 62. Metrodorus; 63. Epicurus and Metrodorus; 64. Epicurus; 68, 69. Masinissa; 70. Antisthenes; 72, 73. Julian the Apostate; 75. Cicero; 76. Terence, according to others C. Asinius Pollio; *82. Æschylus(?). The names of the busts by the window-wall are unknown.

V. ROOM OF THE BUSTS OF THE EMPERORS. Reliefs by the entrance-wall: *92. Endymion asleep, beside him the watchful dog; *89. Perseus liberates Andromeda (these two belong to the eight reliefs in the Pal. Spada, p. 206). Above the window are other sarcophagus-reliefs. — The collection of the emperors' busts is one of the most complete in existence; the names are for the most part verified by coins (comp. p. xxxv). In the centre: *84. Sitting female statue, believed to be Agrippina, daughter of M. Agrippa, wife of Germanicus and mother of Caligula. The numbering of the busts commences in the upper row, to the left of the entrance-door. 1. Julius Cæsar; 2. Augustus; 3. Marcellus, nephew of the latter(?); 4, 5. Tiberius; 6. Drusus the elder; 7. Drusus, son of Tiberius; 8. Antonia, wife of the elder Drusus, mother of Germanicus and Claudius; 9. Germanicus; 10. Agrippina, his wife; *11. Caligula, in basalt; 12. Claudius, son of Drusus; 13. Messalina, fifth wife of Claudius; 14. Agrippina the younger, daughter of Germanicus, mother of Nero; 15. Nero; 17. Poppæa, Nero's second wife; 18. Galba; 19. Otho; 20. Vitellius(?); 21. Vespasian; 22. Titus; 23. Julia, his daughter; 24. Domitian; 26. Nerva (modern?); 27. Trajan; 28. Plotina, his wife; 29. Martiana, his sister; 30. Matidia, her daughter; 31, 32. Hadrian; 33. Sabina, his wife; 34. Ælius Cæsar, his adopted son; 35. Antoninus Pius; 36. Faustina the elder, his wife; 37. M. Aurelius as a boy; 38. M. Aurelius, more advanced in life; 39. Faustina the younger, daughter of Antoninus, wife of Aurelius; 41. Lucius Verus; 43. Commodus; 45. Pertinax; 50, 51. Septim. Severus; 53. Caracalla; 57. Heliogabalus; 60. Alex. Severus; *62. Maximin; 63. Maximus, son of Maximin; 64. Gordian Afr.; 65. Gordian; 76. Gallienus; 80. Diocletian(?); 82. Julian the Apostate (probably a Greek philosopher; the inscription is mediæval). We next enter the —

VI. CORRIDOR. At the left end: Beautiful marble vase on an archaistic *Puteal with the 12 gods: Jupiter, Juno, Minerva, Hercules, Apollo, Diana, Mars, Venus, Vesta, Mercury, Neptune, and Vulcan. By the window to the left: *33. Bust of Caligula; Then, the back of the visitor being turned to the window: (l.) 30. Trajan; (l.) *29. Pallas, found at Velletri, exactly corresponding to the statue (No. 114) in the Braccio Nuovo of the Vatican; (l.) 28. M. Aurelius, as a boy; (l.) *35. Head of Silenus; (l.) 26. Augustus; (l.) 25. Jupiter, on a cippus with relief: Claudia Quinta drawing a boat containing the image of the Magna Mater up the Tiber; (r.) 38. Venus; (r.) 42. Female draped statue. (The door opposite leads to the Venus room.) Left, 21. Head of Apollo; (r.) 43. Antinous; (l.) 20. Psyche; (r.) 46. Selene; below, *Sarcophagus with representation of the birth and education of Bacchus. Here and in the following compartments, on the right, are immured the inscriptions from the columbarium of the freedmen of Livia (found in 1726 near the church of Domine Quo Vadis). Right: 48. Child of Niobe; (l.) 15. Venus; (r.) 49. Juno; (l.) 14. Marble vessel with Bacchanalian scenes; (r.) 50. Copy of the discus-thrower of Myron (Pal. Lancelotti, p. 190), incorrectly restored as a warrior; (l.) 12. Flute-playing Satyr; (r.) 52. Muse; (l.) 10. Octagonal cinerary urn with Cupids in the attitudes of celebrated statues; 54. Venus, with portrait-head; below, (r.) Sarcophagus with the rape of Proserpine and the child Hercules with the snakes; (l.) Archaistic relief, a lute-player(?); (l.) 8. Old woman intoxicated; (r.) 58. Sitting draped statue. Opposite the entrance to the Room of the Doves: (l.) *5. Cupid bending his bow (after *Lysippus*); (r.) 60. Flute-playing Satyr; (l.) 3. Recumbent lion; (r.) 61. Silenus; (r.) 62. Septimius Severus; (l.) by the window, 63. Roman matron (perhaps the elder Faustina); 64. M. Aurelius.

VII. ROOM OF THE DOVES, so called from the *Mosaic on the right wall: *Doves on a Fountain-basin*, found in Hadrian's Villa near Tibur (p. 375), copy of a celebrated work by *Sosus* of Pergamum, mentioned by Pliny. Below it, a sarcophagus: 13. Prometheus forming man, whom Minerva inspires with life, in a style showing the transition to the Christian period of art. Farther on, by the right wall, a mosaic with several masks. Under them: *37. Sarcophagus with Selene and Endymion. On the narrow wall are several fine Roman portrait-busts. By the left wall, in the 2nd window, 83. the *Ilian Tablet*, a small relief in palombino, a soft kind of marble, with the destruction of Troy and flight of Æneas in the centre, and many other incidents from the legends of the Trojan war, explained by Greek inscriptions, probably designed for purposes of instruction, found near Bovillæ. 83a. Fragment of a representation of the shield of Achilles, inscribed on the back as the work of Theodoros, found in 1882 near S. Maria della Vittoria on the Esquiline; on the broad margin of the marble are

seventy-five lines from Homer's description of the shield in Book XVIII. of the Iliad. 83b. Fragment of another representation of the same subject.

VIII. ROOM of VENUS. Adjoining the gallery is the Venus Room, which contains the ***Capitoline Venus*, unquestionably the workmanship of a Greek chisel, and the most admirable of all the existing copies of the Aphrodite of Cnidus by *Praxiteles* (p. xxxii), the perfect type of feminine grace. The statue was found almost uninjured in a carefully walled-up niche between the Viminal and Quirinal. — Left, Leda with the swan, a mediocre work; right, **Cupid and Psyche*, found on the Aventine.

On the S. height of the Capitol, called the *Monte Caprino* (to which a flight of steps ascends to the right at the back of the Palace of the Conservatori, comp. p. 211), stands the so-called *Casa Tarpeia* with the Protestant hospital and the new German *Archaeological Institute*, erected in 1874-76 by Laspeyres, at the cost of the German government. In the garden (custodian, Monte Caprino 25) is shown the *Rupe Tarpeia*, or Tarpeian Rock. If this really be the rock from which the condemned used to be thrown by the ancient Romans, its height and abruptness must have been greatly diminished since that period; and as, moreover, it is by no means certain that it was situated here, a visit to the spot may well be omitted. Ancient substructures of solid stone, which were discovered in the garden of the Pal. Caffarelli (p. 209) in 1866, belong to the temple of the Capitoline Jupiter (p. 208).

The imposing ruins on which the Senatorial Palace has been erected (entrance by the gate in the Via del Campidoglio, comp. p. 211; we then enter the door to the right with the superscription 'Tabulario e Torre Capitolina'; fee 50 pf.; rules as to admission the same as in the case of the Capitoline collections, p. 212) belonged to the **Tabularium*, erected in B.C. 78 by the consul Q. Lutatius Catulus for the reception of the state archives, and resting on the massive substructures which surround the hill. It consisted of a fivefold series of vaults, the last of which opened towards the Forum in the form of a colonnade with half-columns in the Doric style, which are still visible. The vaults were used in the middle ages as a public salt magazine, and the stones have been much corroded by the action of the salt. From this point there is a beautiful **View of the Forum*. The rooms contain architectural fragments from the neighbouring temples and other buildings, and a valuable collection of amphoræ (lower floor) found on the Esquiline within the last few years. An ancient flight of steps, now partly restored, descended hence to the Forum, where, to the left of the temple of Vespasian, the archway where it issued is observed. From the colonnade we may ascend to the left through the door marked 'Torre

Capitolina' to the top (261 steps) of the Campanile of the Palazzo del Senatore (p. 211).

The Forum Romanum.

(Comp. Sketch-Plan.)

In the most ancient times the Capitol and Palatine were separated by a deep and marshy valley. The pavement by the column of Phocas lies 38 ft. above the level of the sea, and 22 ft. above the level of the Tiber, but was nevertheless frequently invaded by inundations. In consequence of the lowness of this valley, it was, as may well be supposed, a difficult and tedious task to raise the level and drain the marsh. For this purpose Tarquinius Priscus, the fifth of the kings, is said to have constructed the *Cloaca Maxima*, which still renders good service (p. 248); and several *canaliculae*, or tributary drains which fell into the main channel, have recently been discovered. Tradition makes this hollow the scene of the conflict of the Romans under Romulus against the Sabines under Titus Tatius after the rape of the Sabine women. After the hostile tribes were amalgamated into a single state, they chose the Forum as its centre, and it was here that some of the most famous scenes in the history of the Roman Republic were enacted. On the N. side (S. Adriano) lay the *Curia Hostilia*, or council-hall, which is said to have been erected by King Tullus Hostilius; while on the S. side, at the foot of the Palatine, rose the *Temple of Vesta* (S. Maria Liberatrice), with its eternal fire, and the *Regia*, or dwelling of the Pontifex Maximus, the president of the Roman hierarchy. The *Comitium*, or open space in the centre, was the place where popular assemblies were wont to be held. The Forum was bounded by streets, the most important of which was the *Sacra Via* ascending to the Capitol. In the Forum and its environs building operations and various changes have been taking place at intervals for upwards of two thousand years, and it is therefore not to be wondered at that a number of topographical questions regarding it are still unsolved, and that the imagination of scholars has indulged in the most extravagant flights with regard to this spot more than any other in Rome. It is, however, ascertained that the Forum extended from the foot of the Capitol, sloping downwards towards the E., although it has sometimes been erroneously supposed that it extended from N. to S. The *Basilica Julia* marks the S. boundary of the REPUBLICAN FORUM, and the E. boundary was probably near the prolongation of the Via di San Lorenzo, as private houses only have been discovered beyond. Along the sides of the Forum were ranged the *tabernae veteres* and *novae*, or shops, which were originally occupied by butchers and other craftsmen, and afterwards by money-changers and goldsmiths. In the course of time a number of temples, public buildings, and monuments



FORUM ROMANUM.



Geograph. Anstalt von

Maßstab 1:1650

0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 160 170 180 190

Mètres



M O N S P A L A T I N U S

Wagner & Debes, Leipzig.



were erected here. Of those still existing the most ancient is the *Curcer Mamertinus* (p. 237), or well-house, situated on the slope of the Capitol, the foundation of which reaches back to the period of the kings. Soon after the temple of the Capitoline Jupiter (p. 208), were founded the *Temples of Saturn* (B.C. 491) and *Castor and Pollux* (484). The *Temple of Concord* (366) commemorates the termination of the protracted struggle between the patricians and the plebeians. At the period of the Samnite War, which resulted in the extension of Rome's supremacy over the whole of Italy, we are informed that the Forum underwent many embellishments. At last, however, as it was only 150 yds. in length, its area became too confined for the important and multifarious business transacted within its precincts; for it was not used for political and commercial purposes only, but for the celebration of the funerals of the nobility, for the gladiator combats which were introduced about the year 264, and on other public occasions. The first expedient for gaining space was the erection of basilicas, or quadrangular courts surrounded by colonnades, adjoining the Forum, with a view to draw off a portion of the traffic. In 184 Cato erected the *Basilica Porcia* on the N. side; in 179 followed the *Basilica Æmilia*, and in 169 the *Basilica Sempronia*. The task was prosecuted with the utmost energy by CÆSAR, who extended the Forum by the addition of the *Forum Julium* (pp. 237, 239), and appears to have projected a cutting through the hill which connected the Capitol with the Quirinal in order to facilitate communication with the new quarter which was rapidly springing up in the Campus Martius. He also restored the Curia Hostilia, and erected the spacious *Basilica Julia* on the S. side of the Forum. *Augustus* proceeded to carry out the plans of his uncle, and to that emperor is chiefly due the arrangement of the Forum which the present excavations are bringing to light. All the edifices of the Republic were restored by him and his successors, whose energetic building operations extended over the first four centuries of the Christian era. They thus endeavoured, as it would appear, to compensate their subjects by external magnificence for the loss of liberty they had sustained. Five new fora, constructed between the time of Cæsar and that of Trajan, adjoined each other on the N. side of the old Forum, thus connecting the central point of the original city with the palatial buildings of the Campus Martius. By these new fora the Forum of the Republic would have been well nigh eclipsed, but for the glorious traditions connected with it, to commemorate which it was profusely adorned with gilded bronzes and rare marbles, with columns, triumphal arches, statues, and works of art, while its history was recorded by innumerable inscriptions.

These ancient buildings were restored for the last time in the reign of King Theodoric, in the first half of the 6th century, and the last new monument erected in the Forum was the *Column of Phocas*, dating from 608, but the rudeness of the architecture distinctly betrays the degraded

taste of the period. As early indeed as the first half of the 6th cent. had begun the war of extermination waged by the MIDDLE AGES against paganism. Ancient temples were transformed into churches, such as those of S. Giuseppe, S. Luca, S. Adriano, S. Lorenzo, SS. Cosma e Damiano, S. Francesca, and S. Maria Liberatrice. These were afterwards frequently altered and restored, while others of the same class have entirely disappeared. Interspersed with these churches were the towers and castles of the Roman nobility, erected among the ruins of the ancient buildings in the style best adapted for the prosecution of their perpetual feuds. In most cases, the dimensions of the monuments of antiquity, were far too vast to admit of their being used for mediæval purposes, but another mode of utilising these immense masses of building materials readily suggested itself. Throughout a thousand years the edifices of ancient Rome were employed as quarries, from which churches and secular buildings alike derived their columns, their blocks of solid stone, and, owing to a still more destructive proceeding, their supplies of lime also from the burning of marble. The fact that in the Basilica Julia alone there have been discovered lime-kilns and stone-masons' yards at three different places will convey an idea of the vast quantity of marble, bearing valuable inscriptions and artistic enrichments, which must have been destroyed in this way; and it need hardly be observed that the bronzes of antiquity were still more eagerly appropriated in an age when metal of every kind was scarce. This accounts for the miserably small number of statues and inscriptions which modern excavations have yielded. After the systematic destruction of the Forum, its remains were gradually buried beneath the rubbish and debris of some four centuries, so that the ancient pavement is at places 40 ft. below the present level of the ground. Down to the 8th cent. the ancient level was unaltered. In the 11th and 12th centuries the Forum was thickly covered with towers and fortress walls, which closed up the old streets, and when these were demolished about the year 1221, the ground appears for the first time to have been covered with an accumulation of rubbish. Fresh deposits were afterwards made when the new buildings on the neighbouring heights were in course of erection. This was particularly the case in 1536, when Paul III. constructed a triumphal street from the Porta S. Sebastiano through the arches of Constantine and Titus, and around the N. side of the Capitol (on which occasion the new approaches to the latter were formed, p. 208). He caused 200 houses between the arches of Titus and Severus to be demolished, and he constructed on their site the piazza as it stood until recently. The large buildings erected by Sixtus V. probably also contributed to the raising of the level of the ground.

In the middle ages, and down to the present day, the Forum was popularly known as the *Campo Vaccino*. Its desolate area was covered with the teams of buffaloes and oxen of the peasantry, and smiths and carpenters established their workshops around it, while a few isolated columns, protruding from the rubbish, alone formed a reminiscence of its departed glory. And thus it remained until the 19th century. As early as 1519 Raphael had indeed formed a plan for restoring the ancient city, and especially the Forum, by means of extensive excavations; and during his lifetime, and subsequently, particularly in 1546-47, the work was begun in the neighbourhood of the temple of Castor and Faustina. The object in view, however, being merely the discovery of monuments and works of art, the excavations were soon filled up again, and in the 17th and 18th centuries were entirely discontinued. At length, during the present century, the plan was revived by the modern spirit of investigation. In 1803 the arch of Severus, in 1813 the column of Phocas, and in 1816-19 the Clivus Capitolinus with its temples, were disinterred under the superintendence of *Carlo Fea*. In 1835, and during the republic in 1848, part of the Basilica Julia was excavated by *Canina*, but from that year down to 1871 the work was discontinued. The Italian government resumed the excavations again with considerable energy; and by these last operations the Basilica, the temples of Castor, Cæsar, and Vesta, the Atrium Vestæ, and a great part of the neighbouring streets have been brought to light,

and an admirable clue to the arrangements of the whole locality has thus been obtained. The excavations are carried on under the superintendence of *Senator Fiorelli*, but serious obstacles are presented to the work by the growing requirements of modern business. When the demolition of the houses between S. Adriano and S. Lorenzo is effected, the undertaking, which was planned and begun when the Renaissance was at its zenith and has since been so frequently resumed, will be finally and satisfactorily completed, and the most memorable spot in the history of Europe will at length be fully brought to light and purged of the unseemly accumulations of rubbish heaped upon it by the neglect of centuries.

The ENTRANCE to the excavations (open in summer 6-12 and 3-7, in winter from 8 till dusk; no fee) adjoins the Temple of Castor, near S. Maria Liberatrice (comp. the Plan). The part of the Forum next the Capitol, containing the Colonnade of the Twelve Gods and the temples of Vespasian and Concordia, is now enclosed by a railing and is best viewed from above. The street uniting the Via Bonella and Via della Consolazione is generally the scene of a busy traffic.

Descending from the piazza of the Capitol through the Via del Campidoglio to the right, past the Senatorial Palace (comp. p. 211), we enjoy from the lower end another good *SURVEY OF THE FORUM. To the left, below us, lie the temple of Saturn, to which the eight unfluted columns belong, the three columns of the temple of Vespasian, and the arch of Septimius Severus. Farther off, partly hidden by the columns of the temple of Saturn, are the column of Phocas, the great Basilica, the three columns of the temple of Castor, and the bare walls of the temples of Vesta and Cæsar. Beyond these, to the left, are the temple of Faustina, now converted into a church, and the circular temple of Romulus with the church of SS. Cosma e Damiano, opposite which are the remains of numerous brick shops and houses; then the huge arches of the basilica of Constantine, the Colosseum, the arch of Titus, and to the right the ruins and gardens of the Palatine.

The first building below the Tabularium (p. 221), in the angle formed with it by the street, is the **Colonnade of the Twelve Gods** (*deorum consentium*), whose images were erected here in A.D. 367 by Vettius Agorius Prætextatus, the præfectus urbis, and one of the principal champions of expiring paganism. In 1858 the ruin was much modernised. The chambers in the colonnade on the side next the Temple of Vespasian are generally but erroneously called the *Schola Xantha* (a meeting-place of scribes and notaries).

To the right of the Colonnade of the Twelve Gods the Tabularium is adjoined by the *Ruin of the Three Columns*, or ***Temple of Vespasian**, erected under Domitian, and restored by Septimius Severus. The inscription ran thus: '*Divo Vespasiano Augusto Senatus populusque Romanus; imperatores Caesares Severus et Antoninus Pii Felices Augusti restituer(unt)*.' A part of the last word only is preserved. The columns and entablature display excellent workmanship. In front the temple had 6 columns, 49 ft. high, and 4½ ft. thick at the base. An egress of the Tabularium (p. 221) through the back of the cella has evidently been built up.

Farther on, to the right, and with its back to the Tabularium,

is the **Temple of Concordia**, founded in B.C. 366 by M. Furius Camillus, and rebuilt on a larger scale by Tiberius, B.C. 7. It was dedicated to Concord to commemorate the termination of the protracted struggle between the patricians and plebeians. The *Cella* of this temple differed from the usual type in having its longer axis (130 ft.) at right angles to the longer axis of the temple; it is 82 ft. wide. The N. part of the cella is concealed by the ascent to Araceli. A broad flight of steps ascended to the *Pronaos*, which lay 20 ft. above the level of the street and was 88 ft. long and 46 ft. wide. The interior of the temple was frequently used in early times for meetings of the Senate, and after the restoration of Tiberius it seems to have served chiefly for the exhibition of works of art.

The *Sacra Via*, or 'Holy Way', forming the chief line of communication between the Capitol and the Forum, passed in front of the buildings just named. The ancient pavement is still well preserved near the Temple of Saturn (see p. 227) and at some other points.


In order to continue our examination of the Forum we now proceed to the entrance at S. Maria Liberatrice (p. 225), where a flight of wooden steps descends to the Temple of Castor. The view from this point, reinforced by a reference to the Plan, will help the visitor to understand the arrangement of the Forum.

The ***Temple of Castor and Pollux**, generally called the *Temple of Castor* (*Ædes Castoris* or *Castorum*), was dedicated to the twin gods out of gratitude for the aid which enabled the Romans to defeat the Latins at the battle of Lake Regillus in B.C. 496, and inaugurated in 484. It was afterwards rebuilt by Tiberius and re-consecrated in A.D. 6. This was one of the most famous temples of the Republic, and was often used for meetings of the senate. The remains consist of the basement and a piece of the stylobate on the E. side, with three splendid columns of Parian marble.

The basement of the cella rises to a height of 22 ft., and was approached by a flight of 18 steps, with two lateral flights, of which that on the S.E. side only is preserved. The building was mainly constructed of concrete, which was faced with blocks of tufa, and around these were placed the blocks of travertine which supported the enclosing colonnade. These blocks, however, as well as the steps on the W. side, have entirely disappeared (although the impression made by them on the concrete is still visible), and the width of the building has thus been diminished by about one half. On the E. side stands a fragment of the STYLOBATE, with three columns of Parian marble, which are among the finest of the kind now existing (height 46 ft., diameter 5 ft.). The Corinthian capitals and the architrave are both in a very superior style of workmanship. The temple had eight columns in front and probably thirteen on each side. Remains of the mosaic pavement of the CELLA are still to be seen, lying about 3 ft. below the level of the portico and the surrounding colonnade. This peculiarity was probably occasioned by the alterations made by Tiberius.



Between the Temple of the Dioscuri and the Basilica Julia runs the *Vicus Tuscus*, a busy street leading to the Velabrum and the cattle-market on the river (p. 248).

The ***Basilica Julia** was founded by Caesar with a view to enlarge



FORO ROMANO

Scala 1:1000




STATO ATTUALE




LATO SETTENTRIONALE

Tabulario Capitolino




RICOSTRUZIONE

Palazzo del Senatore




STATO ATTUALE

RICOSTRUZIONE



Concordia

STATO ATTUALE



Concordia

the Forum; it was inaugurated in B.C. 46, after the battle of Thapsus, though still unfinished. Augustus extended it, but did not witness its completion, as it was destroyed by a fire. The building was again twice injured by fire towards the end of the 3rd century. It was restored several times, the last being in A. D. 377. The building is mentioned in history for the last time in the 7th cent., and it was probably destroyed in the 8th. After several partial excavations, it was entirely extricated in 1871 and 1882-83.

The GROUND PLAN of the basilica is a rectangle, about 111 yds. long and 53 yds. wide. A flight of six, and at places nine, steps ascended to the basilica from the street. Along the four sides were double aisles which enclosed a CENTRAL SPACE, about 90 yds. by 17 yds., paved with variegated African and Phrygian marble, and separated from the aisles by iron railings. The greater part of the pavement has been restored, a few fragments of the original only having been preserved. The sittings of the tribunal of the Centumviri, in four different sections, took place here. The AISLES were paved with white marble, on which are still seen a number of circles, and occasionally writing, scratched on the surface by visitors. These were used in playing a game resembling draughts, to which the ancient Romans were as devoted as the modern. The aisles were separated by a triple row of COLUMNS, of which nothing but the bases remain; the blocks of which they consisted were used in building the Pal. Giraud in the Borgo (p. 276) and others. The brick pillars have been reconstructed, partly with the original materials. On the W. side the remains are somewhat more important, owing to the fact that a mediæval church was built in this part of the basilica. Here, on the side next the street, still stand marble pillars adorned with Doric pilasters, while at the back, facing the Consolazione, are lofty walls of tuffstone and travertine. Steps ascended here to the upper story.

The main arm of the *Cloaca Maxima*, discovered in 1872, runs under the E. end of the Basilica Julia.

The *Vicus Jugarius* (street of the yoke-makers) led between the Temple of Saturn and the Basilica to the Tiber. Between the Rostra and the Basilica the *Sacra Via* was spanned by the *Triumphal Arch of Tiberius*, erected in A.D. 16 to commemorate the defeat of the Germanic tribes and the recovery of the Roman insignia lost at the battle of the Teutoburgian Forest. Its remains were scattered in 1850 on the construction of a modern street, which, however, has since been itself demolished.

The ***Temple of Saturn**, of which eight granite columns are still standing on a high basement, was consecrated by the consuls Sempronius and Minucius, B. C. 497, and restored by Munatius Plancus (B.C. 44?). From the earliest times it was the seat of the *Ærarium Publicum*, or public treasury. The inscription, *Senatus populusque Romanus incendio consumptum restituit*, refers to a later restoration, undertaken hastily and without taste. Of the lofty flight of steps by which the portico was approached there are now but scanty traces.

In front of the Temple of Saturn is a piece of excellent road-paving, contrasting markedly with the rest of the paving in the Forum, which is carelessly laid and of a late period. On the *Clivus Capitolinus*, or road ascending to the Capitol, near the Arch of Severus, are the remains of the *Umbilicus Urbis Romæ*, or ideal

centre of the city and empire. Traces have also been found of the *Milliarium Aureum*, or central milestone of the roads radiating from Rome, erected by Augustus in B.C. 28.

Over the *Sacra Via* rises the ***Triumphal Arch of Septimius Severus**, 75 ft. in height, 82 ft. in breadth, with three passages over the N. branch of the *Sacra Via*. It was erected in honour of the emperor and his sons Caracalla and Geta in A.D. 203, to commemorate their victories over the Parthians, Arabians, and Adiabeni, and was surmounted by a brazen chariot with six horses, on which stood Severus, crowned by Victory. Caracalla afterwards erased the name of his brother Geta, whom he had murdered. The gap thus made was filled by an addition to the titles of Caracalla and his father.

Above the arches are figures of Victory; at the sides, crowded scenes from the wars of the emperor. Side next the Forum: (l.), Raising of the siege of Nisibis in the Parthian war; (r.), Treaty with Armenia, Siege of Atræ. Side next the Capitol: (r.), Siege and capture of Babylon; (l.), Crossing of the Euphrates and Tigris, Conquest of Ctesiphon and Seleucia. On the bases of the columns, Captive barbarians. All these figures are in the degraded style of the sculpture of that period. In the middle ages the arch was temporarily converted by the ruling powers into a kind of castle, and was deeply imbedded in rubbish, but it was unearthed by Pius VII. in 1803.

Passing through the arch and turning to the right, we see before us the massive stone remains of the **Rostra**, or orators' tribune, erected by Julius Cæsar. This tribune consisted of an extensive raised platform, about 80 ft. long and 40 ft. wide, adorned with statues and tablets, and giving the orator room to walk up and down during his speech. It has been aptly compared to the preaching stages in some of the Roman and Neapolitan churches.

The original tribune derived the name of Rostra from the iron prows of the war-ships of Antium with which it was adorned after the capture of that town in B.C. 338. Its position cannot now be definitely fixed, but was certainly nearer the *Curia* (S. Adriano). Cæsar transferred it to the end of the Forum in the course of his extensive building operations. The holes in which the iron prows were fastened are still visible in the massive blocks of hewn stone.

The Rostra naturally faced the Forum proper, the space reserved for public assemblies. Most of this area is still covered with houses, but the S.W. corner, paved with slabs of limestone, is open to view. Anciently it extended to the church of S. Adriano (p. 238), occupying the site of the *Curia*, or hall of the Senate. Between S. Adriano and the temple of Faustina lay the *Basilica Emilia*, the site of which is also covered with modern houses.

Opposite the Rostra, on a rude substructure of blocks of tufa, occupying part of the place used by the popular meetings, rises the latest monument of antiquity in the Forum, the ***Column of Phocas**, 54 ft. in height, which was erected in 608 in honour of the tyrant Phocas of the Eastern Empire, by the exarch Smaragdus, having been taken by him from some older building. It was formerly crowned with a gilded statue of Phocas. This column, which long formed the distinctive mark of the Forum (Byron's 'nameless column with

a buried base'), was at length disinterred in 1813 at the cost of the Duchess of Devonshire.

Among the monuments now standing on the pavement of the Forum, the first place in point of artistic execution and preservation is taken by a marble railing adorned with two admirable reliefs ('*Anaglypha*'). These were found in 1872 incorporated in the foundations of a mediæval building. They probably formed part of the decoration of the balustrade of the steps ascending to the Rostra. They represent events that took place in the Forum itself, and their architectural backgrounds are of great assistance in determining its appearance in antiquity.

THE FIRST RELIEF (next the Capitol) alludes to Trajan's '*Alimenta*', or institution for poor children: on the right is the emperor, in front of him is Italy, holding a child by the hand (destroyed), and another in her arms to which Trajan hands a '*tessera*', or ticket; on the left is a magistrate with his lictors, proclaiming his edict from the rostra. In the background are a Triumphal Arch (perhaps that of Augustus, which stood down to the 9th cent. near the church of S. Martina), the Curia (with its five Corinthian columns), the Basilica *Æmilia*, the Ficus Ruminalis (or fig-tree under which the she-wolf reposed), and the statue of Marsyas (which stood at the lower end of the Forum, near the Temple of Castor). All these were in or near the N.E. part of the Forum. — The SECOND RELIEF represents the remission of arrears of taxes, the records of which are being set on fire in Trajan's presence. In the background are the buildings on the N. and W. sides of the Forum: the Temple of Concordia (with eight Corinthian columns), an arch (perhaps of the Tabularium), the Temple of Saturn (with eight Ionic columns), and the Basilica Julia. Marsyas and the fig-tree also again occur. On the inner sides are a wild boar, a ram, and a bull, the victims sacrificed at the public celebration of the *Suovetaurilia*.

The subjoined VIEWS OF THE N. AND W. SIDES OF THE FORUM are taken from a point in front of the *Anaglypha*. At the top are reconstructions of the ancient appearance of the Forum, and below its present appearance. In the former the flutings of the columns have been omitted for the sake of clearness.

In the middle of the square are the remains of a large pedestal, probably of the equestrian statue of an emperor. The eight square pedestals of brick, which adjoin the Forum on the side next the S. branch of the *Sacra Via*, were formerly lined with marble and probably bore granite columns (fragments of which lie scattered about) surmounted with statues. The hasty construction points to a late origin, perhaps in the reign of Constantine.

On the E. side of the Forum, and facing the Capitol, is situated the Temple of *Cæsar*, near which *Cæsar* had erected a new oratorical tribune. It was from this tribune, at the funeral of the murdered dictator on 19th or 20th March, B.C. 44, that Mark Antony pronounced the celebrated oration which wrought so powerfully on the passions of the excited populace. A funeral pyre was hastily improvised, and the unparalleled honour accorded to the illustrious deceased of being burned in view of the most sacred shrines of the city. A column with the inscription '*parenti patriæ*' was afterwards erected here to commemorate the event. Augustus erected this temple in honour of '*Divus Julius*', his deified uncle

and adoptive father, and dedicated it to him in B.C. 29, after the battle of Actium. At the same time he adorned the tribune with the prows of the captured Egyptian vessels.

The foundation of the substructures of the temple, consisting of concrete, were discovered in 1872, but their covering of solid stone has been removed. In front of the temple there are the remains of a platform, still partly paved with slabs of stone, which is believed to have been the above-mentioned tribune or *Rostra ad Divi Julii*. Its present form appears to have resulted from subsequent alterations.

Between the Temple of Cæsar and the Temple of Castor and Pollux the remains of a *Triumphal Arch of Augustus* were recently found. This arch spanned the Sacra Via and formed the architectural termination of the Forum.

Farther on, to the S.E. of the Temple of Castor, near the slopes of the Palatine, lies a group of buildings connected with one of the most venerable cults of Rome, that of Vesta. The circular erection of tufa belonged to the celebrated *Temple of Vesta*, in which the sacred fire was kept alight by the Vestal Virgins. Numerous fragments of its marble ornamentation strew the ground. The workmanship of these is somewhat careless, dating apparently from the restoration of the temple in the 3rd century of our era. — A small and well-preserved *Ædicula*, or shrine for the image of a god, erected according to the inscription by the Senate and People of Rome, was found behind the temple in 1882.

Adjoining the *Ædicula* are a few steps and a side-entrance leading to the **Atrium Vestæ*, or Palace of the Vestal Virgins, excavated in 1883-84. The extant ruins are of carefully constructed brickwork, which, however, has almost entirely lost its marble facing. They date from the imperial period, probably from the 2nd cent. of our era. The whole building falls into three divisions: a rectangular colonnaded court, corresponding to the Atrium in private houses; the dwelling-rooms of the Vestals, grouped round a lofty square apartment, resembling the ordinary *Tablinum*; and the kitchen and offices to the right, behind the Atrium.

The COURT, 224 ft. long and 75 ft. wide, is the most extensive part of the building. It was surrounded by a two-storied arcade, with columns of veined green cipollino marble below and red breccia corallina above. The middle of the court was probably occupied by fountains and flower-beds, in order to make it as pleasant as possible for the Vestals, who were confined to their palace like the inmates of a nunnery. The court was also adorned with statues of the Head Vestals (*Virgines Vestales Maximæ*), of which eleven are still preserved in whole or in part, some showing excellent workmanship. The intervention of the Vestal Virgins was often very effective in procuring appointments to official and even military posts, and the inscriptions on the bases of some of the statues show that they were erected by grateful relatives and other recipients of such favours. The names (Numisia Maximilla, Terentia Flavola, Flavia Publicia, Coelia Claudiana, Terentia Rufilla) belong to the 3rd and 4th cent. (201-364 A. D.). At the inner end of the court is a marble-lined cistern for the reception of rain-water, as a venerable precept of their cult forbade the priestesses to use water conveyed through artificial channels.

The second division of the palace consists of the DWELLING ROOMS. In the middle is a lofty square room approached by steps. On each side

of it are three doors giving access to what are supposed to be the cells of the six priestesses. There were other apartments in the upper floor, of which, however, a part only, including several bath-rooms, has been preserved. A wooden staircase ascends from one of the apartments on the S. side. Here also is an exit leading to the *Nova Via*, which diverged from the *Sacra Via* at the Arch of Titus (p. 214).

The third group of rooms, behind the *Atrium*, to the right, were used for DOMESTIC PURPOSES. A mill, a kitchen, and several storerooms may be here observed.

We now return to the Temple of Vesta and continue our walk along the *Sacra Via*.

Between the temples of Vesta and Faustina are a few fragments of the marble walls of the *Regia*, or official quarters of the Pontifex Maximus. The Fasti preserved in the Capitol (see p. 215) were found here. At the *Regia* the *Sacra Via* was spanned by the *Arch of the Fabii*, erected in B.C. 120 by Q. Fabius Maximus, the conqueror of the *Allobrogi*, and forming the S.E. boundary of the Forum. A few scattered fragments of its stone-facing and vaulting have been discovered, and may now be seen opposite SS. Cosma e Damiano. The exact site of the arch cannot be identified.

Farther on in the *Sacra Via*, on a base 16 ft. above the street and formerly reached by a flight of steps, is the ***Temple of Faustina**, of which the portico (with ten columns, six of which form the façade) and part of the cella are still standing. It was dedicated by Antoninus in 141 to his wife, the elder Faustina, and re-dedicated to that emperor himself after his death. The first line of the inscription, *Divo Antonino et divae Faustinae ex S.C.*, was then added. In the interior of the temple is the church of *S. Lorenzo in Miranda*.

The portico was excavated in 1807 and 1810. The columns are of cipollino, or marble of Eubœa, and are 46 ft. in height. The cella is of peperino, the marble incrustation of which has entirely disappeared. — The year of the foundation of the church is unknown, and the earliest record of it dates from 1377. The façade was erected in 1602. The entrance is at present in the *Via di S. Lorenzo in Miranda*, on the S.E. side.

A hill, named the *Velia* in ancient times, connects the Palatine and Esquiline, its highest point being marked by the Arch of Titus (97 ft.; p. 233). The *Sacra Via* ascends gradually towards the S.E., and soon reaches —

* **SS. Cosma e Damiano** (Pl. II, 20, 5: entered in the *Via di Miranda*), built by Felix IV. (526-30), having been incorporated with an ancient circular temple erected by the Emp. Maxentius to his son Romulus, and sometimes erroneously called a temple of the Penates. Owing to the dampness of the soil, Urban VIII. raised the level of the pavement so much in 1633, that an upper and a lower church were formed.

The LOWER CHURCH, which retains its old bronze doors with their antique lock, contains the tomb of SS. Cosmas, Damianus, and Felix, an ancient altar, remains of an ancient pavement, and somewhat lower a spring, said to have been called forth by St. Felix.

UPPER CHURCH. On the arch of the choir and in the tribune are interesting **Mosaics* of the 6th cent., the period of the founder, perhaps the most

beautiful of their kind at Rome (see p. xlv), but freely restored about 1660 (best light towards evening). Those on the arch, which has been shortened during a restoration, represent the Lamb with the Book with seven seals, according to Revelations iv.; adjoining these the seven candlesticks, four angels, and two of the symbols (angel and eagle) of the Evangelists. The arms with wreaths, below, belonged to two prophets. In the tribune: Christ, to whom the saints Cosmas and Damianus are conducted by Peter and Paul; on the left side St. Felix with the church (new), on the right St. Theodorus. Beneath, Christ as the Lamb, towards whom the twelve lambs (Apostles) turn.

At the back of the church were found the remains of an ancient plan of Rome, other fragments of which were discovered in 1867-68 and in 1882 (see p. 217). The ancient wall to which the plan was affixed belonged to the *Templum Sacrae Urbis*, an edifice erected by Vespasian in A.D. 78 and restored by Septimius Severus, which seems to have been used as a repository for the archives of the censor, municipal plans, registration lists, etc.

We next reach, on the left, the three colossal arches of the **Basilica of Constantine* (Pl. II, 20, 23), erected by Maxentius, but afterwards altered by his conqueror Constantine. The entrance originally faced the Colosseum, but afterwards the Sacra Via. It was a basilica of three halls, with vaulting of vast span, which has served as a model to modern architects, as in the case of St. Peter's, where the nave-vaulting is of the same width.

The *Ground Plan* is rectangular in form, about 100 yds. long and 88 yds. wide. The principal apse, opposite the entrance from the Colosseum, has lately been extricated from rubbish, but is only partly preserved. After the opening of the second entrance on the side next the Palatine, a second apse was added. The tunnel vaulting of the S. aisle has been preserved; width 66 ft., depth 54 ft., height 78 ft. The span of the nave was about 80 ft.; its height 112 ft., and its width 66 ft. In front of the central pillars stood eight huge Corinthian columns of white marble; the only one now existing stands in front of S. Maria Maggiore (p. 176). The entrance facing the Sacra Via was formerly adorned with columns of red porphyry, some of the shafts of which have been re-erected.

The traveller should not omit to ascend to the summit for the sake of the magnificent ***PANORAMA* of ancient Rome which it commands. As, however, the Via in Miranda is now inaccessible from the Forum, we must make a detour to reach the roof; perhaps the best plan is to ascend on the way back from the Colosseum. Those who wish also to visit the interior follow the road between the side of S. Francesca Romana and the high garden-wall, and opposite the Colosseum turn sharply to the left and descend the Via del Colosseo. At the corner here is No. 61, a home for poor girls (visitors ring; $\frac{1}{2}$ fr.), from the garden of which we ascend a light of steps. A window adjoining the stairs affords the best view of Colosseum, to the left of which are the Thermæ of Titus on the Esquiline; to the right the circular S. Stefano; nearer, SS. Giovanni e Paolo with the new dome, both on the Cælius. Beyond the Colosseum the Alban, and to the left the Sabine Mts. To the S. the Palatine with the ruins of the imperial palaces and two monasteries, and the opposite bank of the Tiber with the Villa Pamphili. Towards the W. the Capitol; to the right of it, between the domes of two churches, Trajan's Column is visible; above the latter Monte Mario; farther to the right the Torre di Nerone and the Quirinal.

Adjoining the basilica of Constantine, and partly occupying the site of a temple of Venus and Roma (see p. 233), is the church of—

S. Francesca Romana (Pl. II, 23), containing the tomb of *Franческа de' Ponziani*, who died in 1440 and was canonised in 1608

(festival, 9th March). It occupies the site of a much older church, mentioned as *S. Maria Antiqua* as early as the 8th cent., which was afterwards repeatedly altered. The most extensive restoration was carried out by Honorius III. about 1216, after a fire. In the later middle ages it was called *S. Maria Nova*. The façade, by *Carlo Lombardo*, was added about 1612.

Interior. On the right, 2nd Chapel: (r.) Monument of Card. Vulcani (d. 1322) and that of the papal commandant and general Antonio Rido (d. 1475). 3rd Chapel: Miracles of St. Benedict, altar-piece by *Subleyras*. In the TRIBUNE mosaics of the 12th cent. (lately restored): in the centre Madonna, (l.) SS. John and James, (r.) Peter and Andrew. Over the high-altar an ancient Madonna, traditionally attributed to St. Luke, which is said alone to have escaped destruction in the conflagration. To the right of the apse: monument of Gregory XI., who transferred the papal residence from Avignon to Rome (d. 1378), with a relief by *Olivieri*. Here on the right, built into the wall, are two stones on which Peter and Paul are said to have knelt when they prayed for the punishment of Simon Magus. In the Confessio a group of the saints with an angel, by *Meli*. Under the tribune (closed) is the tomb of the saint, and over the altar a marble relief by *Bernini*. — **SACRISTY.** On the left wall a Madonna with four saints, by *Sinibaldo Ibi*, a pupil of Perugino, 1524.

Adjoining the church, on the summit of the *Velia* (p. 231) and at the foot of the Palatine, rises the ***Triumphal Arch of Titus**, commemorating the defeat of the Jews (A.D. 70), and dedicated to him under his successor Domitian in 81, as the inscription on the side next the Colosseum records: *Senatus populusque Romanus divo Tito divi Vespasiani filio Vespasiano Augusto*. The arch is embellished with fine ***Reliefs** (p. xxxvii).

OUTSIDE: On the same side as the inscription is a sacrificial procession on the frieze. **INSIDE:** Titus crowned by Victory in a quadriga driven by Roma; opposite, the triumphal procession with the captive Jews, table with the show-bread, and candlestick with seven branches. — In the middle ages the arch was used as a fortress by the Frangipani, and strengthened with battlements and new walls. When these were removed in 1822 under Pius VII., the arch lost its support, and had to be reconstructed, as stated by the inscription on the other side. The central part, in marble, is therefore alone ancient; the restored parts are of travertine.

The street descends past the remains of private houses to the Colosseum. [To the right diverges the Via S. Bonaventura, with the convent of *S. Bonaventura*; the convent-garden, open to gentlemen, contains a fine palm and commands a beautiful view.] On the left is the double apse of the **Temple of Venus and Roma** (Pl. II, 20), erected by Hadrian from a plan by himself in A.D. 135, and restored after a fire by Maxentius in 307. This was one of the most superb temples in Rome. The gilded bronze tiles were removed to St. Peter's by Honorius I. in 626.

There were evidently two temples under the same roof, entered from the sides next the Colosseum and next the Capitol. The cellæ were adjacent, so that there was a niche on each side of the central wall for the image of a god. The older portion, with a well-preserved ***Apse**, is built into the monastery of *S. Francesca Romana* (p. 232), which is now occupied by the Directors of the Excavations; the other half towards the Colosseum is open. The vestibules of the cellæ had each four columns in front. Around each ran a colonnade of ten columns at the ends, and twenty at the sides (length 120 yds., width 58 yds.). This colonnade was

enclosed by a second, of about 200 columns, 180 yds. long, and 110 yds. wide, and projecting as far as the street, where it was supported by massive substructures. To this colonnade belonged the granite shafts scattered about here. The cellæ were encrusted with the rarest marbles.

Descending hence towards the Colosseum, we reach the so-called *Meta Sudans*, the partly restored brick interior of a magnificent fountain erected here by Domitian. To the right we see the Arch of Constantine (p. 236). To the left (N.) we observe the remains of an extensive square *Basis* of masonry. Here once stood the gilded bronze *Colossal Statue of Nero*, as god of the sun, surrounded with rays, and about 117 ft. in height, executed by Zenodorus by order of the emperor himself, to grace the golden palace which he erected with lavish splendour after the burning of Rome in A.D. 64. The palace fell to decay soon after Nero's death in 68 (p. 133), and the statue was removed by Hadrian to this pedestal. In the space occupied by an artificial lake in the gardens of Nero, Vespasian founded the —

****Colosseum** (Pl. II, 24), originally called the *Amphitheatrum Flavium*, the largest theatre, and one of the most imposing structures in the world, completed by Titus in A. D. 80. It was inaugurated by gladiatorial combats, continued during 100 days, in which 5000 wild animals were killed, and naval contests were exhibited; and it contained seats for 87,000 spectators. The building has been known since the 8th cent. under its present name, derived probably from the colossal statue of Nero which once adorned it.

Having been injured by fire in the reign of Macrinus, it was restored by Alexander Severus. In 248 the Emp. Philip here celebrated the 1000th anniversary of the foundation of Rome with magnificent games. In 405 gladiator-combats were abolished by Honorius as inconsistent with the precepts of Christianity, but wild-beast fights were continued till the time of Theodoric the Great. In the MIDDLE AGES the Colosseum was used by the Roman barons, especially the Frangipani, as a fortress. In 1312 the Annibaldi were obliged to surrender it to Emp. Henry VII., who presented it to the Roman senate and people. In 1332 the Roman nobility again introduced bull-fights. After this period, however, the destruction of the Colosseum began, and the stupendous pile began to be regarded as a kind of quarry. In the 15th cent. Paul II. here procured materials for the construction of the Pal. di S. Marco (di Venezia), Card. Riario for the Cancelleria, and Paul III. (1534-49) for the Palazzo Farnese. Sixtus V. proposed to establish a cloth-factory here, and Clement XI. actually used the building for the manufacture of saltpetre. Benedict XIV. (1740-58) was the first to protect the edifice from farther demolition by consecrating the interior to the Passion of Christ, referring to the frequency with which the blood of martyrs had flowed there; and he erected small chapels within it, which were removed in 1874. The following popes, particularly Pius VII. and Leo XII., have averted the imminent danger of the fall of the ruins by the erection of huge buttresses. The steps in the interior were restored by Pius IX.

The Colossenm is constructed of blocks of travertine, originally held together by iron cramps, and tufa and bricks have also been used in the interior. The numerous holes were bored in the middle ages, for the purpose of extracting the then very valuable iron. According to the most trustworthy statistics the external circumference of the elliptical structure measures 576 yds., or nearly one-third of a mile, the long diameter 205 yds., the shorter 170 yds.,

the arena 93 yds. by 58 yds., and the height 156 ft. Above the arena rise the tiers of seats, intersected by steps and passages, most of which are now in ruins and only partly accessible.

The exterior of the still preserved N.E. portion, on the side next the Esquiline, consists of four stories, the three first being formed by arcades, the pillars of which are adorned with half-columns of the Doric, Ionic, and Corinthian order in the 1st, 2nd, and 3rd stories respectively. A wall with windows between Corinthian pilasters forms the 4th story. Statues were placed in the arcades of the 2nd and 3rd stories, as appears from the representations on ancient coins. At the ends of the diameters are the four triple **PRINCIPAL ENTRANCES**, those next to the Esquiline and Cælius being destined for the emperor, the others for the solemn procession before the beginning of the games, and for the introduction of the animals and machinery. On the side next the Esquiline are seen traces of the stucco-decorations, which were used as models by Giovanni da Udine, the pupil of Raphael. The arcades of the lowest story served as entrances for the spectators, and were furnished with numbers up to LXXVI (Nos. xxiii to liv still exist), in order to indicate the staircases to the different seats. Below, on the exterior, are two rows of arcades; inside a massive substructure for the seats. Every fourth arch contains a staircase.

Part of the **TIERS OF SEATS** is still distinguishable; the foremost, called the *Podium*, was destined for the emperor, the senators, and the Vestal Virgins. The emperor occupied a raised seat, called the *Pulvinar*, and the others had seats of honour. Above the *Podium* rose three other classes of seats, the first of which was allotted to the knights. The humbler spectators occupied the last division, in a colonnade, on the roof of which were stationed sailors of the imperial fleet for the purpose of stretching sail-cloth over the whole amphitheatre to exclude the glare of sun. Apertures are still seen in the external coping, with corbels below them, for the support of the masts to which the necessary ropes were attached.

Under the **ARENA**, and adjacent to the foundations of the inner wall, were chambers and dens for the wild beasts. More towards the centre were found a number of walls, pillars, and arches, partly required for the support of the arena, and partly connected with the theatrical apparatus employed in some of the performances. Since 1874 one half of the arena has been disclosed by excavations. The precise uses of the various chambers are not yet ascertained.

Although one-third only of the gigantic structure remains, the ruins are still stupendously impressive. An architect of last century estimated the value of the materials still existing at $11\frac{1}{2}$ million scudi, which according to the present value of money would be equivalent to at least half a million pounds sterling. The Colosseum has ever been a symbol of the greatness of Rome, and gave rise in the 8th cent. to a prophetic saying of the pilgrims: —

'While stands the Colosseum, Rome shall stand,
When falls the Colosseum, Rome shall fall,
And when Rome falls, with it shall fall the World!'

The UPPER STORIES should be visited by those who desire to obtain a distinct idea of the character of the structure (eustodian found at the entrance next to the Palatine; gratuities forbidden). We ascend a new stone staircase to the first story. Of the three arcades here we follow the innermost, which affords a survey of the interior. Over the entrance from the Palatine a modern staircase of 48 steps ascends to the 2nd, and then to the left to a projection in the 3rd story. The VIEW from the restored balustrade to the right in the 4th story, to which 55 more steps ascend, is still more extensive. It embraces the Cælius with S. Stefano Rotondo and SS. Giovanni e Paolo; farther off, the Aventine with S. Balbina, in the background S. Paolo Fuori; nearer, to the right, the Pyramid of Cestius; to the right the Palatine, with the arches of the Aqua Claudia.

The Colosseum is profoundly impressive by MOONLIGHT, or when illuminated (*e.g.*, by Bengal lights; comp. p. 122). The traveller should avail himself of a fine moonlight night for the purpose. Visitors may enter the arena at any hour of the night, but a special permesso of the Ministry is necessary for access to the tiers of seats. The Flora found among the ruins of the Colosseum once comprised 420 species, which were collected by an English botanist, but most of them have disappeared.

To the S.W. of the Colosseum, between the Cælius and Palatine, spanning the *Via Triumphalis* which here joined the *Sacra Via*, stands the —

***Triumphal Arch of Constantine** (Pl. II, 24), the best-preserved structure of the kind in Rome, erected after the victory over Maxentius at Saxa Rubra, near the Ponte Molle, in 311, when Constantine declared himself in favour of Christianity. The inscription runs thus: *Imp. Caes. Fl. Constantino Maximo pio felici Augusto Senatus Populusque Romanus, quod instinctu divinitatis mentis magnitudine cum exercitu suo tam de tyranno quam de omni ejus factione uno tempore justis rem publicam ultus est armis arcum triumphis insignem dicavit*. The arch has three passages. The greater part of the ornamentation and the admirable *SCULPTURES were brought from an arch of Trajan which stood at the entrance to Trajan's Forum, contrasting strongly with the rude additions of the time of Constantine.

From the ARCH OF TRAJAN: Above, the captive Dacians (ancient; but one of them, and the heads and hands of the others, are new). *Reliefs* (facing the Colosseum, to the left): 1. Trajan's entry into Rome; to the right of it, 2. Prolongation of the Via Appia; 3. Trajan causing poor children to be educated; 4. Trajan condemning a barbarian. On the other side, to the left: 5. Trajan crowning the Parthian king Parthamaspates; 6. Soldiers bringing two barbarians before Trajan; 7. Trajan addressing the army; 8. Trajan sacrificing. The eight *Medallions* below these reliefs represent sacrifices and hunting-scenes; on the narrow sides two battles with the Dacians; below the central arch, the vanquished imploring pardon, and Trajan crowned by Victory. — The marked contrast between the two different periods of art is exhibited by the smaller reliefs inserted between the medallions, representing the achievements of CONSTANTINE in war and in peace. In 1804 Pius VII. caused the arch to be thoroughly excavated. In the 10th cent. it was converted into a castle, and afterwards belonged to the Frangipani.

On the opposite side, a few hundred paces to the N.E. of the Colosseum, in the Via Labicana, first gate to the left (whence the

Via della Polveriera ascends to the left between walls in 5 min. to S. Pietro in Vincoli, p. 182), are situated on the Esquiline the —

***Thermæ of Titus** (Pl. II, 26; adm., see p. 124); visitors should be careful not to enter these ruins in a heated condition. Mæcenas once had a villa here, which was afterwards incorporated with the golden palace of Nero. On the site of the latter, in A.D. 80, Titus hastily erected his sumptuous Thermæ, which were altered and enlarged by Domitian, Trajan, and others. The Thermæ themselves, though still nearly entire in the 16th cent., have now almost vanished; some fragments of them are scattered over the vineyards between the Via Labicana and the Via S. Pietro in Vincoli. The small part now accessible, excavated in 1813, belongs almost wholly to Nero's building.

The nine long vaulted parallel passages first entered belong to the building of Titus and formed together the substructure of a large semi-circular Exedra, such as is found at the Thermæ of Dioeletian, Caracalla (p. 255), and others. Nero's buildings form an angle of 45° with the axis of the Thermæ. A suite of seven rooms is first entered here; to the left, near that in the centre, are remains of a spring. The special purpose of these rooms, which seem to have had no connection with the Thermæ, cannot be definitely settled. Their chief interest lies in the beautiful mural paintings, which served as models for Giovanni da Udine and Raphael in the decoration of the loggie. The eustodian points out the spot where the Laocoon is said to have been found, but this famous group was really found at the Sette Sale (p. 181).

Fora of the Emperors. Academy of St. Luke.

In the plain to the N.E. of the Forum of the Republic lay the *Fora of the Emperors*, which were erected rather as monuments to their founders and ornaments to the city than for political purposes, and were chiefly used for judicial proceedings. The chief edifice in these fora was always a temple. The Forum Julium, the first of the kind, was begun by Cæsar and completed by Augustus; the second was built by Augustus. A third, in front of the Templum Sacræ Urbis (p. 232), was constructed by Vespasian. Between this forum and the first two lay the Forum Transitorium (see p. 239), to the N. of which was that of Trajan (p. 240), the most magnificent of all.

We begin our inspection at the N. corner of the Forum Romanum, where the *Via dell' Arco di Settimio Severo* (p. 211), descending from the Capitol, unites with the *Via di Marforio* (p. 163).

Here, in the Via di Marforio, lies the small church of *S. Giuseppe de' Falegnami* (Pl. II, 20, 3), which is built over the **Carcere Mamertinus**, one of the most ancient structures in Rome (entr. from the church; light supplied by the sacristan, 1/2 fr.). This was originally built over a well, named *Tullianum*, and thence traditionally attributed to Servius Tullius, and it was afterwards used as a prison.

It consists of two chambers, one below the other, of very ancient construction. The upper is an irregular quadrilateral, which was probably once adjoined by other similar chambers. An inscription on the front records a restoration, probably at the beginning of the Imperial period.

The lower chamber, which was originally accessible only through a hole in the ceiling, is 19 ft. long, 10 ft. wide, and 6½ ft. high. The vaulting is formed by the gradual projection of the side-walls until they meet. It contains a spring, which, according to the legend, St. Peter, who was imprisoned here under Nero, miraculously caused to flow in order to baptise his jailors. The building has therefore been named *S. Pietro in Carcere* since the 15th century. In this dungeon perished Jugurtha (after having been deprived of food for six days), Vercingetorix, and other conquered enemies. Sallust, in recording the execution of Catiline's confederates, describes the prison thus: — 'Est in carcere locus, quod Tullianum appellatur, circiter duodecim pedes humi depressus. Eum miniunt undique parietes atque insuper camera lapideis fornicibus vineta; sed incultu tenebris odore fœda atque terribilis ejus facies est.' (In the prison is a chamber named the Tullianum, about 12 ft. below the surface of the ground. This is surrounded by walls and covered by a vaulted stone roof; but its appearance is repulsive and terrible on account of the neglect, darkness, and smell.)

A little to the E. the VIA BONELLA reaches the Forum. At the end of it, to the right and left, are the churches of S. Adriano and SS. Martina e Luca, both erected on the sites of ancient buildings. *SS. Martina e Luca* (Pl. II, 20, 4) consists of an upper and lower church, the latter of very ancient origin, and the former erected in the 18th cent. by *Pietro da Cortona*. — *S. Adriano*, with its unadorned façade, was erected by Honorius I. in the 7th cent. and afterwards restored. It occupies the site of the *Curia Hostilia*, which was subsequently re-erected under the name of *Curia Julia* by Cæsar and Augustus, and was used as an assembly-hall by the senate (comp. p. 227).


No. 44, Via Bonella, adjoining SS. Martina e Luca, is the — **Accademia di S. Luca** (Pl. II, 20), a school of art founded in 1577, and re-organised in 1874. The first director was *Federigo Zuccherò*. The picture-gallery of the Academy (adm., see p. 122), a second-rate collection, contains few works of importance.

We ascend the staircase, into the walls of which are built a few casts from Trajan's Column (disfigured with whitewash). On the first landing is the entrance to the collection of the competitive works of the pupils (closed): *Kessel's* Discus-thrower reposing, in plaster; Christ on the Mt. of Olives, drawing by *L. Seitz*; reliefs by *Thorvaldsen* and *Canova*; Ganymede watering the eagle, by *Thorvaldsen*, and several casts from the antique.

We ascend another staircase, and ring at the entrance to the —

Picture Gallery (½ fr.). A small ANTE-CHAMBER (with engravings, etc.) leads to the I. SALOON, lighted from above. Entrance-wall: 1. *Early Flemish School*, Descent from the Cross. 2. *Carlo Maratta*, Madonna; on the back of this picture there is a "Copy, by Marc Antonio, of the first design of Raphael's Transfiguration (figures nude; original supposed to have been lost). 3. *Rubens*, Venus crowned by the Graces; 10. *Van Dyck*, Madonna. — End-Wall: 21, 24. *Jos. Vernet*, Sea-pieces. — Wall facing the entrance: 31. *Berchem*, The Campagna; 36. *Mytens*, Admiral Kortenaar (1636); 39. *P. Veronese*, Toilette of Venus; 40. *Gauli*, Birth of John the Baptist; 153. *Giulio Romano*, Copy of Raphael's Galatea in the Farnesina; 43. *Guido Reni*, Cupid. — Short wall: 52. *J. Vernet*, Sea-piece. — The saloon is adjoined on one side by a Room, containing modern works, most of them painted in competition for academical prizes. To the right of this room is the BIBLIOTHECA SARTI, containing 15,000 vols., chiefly relating to art, presented to the Academy in 1881 by *A. Sarti*, the architect. — To the right is a SMALL ROOM, with portraits of artists, including *Virginie Lebrun* and *Angelica Kaufmann* (to the left of the entrance).






FORA CAESARUM.

1 : 3130

0 10 20 30 40 50 60 70 80 90 100

Meiri



PALATIUM

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894

1894



II. SALOON. 81. *Spagnoletto*, St. Jerome disputing with the scholars; 79. *Titian*, Discovery of the guilt of Callisto, inferior to the other mythological pictures of this master; *78. *Raphael*, Boy as garland-bearer, being a relic of a fresco in the Vatican, sawn out of the wall, and freely retouched; 77. *Guercino*, Venus and Cupid (al fresco); 73. *After Titian*, Tribute-money (original in Dresden); 194. *Salv. Rosa*, Concert of cats; 61. *After Titian*, St. Jerome; 59. *Titian* (?), Vanitas; 57. *Early Flemish School*, Madonna.

III. SALOON. To the right, 91. *Poussin*, Bacchic dance; 103. *Guido Cagnacci*, Lucretia, an admirable work of this master, a painter of no great note belonging to the school of Guido Reni; 107. *Paolo Veronese*, Susanna; 108; *Pellegrini*, Hebe; 109. *Palma Vecchio*, Susanna. — Opposite the entrance, 116. *Guido Reni*, Bacchus and Ariadne; 122. *Albani*, Madonna. — Long wall: 133. *Guido Reni*, Fortuna.

The two small rooms adjoining Saloons II. and III. contain nothing of moment.

To the N.W. of SS. Martina e Luca and the Academy lay the **Forum of Cæsar** or *Forum Julium*, the centre of which was occupied by a *Temple of Venus Genetrix*. Some remains of the massive enclosing wall, of tufa and travertine, may be seen in the court of No. 18, Via delle Marmorelle.

Beyond the intersecting Via Alessandrina (see p. 240), the Via Bonella is terminated towards the N. by an ancient wall with a gateway. On the inner side of the latter, to the left, are three handsome and lofty *Corinthian columns with entablature, which belonged to one of the sides of the *Temple of Mars Ultor* in the **Forum of Augustus** (Pl. II, 20). The forum was enclosed by a lofty *Wall of peperino blocks (a grey volcanic rock), part of which, about 160 yds. long, is seen near the temple, and still better by passing through the gateway (*Arco de' Pantani*). This wall was adjoined by the back of a temple erected by Augustus in B. C. 2, in consequence of a vow which he made during his war against Cæsar's murderers. The forum is now occupied by the nunnery of the *Annunziata*. The original level is about 16 ft. below the surface. This locality was a swamp ('pantano') in the 16th cent., whence the modern name.

The *Arco de' Pantani* leads to the *Via di Tor de' Conti*, so named from a fortified tower erected to the S.E. of the *Arco de' Pantani* by Marchionne of Arezzo in the pontificate of Innocent III., who was a member of the Roman family of Conti. The greater part of the tower was carried away at the beginning of the 17th century.

We proceed to the right along the outside of a massive wall and then turn to the right into the *Via della Croce Bianca*, which crosses the site of the **Forum of Nerva**, founded by Domitian and completed by Nerva, sometimes called the *Forum Transitorium* from having been intersected by an important street. Here stood a temple of Minerva, taken down by Paul V. in order to obtain marble for the decoration of the Fontana Paolina on the Janiculus, and a small temple of Janus. Remains of the external walls exist in the so-called **Colonnacce*, two half-buried Corinthian columns, with entablature enriched with reliefs (representing the practice of the arts, weaving, etc., which were specially protected by the goddess; casts of them in the collection of the French Academy, p. 149); above them is an attic with a Minerva. This fragment, situated at the intersection

of the *Via Alessandrina* and *Via della Croce Bianca*, at the E. corner (Pl. II, 20), is well calculated to afford an idea of the former grandeur of the structure.

The busy *Via Alessandrina* leads hence, crossing the *Via Bonella* and the site of the Forum of Augustus (see p. 239), to the *PIAZZA DEL FORO TRAJANO* (Pl. II, 20, 19).


The ***Forum of Trajan**, which adjoined the Forum of Augustus, was an aggregate of magnificent edifices, and is said to have been designed by Apollodorus of Damascus (111-114). By means of a huge cutting between the Capitol and the Quirinal, Trajan effected a convenient communication between the Fora of the ancient city and the Campus Martius (pp. 223, 132). His Forum must have measured about 220 yds. in width, and was probably of still greater length; and it was considered the most magnificent in Rome.

Ammianus (16, 10) thus describes it on the occasion of the visit of the Emp. Constantine in 356: — 'Verum cum ad Trajani forum venisset, singularem sub omni caelo structuram, ut opinamur, etiam numinum adsensione mirabilem, haerebat adtonitus per giganteos contextus circumferens mentem nec relatu effabiles nec rursus mortalibus adpetendos'. According to a legend of the 7th cent., Gregory the Great, while admiring the ancient splendour of the forum one day, and saddened by the thought that so just and benignant a monarch as its founder should be condemned to everlasting perdition, succeeded by his prayers in obtaining the release of Trajan's soul from purgatory. In the 10th cent. this forum lay in ruins, and the church of S. Nicolao had been erected by the column. This was succeeded by other churches. In 1537 Sixtus V. crowned the column with a bronze statue of St. Peter. At length, in 1812-14, the French government caused two nunneries and other buildings to be demolished, and thus partly brought to light the centre of the forum.

The total arrangement consisted of four parts, reckoned from N. to S.: the Forum proper, the Basilica, the Libraries (with Trajan's Column in the court), and the Temple. Hitherto only the second and third, and these but partially, have been excavated. The Forum adjoined that of Augustus; the principal entrance, dignified by a triumphal arch, lay near the modern *Via del Priorato*. Part of the semicircular wall which bounded it on the E. may be seen in the court of No. 6, *Via di Campo Carleo*; it consists of two stories, the chambers in the lower having probably been used as shops.

In the part already excavated (about 120 by 50 yds.) are seen the foundations of four rows of columns, belonging to the five-halled *Basilica Ulpia*, which lay with its sides towards the end of the present piazza. The central hall was 27 yds., and the whole building 61 yds. in width (these dimensions are about the same as those of S. Paolo Fuori, p. 352). The pavement consisted of slabs of rare marble. It is uncertain whether the remains of granite columns which have been found and erected here are in their original positions.

On the N. side of the basilica rises ****Trajan's Column**, constructed entirely of marble, the shaft of which is 87 ft. high, and the whole, including the pedestal and statue, 147 ft.; diameter 11 ft. below, and 10 ft. at the top. Around the column runs a



MONS PALATINUS.

1:3225

0 25 50 75 100
Metri.

spiral band, 3 ft. wide and 660 ft. long, covered with admirable *RELIEFS from Trajan's war with the Dacians, comprising, besides animals, machines, etc., upwards of 2500 human figures (2-2½ ft. high). (Comp. p. xxxvii; see also the cast of the reliefs in the Lateran, p. 272.) Beneath this monument Trajan was interred, and on the summit stood his statue, now replaced by that of St. Peter. In the interior a staircase of 184 steps ascends to the top (keys kept by the custodian of Trajan's Forum and in the 'Ufficio Tecnico', Via in Miranda 1 D). The height of the column at the same time indicates how much of the Quirinal and Capitoline had to be levelled in order to make room for the buildings: 'ad declarandum quantæ altitudinis mons et locus tantis operibus sit egestus', as the inscription, dating from 114, records. The depth of earth removed amounted to 100 ancient Roman feet (97 Engl. ft.). The column was surrounded on three sides by a two-storied gallery, from which the upper reliefs could be conveniently viewed. The foundations of this may still be traced. Adjacent, to the right and left of the column, were a Greek and a Latin library. More to the N., between the two churches, lay the temple of Trajan, built by Hadrian and dedicated to his adoptive father.

On the N. side of the piazza are two churches. That on the right, *del Nome di Maria*, was erected in 1683 after the liberation of Vienna from the Turks, and restored in 1862. That on the left is *S. Maria di Loreto*, begun by *Ant. da Sangallo Junr.* in 1507; in the 2nd chapel on the right, a statue of St. Susanna by *Fiammingo*; over the high-altar a picture of the school of Perugino.

The Palatine.

(Comp. Sketch-Plan.)

The *Palatine Hill*, situated on the S. side of the Forum, rises in the form of an irregular quadrangle. Like the Capitoline Hill it consisted originally of two summits of almost equal height (S. Bonaventura to the S., 168 ft.; Farnese Gardens to the N., 165 ft.) separated by a saddle; the building operations have, however, materially altered its appearance. In ancient times it was bounded on the N. side, towards the Capitol, by the Velabrum and the Forum Boarium (p. 248); on the W., towards the Aventine, by the Circus Maximus (p. 250); on the S., towards the Cælius, by the Via Triumphalis and the Via Appia (now Via di S. Gregorio). The Palatine was the original site and the centre of the embryo mistress of the world, the *Roma Quadrata*, fragments of whose walls have been brought to light at several places. Tradition places on this hill the dwellings of its heroes Evander, Faustulus, and Romulus; and a reminiscence of them was preserved down to a very late period by a number of ancient temples and shrines. The orator Hortensius, Catiline, Cicero, and his bitter enemy the

tribune Clodius, and other celebrated men of the republican period possessed houses here. Augustus was born on the Palatine, and after the battle of Actium he transferred his residence to this ancient seat of the kings. His palace, the *Domus Augustana*, lay below the Villa Mills, near the Circus Maximus; and adjoining it were a large temple of Apollo erected by him and the Greek and Latin library which is so highly extolled in Roman literature. The Emp. Tiberius built a palace on the N. side of the hill, perhaps near the house in which he was born (see p. 244). The Palatine did not afford scope enough for the senseless extravagance of Nero, who built himself the Golden House, extending from the Palatine to the Esquiline (p. 132). The emperors of the Flavian dynasty once more transferred the imperial residence to the Palatine. Vespasian began and Domitian completed the splendid palace called the *Domus Flavia* (p. 244), which lay in the saddle between the two summits, resting mainly on artificial foundations, and connected the buildings of Augustus on the one side with those of Tiberius and Caligula on the other. The *Stadium* (p. 246) was erected at a later period, perhaps by Hadrian. Septimius Severus extended the Flavian palace by erecting the *Septizonium*, an edifice seven stories high, at the S.W. angle of the hill, to improve the view from the Via Appia; part of this building was still standing in the 16th cent., but it was at length removed by Sixtus V. The Palatium participated in the general decline of the city. It was inhabited by Odoacer and Theodoric, but from the 10th cent. onwards the ruins were occupied by monasteries, fortified towers, and gardens.

The first important excavations, directed by *Bianchini*, took place in 1726 in the *Orti Farnesiani*, or *Farnese Gardens*, which were laid out by Paul III. and covered the whole of the N.E. part of the hill. The Emp. of Russia began another series of excavations in the N.W. corner in 1848, but handed over the ground to the city in 1857. A systematic excavation, under the able superintendence of the architect *Comm. Pietro Rosa*, was begun in 1861, when Napoleon III. bought the Farnese Gardens, and has been continued by the Italian government, which acquired the gardens in 1870. Many interesting topographical discoveries have been made, although as yet few works of art have been found.

The excavations are open to the public daily (comp. p. 123). The following account of them refers mainly to the best preserved remains, which may be visited in about 2-3 hrs.; but many other interesting points may be added. The imposing character of the ruins, coupled with the beautiful and varied views commanded by the Palatine, renders them well worthy of repeated visits. The streets, temples, houses, and palaces are all indicated by notices, with references to ancient authorities; but the identity of many of the localities is doubtful, and the names assigned to them are often merely conjectural. — Permission to sketch and take measurements is given at the 'Ufficio Tecnico della Direzione Generale delle Antichità' (Via in Miranda I D).

The present entrance is in the Via S. Teodoro (Pl. II, 21), and is marked *Ingresso I.* in the plan at p. 241; but it is intended to transfer it to the N. of S. Teodoro (p. 241; '*Ingresso II.*' in the plan). Turning to the right on entering, we observe the largest

existing fragment of the ancient wall of *Roma Quadrata* (p. 241), constructed of blocks of tufa placed alternately length and breadth-wise, without mortar. It was originally 40-48 ft. in height, but is now 13 ft. only. Behind it is a grotto, supposed to be the *Luper-cal* in which the she-wolf sought refuge when driven from the twins by the shepherds. A flight of steps ascended from the grotto to the plateau of the hill. Farther on we pass an altar of travertine, with an ancient inscription ('*sei deo sei deivae sacrum*', etc.), dedicated to an unknown God, who had foretold the invasion of the Gauls in B. C. 390 ('*Ajus Locutius*'). We then begin the following round.

From the present entrance ('*Ingresso I.*') we ascend by the zigzag path to the left, at last by a flight of steps. At the top we turn to the left. The first building, of which only the substructures and steps remain, is believed to be the temple of *Jupiter Victor*, erected in consequence of a vow made by *Fabius Maximus* at the Battle of *Sentinum*, B. C. 295. It is approached by 26 steps in five flights. A round pedestal with an inscription, on the 4th landing, was a votive offering of *Domitius Calvinus*, who triumphed over Spain in B. C. 36; the upper half has been destroyed. At the top of the steps we reach the nearly square substructure of the temple, the great age of which is indicated by the stumps of peperino columns, once covered with stucco.

Farther on, in the direction of the Capitol, we observe considerable remains of squared stone buildings of very ancient appearance. A flight of steps (*Scalae Caci?*), hewn in the rock and defended by a wall and gate, descends to the *Circus Maximus*. — The large temple with the lofty square substructure is generally described, though on insufficient evidence, as the *Auguratorium*, or place where the auspices were consulted. Others take it for the *Temple of Victoria*.

We next reach a ***Private House**, known as the *House of Livia* (*Domus Liviae*), which is recognisable by its modern roof. This house, excavated in 1869, the only one of the kind in the midst of the palaces of the emperors, is believed to have been the house of *Tiberius Claudius Nero*, the father of *Tiberius*, to which his mother *Livia* also retired after the death of *Augustus*, to marry whom she had divorced her first husband. The entrance is at the E. corner.

A flight of six steps descends to the mosaic pavement of the vaulted *VESTIBULUM*, whence we enter a quadrangular Court, originally covered, adjoining which are three chambers opposite the entrance. The **Mural Paintings* here will bear comparison with the finest of those discovered at *Pompeii*. The subject of the first on the right in the *CENTRAL ROOM* is *Io* guarded by *Argus*, while *Mercury* approaches to release her; the second represents street-scenes; on the wall opposite the entrance are *Polyphemus* and *Galatea*. The central pictures represent large windows whence a view of mythological scenes is obtained. The admirable perspective is best observed in the picture of *Galatea* when seen from the entrance of the *Atrium*. The two smaller sacrificial scenes in the corners above afford a good example of an ancient kind of picture, which like the mediæval altar-triptychs could be closed by two folding shutters or wings. By the left wall are leaden water-pipes with inscriptions from which the history of this house has been gathered. The walls of the ROOM ON THE RIGHT are adorned with magnifi-

cent *Garlands of flowers and fruits, from which masks and other Bacchalian objects depend between the columns; the walls of the Room on the Left are divided into brown sections edged with red and green, above which are light arabesques between winged figures on a white ground. Adjoining the right side of the court is the *TRICLINIUM*, or dining-room, recognisable by the inscription, with walls painted bright red. The two large central paintings represent landscapes, that on the right the attributes of Diana (large indented crown, stag's and wild boar's heads). On the entrance-wall are two glass vases with fruits. — At the back of the house are the unpretending OFFICES (bedrooms, storerooms, etc.).

We now retrace our steps to the entrance of the house, turn to the left, and ascend by a small wooden staircase to the remains of the **Palace of Tiberius**, the site of which is now covered with gardens. A fine view is obtained of the Capitol, the valley of the Velabrum, and the Vicus Tuscus. The N. spur, where there is now a small plantation of oaks, commands an excellent view of the Forum and the Basilica of Constantine. It was from near this spot that the mad Caligula caused a bridge to be thrown over the Forum to the Capitol, in order to facilitate his intercourse with the Capitoline Jupiter, whose representative on earth he pretended to be. The imperial buildings here completely covered an ancient paved street, perhaps the *Clivus Victoriae*. A flight of steps descends to the street.

A covered passage (*Cryptoporticus*), to the N.E. of the House of Livia, has remains of ancient stucco ornamentation. This is supposed to have been the scene of the murder of Caligula. Various architectural and sculptural fragments are exposed to view here.

Traversing the pleasure-grounds at the back of the former Casino of the Farnese gardens, we reach the **Palatium**, or *Palace*, the chief building on the hill. Augustus himself resided on this spot, but the sumptuous palace (*Domus Flavia*), to which the extant remains belonged, probably owed its existence to his successors of the 1st and 2nd centuries of the present era. A street led from the Arch of Titus to the *Area Palatii*, an open space, whence a magnificent flight of steps ascended to the main entrance.

On the *Area Palatii* were the scanty remains of several buildings, the names of which carry us back to the most ancient days of Rome. Among these is the temple of *Jupiter Stator*, the foundation of which tradition ascribes to Romulus, and which was situated near the *Porta Mugionis*. Below us in the foreground, near the inscription '*Roma Quadrata*', are some remains of the wall of this, the most ancient city, constructed of regularly-hewn blocks of tufa.

The extant remains of the Palatium belong entirely to the reception and state apartments of the palace and include no part of the private rooms of the emperors. The arrangement of the rooms shows little resemblance to that of an ordinary Roman dwelling-house, such as those of Pompeii. The domestic is replaced by the grandiose.

From the vestibule open three large rooms. The one in the middle, known as the *Tablinum*, was the *Aula Regia*, or throne-room, in which the emperor granted audiences. This extensive hall, 39 yds. by 49 yds., with its large semicircular apse which was occupied by the throne, and its six niches, alternately round and square, con-

taining the now empty pedestals, was originally entirely covered; but an adequate idea of its magnificence can hardly now be formed, as it has been deprived of its decorated ceiling, while the walls have lost their marble covering, the niches their columns, and the pedestals their colossal figures (now in Parma).

The room adjoining the Tablinum on the E. contains a small square altar in marble with figures of the *Genius Familiaris* and the *Lares*. The former stands in front with covered head; the latter are represented at the sides in the conventional style of Pompeian works of the kind, with boots, a short 'chiton', a 'rhyton' or drinking-horn in the raised hand, and a 'situla' or pitcher in the other. This has caused the room to be erroneously named the *Lararium*, or chapel of the *Lares* or household gods. Behind are the remains of a staircase ascending to an upper floor.

To the W. of the Tablinum lies the *Basilica*, where the emperor administered justice. The semicircular tribune was separated from the space for litigants by a marble screen, a fragment of which still stands. This space was flanked on each side by a narrow colonnade. The unfluted columns were adorned with bronze ornaments, the holes for fastening which are still visible.

To the S.W. of the tablinum is the *Peristylum*, two-thirds of which only have been excavated (one-third on the S. side being covered by the court of the Villa Mills, now a nunnery), a large square garden, 58 yds. wide, originally surrounded by a colonnade. Its imposing dimensions and a few traces of its marble covering (giallo antico) now alone witness to its ancient magnificence. The open space in the centre was doubtless occupied by fountains, trees, and flowers.

At the N.W. corner steps descend to two subterranean chambers containing traces of stucco decorations and painting. These belonged to a private house of the republican period, over which the imperial palaces were erected.

Opening on the peristyle along its entire width was the *Triclinium*, or dining-hall (*Jovis Coenatio*), whence the diners could enjoy a view of the fountains and trees in the garden. In the semicircular apse on the W. wall most of the original marble and porphyry covering of the pavement still exists. The remains of the pavement and covering of the wall on the N.W. side are more scanty. — Adjacent to the latter is the *Nymphaeum*, or 'inside garden' for the hot season, containing an elliptical basin, in the centre of which rises a fountain covered with partly-preserved marble slabs, and once used as a stand for plants.

The other smaller chambers, extending along the N. side of the palace, are less interesting, and their purposes are not yet ascertained. The same may be said of those adjoining the back of the dining-hall on the S.W. We first enter a *Colonnade*, with six cippolino columns (two entire, the others in fragments). A view is obtained, through the broken pavement, of the original level over

which the emperors built. Farther on are two other rooms, with semicircular terminations and niches in the walls, which are erroneously termed the *Accademia* and *Biblioteca*.

We now return towards the main entrance and turn to the left at the first bend. This road connects the palaces on the S. side of the hill with those already described. To the left is the S. façade of the palace of Augustus, including a large 'exedra' in the form of a flat arch, on the side next the Circus Maximus. Into this is built the gardener's house below the Villa Mills, the beautiful cypresses of which peep down from above. Beyond the house we ascend a wooden staircase to an open space, bounded on the E. and S. by imposing ruins. These belong to palaces which mainly owed their existence to the later emperors, particularly to *Septimius Severus*, after a great fire in 191. The excavations begun here by Pius IX. have unearthed many of the lower chambers of these palaces and earlier buildings. The irregularity of the arrangement makes it impossible to determine the uses of the different rooms except in a few cases.

Turning to the left, we reach the **Stadium**, which separated the buildings of Septimius Severus from the old palace of Augustus (*Domus Augustana*, the site of which is now again covered up; to the N.E. lies the convent of S. Bonaventura, p. 233, and to our left rise the white convent-walls of the Villa Mills). Although not mentioned by any known author, there is no doubt that this was the stadium, or race-course. The length, 185 mètres (625 Roman or 607 Engl. ft.), is precisely that of the stadium. The oblong space originally occupied by the stadium was enclosed by a colonnade, consisting of pillars of masonry encrusted with marble, with half-columns in front of them; while it was divided into two parallel courses by means of a wall running down the middle. In the centre the colonnade was adjoined by three chambers of the time of Hadrian, covered by the imposing apse of a later edifice. The third of these still shows traces of mural paintings and mosaic pavement. In the large central chamber the beginning of the vaulted ceiling is distinctly traceable. Brick-stamps bearing the name of Theodoric have been found, and in the time of the later empire the original arrangement seems to have been entirely altered. The spaces between the columns of the portico were walled up with brick and tufa and the whole E. part of the buildings, between the apse and S. Bonaventura, was separated from the rest. In the middle of the plateau is a marble base with figures of deities. Some of the numerous architectural fragments show fairly good workmanship.

Ascending towards the S. from the E. end of the Stadium, and passing the back of the apse, the lofty proportions and coffered vaulting of which should be observed, we reach the remains of the **Severus Palace** itself. Rooms with heating-apparatus and baths have been recognised here, but the general plan is not clear. Proceeding between insignificant ruins, we reach a point affording a good view of

the Stadium, and then cross a paved bridge to a *Platform* ('Belvedere') supported by three lower stories, and commanding a magnificent *VIEW.

Towards the E. tower the ruins of the Colosseum, nearer are five arches of the *Aqua Claudia*, which supplied the Palatine with water; more to the right (S.) are the churches of SS. Giovanni e Paolo, the Lateran, in the foreground S. Gregorio, and above it S. Stefano Rotondo and the new casino of the Villa Mattei. Still farther to the right appear the ruins of the Thermæ of Caracalla (the two towers beyond, to the left, belong to the Porta S. Sebastiano), and S. Balbina with its lofty tower; farther off, S. Saba, with its two-storied vestibule, and still more distant the Pyramid of Cestius, and in the Campagna S. Paolo Fuori le Mura; then the Aventine with its three churches; on the slope the white tombstones of the Jewish burial-ground on the site of the Circus Maximus, which occupied the valley between the Palatine and Aventine; and lastly the Janiculum and the dome of St. Peter's.

We recross the bridge and descend to the right by a modern staircase (50 steps) on the S. side of the hill to the open space mentioned at p. 246, adjoining the apse. Instead of passing the gardener's house, we now descend to a series of chambers on the W. slope of the Palatine, below the verandah of the Villa Mills. These belonged to the —

Pædagogium, or school for the imperial slaves, who, like those of all the wealthier Romans, received a careful education. A portico of granite columns, one of which still remains, with a marble entablature now supported by pillars of masonry, lay in front of these apartments. The walls are covered with names, sentences, and sketches (*graffiti*, done with the *stilus*, or ancient substitute for a pen), showing the boyish proclivities of the pupils. The well-known caricature of the Crucified, now in the Museo Kircheriano (p. 156), was found here. These scrawls, one of which is 'Corinthus exit de pædagogio', furnished the clue to the use and to the ancient name of this building.

On the left wall of the THIRD ROOM is the sketch of a mill driven by an ass, under which was written, '*labora aselle quomodo ego laboravi et proderit tibi*'. The figure of a Roman soldier is also scratched on this wall. On the posterior wall one of the most conspicuous names is *Felici*, in large letters, both Greek and Roman. — On each side of the central semicircular chamber with a square niche lies a small irregularly-shaped chamber; that on the right is adorned with mural paintings (Fortuna, etc.).

Proceeding in the same direction we soon reach the exit.

Velabrum and Forum Boarium.

The deep-sunken and swampy valley separating the N. slope of the Palatine from the Capitol formed the important link between the Forum and the Tiber. It was inhabited even under the kings, and was known in ancient times as the *Vicus Tuscus* (comp. p. 226). The direction of its main street was very nearly the same as that of the modern Via S. Teodoro. In this street, behind the church of *S. Maria Liberatrice* (Pl. II, 20), are the remains of a massive brick building, now generally held to be the *Temple of Divus*

Augustus. Considerably lower the remains of an old church (*St. Silvester in Lacu*), with 9th cent. paintings, have been found. Farther to the left, a little back from the street, is the low-lying round church of **S. Teodoro** (Pl. II, 21; open on Frid. till 9 a.m.; festival, 9th Nov.). It is first mentioned in the time of Gregory the Great, and probably occupies the site of a temple. In the interior is a Christian mosaic of the 7th century. — A little beyond S. Teodoro the street divides. We descend to the right to the ancient VELABRUM, a quarter prolonged towards the Forum by the *Vicus Tuscus* (p. 247), and towards the river by the Forum Boarium.

To the right is **S. Giorgio in Velabro** (Pl. II, 21; generally closed; visitors knock at the door to the left, behind the *Arcus Argentariorum*; festivals, 20th Jan. and 23rd Apr.), founded in the 4th cent., re-erected by Leo II. in 682 and dedicated to SS. George and Sebastian, and subsequently often restored. The portico, according to the metrical inscription, dates from one of these restorations. (In the middle ages the word Velabrum was altered to 'velum aureum'.) The interior is a basilica with aisles, 16 antique columns, and an old canopy (p. xlvii). The frescoes of Giotto(?) which are said to have once adorned the tribuna have been painted over.

Adjacent to the church is the small *Arch of the Money-Changers* (*Arcus Argentariorum*; Pl. II, 21, 1), which, according to the inscription, was erected by the money-changers and merchants of the Forum Boarium in honour of Septimius Severus and his wife and sons. The sadly damaged sculptures represent victims and sacrificial utensils. Farther on is the so-called ***Janus Quadrifrons** (*Arco di Giano*; Pl. II, 21), an arched passage with four façades, of the later imperial age, and supposed to have been erected in honour of Constantine the Great. Above it once rose a second story.

From this point to the Tiber stretched the extensive *Forum Boarium*, or cattle-market, a very important centre of business.

Proceeding through the low brick archways opposite the *Arcus Argentarius*, and passing a mill, we reach the **Cloaca Maxima** (Pl. II, 18), constructed by the Tarquinii for the drainage of the Forum and the adjacent low ground. It is the earliest known application of the arch in Rome, and has defied the vicissitudes of more than 2000 years. Two-thirds of the depth are now filled up. A basin was formed here, into which springs were conducted to produce a current through the Cloaca. In the mill (25 c.) is seen the continuation of the Cloaca towards the Forum, and from the Ponte Rotto its influx into the Tiber. The Cloaca is constructed of peperino with occasional layers of travertine, and at the mouth of peperino entirely.

Following the street beyond the arch of Janus, and turning to the left, we reach the **PIAZZA BOCCA DELLA VERITÀ**, which partly coincides with the Forum Boarium; in the centre is a fountain erected in 1715 after *Bizzaccheri's* design (group of Tritons by *Moratti*). To the left, at the foot of the Aventine, is the church of —

***S. Maria in Cosmedin** (Pl. II, 18), sometimes called *Bocca della Verità* from the ancient mouth of a fountain to the left in the portico, into which, according to a mediæval belief, the ancient Romans thrust their right hands when taking an oath. The church occupies the site of a temple, perhaps the *Temple of Fortune* founded by King Servius(?), ten columns of which are built into the walls (three on the left side, the others in the front wall). The nave also is borne by twenty ancient columns. The edifice, which is said to date from the 3rd cent., was rebuilt in the 8th by Hadrian I., who erected the beautiful campanile (p. xlviii), and it has since been frequently restored. It derives the name 'in Cosmedin' from a square at Constantinople, having originally belonged to a Greek brotherhood, and it is also known as *S. Maria in Schola Graeca*.

INTERIOR. The beautiful opus Alexandrinum of the pavement merits inspection. In the nave are preserved remains of the ancient choir; on the right and left are two handsome ambones and a candelabrum for Easter ceremonies. Canopy of the high-altar by *Deodatus* (13th cent.). In the apse a handsome episcopal throne of the same period, and an old Madonna. The sacristy contains a mosaic (Adoration of the Magi), originally presented to St. Peter's by John VII. in 706. The venerable crypt is borne by four columns of granite and two of marble.

The *Via della Salara* (see p. 251) runs hence to the S., towards the Porta S. Paolo.

On the opposite bank of the Tiber, not far from the church, stands a small and picturesque ***Round Temple** (*Hercules Victor? Mater Matuta?*), formerly called a *Temple of Vesta* (now *S. Maria del Sole* or *S. Stefano delle Carrozze*; Pl. II, 18), consisting of twenty Corinthian columns, covered by a poor wooden roof. The ancient entablature and roof and one of the columns next to the river have disappeared.

A new railway-bridge, connecting the Piazza Bocca della Verità with Trastevere and ending at the Lungarina (p. 331), is to be finished in 1890.

To the N. of this (accessible at present from the Via di Ponte Rotto only) is a second small and well-preserved ***Temple** (converted in 880 into the church of *S. Maria Egiziaca*), dating, as its style seems to indicate, from the close of the Republic. It is an Ionic pseudoperipteros, with 4 columns at each end, and 7 on each side; but those of the portico, which is now built up, were alone detached, the others being merely decorative half-columns. The edifice is built of tufa, with the projecting and sculptured parts of travertine, the whole overlaid with stucco. Its designation is unascertained, and there is no authority for assigning it to *Fortuna Virilis*. The interior is uninteresting.

On the other side of the cross-street is the picturesque ***House of Crescentius** (Pl. II, 18, 3), or **Casa di Rienzi**, or *di Pilato*, as it is commonly called, constructed of brick with a singular admixture of antique fragments. On the side, Via del Ricovero, a long inscription records that 'this lofty house was erected by Nicholas,

son of Crescens, not from motives of ambition, but as a reminiscence of the ancient glory of Rome'. The Crescentii were the most powerful noble family in Rome at the close of the 10th cent., but the house, the oldest existing specimen of mediæval domestic architecture, is not earlier than the 11th or 12th cent. (comp. p. xlvii). The building was originally much larger, and was intended to command the bridge over the Tiber. — The ancient bridge which here crossed the Tiber was the *Pons Æmilius*, built in B. C. 181. Its position exposed it to frequent injury from inundations. After frequent restorations, the two arches next the left bank fell in 1598, and the bridge was never rebuilt; hence its present name, *Ponte Rotto*. In 1853 a chain-bridge was thrown across the gap, but this has again been removed, the above-mentioned railway-bridge supplying its place.

In the adjacent *Via di Bocca della Verità*, to the left, standing back, is the church of **S. Nicola in Carcere** (Pl. II, 17), recently restored, containing, on the outer walls and in the interior, ancient columns which appear to have belonged to three different temples, including those of *Spes* and *Juno Sospita*. Visitors may descend and examine the foundations of these temples, which have been excavated (sacristan with light $\frac{1}{2}$ fr.). — The *Via di Bocca della Verità* ends on the N. at the *Piazza Montanara* (p. 203).

If, in proceeding from the Forum through the *Via di S. Teodoro*, we leave the *Janus Quadrifrons* (p. 248) on the right, we soon reach, in the *Via de' Penili*, at the corner, the church of *S. Anastasia* (Pl. II, 21) mentioned as early as 499, frequently restored, and finally modernised during last century. By the buttresses of the interior the ancient columns are still standing. In the left aisle is the monument of Card. Angelo Mai. Below the church are ancient structures belonging to the *Circus Maximus*, and still earlier remains of the walls of *Roma Quadrata*.

The *VIA DE' CERCHI* runs between the Palatine and Aventine, where, as its name suggests, was situated the *Circus Maximus*, which was originally instituted by the kings, afterwards extended by Cæsar and furnished with stone seats, and lastly more highly decorated by the emperors. In the time of Pliny it was capable of containing 260,000 spectators, and after subsequent extensions the number of places was increased to 385,000. The last race which took place here was under the auspices of King Totila in 549, at a time when the city was to a great extent in ruins. In the centre ran a *spina*, or longitudinal wall which connected the *metae*, or goals, and determined the length of the course. With a few trifling exceptions, the walls of the circus have entirely disappeared; but its form is distinctly traceable from a higher point, such as the Palatine. The Jewish cemetery lies within the Circus, at the base of the Aventine (entr. from the *Via dell' Orto degli Ebrei*, to the left of the *Via di S. Sabina*).

The Aventine. Monte Testaccio.

The *Aventine* (150 ft.), anciently the principal seat of the Roman Plebs, and afterwards densely peopled, is now occupied by monasteries and vineyards only. Like the hills to the E. of the city, however, it will soon be covered with the houses of a new quarter.

At the base of the hill is the *Piazza Bocca della Verità* (p. 248),

which we quit by the VIA DELLA SALARA (Pl. II, 18), continued by the VIA DELLA MARMORATA (Pl. III, 18). To the left, beyond S. Maria in Cosmedin, a street diverges from the Via della Salara to S. Prisca (p. 254). About 2 min. farther, at the small *Chapel of St. Anna*, a second street diverges, leading to the churches mentioned at pp. 252, 253. The Via della Marmorata reaches the Tiber in 6 min. from the Piazza Bocca della Verità. Skirting the river for about 2 min., we enjoy to the right a pleasing retrospect of the Capitol; opposite lies the harbour of Ripa Grande, in front the large Ospizio di S. Michele (p. 332). We next reach the MARMORATA (Pl. III, 18, 15), the landing-place and depôt of the unwrought marble of Carrara.

The street, here generally known as VIA DI PORTA S. PAOLO (Pl. III, 17), now leaves the river and leads towards the Porta S. Paolo. The former *Prati del Popolo Romano*, between the street and the river, are now occupied by a new quarter of ugly tenement houses.

After 6 min. the road from the churches on the Aventine descends from the left (p. 253). Just beyond this the street is crossed by the VIA GALVANI, leading on the left to S. Saba, S. Prisca (p. 254), and the Circus Maximus (p. 250), and on the right to the river, Mte. Testaccio, and the Protestant Cemetery.

The ***Monte Testaccio** (Pl. III, 13) is an isolated mound, 115 ft. in height, rising above the Tiber, and consisting, as the name indicates, entirely of broken pottery. It is formed of the large earthenware jars (amphoræ) from Spain and Africa which were unpacked at the neighbouring Emporium. The hill is now honeycombed with cellars, in some of which wine is sold, but it is now less frequented than formerly. — The summit, marked by a wooden cross, commands a magnificent ***PANORAMA**: —

To the N., the city, beyond it the mountains surrounding the crater of Baccano, then the isolated Soracte with its five peaks. To the E. the Sabine Mts., in the background the imposing Leonessa, in the nearer chain M. Genaro, at its base Monticelli, farther to the right Tivoli. Beyond this chain the summits of M. Velino above the Lago Fucino are visible. To the S. of Tivoli appears Palestrina. After a depression, above which some of the Volscian Mts. rise, follow the Alban Mts.: on the buttress farthest E. is Colonna, beyond it Frascati, higher up Rocca di Papa, M. Cavo with its monastery, below it Marino, finally to the right Castel Gandolfo. In the broad Campagna are the arches of the Aqua Claudia and the Acqua Felice towards the S.E., and the tombs of the Via Appia.

Halfway between the Via di Porta S. Paolo and Mte. Testaccio, on the left, is an iron gate marked S. P. Q. R., passing through which we reach the Protestant Cemetery and the Pyramid of Cestius.

The **Protestant Cemetery** (Pl. III, 16) is open from 7 a.m. till dusk (custodian 25 c.). The older burying-ground, adjoining the Pyramid of Cestius, is now disused. In 1825 the present burial-ground was set apart for this purpose. It is a retired spot, rising gently towards the city-wall, affording pleasing views, and shaded by lofty cypresses, where numerous English, American, German, Russian, and other visitors to Rome are interred.

Amongst many illustrious names the eye will fall with interest upon that of the poet *Shelley* (d. 1822), 'cor cordium', whose ashes were buried here (near the upper, or Eastern, wall). His remains were burned in the bay of Speczia, where they were washed ashore; his heart, the only part not consumed by the flames, is now at Boscombe in England. The tombstone of *John Keats* (d. 1821), who also rests here, bears the melancholy inscription, 'Here lies one whose name was writ in water'. The graves of *J. A. Carstens* (d. 1798), the painter (in the old cemetery), *John Gibson* (d. 1866), the sculptor, and several other artists may also be recognized.

The ***Pyramid of Cestius** (Pl. III, 16), originally in the Via Ostiensis, but enclosed by Aurelian within the city-wall, is the tomb of Caius Cestius, who died before B. C. 12. The Egyptian pyramidal form was not unfrequently adopted by the Romans in their tombs. That of Cestius is built of brick and covered with marble blocks; height 116 ft., length of each side of the base 98 ft.

According to the principal INSCRIPTION on the E. and W. sides ('C. Cestius L. F. Pob. Epulo. Pr. Tr. Pl. VII. vir Epulonum'), the deceased was prætor, tribune of the people, and member of the college of Septemviri Epulones, or priests who superintended the solemn sacrificial banquets. The inscription on the E. side below records that the monument was erected in 330 days under the supervision of L. Pontius Mela and the freedman Pothus. Alexander VII. caused the deeply imbedded monument to be extricated in 1660, when the two columns of white marble and the colossal bronze foot now in the Palazzo dei Conservatori (p. 211), were found. According to the inscription on the pedestal, the foot appears to have belonged to a colossal statue of Cestius. — The VAULT (19 ft. long, 13 ft. wide, and 16 ft. high) was originally accessible by ladders only. The present entrance was made by order of Alexander VII. (key kept by the custodian of the Protestant cemetery). The vaulting shows traces of painting.

The *Porta S. Paolo*, immediately to the E. of the Pyramid of Cestius, is the ancient *Porta Ostiensis*. — Hence to the Basilica of *S. Paolo Fuori*, see p. 352.

The second road ascending from the Via Salara to the left, 200 paces to the S. of the Piazza Bocca della Verità (comp. p. 248), leads to the three Churches on the Aventine (*S. Sabina*, *S. Alessio*, *S. Maria Aventina*), situated close together immediately above the river.

***S. Sabina** (Pl. III, 18), which probably occupies the site of a temple, was erected in 425, in the pontificate of Cœlestine I., by Petrus, an Illyrian priest, and restored in the 13th, 15th, and 16th centuries. Honorius III. presented the church, along with the old papal palace adjoining it, to St. Dominic, who made it the headquarters of his Order. It is usually entered by a side-door; if closed, visitors ring at the door to the left, and proceed through the monastery to the old portico, now closed, and the principal portal. The doors are adorned with scriptural scenes carved in wood (5th cent.?).

The INTERIOR (comp. p. xlv), with its twenty-four ancient Corinthian columns of Parian marble and open roof, has retained the character of an early basilica almost unimpaired. — ENTRANCE-WALL: Over the door, an ancient **Mosaic* (5th cent.); inscription with the name of the founder; on the left a figure emblematical of the Ecclesia ex Circumcisione (Jewish Christians), on the right that of the Ecclesia ex Gentibus (Gentile Christians). — NAVE. On the pavement in the centre is the tomb of Munio da Zamora, principal of the Dominican order (d. 1300), adorned with mosaic. — At the end of the RIGHT AISLE, in the Chapel of St. Dominicus, the **Madonna*

del Rosario with SS. Dominicus and Catherine, an altar-piece by *Sassoferrato*, regarded as his masterpiece. The other paintings (by the *Zuccheri* and others) are of no great value. — Festival, 29th Aug.

The small garden of the former *Dominican Monastery*, adjoining the church, contains an old orange-tree said to have been planted by St. Dominic. The handsome cloisters (p. xlvī), with 103 small columns, and the large garden (fine view) belong to a Military Hospital and are generally inaccessible.

S. Alessio (Pl. III, 18) is an ancient church with an entrance-court. The date of its foundation is unknown, but it was re-consecrated by Honorius III. after the recovery of the relics of the saint in 1217. In 1426 it came into the possession of the Order of St. Jerome. In the neighbouring monastery a blind asylum (*Istituto de' Ciechi*) has been established. We enter the fore-court, and, if the church is closed, ring at the door on the left ($\frac{1}{2}$ fr.).

The INTERIOR was modernised in 1750, and again recently. The N. Aisle contains a well and a wooden staircase belonging to the house of the parents of the saint, which formerly stood on this site. Two small columns adorned with mosaic in the choir are, according to the inscription, the remains of a work of 19 columns by Jacobus Cosmas (p. xlvii).

A small piazza is next reached, where the route to Porta S. Paolo (p. 252) turns to the left. The brown door No. 40, to the right in this piazza, with the arms of the Grand Master of the Knights of Malta above it, contains the celebrated *KEY-HOLE through which St. Peter's is seen at the end of the principal avenue of the garden. (Visitors admitted to the garden on Wed. and Sat., 9 till dusk; ring.)

S. Maria Aventina, also called *del Priorato* (Pl. III, 18), belongs to the Maltese Order, which celebrates its periodical festivals here. This church, founded at a very remote period, belonged for two centuries to the Templars, whose symbols are still extant; it was restored by Pius V., and remodelled by the Grand Prior Card. Giov. Batt. Rezzonico from plans by *Piranesi* in 1765.

To the right of the entrance is an ancient sarcophagus, on which the deceased (head unfinished), surrounded by Minerva and the Muses, is represented; the remains of a Bishop Spinelli were afterwards placed in it. Also a statue of *Piranesi* (d. 1778), and the monuments of several members of the Maltese Order: Grand Master Ric. Caracciolo (d. 1395); Gio. Diedo, Grand Prior of Venice and nephew of Pope Eugene III.; the 'bailis' Bart. Carafa, Sergio Seripando, and others of the 15th century. The third recess to the left contains a remarkable marble reliquary of the 13th cent., roughly wrought after the pattern of an antique funeral-urn.

Adjoining the church is the *VILLA MAGISTRALB*, or residence of the Grand Masters of the Maltese Order. The 2nd floor contains a large saloon, hung with portraits of all the grand-masters (74) from Frater Gerhardus (1113) down to the present Grand Master Ceschi. Several relics connected with the Order are also preserved here. The upper floor commands a picturesque *VIEW of Rome, the Campagna, and the mountains. — The garden, which contains one of the finest palm-trees in Rome, affords a similar prospect.

The above-named road to the Porta S. Paolo descends in 10 min. to the main road (p. 251).

The VIA GALVANI (see p. 251) leads to the left through the depression between the N. and S. summits of the Aventine and in 5 min. reaches (left) a *Fragment of the old *Servian Wall*, about 30 ft. high and 100 ft. long. Like the wall mentioned at p. 243, it consists of large blocks of tufa, laid alternately lengthwise and crosswise. The neighbouring arch is of much more recent date. The remains show that the wall was quite out of use and built over in the later days of the Republic.

A little farther on the Via S. Prisca (left) and the Via di San Saba (right) diverge to the churches of these names.

S. Prisca (Pl. III, 21; usually closed), a very ancient church, but modernised in the 17th cent., perhaps occupies the site of the temple of Diana belonging to the Latin League, and founded by Servius Tullius. The old columns have been built into the walls. — About 10 min. farther on the street unites with the Via S. Sabina, which passes the church of that name (p. 252).

S. Saba (Pl. III, 20), another church of great antiquity, was almost entirely rebuilt in 1465. To the left in the portico is an ancient sarcophagus with a representation of a wedding and Juno Pronuba. The interior contains 14 columns, some of granite, others of marble, with mutilated capitals; the walls of the nave show traces of paintings. The church belongs to the Collegium Germanicum, and is most easily seen on Thurs. afternoons. Festival, 5th Dec.

The Via Appia within the City.

Thermae of Caracalla. Tomb of the Scipios. Columbaria.


From the Arch of Constantine (p. 236) we follow the VIA DI S. GREGORIO towards the S., leading between the Palatine and Caelius. On the right we observe the handsome palm of the convent of S. Bonaventura on the Palatine (p. 246), and the arches of the Aqua Claudia (p. 247). After 5 min. S. Gregorio (p. 258) lies on the left, beyond which the Via de' Cerchi (p. 250) diverges to the right. Near the point where the Via S. Gregorio unites with the VIA DI PORTA S. SEBASTIANO (Pl. III, 24, 26), was anciently situated the *Porta Capena*, or Capuan Gate, whence the **Via Appia** issued. We follow the Via di Porta S. Sebastiano to the left.

After 5 min., at the end of the avenue which runs parallel with the street on the right, a road ascends on the right to the church of **S. Balbina** (Pl. III, 23), situated on the slope of the Aventine, perhaps on the site of an ancient temple, and consecrated by Gregory the Great. The roof is still open, but the church is modernised and destitute of ornament. It contains a relief (Crucifixion) by *Mino da Fiesole* and a monument by *Johannes Cosmas*. Festival, 31st March. (Visitors ring at the gate on the right of the church.) The adjacent building is a Reformatory for young criminals. The old tower commands a fine *View. — On the way back to the road we also obtain a pleasing view of the Palatine to the left, and of the Caelius, with the Villa Mattei (p. 259) and S. Stefano Rotondo.

After following the Via di Porta S. Sebastiano for about $\frac{1}{2}$ M., we obtain a view to the left of the Villa Mattei, to which the Via delle

Mole di S. Sisto diverges to the left. The road here crosses the turbid streamlet *Marrana*, beyond which, to the right, the *Via Antonina* leads to the ($\frac{3}{4}$ M. from the Arch of Constantine) ruins of the —

* **Thermæ of Caracalla**, or *Antoninianæ* (Pl. III, 23; adm., see p. 124). They were begun in 212 by *Caracalla*, extended by *Helio-gabalus*, and completed by *Alex. Severus*, and they could accommodate 1600 bathers at once. The magnificence of these baths was unparalleled. Numerous statues, including the Farnese Bull, Hercules, and Flora at Naples, mosaics, etc., have been found here; while the walls, bare as they now are, and notwithstanding the destruction of the roof, still bear testimony to the technical perfection of the structure. The establishment was quadrangular in form, surrounded by a wall, and had its porticoes, race-course, etc.: length 240 yds., width 124 yds.; total area of grounds 360 yds. in length, by as many in breadth. In the time of the Emperors the act of taking a bath had become a highly luxurious and elaborate process, the chief steps in which were as follows: first, a hot-air bath in the so-called *Tepidarium*; second, a hot-water bath in the *Caldarium*; next, a cold plunge in the *Frigidarium* or *Piscina*; and finally, the ‘rubbing down’ or ‘shampooing’ in the drying room. The three



principal rooms, in the main axis of the building, have been identified, but the names of the others are somewhat arbitrary.

We first enter in a straight direction a spacious oblong, once surrounded by columns (*Peristyle*), and containing scanty remains of mosaic pavement. In the middle of the long wall, where the well is now, projected a semicircular *Exedra*. We then enter the *Tepidarium*, a large room formerly covered with a slightly vaulted roof; in the corners are four basins for luke-warm water baths. — To the left lies the *Frigidarium*, a large unroofed room, with a swimming-basin. — To the right is the *Caldarium*, a circular chamber with very thick walls, the vaulting of which has fallen in. The heating apparatus and hot-air pipes have recently been discovered here. A small flight of steps within one of the piers to the right affords a good survey of the ground-plan. — The smaller rooms are arranged symmetrically on both sides of the three principal chambers. In the second (S.) *Peristyle* (where most of the Mosaic of the Gladiators in the Lateran was discovered) are exhibited architectural and sculptural fragments, and the remains of a mosaic pavement with sea-monsters. — Outside these rooms were spaces for gymnastic exercises, libraries, and gardens. Opposite the *Caldarium*, outside the W. wall, are distinct traces of a *Stadium* for foot-races. Other remains of the *Tbermæ* are scattered throughout the neighbouring vineyards.

Returning to the *Via di Porta S. Sebastiano*, we next reach an arboretum (*Semenzaio Comunale*) on the left; then, a little beyond it, on the right, the ancient church of **SS. Nereo ed Achilleo** (Pl. III, 23, 26; open in the morning), on the site of a temple of Isis, rebuilt by Leo III. about 800, and again by Card. Baronius at the end of the 16th century. Festival, 12th May.

The INTERIOR exhibits the characteristics of an early basilica. At the end of the nave is an ambo on the left, supposed to be of great age, brought from S. Silvestro in Capite; opposite is a marble candelabrum for the Easter-candles, of the 15th century. Above the arch of the tribune are fragments of a mosaic of the time of Leo III.: Transfiguration, with Moses and Elias, in front the kneeling Apostles, on the right the Annunciation, on the left the Madonna enthroned (comp. p. xlvii).

The opposite church of *S. Sisto*, restored by Benedict XIII., is uninteresting. The monastery was dedicated to St. Dominic by Honorius III. — The *Via della Ferratella* then diverges to the left to the Lateran (p. 265). — On the right, a little farther on, is **S. Cesareo** (Pl. III, 26; open on Sun. and festival mornings), a small but curious church, mentioned by Gregory the Great, and finally restored by Clement VIII.

INTERIOR. In the centre of the anterior portion of the church are two altars, of the close of the 16th cent.; at the farther end, to the left, the old pulpit with sculptures; Christ as the Lamb, the symbols of the Apostles, and sphinxes; opposite, a modern candelabrum with ancient basis. The inlaid screen of the PRESBYTERIUM, and the decorations of the HIGH ALTAR are mediæval. The tribune contains an ancient episcopal throne.

The piazza in front of the church is adorned with an antique column. The ancient *Via Latina*, which traversed the valley of the Sacco and terminated at Capua, diverges here to the left. The old *Porta Latina* (Pl. III, 28), 5 min. from S. Cesareo, was closed in 1808. — Near it, to the left, beyond the old monastery, is the church of *S. Giovanni a Porta Latina* (Pl. III, 29), which was modernised by restorations in 1566, in 1633, and chiefly by Card. Rasponi in 1686. It contains four antique columns in the portico

and ten in the interior. — To the right, nearer the gate, is an octagonal chapel of 1509 (perhaps designed by Bramante), named *S. Giovanni in Oleo* from the legend that St. John was thrown into a cauldron of boiling oil at this spot, but having come out unhurt was then set at liberty.

Farther on in the Via di Porta S. Sebastiano, on the left by the cypress, in the Vigna No. 13 (formerly Vigna Sassi), is the famous **Tomb of the Scipios** (Pl. III, 25, 28; open 10-3, uninteresting. candles required, 1/2 fr.), discovered in 1780, but now containing a model only of the ancient sarcophagus of peperino, which Pius VII. caused to be removed with the fragments of the others to the Vatican (see p. 311).

This sarcophagus once contained the remains of *L. Cornelius Scipio Barbatus*, Consul in B. C. 298, the eldest member of the family buried here. The bones of the hero, which were found in good preservation, were interred at Padua by Quirini, a Venetian, in order to withdraw them from the gaze of the curious. Here, too, were interred the son of Scipio Barbatus, Consul in 259, many of the younger Scipios, the poet *Ennius*, and several members of other families and freedmen. The tomb was originally above the surface of the earth, with a lofty threshold; the interior was supported by walls hewn in the solid tufa-rock. It was probably injured, or at least altered, during the imperial age, when freedmen were interred here; and as it has since been to some extent modernised, it is hardly worthy of a visit. Various modern alterations have increased the difficulty of realising its original arrangement.

The adjacent Vigna Codini, No. 14, contains three ***Columbaria** in excellent preservation (1 fr.). These Columbaria are subterranean tombs capable of containing a great number of cinerary urns, and derive their name from the resemblance of the niches in which the urns stood to pigeon-holes. They date from the imperial age, and were generally constructed by several persons in common, or as a matter of speculation, and each recess could be purchased or inherited.

Two of these structures are very similar; steep steps descend into a square vault, the walls of which contain the niches (*columbaria, loculi*). The low stone benches (*podia*) round the vault also contain cinerary urns. The vaulting of the larger building, in which there are more than 600 urns, is borne by a massive painted pier, also utilised for *loculi*. The names of the deceased were inscribed over or under the niches on plaster or marble tablets, on which their mode of acquisition of the spot and other remarks were occasionally added. Each niche contained 2, or more rarely 1, 3, or 4 *ollae*, or cinerary urns. The nature of the decorations depended of course on the means and taste of the family. The smaller building, according to the inscriptions, was built in A.D. 10 for the *Slaves and Freedmen of Marcella*, niece of Augustus. The third columbarium (admission generally denied; additional fee), discovered in 1853, consists of three vaulted passages, the walls of which contain rectangular niches of various sizes, some of them formerly adorned with rare marbles and stucco.

There is another structure of the same kind in the same vigna as the tomb of the Scipios (formerly Vigna Sassi, see above), to the E., near the chapel of *S. Giovanni in Oleo* (see above). This columbarium, with interesting decorations in stucco and colours, is the so-called *Tomb of the Freedmen of Octavia*. A staircase, partly modern, descends to a niche decorated with plaster, below which is a cinerary urn with shells and mosaic. The tomb is vaulted; on the right is an apse with painted vine-wreaths and Victories. The key is kept by the custodian of the church (apply at the old Vigna Sassi).

Immediately within the *Porta S. Sebastiano* ($1\frac{1}{4}$ M. from the Arch of Constantine) is the **Arch of Drusus**, a sadly-mutilated monument, which was probably erected in honour of Claudius Drusus Germanicus, B.C. 8. It is constructed of travertine-blocks, partly covered with marble, and still possesses two marble columns on the side towards the gate. It terminated in a pediment, until Caracalla, for the supply of his baths, conducted an aqueduct over it, the brick remains of which seriously mar the effect.

The marble blocks of the *Porta S. Sebastiano* (Pl. III, 28), formerly *Porta Appia*, seem to have been taken from ancient buildings. The gate is surmounted by mediæval towers and pinnacles.

With regard to the *Via Appia* without the city, see p. 348; the *Catacombs of Callistus*, $1\frac{1}{4}$ M. from the gate, see p. 361.

The Cælius.

This once densely-peopled hill (165 ft.) is now deserted, like the Palatine and Aventine.

Starting from the Arch of Constantine (p. 236), and following the *VIA DI S. GREGORIO* (comp. p. 254), or the public walks above it to the left, we reach the *Piazza di S. Gregorio*. A lofty flight of steps ascends hence to the right to **S. Gregorio Magno** (Pl. III, 24), on the site of the house of St. Gregory's father, dedicated by that pope in 575 to St. Andrew, and afterwards by Gregory II. to his first namesake. In 1633 it was restored by Card. Borghese, the steps, colonnade, portico, and façade being designed by *Giov. Batt. Soria*. Its reconstruction was begun in 1725. Festival, 12th March.

ENTRANCE COURT, embellished with Ionic pilasters. Under the colonnade in front of the entrance: left, monument of the Guidiceioni of 1643, but with sculptures of the 15th cent.; right, "Monument of the two brothers Bonsi of the close of the 15th century. — Interior, with sixteen ancient columns. Over the HIGH ALTAR: St. Andrew, altar-piece by *Balestra*. At the end of the RIGHT AISLE: "St. Gregory, altar-piece by *S. Badalocchi* (?). Below it a "Predella: the Archangel Michael with the apostles and other saints, attributed to *L. Signorelli*. Here to the right is a small CHAMBER preserved from the house of St. Gregory, containing a handsome ancient "Chair of marble and relics of the saint. Opposite, from the left aisle, the CAP. SALVIATI is entered. In front of the altar, on the right, an ancient and highly revered Madonna, which is said to have addressed St. Gregory; left, a "Ciborium of the 15th cent., disfigured by regilding.

The sacristan ($\frac{1}{2}$ fr.) now shows three "Chapels detached from the church, and connected by a colonnade. A fragment of the Servian wall, partly covered with remains of other walls, is observed here. To the right, **Chapel of St. Silvia**, mother of Gregory, with her statue by *Cordieri*; above it, in the vaulting of the niche, a fresco by *Guido Reni*, greatly damaged. — In the centre the **Chapel of St. Andrew**. Over the altar: Madonna with SS. Andrew and Gregory, painted on the wall in oils by *Roncalli*. On the right, Martyrdom of St. Andrew (a copy in the Lateran, p. 272), *Domenichino*; on the left, "St. Andrew, on the way to the place of execution, beholding the cross, *Guido Reni*; two pictures once extravagantly admired. — To the left the **Chapel of St. Barbara**, with a sitting statue of St. Gregory in marble, said to have been begun by *Michael Angelo*, completed by *Cordieri*. In the centre a marble table with antique feet, at which St. Gregory is said to have entertained twelve poor persons daily. According to the legend, an angel one day appeared and formed a thirteenth.

We now ascend to the N., between remains of old walls, to — **SS. Giovanni e Paolo** (Pl. II, 24), a small church in the form of a Greek cross, with a conspicuous dome, which has existed since the 5th century. The portico, mosaic-pavement in the interior, and architecture of the apse are of the 12th century. The whole building, as the inscription records, was sumptuously restored by Cardinal Howard in 1880. According to the legend the house of the two saints, who were beheaded in the reign of Julian the Apostate, stood on this spot. In 1887 some interesting remains of an ancient *Dwelling were found here, with Pagan and Christian mural paintings (e.g. the Martyrdom of the saints). Frescoes of the 12th cent. (Christ with the Archangels, St. John, and St. Paul) were also discovered. The entrance is at the end of the S. aisle (sacristan, with light, $\frac{1}{2}$ fr.). — The adjoining *Monastery* belongs to the Passionists.

We now ascend the street flanked by walls, and reach the *Arch of the Consuls Dolabella and Silanus* (Pl. III, 27), constructed of travertine in A. D. 10, and apparently belonging to an aqueduct.

Near this, on the right, No. 8, is the portal of an old hospital which once belonged to the small church of *S. Tommaso in Formis* (Pl. III, 24, 27), situated behind it.

The interesting mosaic-medallion, above the door, representing Christ between a black and a white slave, was executed in the 13th cent. by two masters of the Cosmas family, and is an allusion to the order of Trinitarians founded in 1198 for the purpose of ransoming Christian slaves.

To the left is the street descending to the Colosseum (p. 234). On the right lies the oblong PIAZZA DELLA NAVICELLA (Pl. III, 27) with a double row of trees, so called from the small marble boat copied by order of Leo X. from the ancient original formerly in the portico of the church.

The church of **S. Maria in Domnica**, or *della Navicella*, one of the oldest deaneries of Rome, was rebuilt by Paschalis I. in 817, to which era the columns of the nave and tribune belong; the portico, erected by Leo X., is said to have been designed by *Raphael*.

Interior. The NAVE rests on eighteen fine columns of granite; above, below the ceiling, is a frieze painted by *Giulio Romano* and *Perino del Vaga* (in grisaille; genii and lions in arabesques), afterwards retouched. The arch of the TRIBUNE rests on two columns of porphyry; the mosaics date from the 9th cent., but were freely restored under Clement XI.; above the arch, Christ between two angels and the apostles, below are two saints; in the vaulting, the Madonna and Child imparting blessings, on each side angels, Paschalis I. kissing her foot; beneath all the figures spring forth flowers. — The church is open on the 2nd Sunday of Lent only; at other times visitors ring at the door marked 'Custode', adjoining the church on the right.

Adjoining the church is the entrance to the ***Villa Mattei** (Pl. III, 24; adm., see p. 124), founded in 1582, the property of M. v. Hoffmann, and recently restored (*Villa Caelimontana*). It contains few antiquities, but the grounds are worthy of a visit; the *Oratorio di S. Filippo Neri* commands a striking view of the ruins of Rome and the Alban Mts.

Opposite S. Maria in Domnica, but not accessible from the

Piazza della Navicella, rises S. Stefano Rotondo. We follow the *Via di S. Stefano* to the left, pass through the first green door on the right, and ring a bell to the right under the porch.

S. Stefano Rotondo (Pl. III, 27) is very interesting on account of its construction, and, though greatly diminished in extent, is the largest circular church in existence. It was erected at the close of the 5th cent. by Simplicius, and afterwards gorgeously decorated with marble and mosaics. It then fell to decay, but was restored by Nicholas V. In the original edifice, the diameter of which was 70 yds., the present external wall formed the central row of columns, while another lower wall, decorated with pilasters, 11 yds. distant, and still traceable round the church, formed the circumference. The church thus consisted of three concentric rings, intersected by two transepts. Nicholas V. shut out the external wall, and filled up the spaces between the central columns with masonry, with the exception of a few projecting chapels. The roof is rudely constructed of wood. The old entrance was on the E. side. In the present portico, erected by Nicholas, on the right, is the ancient episcopal throne, from which Gregory the Great delivered one of his homilies. Festival, 26th December.

INTERIOR. To the left of the entrance, an altar-niche with mosaic of the 7th cent.; farther on, to the left, a chapel with (1.) a fine monument of the beginning of the 16th century. Most of the fifty-six columns are of granite, a few of marble. Fearful scenes of martyrdom on the lateral walls, by *Tempesta* and *Pomarancio* (much retouched). In the centre a canopy of wood. The dome is borne by two lofty columns of granite and two pillars.


Beyond the church the *Via di S. Stefano* (Pl. II, 27) leads past a new military hospital (to the left, on the site of the *Villa Casali*) and extensive fragments of an ancient aqueduct in 5 min. to the vicinity of the Lateran (p. 267).

S. Clemente. The Lateran.

From the Colosseum (p. 234; Pl. II, 24) several streets run towards the S.E.: to the left the *Via Labicana* towards the *Thermæ of Titus* (p. 237), to the right the *Via de' Quattro Santi* to SS. Quattro Coronati (p. 264), joining the following street near the Lateran; and lastly, between these, the *VIA DI S. GIOVANNI IN LATRANO* (1½ M. long) to the Piazza of the Lateran and the *Porta S. Giovanni*. The latter street leads in 5 min. to a small piazza, where on the left rises —

***S. Clemente** (Pl. II, 27; side-entrance from the street generally open; if not, visitors ring at the principal door under the portico), one of the best-preserved basilicas of Rome, where recent excavations owing to the praiseworthy exertions of Prior Mullooly have yielded some very interesting results. Below the present church, three different layers of masonry have been brought to light, the first being of early-Christian, the second of imperial, and the third of republican origin. The Christian basilica (now the lower church) is mentioned

by St. Jerome as early as 392, and in 417 was the scene of a council of the church. It was almost entirely destroyed in 1084 on the entry



of Robert Guiscard into Rome, and in 1108 Paschalis II. erected on its ruins the present upper church, with which he incorporated several ornaments of the lower, such as the choir and the ambones. The upper church was also frequently restored, and finally with considerable taste by Clement XI., who however added the unsuitable ceiling. St. Clement (91-100), according to Roman tradition, was the third successor of St. Peter, and suffered martyrdom in the Black Sea. This church, which stands on the traditional site of his house, gives a title to a cardinal, and belongs to Irish Dominicans.

From the principal gate in the Via di S. Clemente, we first enter the *Atrium*, surrounded by a colonnade and paved with fragments of marble (giallo and verde antico), and beyond it the *UPPER CHURCH, consisting of nave and aisles, but, like all genuine basilicas, without a transept. Comp. p. xlv.

Interior. The NAVE with its flat ceiling is separated from the aisles by sixteen antique columns, and contains the **Screen* of the choir and the *Ambones* from the lower church, with the monogram of Pope John VIII. (key kept by the sacristan). The *Canopy* with four columns of pavonazzetto dates from the time of Paschalis II. (p. xlvii). — In the TRIBUNE is an ancient episcopal throne, restored in 1108. *Mosaics* (p. xlviii) of the tribune of the 12th century. On the rood-arch in the centre: Bust of Christ with the Symbols of the Four Evangelists, (l.) SS. Paul and Lawrence, below them Isaiah, lower down the city of Bethlehem, (r.) SS. Peter and Clement, below them Jeremiah, lower down the city of Jerusalem. On the vaulting: Christ on the Cross, with John and Mary surrounded by luxuriant wreaths, below which are the thirteen lambs. On the wall of the apse, Christ and the apostles, restored by means of painting only. — On the walls by the tribune, monuments of the close of the 15th century. The chapel to the right of the Canopy is elaborately adorned with frescoes by *Novelli* of scenes from the lives of SS. Cyril and Methodius, executed in 1886 at the expense of Abp. Strossmayr. In the adjoining chapel in the apse, at the end of the RIGHT AISLE, is a statue of John the Baptist by *Simone di Giov. Ghini* (comp. p. 90). — To the left of the principal entrance, the CAPPELLA DELLA PASSIONE with *Frescoes of the beginning of the 15th cent., the earliest authenticated work of *Masaccio* (b. 1401), who went from Florence to Rome about 1417; they were painted by order of Gabriel Condulmer, Cardinal of S. Clemente, and afterwards Pope Eugene IV., and show indications of the immaturity of the artist. On the arch over the entrance the Annunciation. To the left, near the entrance, St. Christopher. On the wall behind the altar a Crucifixion; on the left, scenes from the life of St. Catharine: above, she refuses to worship a heathen idol; she teaches the king's daughters in prison; below, she disputes before Maxentius with the doctors (best of the series); an angel destroys the wheels on which she was to be broken; her execution. The paintings on the window-wall, greatly damaged, probably referred to St. Clement.

As above mentioned (p. 260), and as the annexed plan and sections show, there exist below the present church several still older strata of masonry. Lowest of all, and forming a right angle, are two massive walls, constructed of blocks of stone quarried on the Caelius itself (No. I. in the ground-plan and in the section). As the stones are more carefully hewn and jointed than those of the Servian wall, these substructures cannot be dated farther back than the republican epoch. Above these are remains of workmanship of the imperial era, executed in the 2nd cent. after Christ (No. II. in the ground-plan and in the section; see also p. 263). Upon

these foundations in the 4th cent. was erected the Christian basilica which now forms the ***LOWER CHURCH** (No. III. in the ground-plan and in the section), the altar of which stood at the point marked *a* in the section. This seems to have been a much grander edifice than the church afterwards superimposed, its nave having been as broad as that of the upper church and one of its aisles put together (see ground-plan), and the lower apse was accordingly wider than the upper. During the construction of the upper church the lower was entirely covered up, and the two churches were never in use at the same time. The lower was again rendered accessible in 1855, and is shown by the sacristan, who provides a light ($1\frac{1}{2}$ -1 fr.). In order, however, to obtain a distinct idea of the original structure, which has been considerably marred by alterations, the visitor should visit it on 23rd Nov., 1st Feb., or on the second Monday in Lent, on which days the lower church is illuminated; even on these days, however, the visitor should carry his own candle for the inspection of details. The entrance is from the sacristy of the upper church (in the right aisle), on the walls of which are hung copies of the frescoes in the lower church, and plans comparing the upper with the lower part of the edifice.

A broad marble staircase, with inscriptions on the walls from the time of Pope Damasus, descends to the **VESTIBULE** in which the nave and aisles of the lower church terminate. The aisles alone have remained in their original condition, while in the nave additions of three distinct periods are observable. The newest are the buttresses constructed during the recent excavations for the support of the upper church, and recognisable by their whitewash. The older additions consist of the wall between the columns of the right aisle, and the lateral wall on the right, both built on the occasion of the erection of the upper church, the former for the support of the external wall above, the latter to sustain the right row of columns above. The most ancient alterations were made at a period when the lower church was still in use, and consist of masonry built round the columns of the left aisle, adorned, like the outer walls, with frescoes, some of which are in excellent preservation.

The ***FRESCOES** date from different periods, extending over seven centuries. We begin with the **VESTIBULE**. Immediately to the left by the staircase is a female head with a halo, believed by De Rossi to date from the 5th century. — Farther on, under the first arch on the left, *Christ blessing in the Greek mode, with first, middle, and little finger extended, between the archangels Michael and Gabriel and SS. Andrew (l.) and Clement (r.). Before him kneel SS. Cyril and Methodius (9th or 10th cent.). The figures in this, as well as in the following scenes, have their names attached. — Opposite (on the right), a Mother finds at the altar of St. Clement her child who had been swallowed up by the sea and thrown on shore a year later. Under it the family of the donor grouped round the medallion-portrait of St. Clement. To the right is the dedication: *Ego Beno de Rapiza pro amore dei et beati Clementis pingere feci* (11th cent.). — On the right, farther on, the Transference of the relics of St. Cyril from the Vatican to S. Clemente in the reign of Pope Nicholas, with the dedication: *Ego Maria Macellaria pro timore Dei et remedio anime mee haec pingere feci*. — At the end of the vestibule on the right is the entrance to the —

LEFT AISLE. Over the door of the latter are three badly-preserved frescoes, of which that in the centre appears to represent the resuscitation of a child. Two only of the frescoes at the end of this aisle are distinguishable: on the posterior wall in the corner, St. Cyril before the Emp. Michael; on the lateral wall, a Youth baptised by St. Methodius (10th cent.).

The NAVE is now entered through the arch in the right wall. Here, immediately to the left, is a *Fresco in three sections, one above the other. Half of the uppermost, the Enthronement of St. Clement, is destroyed. That in the centre represents St. Clement celebrating mass; on the right Theodora converted to Christianity and her husband Sisinius struck with blindness; the smaller figures on the left are those of the donor Beno and his wife. Below it is also the dedicatory inscription: *Ego Beno de Rapizacum Maria uxore mea*, etc. The lowest represents Sisinius causing a column to be bound instead of St. Clement (11th cent.). The lateral surfaces of this pier are also adorned with frescoes (l. St. Anthony, Daniel in the lions' den; r. St. Egidius, St. Blasius), but the adjoining wall prevents them from being seen. Farther on towards the vestibule, on the same wall, is another and larger *Fresco in three sections. The highest, now half obliterated, represents Christ between Michael and St. Clement (l.), and Gabriel and Nicholas (r.). In the centre are three scenes from the life of St. Alexius: a. Alexius returns unrecognised to Rome as a hermit; b. Pope Boniface I. blesses the dying man; c. The betrothed of St. Alexius recognises his corpse. The lowest of the three frescoes is of a decorative character with flowers and birds. — At the end of this wall are three scenes from the life of Christ. Next to them, on the wall of the vestibule, on the right, the Crucifixion, on the left, the Assumption. Over the latter, Christ borne by four angels; at the corners St. Vitus (r.) and Leo IV. (l.) with the inscription *S. Dom. Leo IV. P. P. Ro.*, and the square nimbus with which living persons were usually represented (9th cent.).

The frescoes of the external wall of the RIGHT AISLE are almost obliterated. A niche here contains a group of Mary with Jesus. On the arch above, Christ (beardless), with figures of angels and saints on each side.


Below the apse are the remains of BUILDINGS OF THE IMPERIAL AGE (No. II., marked black, in the plan), built of brick. The first of the three adjoining chambers is enriched with stucco. The next is an antechamber to a *Chapel of Milhras*, in which, rather singularly, a statue of the Good Shepherd was found. These chambers are damp and partly filled with water. A staircase descends to them at the end of the right aisle.

A transverse street opposite to S. Clemente leads to the VIA DE' QUATTRO SANTI, which then ascends to the left to the church of —

SS. Quattro Coronati (Pl. II, 27; entrance by the gate of the Ospizio di Orfane), dedicated to SS. Severus, Severianus, Carpophorus, and Victorinus, who suffered martyrdom under Diocletian. Five sculptors, who met with a similar fate for refusing to make images of heathen gods, are also revered here, and this is accordingly a favourite church with the 'scarpellini', or stone-masons, to whom the chapel of S. Silvestro belongs. The date of the foundation is very remote, and the materials were probably partly obtained from some ancient structure. After its destruction by Robert Guiscard, it was rebuilt by Paschalis II. in 1111, restored under Martin V. by Card. Alph. Carillo, and afterwards partly modernised.

The church now has two ENTRANCE-COURTS (keys in the first, $\frac{1}{2}$ fr.), a peculiarity owing to the diminution of its size on one of the restorations, probably by Paschalis II. It originally extended over the whole of the second court, and its former breadth is indicated by the ancient columns in the walls of this court. The disproportionate size of the tribune in the interior is thus accounted for. — On the right, under the corridor in front of the entrance to the second court, is the *Cap. di S. Silvestro*, consecrated under Innocent IV. in 1246, with valuable, though unattractive ancient paintings from the life of Constantine, in the Byzantine style. — The INTERIOR consists of nave and aisles with galleries. The tribune is decorated with tasteless frescoes by *Giovanni da S. Giovanni*. — Festival, 8th Nov.





Basilica di S. Giovanni in Laterano.

- | | |
|------------------------------|------------------------------------|
| 1. Capp. Corsini | 7. Capp. Orsini |
| 2. Capp. Ceva | 8. Capp. Tortonica |
| 3. Capp. Santorio (Godoi) | 9. Capp. Massimi |
| 4. Capp. Lancelotti | 10. Pittura di Giotto |
| 5. Capp. del S.S. Sacramento | 11. Sep. del Card. Guissano |
| 6. Capp. del Coro | 12. Statua d' Enrico IV di Francia |

Scala 0 10 20 40 60 80 100 Metri

To the right, farther on in the Via S. Giovanni (p. 260), is a large *Hospital for Women*, with the obstetric clinical department of the *Sapienza*. The Via S. Giovanni ends at the —

PIAZZA DI S. GIOVANNI IN LATERANO (Pl. II, 30), the buildings in which were erected by Sixtus V., except the new houses to the left, at the S. end of the Via Merulana (p. 181). In the S.W. corner is the baptistery of *S. Giovanni in Fonte* (see below), in the S.E. angle the transept-façade of *S. Giovanni in Laterano* (see below), and on the E. the *Lateran Palace* with the museum (p. 267).

In the centre rises an *Obelisk* of red granite, originally erected by King Thothmosis III. (B.C. 1597-60) in front of the temple of the Sun at Thebes, and brought by Constantius to the Circus Maximus in 357. In 1587 it was discovered there in three pieces, and in 1588 was erected by Sixtus V. on its present site. This is the largest obelisk in existence, being 104 ft. in height, or with the pedestal 153 ft., and about 600 tons in weight.

We first visit the octagonal **Baptistery, Il Battistëro*, or *S. Giovanni in Fonte* (Pl. II, 30), where, according to a Roman tradition, Constantine the Great was baptised by Pope Sylvester in 324 (his baptism, in fact, taking place in 337, shortly before his death). Sixtus III. (d. 440) is regarded as the true founder. This was long the only baptistery at Rome, and afforded a model for all later buildings of the kind. In 461 Pope Hilarius added to the baptistery the *Oratories of St. John* and *John the Baptist* on the E. and W. sides respectively, and about the year 640 John IV. added the *Oratory of S. Venanzio*, adjoining that of St. John. Leo X. roofed the baptistery with lead, and his successors decorated and modernised it.

From the piazza we at once enter the precincts of the BAPTISTERY itself (Pl. a). It is divided into a central space and surrounding passage by eight large columns of porphyry with an antique architrave in marble, which are said to have been presented by Constantine. In the centre is the font in green basalt. The frescoes are by A. Sacchi, Maratta, and others. — Adjacent, to the right, is the ORATORY OF JOHN THE BAPTIST (Pl. b), containing a statue of the saint in bronze by L. Valadier, executed in 1772 (after Donatello), and placed between two columns of serpentine. The bronze doors, presented by Hilarius, are said to have been brought from the Thermæ of Caracalla. — On the left, opposite this oratory, is the ORATORY OF ST. JOHN (Pl. c), with bronze doors of 1196, and adorned with **Mosaics* (5th cent.) representing birds and flowers on a golden ground. The statue of the saint, between two alabaster columns, is by Landini (d. 1594). — A third door leads into the square ORATORIO DI S. VENANZIO (Pl. d), with elaborate mosaics of the middle of the 7th century. — The fourth door, opposite to the entrance from the piazza, opens on the PORTICO DI S. VENANZIO (Pl. e), formerly the vestibule of the Baptistery, as the chief entrance was originally on this side. In 1154 the portico was converted into two chapels. The apse to the left is enriched with handsome *Mosaic* of the 5th cent., consisting of gold arabesques on a blue ground. Over the door to the Baptistery is a Crucifixion, a relief in marble, of 1194. — The outer door of the portico is adorned with two ancient columns of porphyry with their architrave, built into the wall here by Sixtus III. It leads to the *Court*, which was recently restored at the same time as the choir of S. Giovanni in Laterano.

The basilica of **S. Giovanni in Laterano* (Pl. II, III, 30), 'em-

nium urbis et orbis ecclesiarum mater et caput', was the principal church of Rome after the time of Constantine the Great (p. 135). The emperor presented Pope Sylvester with a large palace, which had hitherto belonged to the wealthy family of the Laterani, and fitted up a church within it. It was called the *Basilica Constantiniana* after its founder, and sometimes *S. Salvatoris*, or *Aula Dei*, as being a second Zion, and gradually became privileged to grant the most ample indulgences. It was overthrown by an earthquake in 896, but was re-erected by Sergius III. (904-911), and dedicated to John the Baptist. In 1308 it was burned down, but was restored by Clement V., and decorated with paintings by Giotto. A second fire destroyed the church in 1360, after which it was rebuilt by Urban IV. and Gregory XI. It was again altered by Martin V. (1430), Eugene IV., and Alexander VI., and modernised by Pius IV. (1560), by the alterations of *F. Borromini* (1650), and by the façade of *A. Galilei* (1734). Quite lately the church has been enlarged by an extension of the tribuna and choir. — Five important Councils have been held in this church, viz. those of 1123, 1139, 1179, 1215, and 1512.

The PRINCIPAL FAÇADE, by Galilei, is turned to the E., abutting on the Piazza di Porta S. Giovanni (p. 265). With its portico (33 ft. deep and 196 ft. long) and the open loggia above it, it is one of the best of this description in Rome. From the loggia the Pope used to pronounce his benediction on Ascension Day. Of the five entrances the *Porta Santa* is walled up and is opened only in the year of jubilee. The central entrance has two bronze doors adorned with garlands, etc. To the left is an ancient statue of Constantine the Great, found in his Thermæ.

The Façade of the S. Transept, looking on the Piazza di S. Giovanni in Laterano (p. 265), is also adorned with a portico, added by Sixtus V. The caps of the small campanili, standing far apart, were added by Pius IV. The vestibule below, to the right, contains a bronze statue of Henri IV. of France, by *Nic. Cordieri* (Pl. 12).

Interior. The NAVE (426 ft. in length), flanked by double aisles, is borne by twelve pillars, the work of *Borromini*, partly enclosing the ancient columns. In the niches are the Twelve Apostles, of the school of *Bernini*; reliefs by *Algardi*. Over these are the figures of twelve prophets. The Ceiling, said to have been designed by *Michael Angelo*, is more probably by *Giacomo della Porta*. The richly inlaid pavement dates from the time of Martin V. On the right and left at the end of the nave are the only two ancient granite columns now visible. Below, in front of the *Confessio*, is the Monument of Pope Martin V. (d. 1431), in bronze, by *Simone di Giov. Ghini* (p. 90). — In the centre of the TRANSEPT, which is raised by four steps, is the Canopy, a beautiful work of 1367, lately restored, with paintings by *Barna da Siena*, dating from 1390, but freely restored. It contains numerous relics, including, it is said, the heads of SS. Peter and Paul. Below it is the high-altar (*altare papale*), at which the pope or a substitute named by him alone read mass, containing a wooden table from the catacombs which is said to have been used as an altar by St. Peter. The transept was restored under Clement VIII. by *Giac. della Porta* (1603) and adorned with frescoes.

Here to the right are two fine columns of giallo antico. Adjoining the organ is the monument of the philologist Laurentius Valla (d. 1465), a canon of this church. To the left is the great *Altar of the Sacrament*, with four ancient columns of gilded bronze, which belonged to the original basilica. — The chapel to the left of the choir (Pl. 6) contains a portrait of Martin V. by *Scip. Gaetano*, and an altar-piece by the *Cav. d'Arpino*. Carved choir-stalls by *Girol. Rinaldi*.

The walls and floor of the CHOIR, which has recently been enlarged, are covered with slabs of polished marble. To the right and left are three balconies with gilded railings. The ancient *Apse*, moved back at the extension of the choir, contains precious mosaics by *Jacobus Torriti* (p. xlix; 1290; or perhaps older works restored by him), representing the Saviour enveloped in clouds; below, at the sides of a cross, (l.) the Virgin, at whose feet Nicholas IV. kneels, SS. Francis, Peter, and Paul, and (r.) John the Baptist and SS. John, Andrew, and Anthony. — The AMBULATORY is embellished on each side with mosaic tablets, the subjects of which relate to the construction of the church, statues of Peter and Paul, of the 10th cent., and a fine marble sanctuary of about 1500. Adjoining the last is the *Tabula Magna Lateranensis*, or list of relics. — Adjoining the ambulatory is the SACRISTY, the inner bronze doors of which date from 1196. It contains the monument of Fulvius Ursinus, a canon of this church (d. 1600); an *Annunciation by *Marcello Venusti* after a drawing by *Michael Angelo*; a statue of John the Baptist in wood by *Donatello*; cartoon of *Raphael's* Madonna di Casa d'Alba (original at St. Petersburg).

AISLES. At the back of the first pillar on the right in the nave (Pl. 10), *Boniface VIII. between two cardinals proclaiming the first jubilee (1300), by *Giotto*. ON THE RIGHT: The 2nd chapel (Pl. 8) belongs to the Torlonia family, and is richly decorated with marble and gilding; over the altar, *Descent from the Cross, a marble relief by *Tenerani* (a custodian opens this and other chapels, 1/2 fr.). The 3rd chapel (Pl. 9), belonging to the Massimi, constructed by *Giac. della Porta*, contains the Crucifixion, an altar-piece by *Sermoneta*. Farther on in the right aisle, the monument (Pl. 11) of Card. Guissano (d. 1287) and that of Card. Ran. Farnese, by Vignola (at the back of the last pier of the nave). — ON THE LEFT: The *1st chapel, that of S. Andrea Corsini (Pl. 1), designed by *Galilei* in 1734, contains four ancient columns and a large vessel of porphyry from the portico of the Pantheon, in front of the bronze figure of Clement XII. (Corsini, d. 1740); the walls sumptuously inlaid with precious stones. Below the chapel is the burial-vault of the Corsini, with a *Pietà by *Antonio Montauti*(?).

The sacristan conducts visitors from the last chapel of the N. aisle into the interesting *MONASTERY COURT ('Chiostro'), constructed in the 13th cent. by Vassallettus (comp. p. 354), with numerous small spiral and inlaid columns (p. xlvii), at present undergoing restoration. Various fragments from the old church are deposited in the passages. The monastery was founded at the end of the 6th cent. by Benedictines from Mte. Casino.

Adjoining S. Giovanni in Laterano, on the N., is the —

Palazzo del Laterano (Pl. II, 30), to which, together with the Vatican and Castel Gandolfo, the privilege of extraterritoriality was secured by a law of 13th May, 1871. This was the residence of the popes from the time of Constantine down to the migration to Avignon. The old palace was much larger than the present, and included the Sancta Sanctorum Chapel (p. 272). After a great fire in 1308 it lay in ruins, but these were removed, and the new palace erected by *Domenico Fontana*, by order of Sixtus V. in 1586. As it remained unoccupied, it was converted by Innocent XII. into an orphan-asylum in 1693. In 1843 Gregory XVI. set apart the palace for the heathen and Christian antiquities for which the Vatican and Capitoline museums no longer afforded space, and

named it the ***Museum Gregorianum Lateranense** (adm. daily, except holidays, 9-3). The entrance is by the portal in the piazza opposite the obelisk (p. 265); visitors ring on the right in the passage. Compare ground-plan, p. 265.

On the ground-floor is the so-called ***Museo Profano**, a collection of ancient sculptures, including several admirable works. There is no catalogue, but the custodian ($\frac{3}{4}$ -1 fr.) is well informed. A scientific German catalogue was published by Benndorf and Schöne at Leipsic in 1867.

We begin on the right, under the arcades of the entrance-wing.

I. Room. Entrance-wall: 8. Relief of the Abduction of Helen; 10. Tomb-relief (warrior's farewell); 11. Priest of the oracle of Dodona (fountain-relief). Left wall: 13. Two pugilists, named Dares and Entellus (in relief); 15. Bust of Marcus Aurelius; 20. Trajan (head restored by Thorvaldsen) accompanied by senators (relief from Trajan's Forum); in front of the last, 19. Statuette of Nemesis; 26. Nymph suckling a child, perhaps the infant Pan, in relief. Right wall: 40. Sarcophagus-reliefs (p. xlii) of Mars and Rhea Silvia (the latter being a likeness of the deceased woman), Diana and Endymion, and Adonis (Nos. 40, 49, 53). In the centre a mosaic with pugilists, from the Thermæ of Caracalla (see 1st floor, p. 271). — II. Room: interesting architectural fragments, especially from the Forum of Trajan. Fragments of a *Frieze in the centre of the walls of the entrance, the egress, and that on the right merit inspection. — III. Room: by the entrance-wall: 255. Statue of Æsculapius. Right wall: 256. *Antinous (p. xxxvii; head new), found at Ostia. Wall of egress: *258. Child's sarcophagus with scenes of pugilism. In the window several handsome feet of tables. — IV. Room: on the entrance-wall, 278. *Medea with the daughters of Peleus, a Greek relief; 291. Statue of Germanicus. Right wall: 319. *Statue of Mars. Wall of egress: 348. Replica of the reposing satyr of Praxiteles (p. xxxii). On a cippus: 352. *Bust of the youthful Tiberius. In the centre a beautiful basin of lumacchella (a kind of shell-marble).

We now cross the passage to the —

V. Room. Right wall: 394. Roman portrait-bust; 396, 405. Hermæ of Pan; Muse; 407. *Cinerary urn with the head of Medusa and representation of a cock-fight. In the centre: 391. Sacrifice of Mithras; 399. Stag of basalt; 406. Cow. — VI. Room: collection of sculptures from Cervetri, the ancient Cære. Entrance-wall: left, 427. Circular altar with Pan and two dancing Horæ; on it, 428. Colossal portrait-head (perhaps Augustus); right, 433. Statue of an emperor, head new. Right wall: 434. Draped statue; 435, 437. Colossal sitting figures of Tiberius and Claudius, between them, 436. The younger Agrippina; 438. Toga statue (perhaps the elder Drusus). Wall of egress: 439. Statue of an emperor (perhaps the younger Drusus); 444. Bust of Caligula. In

front of it: 442. Relief with representation of the deities of three Etruscan cities (Vetulonia, Volci, Tarquinii). On the pillar between the windows: 445. Female portrait-statue (perhaps Drusilla). In the centre, 447, 450. Two sleeping Silens (from a fountain); 448. Altar with representation of sacrifice. — VII. Room. On the right: 462. **Dancing Satyr*, found near S. Lucia in Selce, possibly from a group by Myron: Marsyas endeavouring to pick up the flutes thrown away by Athene, and staggering backwards on the appearance of the goddess (p. xxxi; arms new). By the door: 465. (r.) Head of Paris (?); 468. (l.) Barbarian monarch. Left wall: Apollo. Opposite the entrance: 476. ***Sophocles*, one of the most beautiful ancient portrait-statues in existence, found at Terracina in 1838. 'In the statue of the poet the sculptor has endeavoured to produce a type of perfect manhood, to pourtray the self-reliance of genius and the unruffled dignity of manly beauty; and he has accomplished his object by the general grandeur of his design, the easy attitude and noble symmetry of the figure, and the expressive attitude of the head; while the broad and lofty forehead, the gentle and imaginative eye, the firm cheek, and the earnest but benevolent mouth complete the picture of a man who has attained the zenith of human excellence and happiness' (Benndorf & Schöne). — VIII. Room: Entrance-wall: left, 487. Relief of a poet, with masks, and a Muse; right, 494. Sarcophagus with the Calydonian Hunt; above, 496. Small head of a sleeping nymph. Left wall: 517. Meleager slain by Apollo. In the centre: 534. *Statue of Poseidon, found at Porto. — IX. Room, containing numerous architectural fragments brought to light by the excavations in the Forum and the Via Appia. Wall of egress, to the left by the door: 630. Small head of Victory. In the centre: 656. Triangular *Ara with Bacchanalian dances. — X. Room: chiefly sculptures from the tombs of the Haterii, on the Via Labicana near Centocelle. Entrance-wall: 675, 677. Portrait-busts; between them, 676. Relief of a large tomb, with powerful lifting-machine adjacent. Right wall: 691. Relief of the laying-out of a dead woman, surrounded by mourners. Wall of egress: 729. Relief with representation of Roman buildings, among which the Colosseum is distinguishable. Above it, 721. Relief with Mercury (broken), Ceres, Pluto, and Proserpine. In the centre: 740. Cupid on a dolphin.

We next cross a second passage to the —

XI. Room. The sculptures are chiefly from the tombs on the Via Latina (p. 346). Entrance-wall: to the left, 743. Sleeping nymph, from a fountain; to the right, 751. Bacchanalian sarcophagus; 752, 757. Hermæ of Liber and Libera. Right wall: several hermæ of the bearded Bacchus; 768. Ephesian Diana; 769. Sarcophagus with Adonis. Wall of egress: 777. Sarcophagus with Adonis; 783. Greek tomb-relief (farewell-scene). In the centre: 792. Large sarcophagus with triumphal procession of Bacchus. — XII. Room,

Entrance-wall: (l.) 793. Youthful Hercules (perhaps with portrait-features); (r.) 799. *Sarcophagus with the story of Orestes (death of Ægistheus, etc.). 808. Head of Augustus. 807. *Boy with a bunch of grapes. In the corner: 810. Herma of a Satyr. Wall of egress: 813. *Sarcophagus with the destruction of the Children of Niobe. In the centre, 831. Fine circular altar from Veii, an imitation of the Puteal Libonis in the Roman Forum. — XIII. Room. Entrance-wall: 842. Relief of a Titan fighting; several marble 'autefixæ' (facing-tiles), with representations of the Palladium; 846. *Portrait-statue of C. Cælius Saturninus. Wall of egress: 868. Relief, Pylades supporting the exhausted Orestes. In the centre: 882. Oval sarcophagus of P. Cæcilius Vallianus, with the representation of a funeral-banquet. Then, *885. Three-sided Candelabrum-stand with Pluto, Neptune, and Persephone. — XIV. Room. Entrance-wall: 890. (r.) Small group in relief, possibly Orpheus and Eurydice. Left wall: 909. Unfinished statue of porphyry. Opposite the entrance: 902. Statue of a captive barbarian, unfinished, interesting on account of the marks of measurement made by the sculptor. Adjacent, 895. Sarcophagus of L. Annii Octavius, with representation of bread making; adjacent is the inscription: — *Evasi, effugi, Spes et Fortuna valete! Nil mihi voviscum est, ludificate alios.* By the right wall, 892. *Mosaic with representation of the pavement of an unswept dining-room ('Opus Asarotum'), by *Heraclitus*, found on the Aventine in 1833. — XV. Room and the following are devoted to the yield of the new excavations at Ostia. In the glass-cabinets under the windows are lamps, terracottas, fragments of glass, ivory articles, etc. On the pillar, mosaic from a niche, with *Silvanus*; on each side fragments of slabs of terracotta. Wall of egress: (l.) *975. Small female head, probably of a nymph; 977. Tomb-relief of the Eques T. Flavius Verus. — XVI. Room. On the right, lead pipes from ancient aqueducts. 1062-66. Pictures from a tomb near Ostia with scenes from the lower regions. In the centre: 1061. Recumbent figure of *Atthis*, found at Ostia in 1869 (p. 396), with the traces of gilding on the hair and the crescent; 1043. Bronze statuette of *Venus*.

The **Christian Museum** and the **Picture Gallery** are on the first floor of the palace. The principal entrance to them is on the farther side of the court, to the right. If this entrance is closed, we ring, as mentioned at p. 268, in the entrance-passage, then, in the arcades to the right, ascend a staircase to the left, into the walls of which are built ancient Christian inscriptions, and knock at the door at the top ($\frac{1}{2}$ fr.). Compare also Plan (p. 265).

The *CHRISTIAN MUSEUM was founded by Pius IX. and arranged by the *Padre Marchi* and the *Commendatore de Rossi*. We begin our description from the principal entrance.

In the first hall a large sarcophagus, said to be that of *Probus*; in the wall three mosaics: that in the centre, *Christ*, *Peter*, and *Paul* from the lower church of *St. Peter*; the two others from the catacombs.

In the large CORRIDOR OF THE STAIRCASE a *Collection of ancient Christian sarcophagi, chiefly of the 4th and 5th centuries, with representations from the Old and New Testament. On the right, by the end-wall: two statues of the Good Shepherd; large sarcophagus with reliefs of the Creation, Miracle of the loaves, Raising of Lazarus, Adoration of the Magi, Daniel among the lions, Moses striking the rock for water, etc. On the staircase (1.) 1st sarcophagus, Miracle of Jonah; 2nd. Christ's entry into Jerusalem. At the top: (1.) 4th. The Good Shepherd among vines, with genii gathering grapes, in allusion to the parables of the New Testament. There are also: the Denial of Peter, the Healing of the lame man, and that of the blind man, the Sacrifice of Isaac, the Men in the fiery furnace; then, farther on, a mediæval canopy and an interesting sarcophagus with scenes from the Passion. Above, on the wall of the staircase, the manger and adoration of the Magi. Below, translation of Elijah. Above, on the end-wall, sitting *Figure of St. Hippolytus, upper part modern, from the catacombs near S. Lorenzo Fuori le Mura; on the chair a Greek inscription recording the saint's achievements and an Easter-table. Comp. pp. xlii, xlii, 356-363. — The door on the left leads to the upper arcades, where the door opposite leads to the rooms with the copies of the Catacomb paintings; to the right is the entrance to the room with the large mosaic.

The posterior walls of the three open ARCADES present a selection of *Ancient Christian Inscriptions, systematically arranged by De Rossi, an invaluable aid to the student of Christian archaeology. They are distributed according to arches thus: i-iii. Elegies on martyrs, etc., of the age of Damasus I. (366-384); iv-vii. Dated inscriptions (238-557); viii, ix. Inscriptions of doctrinal importance; x. Bishops, presbyters, deacons; xi, xii. Other illustrious personages; xiii. Relations, friends, etc.; xiv-xvi. Symbolic and other records; xvii and follg. Simple epitaphs from various catacombs.

From the first arcade we pass to the right into a room (Pl. A), or the floor of which is the large *Mosaic with 28 pugilists, found in the Thermæ of Caracalla in 1824, bearing obvious indications of the decline of the art. The original arrangement of this mosaic, which has been freely restored and supplemented, is shown in the drawings on the walls.

The COLLECTION OF PICTURES contains a few ancient mosaics, several good pictures of Italian masters, chiefly of the 15th and 16th cent., and copies of pictures from the catacombs. A re-arrangement of the pictures is imminent.

Room I. (Pl. a), adjoining Room A, contains dilapidated frescoes from S. Agnese Fuori le Mura.

Room II. (Pl. B). In the middle: Mosaic, found near the Pal. Sora, not far from the Ponte S. Angelo. Entrance-wall: *Fra Filippo Lippi*, Coronation of the Virgin; *Benozzo Gozzoli*, St. Thomas receiving the girdle from the Virgin, with *Predella (resembling Fra Angelico in style). Left wall: *Antonio da Murano*, Altar-piece (1464). **C. Crivelli*, Madonna (1482), Madonna with saints (altar-piece; 1481). Exit-wall: *Cola dell' Amatrice*, Assumption (1515) and SS. Lawrence, Benedict, and Agnes (the latter credited to Signorelli). Between the windows: *St. Jerome, by *Giov. Santi*, the father of Raphael.

Room III. (Pl. C). Entrance-wall: *And. del Sarto*, Holy Family; *Fr. Francia*, Annunciation. Left wall: *Cesare da Sesto*, Baptism of Christ. Exit-wall: Copies of Raphael; *Venetian School*, Entombment. — Between the windows: *Giulio Romano*, Stoning of Stephen, a cartoon.

Room IV. (Pl. D). Entrance-wall: Madonna, by an unknown master; *Madonna with John the Baptist and St. Jerome, by *Marco Palmezzano* of Forlì, a pupil of Melozzo (p. 89; 1510). Left wall: *Sassoferrato*, Sixtus V. Adjacent, two pieces of modern tapestry from pictures by *Fra Bartolommeo*. Exit-wall: **Marco Palmezzano*, Madonna with SS. Lawrence, John the Baptist, Peter, Francis, Anthony the Abbot, and Dominic (1537).

Room V. (Pl. E). To the left, *Daniele da Volterra*, Descent from the Cross, a rough sketch in colours (the finished fresco is in S. Trinità de' Monti, p. 150); *Cav. d'Arpino*, Annunciation. To the right: *Caravaggio*, Supper at Emmaus, Christ with the tribute-money.

Room VI. (Pl. F). Entrance-wall: *Guercino*, Assumption; *Van Dyck* (?), Portrait. Left wall: Large copy in oils of a fresco by *Domenichino*, the Martyrdom of St. Andrew, original in S. Gregorio (p. 258). Between the windows: Christ and Thomas, cartoon by *Canuccini*.

Rooms G and H contain large copies in oil, some of them made for the mosaics in St. Peter's. In the last room (I) are some plaster-casts from the antique. — Another room on the same floor, opened by the custodian on application, contains casts by *Peltrich* of Dresden representing scenes from the life of the N. American Indians.

The N. side of the Piazza di S. Giovanni in Laterano, opposite the Museum, is occupied by the new buildings on the site of the *Villa Massimi*. Between the Via Ariosto and the Via Tasso, which begin here, lies the CASINO MASSIMI (not visible from the piazza), the only relic of the villa. Three rooms in this are adorned with *Frescoes* from the great Italian poets, painted for Prince Camillo Massimi in 1821-28 by German artists.

The entrance to the Casino is in the Via Ariosto; but admission is not now granted except on special introduction. The central room is adorned with scenes from Ariosto's 'Orlando Furioso' by *Jul. Schnorr*. The room on the right contains scenes from Dante, originally undertaken by Cornelius, but carried out after his removal to Munich by *Ph. Veil* (ceiling-paintings) and *A. Koch* (walls). The scenes from Tasso's 'Jerusalem Delivered', in the room to the left, are by *Overbeck* and *Führich*.

Opposite the N.E. corner of the Lateran is the edifice containing the **Scala Santa**, a flight of twenty-eight marble steps from the palace of Pilate at Jerusalem, which our Saviour is said to have once ascended. They were brought to Rome in 326 by the Empress Helena, and may only be ascended on the knees. They are now protected with a covering of wood. The two adjoining flights are for the descent. At the foot of the steps are two marble groups by *Giacometti*, Christ and Judas, and Christ before Pontius Pilate.

At the top of the steps is the *Sancta Sanctorum* chapel (not accessible), formerly the private chapel of the popes, and the only part of the old Lateran palace now preserved. It was erected in 1278 by a member of the Cosmas family for Nicholas III., and contains a Christ in mosaic in the 9th cent. style, another painted on wood, attributed to St. Luke, and other reliefs. — The portico towards the piazza was erected by Sixtus V.

To the E. of the Scala Santa is a tribune erected by Benedict XIV., with copies of the ancient *Mosaics from the Triclinium of Leo III.*, or principal dining-room of the ancient palace. These copies are from drawings of the 8th century. The originals were destroyed in the pontificate of Clement XII. Their subject is the union of spiritual and temporal power effected by Charlemagne. In the centre, Christ sending out his disciples; on the left, Christ enthroned delivers the keys to Pope Sylvester and the banner to the Emp. Constantine; on the right, St. Peter presenting the papal stole to Leo and the banner to Charlemagne.

At the top of the road ascending to the left is the entrance to the *Villa Wolkonsky* (Pl. II, 32; adm. on Wed. and Sat. by permesso to be obtained from the consul). The tasteful grounds are intersected by the *Aqua Claudia*, now almost wholly enclosed by modern buildings. A few ancient tombs and sculptured fragments are preserved in the garden.

Opposite the tribuna with the mosaics extends the spacious

PIAZZA DI PORTA S. GIOVANNI (Pl. II, 33), towards which S. Giovanni in Laterano faces. The piazza contains several modern buildings. — A dusty street leads hence to the right past unattractive modern edifices to (5 min.) S. Croce in Gerusalemme (p. 181).

The *Porta S. Giovanni*, named after the church, was erected in 1574, taking the place of the ancient *Porta Asinaria*, now built up, which stood a little to the right. Route to the Campagna, see p. 346.

The road skirting the town-wall to the left, outside the gate, brings us in 7 min. to the *Amphitheatrum Castrense* (Pl. II, 36), the only structure of the kind in Rome with the exception of the Colosseum. The building itself and the Corinthian capitals and other decorations are of burned brick. The longer diameter of the amphitheatre is 57 yds. The interior (uninteresting) is entered by the gate near S. Croce in Gerusalemme. — Hence to the *Porta Maggiore* (p. 180), 12 minutes.

V. Quarters of the City on the Right Bank.

On the right bank of the Tiber are situated two distinct quarters: towards the N. the *Borgo*, or quarter of the Vatican; and farther S., *Trastevere*. They are connected by means of the *Lungara* street.

The Borgo.

The *Vatican Hill* (206 ft.), with the plain lying beyond it, which is notorious for its malaria, was never reckoned as part of the city in ancient times, and was not enclosed within Aurelian's wall. It was once covered with the gardens of the emperors. *Caligula* constructed a *Circus* here and embellished it with a large obelisk. This circus was the scene of the races instituted by *Nero* and of his revolting cruelties to unoffending Christians in the year 65. ('Pereuntibus addita ludibria, ut ferarum tergis contacti laniatu canum interirent, aut crucibus affixi, aut flammandi, atque ubi defecisset dies, in usum nocturni luminis urerentur.' *Tacitus*, xv, 44.) On the ruins of the ancient walls thus hallowed by the first great martyrdoms at Rome sprang up the *Church of St. Peter*, in the immediate neighbourhood of which paganism maintained its footing with greater obstinacy than in any other part of the city. Not far from the church was situated a highly-revered shrine of *Cybele* (*Mater Deum Magna Idaea*), the monuments in whose honour are proved by inscriptions to extend down to the year 390. Another circumstance which tended to shape the future of this part of the city was the erection by *Hadrian* of his gigantic *Tomb* on the bank of the river. This monument was afterwards converted into a tête-de-pont, but at what date is uncertain. In 537 it effectually repelled the attacks of the Goths, and since that period it has constituted the citadel of Rome, commonly called the Castle of S. Angelo, on the possession of which the mastery over the city has always depended. Around the Church of St. Peter sprang up a number of chapels, churches, monasteries, and hospitals, and in the pontificate of *Symmachus* (496-514) a

papal palace also. Foreign pilgrims soon began to establish settlements here, named *scholæ*, or *borghi*, of which in the 8th cent. four are mentioned in history, *viz.* those of the Saxons (*i. e.* English), the Frisians, the Lombards, and the Franks, who in time of war formed separate companies of soldiers. In order to protect the whole of this region against the predatory incursions of the Saracens, *Leo IV.* surrounded it, in 848-52, with a wall 40 ft. in height, and thus became the founder of the *Civitas Leonina* named after him. This quarter of the city was repeatedly destroyed during the conflicts of the middle ages, as on the occasion of the retreat of Henry V. before Robert Guiscard in 1085, and when the Castle of S. Angelo was destroyed by the Romans in 1379. A new era in the history of the Borgo began with the return of the popes from Avignon; streets gradually sprang up; and the walls were considerably extended. *Eugene IV.* and *Sixtus IV.* were particularly active in developing the Borgo, and it attained the height of its prosperity in the pontificate of *Julius II.* and *Leo X.* at the beginning of the 16th century. The papal court, however, was unable permanently to attract the business of the city to its neighbourhood, and a sparse and poor population, engaged in the humbler branches of trade, now lives beneath the shadow of the most famous church and the most imposing palace in Christendom. Down to the pontificate of *Sixtus V.* the Borgo belonged to the popes, and lay without the bounds of the municipal jurisdiction; but that pope incorporated it with the city as a '14th Rione', and in the plebiscite of 2nd Oct., 1870, the inhabitants of the Borgo declared their desire that it should continue to form an integral part of Rome.

The principal channel of communication with the Vatican quarter is afforded by the **Ponte S. Angelo** (Pl. I, 10), which consisted originally of seven arches, but now has five only, one next the land on each side being built up. It was erected by Hadrian to connect his tomb with the city in A.D. 136, and named after him *Pons Ælius*. At the beginning of the bridge, on the site of two old chapels, Clement VII. erected statues of St. Peter by *Lorenzetto*, and St. Paul by *Paolo Romano*. The ten colossal statues of angels, formerly much admired, were executed from *Bernini's* designs in 1688, and testify to the low ebb of plastic taste at that period (p. lix). (The two angels in S. Andrea delle Fratte, p. 151, were also destined for the bridge.) The bridge commands a pleasing view of the Pincio with the Villa Medici. — At low water, to the left, are visible some remains of the piers of the ancient *Pons Triumphalis*, over which the triumphal processions of victorious emperors entered the city.

The bridge leads direct to the **Castello S. Angelo** (Pl. I, 10), which was originally the tomb erected by Hadrian for himself and his successors (*Moles Hadriani*), after the example of the mausoleum of Augustus, the tomb of Cæcilia Metella, etc. It was completed in 139 by Antoninus Pius. On a substructure, 114 yds. square, now

concealed by rubbish, arose a cylinder of travertine, 80 yds. in diameter, encrusted with marble, of which covering no trace now remains; and around the margin of the top stood numerous statues in marble. The cylinder was probably surmounted by another of smaller dimensions, on which a colossal statue of Hadrian was placed. The head in the Sala Rotonda of the Vatican (p. 306) is supposed to have belonged to this statue. The total height was about 165 ft. From Hadrian to Caracalla (d. 217) all the emperors and their families were interred here. When the Goths under Vitiges besieged Rome in 537, the tomb was converted into a fortress, and the statues on the summit were hurled down on the besiegers. At the end of the same century, Gregory the Great, while conducting a procession to pray for the cessation of the plague then raging, 'beheld the Archangel Michael sheathing his sword' above the Castello S. Angelo, in commemoration of which Boniface IV. erected the chapel of *S. Angelo inter Nubes* on the summit. This was afterwards replaced by the marble statue of an angel by *Montelupo* (now on the staircase in the interior), and in 1740 by the present bronze statue by *Verschaffelt*. From 923 onwards the edifice was always used by the party in power as a stronghold for the purpose of overawing the citizens. In 1379 it was almost entirely destroyed by the Romans. From the time of Boniface IX. downwards the castle was held by the popes, and in 1527 Clement VII. sustained a terrible siege here, on which occasion Benvenuto Cellini asserted he had thence shot the Connétable de Bourbon. The out-works were constructed by Urban V., and about 1500 the covered passage leading from the Vatican to the castle was added. In 1822 the interior was freed from rubbish. The fort was newly fortified by Pius IX. Entrance by the sentinel's post, to the right of the bridge.

Permessi, sec p. 123 (fee 1/2-1 fr.). It is important to arrive punctually at the hour named in the permesso, for visitors who arrive later must immediately join the soldier who acts as guide, and have therefore only a hasty glimpse of what the more punctual members of the party have already inspected. Visitors beginning about 11 a.m. have an opportunity of watching the reception of the midday signal and the firing of the 12 o'clock gun.

The ancient entrance is seen in the court, opposite the bridge. A passage gradually ascended thence, winding round the walls in the interior, and then diverging from them to the Tomb Chamber in the centre, which is now reached partly by other approaches. This was the last resting-place of Hadrian and his family, and still contains four niches for the urns. These are now empty; but a sarcophagus of porphyry, the lid of which is now used as a font in St. Peter's (p. 281), is said to have been found here. The visitor is also shown several gloomy dungeons in which Beatrice Cenci, Cellini, Cagliostro, and others are said to have been incarcerated; former apartments of the popes; and a saloon with frescoes by Raphael's pupil *Perino del Vaga*. Fine view of St. Peter's from the summit, and of the passage connecting the castle with the Vatican.

A new quay leads to the right from the entrance of the Castle of S. Angelo to the new quarter springing up on the *Prati di Castello*, a congeries of long and regular rows of tasteless four-story houses. Some public buildings, including a large court of law, are to

be erected here. At the N. end are the extensive new *Barracks of the Carabinieri*.

The Castle of S. Angelo is adjoined by the *PIAZZA PIA* (Pl. 1, 10), for some time named the 'Piazza del Plebiscito'. Four streets here diverge to the W.: in the centre, to the left and right of the fountain, are the streets called the *Borgo Vecchio* and the *Borgo Nuovo*; to the left, by the river, the *Borgo S. Spirito*; to the right the *Borgo S. Angelo*.

The usual route to the Vatican is by the *BORGHINO*. To the right in this street is the church of *S. Maria Traspontina* (Pl. 1, 7, 5), erected in 1566. Farther on, to the right, in the small *Piazza Scossa Cavalli*, is the handsome **Palazzo Giraud* (Pl. 4), the property of Prince Torlonia, erected by Ant. Montecavallo in 1503-6, from designs by *Bramante* (p. li), for Card. Adriano da Corneto; the poor portal dates from the 18th century.

To the right in the *Borgo Nuovo*, farther on (Nos. 101-105), is the *Pal. Ricciardi*, built for Giac. da Brescia, the physician of Leo X., from a design by Bald. Peruzzi (?). We then proceed straight to the *PIAZZA RUSTICUCCI* (Pl. 1, 7; 88 yds. long), forming a kind of entrance-court to St. Peter's. Raphael's house, designed by Bramante, which stood on the right, near the *Pal. Accoramboni* (Pl. 2), was removed when the piazza was enlarged.

The *BORGHINO S. SPIRITO*, issuing from the *Piazza Pia*, terminates as the *Borgo S. Michele* under the colonnades of the piazza of St. Peter. To the left in this street, by the river, is the spacious *Ospedale di S. Spirito* (Pl. 1, 7). The building, with its striking octagonal dome, dates from the time of Sixtus IV. and is one of the most important examples of the early Renaissance in Rome. The institution was founded by Innocent III. and embraces a hospital, a lunatic-asylum, a foundling-institution (shown 2-4 p.m.; permesso at the office on the first floor, or in the library), a home for girls, a refuge for the aged and infirm, and a valuable medical library (8-12). The three departments first mentioned can accommodate 1000, 500, and 3000 inmates respectively. The *Military Hospital* is on the opposite side of the street. The 'borgo', or settlement, of the 'Saxons' or English once lay here (comp. p. 274).


Farther on, to the left, is the church of *S. Spirito in Sassia* (Pl. 12), ascribed to Antonio da Sangallo the Younger, under Paul III.; the façade was added by Mascherino under Sixtus V. It belongs to the adjoining hospital and contains nothing noteworthy, except a bronze ciborium, ascribed to Palladio, over the altar. The brick campanile, with its corner-pilasters, is described by Burekhardt as 'perhaps, in its virile simplicity, the noblest tower of the early Renaissance'.

To the left, at the end of a side-street, rises the *Porta S. Spirito*, whence the *Via della Lungara* leads to Trastevere (see p. 327).

Near the colonnades, on the right, is *S. Lorenzo in Piscibus* (Pl. 10), a church of early origin, rebuilt in 1659; on the left is the







PALAZZO PONTIFICIO
e
Basilica di S. Pietro
al
VATICANO.

small church of *S. Michele in Sassia*, formerly the church of the Friars, rebuilt last century, with the tomb of the artist Raphael Mengs.

The ****Piazza di S. Pietro** is a square preceded by an elliptical space which is enclosed by the imposing colonnades of *Bernini* (length to the portico of the church, 370 yds.; greatest breadth 260 yds.). Each of the colonnades, which were erected in 1667, contains four series of columns of the Doric order. Three covered passages, the central of which has space for two carriages abreast, are formed by 284 columns and 88 buttresses. On the roofs are placed 162 statues of saints in *Bernini's* style. The cost of the construction amounted to 850,000 scudi (184,000*l.*); the pavement, laid by *Benedict XIII.*, alone cost 88,000 scudi. The effect is striking, and the piazza forms a fitting approach to the largest church in the world.

The great *Obelisk* in the centre of the piazza, which is destitute of hieroglyphics, was brought from Heliopolis to Rome by *Caligula* and placed in the Vatican Circus, and is the only monument of the kind at Rome which has never been overthrown.

Under *Sixtus V.* in 1586 this huge monument, estimated by *Fontana* to weigh about 500 tons, was removed on rollers from its original position, and on 10th Sept. erected under the superintendence of *Domenico Fontana* on its present site. Representations of this extremely difficult undertaking are frequently seen. It is related that *Fontana* in the construction of his apparatus had omitted to allow for the tension of the ropes produced by the enormous weight, and that at the most critical moment, although silence was imposed on the bystanders under pain of death, one of the 800 workmen, the sailor *Bresca* of *S. Remo*, shouted: 'Acqua alle funi!' (water on the ropes), thus solving the difficulty. As a reward, his relations (of *Bordighera* near *S. Remo*) were granted the privilege of providing the palm-branches for *St. Peter's* on Palm Sunday.

On the pavement round the obelisk is placed an indicator of the points of the compass. At the sides are two handsome **Fountains*, 45 ft. in height, the one next the Vatican erected by *Maderna*, the other under *Innocent XI.* On each side, between the obelisk and the fountains, is a round slab of stone indicating the centres of the radii of the colonnades, each series of which appears thence as one. At the sides of the steps leading to the portico of *St. Peter's*, formerly stood the statues of *SS. Peter and Paul* which are now at the entrance to the Sacristy (p. 284), and were replaced under *Pius IX.* by works of *De Fabris* and *Tadolini*.

To the right, at the end of the colonnades, is the *Portone di Bronzo*, the entrance to the Vatican, where the Swiss guard is stationed (see pp. 124, 286).

****St. Peter's (S. Pietro in Vaticano).**

The Church of *St. Peter*, like *S. Giovanni* in *Laterano*, *S. Paolo*, *S. Croce*, *S. Agnese*, and *S. Lorenzo*, is said to have been founded by the *Emp. Constantine* at the request of *Pope Sylvester I.* It was erected in the form of a basilica with nave, double aisles, and transept, on the site of the circus of *Nero*, where *St. Peter* is said to have suffered martyrdom, and it contained the brazen sarcophagus of

the apostle. The church was approached by an entrance-court with colonnades and was surrounded with smaller churches, chapels, and monasteries. The interior was sumptuously decorated with gold, mosaics, and marble. At Christmas, in the year 800, Charlemagne received here the Roman imperial crown from the hands of Leo III., and numerous emperors and popes were subsequently crowned here.



In the course of time the edifice had at length become so damaged that *Nicholas V.* (p. xlix) determined on its reconstruction, and in 1450 began the posterior tribune, from the design of the Florentine *Bernardino Rossellino*. According to this, the church was to have the form of a Latin cross (*i.e.*, with one arm longer than the others), and the choir was to be rounded internally, and to form half of a hexagon externally. The proportions were so adjusted that the choir and the transept completely enclosed the corresponding parts of the old church. The walls had risen to a height of 4-5 ft. only when it was interrupted by the death of the pope.

The work was not resumed till 50 years later, when a new impulse was given to the undertaking by the idea of *Julius II.* to erect a monument to himself during his own lifetime (p. li), for which, as there was no sufficient room in the church, it was proposed to add a chapel. For this proposal was next substituted another, that the church itself should be altered, and that the beginning of *Rossellino's* building should be utilised; but this last suggestion was afterwards abandoned as being likely to interfere with the independence of the work, and it was at length resolved to erect an entirely new edifice. The tradition, that *Julius II.* had invited numbers of architects, including *Giuliano da Sangallo*, to submit designs, and that *BRAMANTE* was the successful competitor, is probably true. The numbers of sketches and designs preserved in the collection of drawings in the Uffizi at Florence testify to the enthusiasm and zeal with which the various masters entered into the lists, and particularly to the assiduity with which *Bramante* revised, corrected, and perfected his designs. His aim seems to have been to crown a substructure like the *Basilica of Constantine* (p. 232) with a superstructure like the *Pantheon*. He intended the new church to be in the form of a Greek cross covered with gigantic domes, with rounded choir and transept, and an aisle adjoining each of the dome pillars and ending in small cupolas at the corners, while the entrances were to be in the axes of these aisles, opening outwards in the form of tunnel-vaulted porches. The foundation-stone was laid on 18th April, 1506, in the presence of 35 cardinals, under the choir-pillar of *St. Veronica* (No. 4 on the large plan).


This plan, which had the merit of majestic simplicity, was, it is well known, not adhered to. The year preceding *Bramante's* death (d. 1514), *Giuliano da Sangallo* (d. 1516), and with him *Raphael* and *Fra Giocondo da Verona* (d. 1515), were entrusted with the superintendence of the work. The great age of the first and the third, and the



SAGRE GROTTE
VATICANE.



SAGRESTIA



PIANTA
della
BASILICA DI SPIETRO
in
VATICANO.

Scala




Spiegazione de' numeri.

1. Statua di S. Pietro
2. _____ di S. Longino
3. _____ di S. Elena
4. _____ di S. Veronica
5. _____ di S. Andrea
6. _____ di Pio VI.
7. Sepolcro di Urbano VIII.
8. _____ Paolo III.
9. Musaico (S. Pietro)
10. La Pietà del Michelangelo
11. Monumento di Leone XII.
12. _____ di Maria Cristina di Svezia
13. Martirio di S. Sebastiano (Domenichino)
14. Sepolcro d'Innocenzo XIII.
15. _____ della contessa Matilda
16. Cappella del Sacramento
17. Sepolcro di Sisto IV.
18. _____ di Gregorio XIII.
19. _____ di Gregorio XIV.
20. Comunione di S. Girolamo (Domenichino).
21. Cappella Gregoriana
22. Sepolcro di Gregorio XVI.
23. Madonna del Soccorso
24. Sepolcro di Benedetto XIV.
25. Messa di S. Basilio (Sublayras)
26. Quadro di Caroselli
27. _____ di Valentin
28. _____ di Poussin.
29. Monumento di Clemente XIII:
30. Altare della Navicella
31. Cappella di S. Michele Arcangelo
32. Sepoltura di S. Petronilla (Guercino)
33. Sepolcro di Clemente X.
34. _____ di Alessandro VIII.
35. S. Pietro guarisce il paralitico (Mancini)
36. Altare di S. Leone Magno
37. Cappella della Colonna
38. Sarcofago di Leone II, III e IV.
39. Monumento di Alessandro VII.
40. Caduta di Sanone Mago (Vanni)
41. S. Tommaso (Carracci)
42. Sepolcro di Palestrina
43. S. Francesco (Domenichino)
44. Porta alla sagrestia
45. Cappella Clementina
46. Tomba di S. Gregorio Magno
47. Sepolcro di Pio VII.
48. Morte di Anania e Zaffira (Roncalli).
49. Trasfigurazione di Raffaello (musaico)
50. Sepolcro di Leone XI.
51. _____ d'Innocenzo XI.
52. Cappella del Coro
53. Sepolcro d'Innocenzo VIII.
54. Cappella della Presentazione
55. Monumento di Maria Clementina Sobieski
56. Tomba della famiglia Stuarda
57. Cappella del fonte battesimale
58. Sagrestia comune
59. _____ dei canonici
60. Stanza capitolare
61. Sagrestia de' beneficiati
62. Tesoro della chiesa

Scala
regia



early death of Raphael (d. 1520), were unfavourable to the work, and the original plan was much altered, the masters being divided between the Greek and Latin form of cross. The next directors of the work were *Antonio da Sangallo the Younger* (appointed in 1518), *Bal-*



S. Pietro in Vaticano. Disegno di Bramante.

0 10 20 30 40 50 Metri

dassare Peruzzi of Siena (1520), and *MICHAEL ANGELO* (1546), who distinguished himself by rejecting the innovations of Ant. da Sangallo, and rescuing Bramante's ground-plan. He strengthened the pillars of the dome, simplified the form of the aisles, and planned a porch borne by ten columns, and terminating in a pediment, but this last part of his design was afterwards abandoned. Michael Angelo was most fortunate with his construction of the dome. He

The original of the above plan (so far as shaded), signed, '*Bramante Arch. et pil.*', is preserved in the collection of architectural drawings in the Uffizi at Florence (No. 3).

completed the drum of the dome, and left behind him drawings and models for the completion of the work up to the lantern, a task which was executed by *Giacomo della Porta* and *Carlo Fontana*. Notwithstanding the vastness of its dimensions, the dome presents a marvellously airy and symmetrical appearance.

After the death of Michael Angelo (d. 1564) the building of the church was continued by *Vignola*, *Pirro Ligorio*, and *Giacomo della Porta*. In 1606 the church was completed with the exception of the façade, when *Paul V.* introduced an unfortunate alteration. Contrary to the plan of Bramante and Michael Angelo, he caused the nave to be lengthened, and the present weak and unsuitable façade to be erected by *Carlo Maderna*. Lastly *Bernini* (after 1626) finished the building in a most unsuitable way. He designed two campanili to be erected on each side of the church, but the only one which was built had to be removed owing to the insecurity of the foundation. A fine effect is produced by the double colonnades erected in front, also by *Bernini*, in the pontificate of Alexander VII.

The new church was consecrated by Pope Urban VIII., on 18th Nov. 1626, on the 1300th anniversary of the day on which St. Sylvester is said to have consecrated the original edifice. By the end of the 17th cent. the cost of building St. Peter's had amounted to upwards of 47 million scudi (nearly 10,000,000*l.*), and the present expense of its maintenance is about 7500*l.* per annum. The new sacristy, erected by Pius VI., cost 900,000 sc. (about 180,000*l.*).

The result of these various vicissitudes is that St. Peter's is the largest and most imposing, if not the most beautiful church in the world; its area is about 18,000 sq. yds., while that of the cathedral at Milan is 10,000, St. Paul's at London 9350, St. Sophia at Constantinople 8150, and Cologne Cathedral 7400 sq. yds.

The measurements are variously stated by different authorities, but the following are approximately accurate. Length of the interior 205 yds., or including the walls 213 yds.; length of St. Paul's in London 170 yds.; cathedral at Florence 163 yds.; cathedral at Milan 148 yds.; S. Paolo Fuori le Mura 139 yds.; St. Sophia at Constantinople 118 yds. — According to the measurements of Carlo Fontana, the total length of St. Peter's, including the portico, is 232 yds.; height of nave 150 ft.; breadth of nave in front 29 yds., and at the back, behind the tribune 26 yds.; length of transept inside 150 yds. — The Dome, from the pavement to the summit of the lantern, is 403 ft. in height, to the summit of the cross 435 ft.; its diameter is 138 ft., or about 5 ft. less than that of the Pantheon. The church contains 29 altars, in addition to the high-altar, and 148 columns.

The FAÇADE, with 8 columns, 4 pilasters, and 6 semi-pilasters of the Corinthian order, is 123 yds. long and 165 ft. high. It is surmounted by a balustrade with statues of the Saviour and apostles, 19 ft. high. The inscription records that it was erected by Paul V. (Borghese) in 1612. Over the central of the five entrances is the Loggia in which the new pope used to be crowned, and whence he imparted his benediction at Easter to the concourse in the piazza (discontinued since the Italian occupation, comp. p. 120).

The PORTICO, the ceiling of which is magnificently decorated in stucco, is 78 yds. in length, $14\frac{1}{2}$ in width, and 66 ft. in height. At the ends are equestrian statues: on the right, Constantine the Great by *Bernini*, on the left, Charlemagne by *Cornacchini*. At the entrances are antique columns of pavonazzetto and African marble.

Over the interior of the central external entrance is *St. Peter on the sea, termed '*La Navicella*', a mosaic after *Giotto*, formerly in the entrance-court of the earlier church, unfortunately considerably altered by *Marcello Provenziale* and *Fr. Beretta*. A copy of the original is preserved in S. Maria della Concezione in the Piazza Barberini (p. 172). — Of the five doors of the church that on the extreme right is called the PORTA SANTA, indicated by a cross, and is only opened in the years of jubilee (every 25 years; but the last celebration was in 1825). The great CENTRAL ENTRANCE is closed by the brazen *Doors which Eugene IV. caused to be executed in 1447 by *Ant. Filarete* and *Simone* (p. 1) after the model of those of S. Giovanni at Florence. The Christian subjects represented on them contrast strangely with those on the surrounding arabesques, such as Phrixus and Hella on the ram, Europa on the bull, Ganymede carried off by the eagle, etc. — The portico unfortunately detracts greatly from the effect of the whole, and, even when the spectator is at some distance off, it conceals a considerable part of the cylinder of the dome. The effect which Michael Angelo intended the dome itself to produce cannot be appreciated except from a considerable distance.

While the exterior of St. Peter's is open to criticism, the *INTERIOR, notwithstanding its meretricious enrichments (sculptures by Bernini and his contemporaries, coloured marble incrustation of the walls, and niches formed in the principal pillars by the same master) is strikingly impressive; and the effect is produced not so much by the vastness, as by the harmony and symmetry of its proportions. The finest features, such as the great breadth of the three arms of the cross, the four great dome-pillars, the arcades below the dome, and the diameter of the latter, are all due to *Bramante*, to whom the coffering of the tunnel-vaulting must also be ascribed.

Interior. On the pavement of the NAVE, close to the central door, is a round slab of porphyry on which the emperors were formerly crowned, and beyond it are stones on which are inscribed the length of several other large churches (see above; half obliterated). On each side, as far as the dome, are four pillars with Corinthian pilasters; above these a rich entablature, which bears the arches extending from pillar to pillar and the gorgeously coffered and gilded *Vaulting of the ceiling. The niches of the pillars here and in the other parts of the church contain mediocre statues of the founders of various orders. The pavement, like the walls, consists entirely of coloured marble, inlaid from designs by *G. della Porta* and *Bernini*. — By the fourth pillar to the right is the sitting *Statue of St. Peter in bronze, on a throne of white marble beneath a canopy, a work of the 13th cent. (?), brought by Paul V. from the monastery of S. Martino. The right foot is almost entirely worn away by the kisses of devotees; in front of it two large candelabra. Above is a mosaic portrait of Pius IX., commemorating the 25th anniversary of his accession to the papal see, 16th June, 1871.

The magnificent and plainly decorated DOME rests on four huge buttresses, 234 ft. in circumference, the niches in the lower parts of which are occupied by statues, 16 ft. in height, of (r.) St. Longinus (2) by *Bernini* and St. Helena (3) by *Bolgi*, (l.) St. Veronica (4) by *Mocchi* and St. Andrew (5) by *Duquesnoy*; above them are the four loggie of Bernini, where the greatest relics are exhibited on high festivals, on which occasions the loggie may be entered by none but the canons of St. Peter's. Above these are four mosaics of the Evangelists after the *Cav. d'Arpino*, of colossal

dimensions. The frieze bears the inscription in mosaic on a blue ground : *Tu es Petrus et super hanc petram aedificabo ecclesiam meam et tibi dabo claves regni caelorum.* The sixteen ribs of the vaulting of the dome are decorated with gilded stucco; between them are four series of mosaics. In the lowest the Saviour, the Virgin, and the Apostles. On a level with the lantern, God the Father, by *Marcello Provenzale*, after *Car. d'Arpino*.

Beneath the dome rises the imposing, but tasteless bronze CANOPY ('Baldacchino') borne by four richly gilded spiral columns, constructed in 1633 under Pope Urban VIII., from designs by *Bernini*, of the metal taken from the Pantheon (p. 193). It is 95 ft. in height, including the cross, and weighs about 93 tons. Under the canopy is the HIGH ALTAR, consecrated in 1594, where the pope only reads mass on high festivals. It stands immediately over the *Tomb of St. Peter*. The CONFESSION, constructed by *C. Maderna* under Paul V., is surrounded by 89 ever-burning lamps. The descent to it is by a double flight of marble steps. Doors of gilded bronze, dating from the earlier church, close the niche which contains the sarcophagus of the apostle. Between the steps is the "Statue (6) of Pius VI. in the attitude of prayer, by *Canova*, 1822.

The nave is continued beyond the dome, and terminates in the TRIBUNE, containing the mediocre bronze *Cathedra Petri* of *Bernini*, which encloses the ancient wooden episcopal chair of St. Peter. On the right (7) is the monument of Urban VIII. (d. 1644) by *Bernini*; on the left (8) "that of Paul III. (d. 1549) by *Gugl. della Porta*, probably under the supervision of Michael Angelo. Above is the figure of the pope pronouncing his benediction; beneath on the right Prudence, on the left Justice. The names of the bishops and prelates who on 8th Dec., 1854, accepted the new dogma of the immaculate conception of the Virgin were engraved by order of Pius IX.

Having traversed the nave and surveyed the stupendous dimensions of the fabric, we now proceed to examine the aisles and transepts. St. Peter's contains but few pictures; those formerly here, some of which are now in the Vatican Gallery, are replaced by copies in mosaic.

RIGHT AISLE. Over the 'jubilee-door' St. Peter in mosaic (9), placed here by Clement X. in the year of jubilee 1675. The (1st) CHAPEL DELLA PIETÀ (10) contains a celebrated "Pietà by Michael Angelo, executed in 1498 at the instance of the French Cardinal Jean de Villiers de la Grolaie. This masterpiece was produced under the direct influence of classic art, and the depth and truth of the conception are mirrored in the exquisite finish of the execution. Neither the grief of the Mother nor the effect of death on the Son detracts from the ideal beauty imparted to them by the artist. This chapel also contains, to the left, a large early-Christian sarcophagus, in which, according to the inscription, *Junius Bassus*, prefect of the city (d. 395), was buried. It was discovered in 1595 during the rebuilding of St. Peter's. To the right is a column which tradition affirms to have been brought from the Temple at Jerusalem, and which served Bernini as a model for the twisted pillars of the Baldacchino. — Adjacent, to the right under the arch, is the monument (11) of Leo XII., erected by Gregory XVI., by *De Fabris*; to the left, cenotaph (12) and bronze relief-portrait of Christina of Sweden, daughter of Gustavus Adolphus, and a convert to the Romish faith. The 2nd altar (13) is adorned with the Martyrdom of St. Sebastian after *Domenichino*. Under the next arches are the monuments of (r.) Innocent XII. by *Fil. Valle* (14), and (l.) the Countess Matilda of Tuscia (d. 1115) by *Bernini* (15), executed by order of Urban VIII. who had transferred her remains from Mantua hither. On the right the (3rd) CHAPEL OF THE HOLY SACRAMENT (16), closed by an iron gate, contains an altar-piece by *Pietro da Cortona*; right, the finely executed "Monument (17) of Sixtus IV. (d. 1484) in bronze, by *Ant. Pollajuolo* (1493). Julius II. (of the della Rovere family, like Sixtus), who was the first to resume the construction of the church after Nicholas V., is also interred here. Under the next arch: right, the monument (18) of Gregory XIII., the rectifier of the calendar (d. 1585), by *Camillo Rusconi*; left, the plain sarcophagus (19) of Gregory XIV. Opposite, over the altar by the principal buttress, is the Communion of St. Jerome (20), after *Domenichino* (original in the Vatican). On the right, the GREGORIAN CHAPEL (21), erected under Gregory XIII. from the design of

Michael Angelo, at a cost of 80,000 scudi; here to the right is the "Monument (22) of Gregory XVI. (d. 1846), by *Amici* (1854); below it a relief representing the dissemination of Christianity. Above the altar is the "Madonna del Soccorso (23), from the old church of St. Peter, dating from about 1118; under it is the tomb of St. Gregory of Nazianzus (d. 390). Under the following arch: right, the tomb (24) of Benedict XIV.; left, altar (25) with the mass of St. Basilus, after *Subleyras*.

THE RIGHT TRANSEPT was used by the Ecumenical Council for its meetings in 1870. By the tribune, three altars with pictures by *Caroselli* (26), *Valentin* (27), and *Poussin* (28), representing the Martyrdom of St. Erasmus.

PROLONGATION OF RIGHT AISLE. Under the arch: right, "Monument (29) of Clement XIII. (Rezzonico of Venice, d. 1769), by *Canova*; figure of the pope and the two lions worthy of inspection; left, altar of the Navicella (30) with Christ and Peter on the sea, after *Lanfranco*. Right, the CHAPEL OF THE ARCHANGEL MICHAEL (31), the "Archangel, after *Guido Reni*; in a straight direction, Burial of St. Petronella (32), after *Guercino*. Under the (left) following arch: right, monument (33) of Clement X.; Raising of Tabitha by Peter, after *Costanzi*. — We now pass the principal tribune, and enter the —

W. DIVISION OF LEFT AISLE. Immediately on the right is the monument (34) of Alexander VIII. (Ottoboni of Venice, d. 1691), by *Arrigo di S. Martino*; left, Healing of the lame man by Peter and John (35), after *Mancini*; farther on, right, the altar (36) of Leo I. with a marble relief by *Algardi* (about 1650), representing the Retreat of Attila. Facing the visitor is the CAPPELLA DELLA COLONNA (37), containing a highly revered "Madonna from a pillar of the older church. Beneath the altar an ancient Christian sarcophagus (38), with Christ and the apostles in front, containing the remains of Leo II. (d. 683), Leo III. (d. 816), and Leo IV. (d. 855). Turning hence to the left, we first perceive on the right, over the small door (of egress), the unattractive monument (39) of Alex. VII. (d. 1667) by *Bernini*. Opposite is an altar (40) with an oil-painting (on slate) by *Fr. Vanni*, Punishment of Simon Magus.

The LEFT TRANSEPT, with its tribune and three altars, is next entered. It contains confessionals for eleven different languages, as the inscriptions indicate. By the pillar of S. Veronica, below the statue of S. Juliana, is an elevated seat, whence on high festivals the grand-penitentiary dispenses absolution. Over the first altar on the right, St. Thomas (41), by *Camuccini*; in front of that in the centre, the tomb (42) of the great composer Palestrina (1520-94), whose works are still performed in St. Peter's; altar-piece, Crucifixion of Peter, after *Guido Reni*; left, St. Francis (43), after *Domenichino*. The portal to the right under the following arch (44) leads to the Sacristy; above it the monument of Pius VIII. by *Tenerani*. To the left (48), Death of Ananias and Sapphira, after *Roncalli*. From this point the effect of the dome, tribune, and transept collectively is best appreciated. Then the CLEMENTINE CHAPEL (45), erected by Clement VIII. (1592-1605); below the altar (46) on the right reposes Gregory I., the Great (590-604); altar-piece after *Andr. Sacchi*; facing us, the "Monument (47) of Pius VII. (d. 1823), by *Thorvaldsen*. — We now turn to the left, and perceive below the arch, on the left, the mosaic copy of Raphael's Transfiguration (49), four times the size of the original. — Opposite, to the right, begins the —

LEFT AISLE. Here, under the arch on the right, the monument (50) of Leo XI. (d. 1605) by *Algardi*, with a relief of the recantation of Henry IV. of France; left, monument (51) of Innocent XI. (d. 1689) by *C. Maratta*, with relief of the delivery of Vienna by King John Sobieski. The large CHOIR CHAPEL (52), gorgeously decorated by *Della Porta* with stucco and gilding, contains the tombstone of Clement IX. (d. 1721) and two organs. Here on Sundays ceremonies accompanied by beautiful musical performances frequently take place; ladies only admitted when provided with black dress and veil, gentlemen also in black (evening-dress). — Beneath the arch, to the right over the door, is the tomb in which the most recently deceased pope rests until the completion of his tomb and monument elsewhere; Pius IX. (d. 1878) lay here till July 12th, 1884, when his body was transferred to S. Lorenzo Fuori le Mura (see p. 344). To the left, the "Monument (53) of Innocent VIII. (d. 1492), by *Ant. and Pietro Pollajuolo*. Then on the right an altar (54) with the Purification of the Virgin, after *Romanelli*. Under

the arch to the right, over the door which leads to the dome, the eye of the English traveller will rest with interest upon the monument (55) of Maria Clementina Sobieski (d. 1735 at Rome), wife of Charles Edward, the young Pretender, and to the left the tomb (56) of the last of the Stuarts, by *Canova* (1819), with busts of 'James III.' and his sons Charles Edward, and Henry, better known as Cardinal York. In the last chapel (57) on the right is a font consisting of the cover of a sarcophagus from the mausoleum of Hadrian (p. 275). Over the altar, Baptism of Christ, after *Maratta*.

The SACRISTY (entrance by the grey marble portal, ground-plan 44; visited most conveniently 9-11 a.m.), erected in 1775 by Pius VI. from designs of *C. Marchionne*, consists of three chapels in a corridor adorned with ancient columns and inscriptions.

At the entrance the statues of (r.) St. Peter and (l.) St. Paul, executed under Pius II. by *Mino del Regno*, and formerly in the Piazza of St. Peter. The central chapel, SAGRESTIA COMUNE (58), octagonal in form, is embellished with eight columns of bigio from the villa of Hadrian at Tibur. A guide ($\frac{1}{2}$ fr.) is found here to show the others. Left, the SAGRESTIA DEI CANONICI (59), with the Cap. dei Canonici, altar-piece by *Francesco Penni* (Madonna with SS. Anna, Peter, and Paul), opposite to which is a *Madonna and Child by *Giulio Romano*. Adjacent is the —

STANZA CAPITOLARE (60), containing *Pictures from the old Confessio, by *Giotto*: Christ with a cardinal; Crucifixion of Peter, a good example of Giotto's dramatic power; Martyrdom of St. Paul; on the back, Peter enthroned; SS. Andrew, John, Paul, and James; on the predella (by the window), Madonna and Apostles. This work alone would entitle Giotto to be regarded as the founder of a new school of painting. This Stanza also contains fragments of the *Frescoes by *Melozzo da Forlì* from the former dome of SS. Apostoli (angels with musical instruments and several heads of apostles). On the right, the —

SAGRESTIA DE' BENEFIZIATI (61), with an altar-piece by *Muziano*, the Delivery of the Keys. Contiguous is the TREASURY (62) of St. Peter's, containing jewels, candelabra by *Benvenuto Cellini* and *Michael Angelo*, the dalmatica worn by Charlemagne at his coronation, etc. — Over the sacristy are the ARCHIVES of St. Peter's with ancient MSS., e.g. Life of St. George, with miniatures by *Giotto*; also a few classical authors. The treasury and archives are seldom shown.

The SAGRE GROTTA VATICANE (or crypt), consisting of passages with chapels and altars beneath the pavement of the present church, also deserve a visit. The so-called 'Grotte Vecchie' are only shown by special permission of the Pope (which lady-visitors require in the case of the others also). For admission to the 'Grotte Nuove' apply at the sacristy (fee $\frac{1}{2}$ fr.). Entrance, see ground-plan, *a*.

The Grotte Nuove, situated under the dome, consist of a corridor in the form of a horseshoe, which encloses the Confessio. In the four great buttresses which support the nave, steps descend to as many CHAPELS: *a*. St. Veronica, *k*. St. Helena, *i*. St. Longinus, *d*. St. Andrew. — In the CHAPEL OF S. MARIA DE PORTICU (*b*), to the right by the entrance, is St. Matthew, on the left, St. John, both from the tomb of Nicholas V. (d. 1455); over the altar a Madonna by *Simone Memmi*, from the colonnade of the old church, much injured. Outside the chapel, on the right, a mosaic: Christ between SS. Peter and Paul, from the tomb of Emp. Otho II. — In the CHAPEL OF S. M. PREGNANTIUM (*c*), at the entrance, the two SS. James, from the tomb of Nicholas V.; half-figure of Boniface VIII.; angels in mosaic, after *Giotto*. Here, and throughout the whole corridor, are preserved numerous reliefs of the 15th cent. from the tombs of the popes; among them, on the right, a Madonna with St. Peter and St. Paul (*h*) by *Mino da Fiesole*. Reliefs from the tomb of Paul II.: Hope, Faith, Charity, and the Last Judgment. On the left, by the sides of the entrance to the Confessio, marble *Reliefs (*m*) of the martyrdom of SS. Peter and Paul, from

the tombstone of Sixtus VI. The CONFESSIO, or Shrine of SS. Peter and Paul, in the centre of the circular passage, is richly decorated with gold, jewels, etc. Over the altar, which was consecrated in 1122, are two ancient pictures of St. Peter and St. Paul. The sarcophagus of St. Peter (formerly in the catacombs on the Via Appia, then in the Lateran) has been preserved here since the 15th century.

The *Grotte Vecchie* are about 147 ft. long and 57 ft. wide. The pavement was originally that of the ancient church, and lies 11 ft. below that of the present church. These vaults contain the tombs of many popes and princes. In *e.* those of Nicholas I. (d. 867), Gregory V. (d. 999), and Emp. Otho II. (d. at Rome, 983). At the end of *f.* that of Alexander VI. (d. 1503). In *g.* those of Hadrian IV. (Nicholas Breakspeare, the only English pope, d. 1159), an old sarcophagus in granite; Pius II. (Æneas Sylvius Piccolomini, d. 1464), an early-Christian sarcophagus; Pius III. (d. 1503), Boniface VIII. (d. 1303), Nicholas V. (Thomas of Sarzana, d. 1455), and Paul II. (d. 1471), these four by *Mino da Fiesole*; Urban VI. (d. 1389); Marcellus II. (d. 1555), in an early-Christian sarcophagus; Cardinal Fonseca (d. 1422).

For the *ASCENT OF THE DOME (daily 8-11 a.m.) a permesso is required, and may be obtained in the 'Rev. Fabbrica di S. Pietro', Via della Sagrestia 8 (first floor). Visitors knock at the door in the left aisle (Pl. 55). Eight flights of easy steps, 142 in all, ascend to the roof. The walls bear memorial-tablets of royal personages who have performed the ascent. On the roof a number of domes and small structures are seen, some of which serve as dwellings for the workmen and custodians.

One of the eight octagonal chambers in the piers which support the dome contains a *Model of the church by *Michael Angelo* and his predecessor *Ant. da Sangallo*, for admission to which a permesso of the 'Rev. Fabbrica di St. Pietro' (see above), obtainable by special recommendation only, must be procured; here, too, a model of the ancient throne of St. Peter is preserved.

The DOME rises 308 ft. above the roof, and is 630 ft. in circumference. The visitor will observe the huge hoops of iron by which the dome was strengthened in the 18th cent., when threatening fissures had begun to appear. The gallery within the dome affords a striking view of the interior. An easy staircase ascends between the outer and inner dome to the **Lantern*, which commands a view of the whole church and its environs. A narrow iron staircase, admitting one person only at a time, ascends to the copper ball on the summit, which can contain 16 persons, but affords no view.

Ascending by St. Peter's, to the left beyond the colonnades (way to the Vatican gallery of statues, see p. 304, and Plan, p. 276), we reach, on the left near the sacristy, the *Cimitero dei Tedeschi*, the most ancient Christian burial-ground, instituted by Constantine, and filled with earth from Mt. Calvary. In 1779 it was granted to the Germans by Pius VI. Adjacent is the church of *S. Maria della Pietà in Campo Santo* (Pl. I, 4, 4), adjoining which is the German and Flemish refuge for pilgrims.

Near it is situated the *Palace of the SS. Offizio*, or Inquisition, now a barrack. That tribunal was established in 1542 by Paul III.

by the advice of Card. Caraffa, afterwards Pope Paul IV., and this edifice was assigned to it by Pius V.

The Vatican.

The *Vatican Palace*, the largest in the world, was originally a dwelling-house for the popes, erected by Symmachus (p. 273) near the anterior court of the old church of St. Peter, and afterwards gradually extended. Charlemagne is believed once to have resided here. This building having fallen to decay during the tumults of the following centuries, Eugene III. erected a palace near St. Peter's, which was greatly enlarged by Nicholas III. The Vatican did not, however, become the usual residence of the popes until after their return from Avignon, when the Lateran was deserted. After the death of Gregory XI. the first conclave was held in the Vatican in 1378, which resulted in the schism. In 1410 John XXIII. constructed the covered passage to the castle of S. Angelo. In 1450 Nicholas V. (p. xlix), with a view to render the Vatican the most imposing palace in the world, determined to unite in it all the government-offices and residences of the cardinals. The small portion completed by him, afterwards occupied by Alexander VI. and named *Tor di Borgia*, was extended by subsequent popes. In 1473 the *Sistine Chapel* was erected by Sixtus IV., and about 1490 the *Belvedere*, or garden-house, by Innocent VIII. Bramante, under Julius II., united the latter with the palace by means of a great court, which under Sixtus V. was divided by the erection of the library into two parts, the anterior court and the Giardino della Pigna. The *Loggie* round the Cortile di S. Damaso were also constructed by Bramante. In 1534 Paul III. founded the *Pauline Chapel*, and Sixtus V. the *Library* and the present residence of the popes, which last was completed by Clement VIII. (1592-1605). Urban VIII. erected the *Scala Regia* from Bernini's design, Pius VII. the *Braccio Nuovo* for the sculptures, Gregory XVI. the *Etruscan Museum*, and Pius IX. closed the fourth side of the Cortile di S. Damaso by covering and reconstructing the great staircase which leads from the arcades of the piazza into the court. The palace now possesses 20 courts, and is said to comprise 11,000(?) halls, chapels, saloons, and private apartments. By far the greater number of these are occupied by collections and show rooms, a comparatively small part of the building being set apart for the papal court. A law passed on 13th May, 1871, secures to the Vatican, the Lateran, and the papal villa at Castel Gandolfo the privilege of extraterritoriality.

The PRINCIPAL ENTRANCE to the Vatican (*Portone di Bronzo*) is at the end of the right colonnade of the Piazza of St. Peter. Within the gate visitors apply to the Swiss guard (comp. p. 124), and are conducted to the Maggiordomato to receive their permesso. The steps (*Scala Pia*), originally uncovered, but altered by Pius IX., lead to the CORTILE DI S. DAMASO, a court which

derives its name from the fountain of St. Damasus erected here by Innocent X., and sometimes called *Cortile delle Loggie* from the Loggie of *Bramante* (p. lii) by which it is bounded on three sides. On the right is the wing occupied by the Pope. On the left a door with the inscription *Adito alla Biblioteca ed al Museo* (now available for readers in the library only; collection of antiquities, see p. 304). The loggie on the first floor are embellished with paintings by Giovanni da Udine (freely but judiciously retouched), those on the second floor by Raphael (p. 299).

The visitor should be well provided with 50 c. notes and copper money, as fees are exacted from him at a dozen different places (in each department $\frac{1}{2}$ fr., frequent visitors 25 c.). The ciceroni who proffer their services at the entrance are generally ignorant and importunate.

Apartment not usually shown at present are enclosed within square brackets in the following description.

A. Paintings.

Cappella Sistina. Raphael's Stanze and Loggie. Picture Gallery.

(Comp. Plan, p. 289.)

Permesso, see p. 124. The name of each department where it is shown is deleted by the custodian. Catalogue of the picture-galleries and decorative paintings by the Conservatore *Ercole Massi*, in Ital. 2 fr., Engl. 4 fr., abridgment in French 2 fr.

We pass the *Portone di Bronzo* (see above) with the Swiss guard and proceed to the *SCALA REGIA*, a magnificent flight of steps, constructed by *Ant. da Sangallo the Younger*, and restored by *Bernini* under Alexander VII., covered with tunnel-vaulting borne by Roman columns. We mount these steps and pass through a door to the *Staircase on the Right*, which ascends to the first floor, where we are admitted by a side-entrance to the Sistine Chapel (see below), indicated by an inscription. On the second floor are Raphael's Stanze and Loggie (p. 292), and on the third the picture-gallery (p. 301).

****CAPPELLA SISTINA. SALA REGIA. SALA DUCALE.
CAPPELLA PAOLINA.**

The ****Sistine Chapel** was erected under Sixtus IV. by *Baccio Pintelli* (?) in 1473; length 133 ft., width 45 ft., six windows on each side above. Beautifully decorated marble screens enclose the space set apart for religious solemnities. The lower part of the walls was formerly hung with Raphael's tapestry (p. 303) on the occasion of festivals, while the upper part, with the exception of the wall of the altar, is decorated with interesting frescoes by Florentine masters of the 15th cent. (p. xlix; best light in the morning).


These **FRESCOS** represent parallel scenes from the life of Christ (right) and Moses (left), beginning at the altar, and meeting on the entrance-wall. Left: 1. (by the altar) *Perugino*, Moses with his wife Zipporah journeying to Egypt, Zipporah circumcises her son (sometimes attributed to *Luca Signorelli*, or with more probability to *Pinturicchio*); *2. *Sandro Botticelli*, Moses kills the Egyptian,

drives the shepherds from the well, kneels before the burning bush; 3. *Cosimo Rosselli*, Pharaoh's destruction in the Red Sea; 4. *Cos. Rosselli*, Moses receives the Law on Mt. Sinai, Adoration of the calf; 5. *S. Botticelli*, Destruction of the company of Korah, and that of the sons of Aaron; 6. *Luca Signorelli*, Moses as a law-giver, Investiture of Aaron, Mourning over the body of Moses, with boldly drawn male figures. — Adjoining the latter, on the entrance-wall: *Salviati*, Contest of the Archangel Michael for the body of Moses, now entirely repainted. — Right: 1. *Perugino*, Baptism of Christ; 2. *S. Botticelli*, Christ's Temptation (vigorous and finely individualised); *3. *Dom. Ghirlandajo*, Vocation of Peter and Andrew, completed about 1484, in a dignified and severe monumental style; 4. *C. Rosselli*, Sermon on the Mount, Cure of the leper; *5. *Perugino* (who, according to Vasari, was assisted by *Bartol. della Gatta*), Christ giving the keys to Peter, one of the master's finest monumental works, in spite of defects in the composition; 6. *C. Rosselli*, Last Supper. — On the entrance-wall: Resurrection of Christ, originally by *D. Ghirlandajo*, renewed by *Arrigo Fiammingo*. — On the pillars between the windows 28 popes by *S. Botticelli*, not easily distinguishable. — The place of honour at the altar, before Michael Angelo painted his Last Judgment (p. 291), was occupied by three other frescoes by Perugino: the Finding of Moses, Coronation of the Virgin, and Adoration of the Magi.

The **CEILING (p. lii; mirrors provided by the custodian) was begun by Michael Angelo on 10th May, 1508, and, as proved by existing documents, completed in the autumn of 1512 (although the master's biographers have stated that he executed the work 'in 22 months'). Whether the ceiling of the Sistine Chapel, or the Stanze of Raphael are to be regarded as the culminating effort of modern art, has long been a subject of controversy. The merit of uniformity of thought and compactness of composition must be awarded to the ceiling-painting, and these attributes are the more worthy of admiration, as the subjects of the whole series had not been agreed upon from the outset. The pictorial enrichment of the ceiling was at first to be limited to the figures of the Twelve Apostles, but Michael Angelo, perceiving the poverty of the design, prevailed on the pope to allow him to extend it. In order to connect the different scenes, Michael Angelo invented an imaginative structure with columns, pillars, and cornices in bronze and marble, which rises from the walls, and encloses in the middle of the ceiling (which is vaulted, with a flat surface in the middle) nine sections of different sizes. The lifelike figures which step forth from the architectural members, some of them in their natural colour, and others of a bronze tint, impart to the background such animation and significance, as to render it an admirable introduction to the large central pictures. It is here that the spectator will become fully aware of the importance to a painter of

a thorough acquaintance with architectural designs, and of the extent to which Michael Angelo availed himself of such acquaintance.

A description of the CENTRAL SCENES may be given nearly in



the words of *Ascanio Condivi*, a pupil of Michael Angelo, who in 1553 wrote the master's life before the death of the latter. — 'In the *1st Section* of the ceiling (reckoned from the altar), which is one of the smaller ones, you observe in the air God Almighty, who with the motion of his arms separates light from darkness. — In the *2nd Section* he creates the two great lights of the world, his outstretched right hand touching the sun, and the left the moon. Around him are several angels, one of whom (to the left) hides his face, and presses close to the Creator, as if to screen himself from the baneful influence (dazzling light) of the moon. In the same section God is again represented as engaged in creating the herbs and plants on the earth. He is portrayed with such art, that wherever you turn he appears to follow you, showing his whole back down to the soles of his feet, — a very excellent work, proving what can be done by foreshortening. — In the *3rd Section* God the Lord appears in the air surrounded with angels, regarding the waters, and commanding them to bring forth all those kinds of animals which that element nourishes. — In the *4th Section* the creation of man is represented, and God is seen with outstretched arm and hand, as if prescribing to Adam what to do, and what to abstain from. With his other arm he encloses a group of angels (the figure immediately behind the shoulder of the Father bears distinctly female features, and it is a not improbable conjecture that the master meant here to represent the uncreated Eve). — In the *5th Section* God draws from Adam's side the woman, who with folded hands stretched out towards God, bows herself with a sweet expression, so that it seems she is thanking him, and that he is blessing her. — In the *6th Section* the Demon, in human form from the waist upwards, and otherwise a serpent, coils himself round a tree; he converses with Adam and Eve, whom he persuades to disobey their Creator, and hands the forbidden fruit to the woman. In the second part of the section you see the pair, driven out by the angel, fleeing terrified and sad from the face of God. — In the *7th Section* the sacrifice of Abel and Cain (or rather Noah's thank-offering) is represented. — In the *8th Section* is seen the Flood, with Noah's Ark on the water at a distance, and a few persons clinging to it in hopes of saving themselves. Nearer is a boat crowded with people, which, owing to its undue load, and to the numbers of violent shocks of waves, is already shipping water, and threatening to sink, and it is indeed a strange thing to see the human race perishing so miserably in the waves. Still nearer the eye appears above the water the top of a mountain, where a number of men and women have sought refuge as if on an island; they show different emotions, but they all cower, miserable and terrified, under a tent stretched over a tree, to shelter themselves from the excessive rain. And in this scene the wrath of God is represented with great art, for he sends upon them lightnings, waters, and

storms. There is also another mountain-top on the right side with a group of people on it in similar distress, but it would take too long to describe each one of them. — In the 9th Section, the last, is narrated the story of Noah, who, when lying drunken and naked on the ground, is mocked by his son Ham, but is being covered by Shem and Japheth'.

On the lower part of the vaulting are the ****PROPHETS AND SIBYLS** in earnest contemplation, surrounded by angels and genii. To the left of the altar: 1. *Jeremiah*, in a profound reverie; 2. *Perseian Sibyl*, reading; 3. *Ezekiel*, with half-opened scroll; 4. *Erythraean Sibyl*, sitting by an open book; 5. *Joel*, reading a scroll; 6. (over the door) *Zacharias*, turning the leaves of a book; 7. *Delphian Sibyl*, with an open scroll; 8. *Isaiah*, his arm resting on a book, absorbed by divine inspiration; 9. *Cumaeen Sibyl*, opening a book; 10. *Daniel*, writing; 11. *Libyan Sibyl*, grasping an open book; 12. (above the Last Judgment) *Jonah*, sitting under the gourd. 'All these are truly wonderful', says Condivi, 'both owing to the attitudes, and to the ornamentation, and the variety of the drapery. But most wonderful of all is the prophet Jonah who sits at the top of the vaulting. His body is foreshortened towards the inside, towards the part nearest the beholder's eye, while the legs project outside, in the more distant part: a marvellous work, for so great is the skill of Michael Angelo in foreshortening and perspective'.

In the pointed arches and lunettes of the vaulting are the ancestors of the Saviour in calm expectation. In the four corner-arches: on the altar-wall, right, the Israelites in the wilderness with the brazen serpent; left, king Ahasuerus, Esther, and Haman. On the entrance-wall, left, David and Goliath, right, Judith.

Nearly 30 years later than this ceiling Michael Angelo painted on the altar-wall the ****LAST JUDGMENT**, 64 ft. in width, completed under Paul III. in 1541. Careful and repeated study alone will enable the spectator to appreciate the details of this vast composition, which is unfortunately blackened by the smoke of centuries, and unfavourably lighted. To fathom the religious views and artistic designs of the talented master is a still more difficult task. On the right of the figure of Christ as Judge hover the saints drawn back by devils and supported by angels, on his left the sinners in vain strive to ascend; above are two groups of angels with the Cross, the column at which Christ was scourged, and the other instruments of his passion; in the centre Christ and the Virgin, surrounded by apostles and saints; below the rising dead is hell, according to Dante's conception, with the boatman Charon and the judge Minos, whose face is a portrait of Biagio of Cesena, master of the ceremonies to Paul III., who had censured the picture on account of the nudity of the figures. Paul IV., who contemplated the destruction of the picture on this account, was persuaded, instead, to cause some of the figures to be partly draped by *Daniele*

da Volterra. Clement XII. caused this process to be extended to the other figures by *Stefano Pozzi*, whereby, as may be imagined, the picture was far from being improved.

Most of the solemnities at which the Pope officiates in person take place in the Sistine Chapel (see pp. 120, 121).

Adjacent to the Sistine Chapel on the E. is the **Sala Regia**, which is shown by the custodians of the Sistine Chapel on special request. It was built by *Ant. da Sangallo the Younger*, as an entrance hall to the Sistine Chapel, and was originally destined for the reception of foreign ambassadors. The cornicings of the ceiling are by *Perino del Vaga*, and those over the doors by *Dan. da Volterra*.

The mediocre FRESQUES of *Vasari*, *Salviati*, and the *Zuccari*, represent, according to the titles inscribed below them: on the window-wall, to the right, scenes from the Night of St. Bartholomew (the inscription *Strages Hugonottorum*, etc., which was once under them, has been obliterated). On the wall opposite the entrance, the door in which leads to the Sistine, the Alliance of the Spanish and Venetians with Paul V., Battle of Lepanto in 1571; on the end-wall, Gregory VII. absolving the Emp. Henry IV. (door to the Pauline), Conquest of Tunis. On the entrance-wall, Gregory XI. returning from Avignon, Alexander III. absolving Fred. Barbarossa.

The **Sala Ducale**, which adjoins the Sala Regia, constructed by *Bernini*, is decorated with frescoes and landscapes by *Bril*.

From the Sala Regia a door to the left, with the inscription 'Paulus III. P. M.', leads into the **Pauline Chapel** (*Cappella Paolina*), built in 1540 by *Antonio da Sangallo the Younger* for Paul III. Here also are two frescoes by *Michael Angelo*, painted by him at a very advanced age: on the left, the Conversion of St. Paul, on the right, the Crucifixion of St. Peter. The other pictures are by *Lor. Sabbatini* and *F. Zuccaro*, the statues in the corners by *P. Bresciano*. The chapel is used on the first Sunday in Advent for the *Quarant' Ore*, or exposition of the host during 40 hrs., when, as well as on Holy Thursday, it is brilliantly illuminated.

RAPHAEL'S **STANZE AND **LOGGIE. *CAPPELLA NICCOLINA (DI S. LORENZO). **PICTURE GALLERY. RAPHAEL'S TAPESTRY.

(Comp. the Ground-Plan, p. 289.)

We follow the staircase mentioned at p. 287, passing the present entrance to the Sistine Chapel, and ascend thence to the right 63 steps, to the second floor, where we knock at the white door, through which Raphael's Stanze and Loggie at present are entered from the back. Sticks and umbrellas are left at the door. — In front, and to the right are two rooms with indifferent modern pictures, chiefly representing scenes from the lives of persons canonised by Pius IX. The room to the right also contains a picture representing the Relief of Vienna in 1683 by John Sobieski, by *Matejko*, presented by Poles. We traverse that to the right, and then a saloon, the *Sala dell' Immacolata*, decorated by *Podesti*, by order of Pius IX., with frescoes relating to the doctrine of the Immaculate Conception of the Virgin, promulgated on 8th Dec., 1854 (comp. p. 1x).

The door in a straight direction leads to the first of —

****Raphael's Stanze.** The frescoes executed by *Raphael* in 1508-1520 in the papal apartments (*Stanze* or *Camere*) of the Vatican, by order of the Popes Julius II. and Leo X., are unquestionably the foremost among the creations of the master and are rivalled by no modern works of art in existence except the ceiling-paintings in the Cappella Sistina (p. 287). The work, however, in its entire grandeur had not been planned, nor the task committed to Raphael from the outset. Julius II. originally intended these rooms to be decorated in a much simpler style, and he entrusted the task to *Perugino*, *Sodoma*, and other painters of Umbria and Siena. Among these was the young Raphael, who had probably been introduced by *Perugino*, and who after the completion of the first frescoes became so prominent among his fellows, that the work was then entrusted to him exclusively. Raphael did not, however, live to complete his task, and it was finished by his pupils. The earliest pictures in the first and second stanza only are by Raphael's hand. For each of these paintings he received 1200 gold scudi (nearly 500*l.*). They were seriously injured during the plundering of Rome in 1527, but were restored by Carlo Maratta under Clement XI. (comp. also p. liii, and the Plan, p. 289).

I. Stanza dell' Incendio, which we enter first, is the third in chronological order. The frescoes were completed in 1517, but only the Incendio del Borgo was actually executed by Raphael; the others were painted from his designs and under his supervision. — The ceiling-paintings (angels and saints) are by *Perugino*; those on the walls represent scenes from the reigns of Leo III. and Leo IV.

Over the window: 1. OATH OF LEO III., sworn by him in presence of Charlemagne (with the gold chain, his back turned to the spectator), in order to exculpate himself from the accusations brought against him, by *Perino del Vaga*.

To the right of this, on the entrance-wall: 2. VICTORY OF LEO IV. OVER THE SARACENS AT OSTIA, executed by *Giov. da Udine*. The pope is represented as Leo X., accompanied by Card. Julius de' Medici (Clement VII.), Card. Bibbiena, and others. Below: Ferdinand the Catholic, and the Emp. Lothaire.

3. INCENDIO DEL BORGO, conflagration of the Borgo, whence the name of the room.

The apparently ungrateful task of painting a miracle has been executed so happily by the genius of Raphael, that he has presented us with what would be termed in modern language a magnificent genre picture. The traditional incident, — the extinguishing of a fire which had broken out in the Borgo, or Vatican quarter, by the sign of the cross made by Pope Leo IV. (9th cent.) in the Loggia of St. Peter's — is placed in the background. The foreground exhibits the terrors of a conflagration, the efforts of the people to save themselves and their movables, and the half-paralysed

condition especially of the mothers and other women. We are then transported to the heroic age, by a group in the left corner, representing the aged Anchises on the back of Æneas, the classical derivation of which justifies the powerful delineation of the limbs. The *Incendio* is unquestionably the most popular picture of the series, and is well adapted to illustrate the superiority of Raphael's art to that of a later period. The antiquarian will also scan with interest the façade of the old church of St. Peter, represented here as it still existed in Raphael's time.

Below: Godfrey de Bouillon and Aistulf.

4. CORONATION OF CHARLEMAGNE in the old Church of St. Peter. Leo III. has the features of Leo X., and the emperor those of Francis I. of France. Below: Charlemagne.

II. *Stanza della Segnatura*, so named from the fact that the papal indulgences were signed here. The frescoes in this apartment, begun by Raphael in 1508, at the age of 25, were the first works of the master in the Vatican. They were completed in 1511. The sections of the vaulting of the apartment had already been arranged by Sodoma. On the four circular and quadrangular spaces Raphael painted allegorical figures and Biblical and mythological scenes, which in connection with the paintings in the large lunettes are symbolical of the four principal spheres of intellectual life.

Ceiling Paintings. 1. THEOLOGY (*divinarum rerum notitia*), a figure among clouds, in the left hand a book, with the right pointing downwards to the heavenly vision in the *Disputa* beneath; adjacent, the Fall of man; 2. POETRY (*numine afflatur*), crowned with laurels, seated on a marble throne with book and lyre; adjoining it, the Flaying of Marsyas; 3. PHILOSOPHY (*causarum cognitio*), with diadem, two books (*natural* and *moral science*) and a robe emblematical of the four elements; adjoining it, the Study of the heavenly bodies; 4. JUSTICE (*jus suum unicuique tribuit*), with crown, sword, and balance; adjacent, Solomon's Judgment.

Mural Paintings. Under the Theology: 1. THE DISPUTA. This name continues to be applied to this painting, although it is based on a misunderstanding and error. The scene represented is not a dispute about the doctrine of transubstantiation, as commonly supposed, the monstrance with the host on the altar being merely intended as a clue to the nature of the subject, and as a symbol of the church. The scene is rather to be defined as the *Glorification of the Christian Faith*. The congregation gathered round the altar, full of religious emotion, and burning with enthusiasm, see heaven open, disclosing Christ with the heroes of the faith grouped around him. The composition thus consists of two halves, the upper and the lower, whereby not only the heavenward direction of the religious sentiment is clearly indicated, but a definite basis for its formal expression is also obtained. In the UPPER HALF is Christ enthroned, attended by the Madonna and the Baptist; above him

hovers the half-figure of God the Father; and below him is the symbol of the Holy Spirit, at whose side are two angels holding the books of the gospel. A choir of angels forms the background, and angels likewise bear the clouds, on which, a little lower down, the heroes of the Old and New Testament are sitting. These last are arranged alternately, and the heroes of the Old Testament at the same time represent the epochs of the world. To the left of the spectator sit *St. Peter*, *Adam*, *St. John the Evangelist*, *David*, *St. Lawrence*, and a half-concealed personage from the Old Testament (a prophet?); on the right, *St. Paul*, *Abraham*, *St. James*, *Moses*, *St. Stephen*, and lastly an armed hero of the Old Testament. — In the LOWER HALF the four Fathers of the Church, sitting next to the altar, constitute the historical foundation of the picture; to the left *St. Gregory* and *St. Jerome*; on the right *St. Augustine* and *St. Ambrose*. From a very early period attempts have been made to attach historical names to the other figures, which are supposed to be portraits of theologians. Vasari states that they represent SS. *Domenicus* and *Francis*, *Thomas Aquinas*, *Bonaventura*, *Scotus*, and *Nicholas of Lira*. The figure in the antique costume beside *St. Ambrose*, stretching his right hand towards heaven, has been identified with *Petrus Lombardus*, the monk behind *St. Augustine* with *Thomas Aquinas*, the cardinal with *Bonaventura*, and the two popes with *Anacletus* and *Innocent III*. These, however, are mere conjectures; and as Raphael has clothed these figures in an ideal costume, he seems to desire chiefly to emphasize their purely human psychological traits of character. The artist has also shown his independence by introducing several of his contemporaries. To the extreme left, in the background, is *Fra Angelico da Fiesole*, on the right side is the laurel-crowned profile of *Dante*, and, separated from him by an old man, appears the head of *Savonarola*.

In the space below the picture (added by *Perino del Vaga* under Paul III.), from left to right: Heathen sacrifice; *St. Augustine* finding a child attempting to exhaust the sea; the Cumæan Sibyl showing the Madonna to Augustus; allegorical figure of the apprehension of divine things.

Under the Poetry: 2. The PARNASSUS (to the right of the Disputa). — This composition is the most perspicuous of the whole series. The spectator will not fail to appreciate the poetical life and exalted sentiment which pervade the picture, while the impression it conveys is at the same time exceedingly pleasing. Raphael has shown consummate skill in adapting his work to the unfavourable character of the space to be covered. *Apollo* sits under laurels playing the violin. This instrument was not chosen by Raphael from ignorance or for the purpose of paying a compliment to *Giacomo Sansecolo*, a famous violinist of that period, but on the sole ground that the motion of the hand seemed to him easier when playing the violin than the lyre. Around *Apollo* are grouped the

nine *Muses*, forming with him a compact central group. The imposing figure of the blind singer, on the left, next arrests our attention. The tunes of the god have so inspired him, that he begins to sing. Near him are *Dante* and *Virgil*. In the foremost group *Petrarch* and *Sappho* are recognisable, and the front figures in the opposite group are called *Pindar* and *Horace*. The personages behind are evidently contemporaries of Raphael, whose names cannot now be ascertained. — Below, in grisaille: left, Alexander the Great causes the poems of Homer to be placed in the grave of Achilles; right, Augustus prevents the burning of Virgil's *Æneid*.

Under the Philosophy: 3. The so-called SCHOOL OF ATHENS (a name not originally applied to the work), the companion to the Disputa, not only in point of situation, but with respect to its subject likewise. There we are introduced to a congregation of believers, here to an *Assembly of Scholars*. The scene is not divided between heaven and earth, as in the case of the Disputa, but is confined to earth alone; while at the same time, as in the Disputa, a gradation of knowledge, from the imperfect empirical to the perfect and universal, is suggested. A flight of steps leads to an open colonnade, crowned with a dome at the back (supposed to have been designed by Bramante), which forms the most admirable temple of knowledge ever created. Apollo, Minerva, and numerous gods adorn the niches. *Plato* and *Aristotle*, the princes in the realm of thought, whom the Renaissance especially revered, surrounded by a numerous train, approach the steps which descend to the foreground, where, in contrast to the pure philosophers, is a crowd of representatives of the empirical sciences, of geometry, arithmetic, astronomy, and music. Such are the two main contrasts presented by the picture, and with them are combined a gradual raising of the sentiments and aspirations from mere mechanical learning and teaching, copying, meditating, and disputing, to the glorious revelation of the truth, as embodied in the 'divine Plato'. To these general features Raphael imparted the warmth of life and individuality by interweaving with the scene a number of ancient Greek and other personages, in conformity with the prevalent aims of his contemporaries, who were enthusiastic admirers of the antique. He by no means intended, as has been supposed, to give a complete picture of the development of Greek philosophy, but he merely introduced various popular characters of antiquity, with a view to direct the spectator's imagination into the proper channel, and, as it were, to localise a scene which would otherwise have been too general and abstract. Besides *Plato* and *Aristotle*, the masks of the bald *Socrates*, and of *Diogenes* lying on the steps, are unmistakable. *Ptolemy* (who from having been mistaken for one of the kings of that name is furnished with a crown), and *Zoroaster* with the globe in the foremost group on the right, are easily recognised. The names of the other figures are merely conjectural.

The bearded old man in the corner to the left, in profile, is supposed to be *Zeno*, the Stoic; the vine-wreathed figure beside him, holding a book, is perhaps *Epicurus* or *Democritus*. The Oriental, who bends over the writing *Pythagoras*, is *Averrhoes* (or, perhaps, *Hermes Trismegistus*). By the base of a column sits *Empedocles*, who is also looking towards the tablet of *Pythagoras*. The figure resting his foot on a block of marble is either *Anaxagoras* or *Xenocrates*. Lastly, the isolated figure in the foreground, terminating the group to the left, is supposed to be *Heraclitus*. In the Socrates group above is a youthful warrior, representing either *Alcibiades* or *Xenophon*, and the figure behind the warrior, beckoning to Socrates, is said to be *Chrysippus*. No clue, however, has yet been discovered to the names of the figures in the corresponding group to the right, in the upper part of the picture. Raphael has introduced several of his contemporaries into this picture also. Thus, the handsome youth in the foremost group to the left, bears the features of *Francesco Maria della Rovere*, Duke of Urbino; the geometer with the compasses is the portrait of *Bramante*; and the youth bending forward with outstretched arms is Duke *Frederick II. of Mantua*. We are also introduced to the master himself, who enters the assembly from the right, accompanied by his teacher *Perugino*.

Below this picture, in different shades of brown, by *Perino del Vaga* (from left to right): Allegorical figure of Philosophy; Magicians conversing about the heavenly bodies; Siege of Syracuse; Death of Archimedes.

Under the Justice: 4. Over the window the three cardinal virtues: Prudence with double visage looking to the future and the past; right, Moderation; left, Strength. Below, at the side of the window, the administration of ecclesiastical and secular law; right, Gregory IX. (with the features of Julius II.) presenting the Decretals to a jurist (surrounded by numerous portraits; to the left in front Card. de' Medici, afterwards Leo X.). Below (by *Perino del Vaga*): Moses brings the tables of the Law to the Israelites; left, Justinian entrusts the Roman Code to Tribonian. In the space beneath: Solon's address to the Athenian people (?).

III. Stanza d'Eliodoro, the frescoes of which were painted in 1511-14, almost wholly by Raphael's own hand. The advance of the master in technical freedom and precision is easily recognisable in the execution of these paintings.

On the ceiling are four scenes from the Old Testament, probably by *Giul. Romano*, but sadly damaged: Jehovah appears to Noah, Jacob's Vision, Moses at the burning bush, Sacrifice of Isaac.

The Mural Paintings, from the first of which the saloon derives its name, represent the triumph and divine protection of the church, in connection with the age of the warlike Julius II. and the elevation of Leo X. Below the Moses: 1. MIRACULOUS EXPULSION

of HELIODORUS from the Temple at Jerusalem by a heavenly horseman (Maccab. ii, 3), being an allusion to the deliverance of the States of the Church from their enemies. On the right Heliodorus lies on the ground; one of his companions attempts to defend himself, a second shouts, a third is securing his booty; in the background the high-priest Onias praying; to the left in the foreground women and children, and Pope Julius II. on his throne (the foremost of the two chair-bearers is the engraver Marcantonio Raimondi). This composition is remarkable for its vigour of expression.

Below the Sacrifice of Isaac: 2. *THE MASS OF BOLSENA*. An unbelieving priest is convinced of the truth of the doctrine of transubstantiation by the bleeding of the host (comp. p. 66), a miracle which is said to have taken place at Bolsena in 1263; below are women and children; opposite the priest, Julius II. kneeling with calm equanimity; the wrathful cardinal is Riario (founder of the Cancelleria). This work is probably the most perfect of Raphael's frescoes with respect to execution.

Below Noah: 3. *ATTILA REPULSED FROM ROME BY LEO I.*, in allusion to the expulsion of the French from Italy after the battle of Novara in 1513. The pope, with the features of Leo X., is seated on a white mule, around him cardinals and attendants on horseback, above him St. Peter and St. Paul enveloped in a brilliant light, and visible only to Attila and his Huns, who are struck with terror at the apparition. To the right of this —

Below Jacob's Vision: 4. *THE LIBERATION OF PETER*, in three sections. Over the window Peter in the dungeon sleeping between the watchmen and awakened by the angel; right, he is conducted away; left, the watchmen awake.

Under the pictures are painted eleven Caryatides and four *Hermæ* in grisaille. They are symbolical of a life of peace, and bear the distinct impress of Raphael's inventive genius, notwithstanding considerable restoration. The paintings in different shades of brown between these, of similar import with the large figures, have been still more freely retouched.

IV. Sala di Costantino. The pictures of this saloon were executed under Clement VII. (Giulio de' Medici), after Raphael's death, by *Giulio Romano*, aided by *Francesco Penni* and *Raffaello dal Colle*. It has been supposed that the allegorical figures of *Comitas* and *Justice*, in oil, and not 'al fresco' like the rest of the work, were painted by Raphael's own hand; but it appears, from letters of Fra Sebastiano del Piombo (who took an interest in the work after Raphael's death) to Michael Angelo, that one figure only was painted in oil by Raphael's pupils, and that the objects to be depicted were not finally agreed upon at the time of Raphael's death, or, at least, that they underwent many changes during their execution. For some of the pictures, however, particularly for the *Battle of Constantine*, preliminary sketches had been made by Raphael himself.

On the long wall: 1. **BATTLE OF CONSTANTINE** against Maxentius at Ponte Molle, the emperor advancing victoriously, behind him flags with the cross, Maxentius sinking in the river (p. 337), flight and defeat on all sides, painted by *G. Romano*. This fine composition is full of expression and vigour, but the colouring is less successful. — On the left side of the picture Sylvester I. between Faith and Religion; on the right Urban I. between *Justice and Charity.

2. **BAPTISM OF CONSTANTINE** by Sylvester I. (with the features of Clement VII.) in the baptistery of the Lateran, by *Francesco Penni*. To the left of this: Damasus I. between Prudence and Peace; right, Leo I. between Innocence and Truth.

3. (on the window-wall) **ROME PRESENTED BY CONSTANTINE TO SYLVESTER I.**, by *Raffaello dal Colle*; left, Sylvester with Fortitude, right, Gregory VII. (?) with Power (?).

4. **CONSTANTINE'S ADDRESS** to his warriors regarding the victorious omen of the cross, designed by Raphael (?), and executed by *G. Romano*, who added the dwarf (perhaps Gradasso Beretta of Norcia, dwarf of Card. Hippolytus de' Medici) and several other figures. — On the left, St. Peter between the Church and Eternity, right Clement I. between Moderation and *Urbanity. — The scenes below are from the life of Constantine, designed by *G. Romano*.

The **CEILING**, completed under Sixtus V., is adorned with an allegory of the triumph of Christianity over paganism. In the pendentives are Italian landscapes, with corresponding allegorical figures in the lunettes.

One of the custodians of this saloon ($1\frac{1}{2}$ fr.) shows the neighbouring ***Cappella di Niccolò V.**, erected by Nicholas V. and decorated by *Fra Angelico da Fiesole* in 1447 with frescoes from the life of SS. Lawrence and Stephen. They are one of the last and finest works of that master, but were buried in oblivion until restored under Gregory XIII. and Pius VII.

The **UPPER SERIES** represents scenes from the life of St. Stephen: 1. (to the right of the door) Stephen consecrated deacon by Peter; 2. He distributes alms as deacon; 3. He preaches; 4. He is brought before the council at Jerusalem; 5. He is dragged away to his martyrdom; 6. His death by stoning. — **BELOW**, in the same order, scenes from the life of St. Lawrence: 1. Consecrated deacon by Sixtus II.; 2. Sixtus (with the features of Nicholas V. ?) gives him treasures for distribution among the poor; 3. Distribution of the same; 4. The saint is condemned by the emperor; 5. His martyrdom. Also on the wall below: 1. St. Bonaventura, r. St. Johannes Chrysostomus. In the vaulting: 1. St. Augustine, r. St. Gregory. On the lower part of the right wall: 1. St. Athanasius, r. St. Thomas Aquinas. On the vaulting: 1. St. Leo, r. St. Ambrose. On the ceiling the Four Evangelists. Though thus in immediate proximity to the boundless energy of Michael Angelo and the lovely forms of Raphael, the frescoes of the Cappella Niccolina yet hold their ground in virtue of their air of perfect devotion, calm contemplative worship, and prayerful mood. The contrast, in fact, heightens the effect of Fra Angelico's work.

****Raphael's Loggie.** Leaving the Sala di Costantino, we proceed to the second floor of the loggie which enclose the Cortile di S. Damaso (comp. ground-plan, p. 289), the W. (right) wing of

which was embellished with stucco mouldings, painted enrichments, and ceiling-paintings, from designs by *Raphael* and under his superintendence, by *Giulio Romano*, *Giovanni da Udine*, and others of his pupils. The hall was originally open, and the paintings have therefore suffered seriously from exposure to the air, but since 1813 they have been protected by windows of glass. The stucco work and the painted ornamentation are by *Giov. da Udine*, and its style has manifestly been influenced by the antique works of the kind which had been found a short time previously in the *Thermæ of Titus* (p. 237). Amongst the ceiling-paintings after *Raphael's* designs those in the first vault are by *Giulio Romano*, the others by *Franc. Penni*, *Perino del Vaga*, *Polidoro da Caravaggio*, and others. Each of the 13 sections of the vaulting contains four quadrangular frescoes, which are together known as '*Raphael's Bible*'. All these compositions display rare fertility of invention and gracefulness of treatment (20 c. to the custodian who opens the door).

CEILING PAINTINGS. The first twelve vaults contain scenes from the Old, and the thirteenth scenes from the New Testament. We begin to the right of the principal approach, *i. e.* the side opposite the present entrance. Staircase: I. (over the door) 1. Separation of light from darkness; 2. Separation of land from sea; 3. Creation of the sun and moon; 4. Creation of the animals. — II. 4. Creation of Eve; 1. The Fall; 2. Banishment from Paradise; 3. Adam and Eve working (destroyed). — III. 1. Noah building the ark; 2. Deluge; 3. Egress from the ark (destroyed); 4. Noah's sacrifice. — IV. 1. Abraham and Melchisedek; 3. God promises Abraham posterity; 2. Abraham and the three angels; 4. Lot's flight from Sodom. — V. 1. God appears to Isaac; 3. Abimelech sees Isaac caressing Rebecca; 2. Isaac blesses Jacob; 4. Esau and Isaac. — VI. 1. Jacob's vision of the ladder; 2. Jacob and Rachel at the well; 3. Jacob upbraids Laban for having given him Leah (destroyed); 4. Jacob on his journey. — VII. 1. Joseph relates his dream to his brethren; 2. Joseph is sold; 3. Joseph and Potiphar's wife; 4. Joseph interprets Pharaoh's dream. — VIII. 1. Finding of Moses; 2. Moses at the burning bush; 3. Destruction of Pharaoh in the Red Sea; 4. Moses strikes the rock for water. — IX. 1. Moses receiving the tables of the Law; 2. Adoration of the golden calf; Moses breaks the tables; 3. Moses kneels before the pillar of cloud; 4. Moses shows the tables of the Law to the people. — X. 1. The Israelites crossing the Jordan; 2. Fall of Jericho; 3. Joshua bids the sun stand still during the battle with the Ammonites; 4. Joshua and Eleazar dividing Palestine among the twelve tribes. — XI. 1. Samuel anoints David; 2. David and Goliath; 4. David's triumph over the Syrians; 3. David sees Bathsheba. — XII. 1. Zadok anoints Solomon; 2. Solomon's Judgment; 4. The Queen of Sheba; 3. Building of the Temple (destroyed). — XIII. 1. Adoration of the Shepherds (destroyed); 2. The wise men from the East; 3. Baptism of Christ; 4. Last Supper.

Stucco Mouldings. Among these should be particularly noticed the charming small reliefs in the arches of the windows of the first section. Here to the left, above, is perceived *Raphael*, sitting and drawing, with a grinder of colours below him. Lower down are a number of his pupils busied in executing their master's designs, and below them *Fama*, who proclaims the celebrity of the work. On the right an old bricklayer is seen at work, and there is a similar figure in the right curve of the 2nd window, both apparently portraits. The whole affords a charming picture of the life and habits of the artists during the execution of the work.

The decoration of the two other wings of the loggie of this story, with stucco work by *Marco da Fuenza* and *Paul Schor*, and paintings by artists of the 16th and 17th cent., is very inferior to the

above described works of Raphael's period. — Immediately to the left, in the N. (first) wing, is the approach to the picture-gallery; we ascend the stairs, and at the top ring at the door on the left.

The ****Picture Gallery** of the Vatican was founded by Pius VII. by collecting the pictures restored by the French in 1815, most of which had been taken from churches, and by adding others. With the Borghese Gallery, this is the most important collection in Rome, being inferior to that gallery, and to other great Roman private collections in the number of its works alone, while surpassing them in selectness. — Permesse, see p. 124 (fee 1½ fr.). The pictures are not numbered, but are furnished with notices of the subjects and the names of the artists. Catalogue, see p. 287.

I. Room. On the left: *Guercino*, John the Baptist; *Leonardo da Vinci*, St. Jerome, dead-colouring, in shades of brown, evidently a study of strong perspective, probably painted about 1480-83; **Raphael*, Annunciation, Adoration of the Magi, Presentation in the Temple, predelle to the Coronation of Mary in the 3rd Room; *Angel. da Fiesole*, Scenes from the life of St. Nicholas of Bari; *Guercino*, Christ and Thomas; *Giov. Bellini*, M. Magdalene anointing the wounds of the Dead Christ, painted in Mantegna's school, about 1470-80; *Francia*, Madonna with St. Jerome; *Murillo*, Martyrdom of St. Peter Arbues; *Benozzo Gozzoli* (?), Miracles of St. Hyacinth. — Window-wall: *Carlo Crivelli*, Dead Christ with Mary, St. John, and Magdalene; *Garofalo*, Madonna with SS. Joseph and Catharine. — On the entrance-wall: *Murillo*, Adoration of the Shepherds; *Murillo*, Nuptials of the infant Christ with St. Catharine (p. 34); *Perugino*, SS. Benedict, Scholastica, and Placidus; **Fra Angelico*, Small Madonna with angels on a gold ground; **Bonifacio*, Madonna with St. John and St. Catharine, and St. Peter and St. Paul (fine colouring). — Exit-wall: **Raphael*, Faith, Hope, and Charity, three charming female figures, predella of the Entombment in the Pal. Borghese, in grisaille (1507).

II. Room. On the right: **Domenichino*, Communion of St. Jerome, one of his best works (1614). — Opposite the window: ***Raphael*, Madonna of Foligno, 1512; in the background the town of Foligno, into which a bomb falls; to the right, below, St. Jerome recommends to the Madonna Sigismondo Conti, secretary of Julius II., who ordered the painting for S. Maria in Aracœli, whence it was transferred to S. Anna delle Contesse in Foligno in 1565 (comp. p. 210); to the left St. Francis of Assisi, and John the Baptist. 'In its striking vigour, the lifelike individuality of its portraits, and the powerful and delicately-blended colouring the Madonna of Foligno far surpasses all Raphael's earlier oil-paintings'. The transference of the picture from wood to canvas, effected at Paris, to which the picture had been carried during the wars of the Revolution, has necessitated a little restoration. — ***Raphael*, The Transfiguration, his last great work, painted for Card. Giulio de' Medici (afterwards

Clement VII.), and preserved down to 1797 in S. Pietro in Montorio. The upper part is by Raphael's own hand: Christ hovering between Moses and Elias; Peter, James, and John prostrate on the ground, dazzled by the light. The figures, to the left, in an attitude of adoration, are St. Lawrence and St. Stephen. The lower half (much darkened by age), where the other disciples are being requested to heal the possessed boy, was partly executed by Raphael's pupils.

III. Room. On the entrance-wall: **Titian*, 'Madonna of S. Niccolò de' Frari', completed in 1523, and carried in 1770 to Rome, where the rounded upper part of the picture was cut off. The energetic fidelity of the colouring, the dignity of the design and details, and the lofty gravity of the whole composition renders this one of the most important works of the master's middle period. *Guercino*, St. Margaret of Cortona. — Right long-wall: *Spagnoletto*, Martyrdom of St. Lawrence; *Guercino*, M. Magdalene; *Bern. Pinturicchio*, Coronation of the Virgin, painted for the church delle Fratte at Perugia, about 1500; below are the Apostles, St. Francis, St. Bonaventura, and three Franciscans. Then, Resurrection, probably painted by *Raphael* when a youth, from a design of his master *Perugino*; the sleeping soldier to the right is said to be Raphael's own portrait, the one fleeing to the left that of Perugino. Coronation of the Virgin, designed by *Raphael* for the monastery of S. Maria di Monte Luce near Perugia, the upper half painted by *G. Romano*, the lower by *Francesco Penni (il Fattore)* in 1525; *Lo Spagna*, Adoration of the infant Christ (formerly in La Spineta near Todi); **Raphael*, Coronation of the Virgin, painted in 1503 in Perugino's school, for S. Francesco at Perugia; **Perugino*, Madonna on a throne with Laurentius, Ludovicus, Herculanius, and Constantius, the guardian saints of Perugia, painted in 1496; *Sassoferrato*, Madonna. — End-wall: **Caravaggio*, Entombment, one of the ablest works of the Naturalistic School. — Window-wall: **Titian*, Portrait of Nicc. Marcello, Doge of Venice (1473-74), not painted from nature, but full of individuality, and a good specimen of the ugliness which at once repels and attracts the spectator. *Niccolò Alunno*, Crucifixion of Christ and Coronation of the Virgin, two large paintings in several sections. Between these: **Melozzo da Forlì*, Fresco from the former library of the Vatican, representing Sixtus IV. the donor, with Card. Giul. della Rovere (Julius II.) and his nephew Pietro Riario; before him kneels Platina, prefect of the library.

IV. Room. Entrance-wall: *Valentin*, Martyrdom of Processus and Martinianus; *Guido Reni*, Crucifixion of St. Peter; *N. Poussin*, Martyrdom of St. Erasmus. — Right wall: *F. Baroccio*, Annunciation; *A. Sacchi*, Mass of Gregory the Great (there are mosaic copies of these three pictures in St. Peter's); *Baroccio*, St. Michelina. — Window-wall: **Moretto*, Madonna with SS. Jerome and Bartholomew; *Paolo Veronese*, Vision of St. Helena; *Correggio* (?),

Christ in a nimbus. — Left wall: *Guido Reni*, Madonna, with SS. Thomas and Jerome below; *A. Sacchi*, St. Romuald.

Among the treasures of the Vatican, in the domain of painting, must also be reckoned ***Raphael's Tapestry**, exhibited in the *Galleria degli Arazzi*, adjoining the *Gallerie dei Candelabri* (see Pl., p. 314), and now accessible, without special permesso, to visitors to the collections of antiquities. The tapestry was executed from cartoons drawn by *Raphael* in 1515 and 1516, seven of which were purchased in Flanders by Charles I. of England, and are now exhibited in the South Kensington Museum. These designs, derived from the history of the New Testament, are among the most admirable of the great master's works. Each piece of tapestry, wrought at Brussels (not, as formerly supposed, at Arras, the cradle of the handicraft) with great skill in wool, silk, and gold, when complete cost about 700*l*. They were originally intended to cover the lower and unpainted part of the walls in the Sistine Chapel. They are now sadly damaged and faded, especially in the flesh tints. During the siege of Rome in 1527 the tapestry was carried off and seriously injured, but was restored to Julius III. in 1533. In 1798 it fell into the hands of the French, and was sold to a Genoese Jew, from whom it was repurchased by Pius VII. in 1808. The numerous other copies in tapestry of these cartoons, of which the oldest are in Berlin and others in Dresden, Paris, and Vienna, testify to the widespread admiration which they excited.

THE MARGINAL SCENES in bronze-colour partly represent scenes from the life of Leo X. when Cardinal de' Medici. The decorations and arabesques which surround the principal designs are chiefly by Raphael's pupil *Giovanni da Udine*. The following are the PRINCIPAL SCENES. *1st Section*: to the left, *1. The people of Lystra about to offer sacrifice to Paul and Barnabas; *2. Paul preaching; *3. St. Peter receiving the keys; *4. Death of Ananias; to the right, *5. Conversion of St. Paul; *6. St. Peter healing the lame man in the Temple; *7. Miraculous Draught of fishes. — *2nd Section*: to the left, 8. Christ appearing to Mary Magdalene; 9. The supper at Emmaus; 10. Presentation of Christ in the Temple; 11. Adoration of the Shepherds; 12. Ascension; 13. Adoration of the Magi; to the right, *14. Massacre of the Innocents, on three pieces of tapestry; 15. 'Feed my lambs'. — *3rd Section*: to the left, 16. Resurrection; 17. Descent of the Holy Ghost; to the right, *18. Stoning of Stephen; 19. Religion between Justice and Mercy; *20. Paul in prison at Philippi; 21. Elymas struck with blindness; *22. Coronation of the Virgin. Those indicated with asterisks are from the cartoons of Raphael; the others may have been executed from small sketches by the same master, but the designs used by the tapestry-workers are believed to have been drawn by Flemish artists. The pieces of fine early-Flemish tapestry at the end of the first and the beginning of the second section are much superior in technical workmanship to Italian tapestry. The best are the Madonna and Child and several scenes from the Passion.

The gallery of the tapestry is adjoined by the *Galleria Geografica*, a corridor 160 yds. long, with maps designed by the Dominican *Ignazio Dante*, and executed by his brother *Antonio* under Gregory XIII. in 1580; ceiling-paintings by *Tempesta* and others; also a number of ancient busts, some of them valuable.

B. Antiquities.

Museo Pio-Clementino. Museo Chiaramonti. Braccio Nuovo. Egyptian Museum. Etruscan Museum.

(Comp. Plan, pp. 306, 307.)

PERMESSO, see p. 124. CATALOGUE by *Ercole Massi*, 4 fr. (abridgment in English, French, or Italian, 2 fr.).

The VATICAN COLLECTION OF ANTIQUITIES, the finest in the world, was begun by the Popes Julius II., Leo X., Clement VII., and Paul III. in the *Belvedere*, which was erected by *Bramante* under Julius II. and commands a magnificent view of Rome. Here, for example, were preserved the Torso of Hercules, the Apollo Belvedere, and the Laocoon. Clement XIV. (Ganganelli, d. 1774) determined to institute a more extensive collection, in consequence of which the *Museo Pio-Clementino* arose under him and his successor Pius VI. The museum was arranged by the celebrated *E. Q. Visconti*. It was despoiled of its costliest treasures by the French in 1797, but most of these were restored to Pius VII. in 1816 after the Treaty of Paris. Pius VII. extended the collection by adding to it the *Museo Chiaramonti*, and in 1821 the *Braccio Nuovo*; and Gregory XVI. added the *Egyptian* and the *Etruscan Museum*.

The ENTRANCE is on the W. side of the palace, not far from the N.W. corner. Approaching from the Borgo, we cross the Piazza S. Pietro, proceed to the left great flight of steps of St. Peter's through the passage under the portico, walk round the whole of St. Peter's, of the dimensions of which we thus obtain an excellent idea (comp. also plan, p. 278), and then, between the Vatican Gardens (closed) and the palace, reach the gate under the Sala della Biga. (This point may be reached by carriage; so that it is not necessary for visitors to alight in the Piazza of St. Peter, as the drivers sometimes pretend.) We ring at the gate, give up our permesso, and ascend to the *Sala a Croce Greca*, described below. (The glass-door opposite the staircase leads to the *Library*, p. 319.)

**MUSEO PIO-CLEMENTINO. *MUSEO CHIARAMONTI. *BRACCIO NUOVO.

The ***Museo Pio-Clementino*, the real nucleus of the Vatican collection, contains several of the most celebrated antiques. It is divided into 11 departments, denoted by Roman numerals. The main entrance was formerly from the Museo Chiaramonti (p. 311), and the numbering of the sculptures still begins there. According to the present arrangements, as already said, we first enter the —

I. *Sala a Croce Greca*, constructed by *Simonetti*, under Pius VI., in the form of a Greek cross. On the floor are three ancient mosaics. In the centre a head of Pallas, found in 1741 in the Villa Ruffinella, near Frascati. By the steps, between the two sphinxes, *Flower-basket from Roma Vecchia (p. 350). At the entrance to the following room (*Sala Rotonda*, p. 306): Bacchus. We here begin to enumerate the more important sculptures: 559. Augustus; 564. Lucius

Verus. 566. Large sarcophagus in porphyry, of Constantia, daughter of Constantine the Great, from her tomb, afterwards the church of S. Costanza, near S. Agnese (p. 342); it is adorned with vintage-scenes (perhaps in illusion to the Vineyard of the Lord). 567. Priestess of Ceres; 569. Clio; 570. The elder Faustina; *574. Venus, perhaps a copy of the Cnidian Venus of *Praxiteles* (p. xxxii), drapery of metal modern; 578, 579. Egyptian Sphinxes; left, 581. Trajan; 582. Apollo Citharædus, restored as a Muse; 589. Sarcophagus of St. Helena, mother of Constantine, from her tomb near Torre Pignattara (p. 345), transferred to the Lateran by Hadrian IV., and thence to the Vatican by Pius VI.; 592. Augustus. By the stairs: to the right, 600. Recumbent river-god, said to have been restored by Michael Angelo (opposite the entrance to the Egyptian Museum, p. 316).

We now ascend the staircase (with 20 antique columns from Præneste), leading to the right to the —

II. Sala della Biga, a circular hall with a cupola.


In the centre: *623. Biga, or two-horse chariot, from which the saloon derives its name. The body of the chariot, richly adorned with leaves, which was used for centuries as an episcopal throne in S. Marco, and a part of the right horse are alone ancient. *608. Bearded Bacchus, inscribed 'Sardanapallos'; *610. Effeminate Bacchus; 611. Combatant, in the head resembling Alcibiades, and in position a figure of the group of Harmodius and Aristogeiton at Naples; *612. Draped statue, from the Palazzo Giustiniani in Venice; 614. Apollo Citharædus; *615. Discobolus, of the Attic school, perhaps after Alcamenes; 616. Portrait-statue of Phocion, Epaminondas, or Aristomenes (?). *618. Discobolus of *Myron* (p. xxxi); the original was of bronze; head modern, and inaccurately replaced; it should have been turned to the side, as the excellent replica in the Pal. Lancelotti (p. 190) shows. 619. Charioteer; 621. Sarcophagus-relief, race of Pelops and Ctenomachus; 622. Small Diana.

Turning to the right on leaving the Sala della Biga, straight in front of the staircase, we reach the —

III. Galleria dei Candelabri, a corridor 110 yds. in length, divided into 6 sections. The ceiling-paintings, by *L. Seitz* (1883-86), consist partly of incidents in the reign of Leo XIII. and partly of allegorical scenes (Apotheosis of St. Thomas Aquinas; Arts and Sciences under the protection of the church). The handsome marble pavement is quite new.

SECTION I., to the right and left of the entrance: 2, 66. Birds' nests and children; to the right, *19. Boy in a stooping posture, as if reaching after scattered nuts or the like; 31 (to the right) and 35 (to the left), Candelabra from Otricoli, the former with a satyr, Silenus, and a Bacchante, the latter with Apollo, Marsyas, and the Scythian; to the left, 45. Head of a youthful satyr; 52. Sleeping satyr, in green basalt. — SECTION II: to the right, 74. Fountain-figure of Pan, removing a thorn from the foot of a satyr; 81. Diana of Ephesus, from Hadrian's Villa; to the right, 83. Sarcophagus, with the murder of Ægistheus and Clytæmnestra by Orestes; 93 (to the right) and 97 (to the left), Candelabra from S. Costanza; to the left, 104. Ganymede and the eagle; to the left, 113. Sarcophagus-relief

of Protesilaus and Laodameia; 117, 119. Boys with water-vessels (fountain-figures); *113a. Ganymede carried off by the eagle, copy of a celebrated work by *Leochares*. — SECTION III.: to the right, Mosaics of dead fish, dates, etc.; 134a. Circular rim of a fountain (puteal), with Bacchanalian scenes; 134b. Modern work of the same kind. Between the last two, archaic figure of a god, on a basis bearing a dedicatory inscription by Semo Sancus; 135. Sitting statuette of Sophocles; to the left, 140. Socrates; to the left, 141, 153. Bacchus with the panther; 148. Satyr with the infant Bacchus. — SECTION IV.: 157 (to the right) and 219 (to the left), Candelabra from S. Costanza; to the right, 163. Draped statue of a Roman matron; to



eophagus, with Diana and Endymion; to the right, 257. Ganymede; to the left, 264. One of Niobe's children; to the left, 269. Sarcophagus, with the rape of the daughters of Leucippus by the Dioscuri. Upon the last, statue of a fighting Gaul, from the trophy of King Attalus on the Acropolis at Athens (p. xxxiii). — The next gallery contains the Tapestry of Raphael, p. 303.

We now descend and return to the Sala a Croce Greca, and pass through it (comp. ground-plan, p. 307) to the —

IV. Sala Rotonda, erected under Pius VI. by *Simonetti*, after the model of the Pantheon. The floor contains an admirable **Mosaic*, found in 1780 in the Thermæ at Otricoli, with Nereids, Tritons, Centaurs, and masks. In the centre a magnificent basin of porphyry from the Baths of Diocletian. On the right and left of the entrance: 554. Julia Domna, wife of Septimius Severus; 553. Plotina, wife of Trajan. Then, to the left, 552. *Juno Sospita*, from Lanuvium (p. 382), copy of an ancient Latin image made in the age of the Antonines; 551. Claudius; 550. Statue of Claudius as Jupiter, found in 1865 at Cività Lavinia, the ancient Lanuvium (p. 382); 549. Jupiter Serapis; 548. Nerva, on the pedestal a fine relief, but of doubtful meaning; 547. Sea-god, found near Pozzuoli, perhaps a personification of the Bay of Naples or the Mediterranean Sea, the ornaments of leaves and fruits indicating the riches of the shores; *546. So-called *Barberini Juno*; 545. Bust of Antinous; 544. Hercules, colossal statue in gilded bronze (12 ft. in height), found in 1864 in the foundations of the Pal. Righetti, near the theatre of Pompey (p. 205); 543. Colossal head of Hadrian, from that emperor's mausoleum (Castello S. Angelo; comp. p. 275); *542. Female statue restored as Ceres; 541. Faustina, wife of Antoninus Pius. 540. Antinous as Bacchus, from Hadrian's Prænestine villa (p. 384; 'Antinous Braschi'); the unchiselled state of the body seems to indicate that the statue was originally draped, perhaps with metal; the present drapery, however, is modern. **539. *Bust of Zeus from Otricoli*, the finest and most celebrated extant, formerly regarded as a faithful reproduction of the Zeus of Phidias, whereas, according to modern critics, the head is a modification of the Lysippus type. Then, 556. Pertinax; 555. Genius of Augustus. — In the spaces between the above sculptures are a number of excellent Greek portrait-heads, removed from the next room: 510. Alcibiades; 512. Sleeping Epimenides; 514. Socrates; 518. Themistocles (?); 519. Zeno, the Eleatic; 521. Euripides. Opposite: 498. Epicurus; 500. Zeno, the Stoic; 502. Æschines, the orator; 506. Demosthenes; 507. Antisthenes, the Cynic; 509. Metrodorus, the Epicurean. At the entrance to the next room: 537, 538. Tragedy, Comedy, two hermæ from Hadrian's Villa. — In the passage to the next room: 533. Minerva; 535. Mnemosyne, mother of the Muses. We next enter the —

V. Sala delle Muse. We first enter an *Ante-Room*: (left) *525. Pericles; 524. Sappho (?); 523. Aspasia. so-called from the modern

inscription on the base. Right: 531. Periander of Corinth; 530. Lycurgus (?); 528. Bias, the misanthrope of the Seven Wise Men.

The magnificent Sala itself, also constructed by *Simonetti* under Pius VI., is octagonal in form, covered with a dome, and adorned with sixteen columns of Carrara marble. It derives its name from the statues of the Muses preserved here, which, with the exception of Nos. 504, 520, were found with the Apollo at Tivoli in 1774. In the centre of the right wall: *516. *Apollo Musagetes*, in a long robe, with an air of poetic rapture, standing on an altar with a representation of the Lares. To the right of the Apollo: 515. *Calliope* (Muse of epic poetry); 511. *Terpsichore* (dancing); to the left, 517. *Erato* (erotic poetry); 520. *Euterpe* (music). Then, on the other side: 499. *Melpomene* (tragedy); 503. *Thalia* (comedy); 504. *Urania* (astronomy); 505. *Clio* (history); 508. *Polyhymnia* (higher lyric poetry).

Ante-Room on the other side, forming also the ante-room of the Sala degli Animali: (right) 494. Greek portrait-herma; 495. Bacchus in female attire; 496. Herma of Hesiod. Above: 493. Relief of the birth of Bacchus. Left side: 492. Herma of Sophocles, the only one authenticated by an inscription (mutilated); 491. Silenus; 490. Herma of Diogenes. Above: 489. Dance of the Corybantes.

VI. Sala degli Animali, containing a number of animal-pieces in white and coloured marble, most of them modern or freely restored; a great part of the floor is paved with ancient mosaics.

This hall is divided into two sections by means of four granite columns, which form a passage from the Sala delle Muse into the court of the Belvedere (p. 309). To the RIGHT: 194. Sow and litter; 202. Colossal camel's head as the aperture of a fountain; 208. Hercules with Geryon; 210. Diana, badly restored; 213. Hercules and Cerberus; 220. Bacchanalian genius on a lion; 228. Triton carrying off a nymph. Below, on an oval sarcophagus-cover, triumphal procession of Bacchus; 232. Minotaur.

To the LEFT: 116. Two greyhounds playing; 134a, 125a. Mosaics from Hadrian's Villa; 124. Sacrifice to Mithras; 134. Hercules with the slain Nemean lion; 137. Hercules slaying Diomedes; 138. Centaur with a Cupid on his back. (Adjacent is the entrance to the Galleria delle Statue, see below.) 139. Commodus on horseback (Bernini's model for the statue of Constantine in the Portico of St. Peter's); 151. Sheep sacrificed on the altar; 153. Small group of a goat-herd and his goats; 157. (in the next window) Relief of a cow and calf.

VII. Galleria delle Statue, originally a summer-house of Innocent VIII., and converted into a museum by Clement XIV. and Pius VI. The lunettes contain remains of paintings by *Pinturicchio*. — To the right of the entrance: 248. Clodius Albinus, the opponent of Septimius Severus. The statue stands on an interesting cippus of travertine (found in 1777 not far from the mausoleum of Augustus, near S. Carlo al Corso), which marked the spot where the body of Caius, son of Germanicus, was burned. *250. *Eros of Praxiteles* ('*Il Genio del Vaticano*', p. xxxii), found near Centocelle on the Via Labicana; on the back are traces of wings; above it, 249. Relief, attributed to *Mich. Angelo*: Cosimo I. aiding Pisa; 251. So-called Doryphorus; *253. Triton, upper part only, found

near Tivoli; 255. Paris, copied from a fine original; 256. Youthful Hercules; 257. Diana (relief); 258. Bacchus; 259. Figure with male torso, probably Apollo, incorrectly restored as Pallas (so-called Minerva Pacifera) with the olive-branch; 260. Greek tomb-relief; *261. Mourning Penelope, an imitation of the more ancient style, on the pedestal a relief of Bacchus and Ariadne; 263. Relief of a female figure in a quadriga; 264. *Apollo Sauroctonus*, lying in wait for a lizard, after a bronze statue by *Praxiteles*; *265. *Amazon*, from the Villa Mattei; 267. Drunken satyr; 268. Juno, from the *Thermæ of Otricoli*; 269. Relief, Jason and Medea (?); 270. *Urania*, from Tivoli, freely restored; *271. and 390. (one on each side of the arch which leads into the room of the busts) *Posidippus* and *Menander*, two admirable portrait-statues of these comic dramatists, in Pentelic marble, perhaps original works of *Cephisodotus*, son of *Praxiteles* (p. xxxii), from the theatre at Athens, found at Rome under Sixtus V. near S. Lorenzo in Panisperna, where they were long revered as saints. — The visitor may conveniently quit this gallery here and inspect that of the busts (see below).

Window-wall, beyond the *Menander*: 392. *Septimius Severus*; 393. Girl imploring protection, erroneously regarded as a *Dido*, the original in the *Pal. Barberini* (p. 171); 394. *Neptune Verospi*; 395. *Apollo Citharædus*, archaic; 396. Wounded *Adonis* (the hand, of which there are traces was probably that of a *Cupid* dressing the wound); 397. Reclining *Bacchus* from the Villa of *Hadrian*; 398. *Macrinus*, successor of *Caracalla*. In front of it, in the centre, a large alabaster basin, found near SS. *Apostoli*. 399. *Æsculapius* and *Hygieia*, from *Palestrina*; 400. *Enterpe*; 401. Mutilated pair from the group of *Niobe* (p. xxxii), a son and a daughter, found, like the Florentine statues, near the *Lateran*; 405. Nymph; 406. Replica of the *Satyr* of *Praxiteles*. — In the window-niche: 421. Cinerary urn of oriental alabaster, found with the travertine cippi placed under the statues numbered 248, 408, 410, 417, and 420; it once contained the remains of a member of the imperial Julian family. End-wall: *414. *Sleeping Ariadne*, formerly taken for *Cleopatra*, found in the reign of *Julius II.*; below it, **Sarcophagus* with battle of the giants, resembling the *Pergamenian Ara*. At the sides: *412, 413. The *Barberini Candelabra*, the largest and finest in existence, found in *Hadrian's villa*; on each three reliefs, (l.) *Jupiter*, *Juno*, *Mercury*, and (r.) *Mars*, *Minerva*, and *Venus*. 416. Relief of the forsaken *Ariadne*, similar in expression to the large statue; 417. *Mercury*; 420. *Lucius Verus*.

VIII. Hall of the Busts, in four sections. We begin on the right. I. Section. Above, 173. Head of *Hadrian*; 278. *Nero* as *Apollo Citharædus*, with laurel-wreath; 281. *Augustus*, with chaplet of ears of corn. Below, 290. *Caracalla*. — II. Above, *298. *Zeus Scrapis*, in basalt. Below, 303. *Apollo*; *307. *Saturn*; 308. *Isis*; *311. Head of *Menelaus*. from the group of *Menelaus* with the body of

Patroclus (or Ajax with the body of Achilles), found in 1772 in the Villa of Hadrian, a duplicate of the Pasquino group (see p. 201); *384b. Legs of the body by the window of the first section; 346. Hercules. — III. Above, 313, 314. Masks; 315, 316. Satyrs. In the central niche: *Zeus, formerly in the Pal. Verospi. To the left above, 329. Barbarian; below, 338. Hermes (holes for the wings near the head). — IV. In the niche: 352. Woman praying, a so-called Pietà; under it an interesting sarcophagus, adorned with Prometheus and the Fates, perhaps of Christian workmanship; to the left, below, 357. Antinous; 363. Hera, a poor replica of that by Polycletus. — In Section I., below, 376. Head of Pallas from the Castle of St. Angelo; 382, 384. Anatomical representations, in marble. In the centre, Candelabrum with three female figures. By the entrance, r. *388. Roman man and woman, tomb-relief (Niebuhr's favourite group, copied on his tomb at Bonn by Rauch).

IX. Gabinetto delle Maschere, so-called from the **Mosaic* on the floor, adorned with masks, etc., found in Hadrian's Villa in 1780 (usually closed; apply to custodian of the Galleria delle Statue; 20 c.). On the right of the entrance: *425. Dancing girl, in Pentelic marble, found at Naples; Relief, called the apotheosis of Hadrian; 427. Stooping Venus in the bath; 429. Venus Genetrix. — Wall opposite the entrance: Four reliefs of the exploits of Hercules; 432. Satyr in rosso antico, replica in the Capitoline; 435. Venus drying her hair. — Window-wall: at the first window, Bathing-chair, at the second, Vase, both of rosso antico; between the windows, Venus, resembling No. 435. — In the window: Relief of Bacchanalian procession. — Entrance-wall: 442. Apollo. — A door (which the custodian opens if desired) leads hence to the LOGGIA SCOPERTA, which commands a charming view of Mte. Mario and Soracte to the left, and the Sabine Mts. to the right.

We now return to the Sala degli Animali, and enter the (left) —

X. Cortile del Belvedere (comp. ground-plan, p. 307), an octagonal court constructed by *Bramante*, but afterwards altered. It is surrounded by arcades, in the corners of which are four apartments containing several of the most important works in the collection. The entrance is flanked with two **Molossian Hounds*. In the centre is a fountain with ancient embouchure; above the arcades are eight ancient masks, and by the wall eight sarcophagi and sixteen statues.

The First Corner Cabinet on the right as we enter from the Sala degli Animali contains: **74. The famous group of *Laocoon*, with his two sons, strangled by serpents by command of the offended Apollo. According to Pliny, it was executed by the three Rhodians *Agesander*, *Polydorus*, and *Athenodorus*, and was placed in the palace of Titus. It was discovered under Julius II. in 1506 near the Sette Sale (p. 182), and was termed by Michael Angelo a 'marvel of art'. The work (in Pentelic marble, but not of a single block) is admirably preserved, with the exception of the three uplifted

arms, which have been incorrectly restored by *Giov. da Montorsoli*. Owing to the delicacy of the workmanship, the dramatic suspense of the moment, and the profoundly expressive attitudes of the heads, especially that of the father, this group forms the grandest representative of the Rhodian school of art (p. xxxiv). — Then, in the Arcade: 79. Relief of Hercules with Telephus, and Bacchus leaning on a Satyr; 80. Sarcophagus with Cupids; 81. Sacrificial procession after a victory. In the niche: *85. Hygieia; 88. Roma, accompanying a victorious emperor, probably relief from a triumphal arch.

Second Corner Cabinet. **92. *Apollo Belvedere*, found at the end of the 15th cent. near Porto d'Anzio, the ancient Antium. According to the most recent interpretation, the god, whose left hand has been restored, originally held in it, not the bow, but the ægis (as has been discovered from comparison with a bronze at St. Petersburg), with which he is supposed to be in the act of striking terror into the Celts who have dared to attack his sanctuary of Delphi. (Comp. 'Childe Harold's Pilgrimage', Canto iv, line 161.) On the left: 94. Relief, Women leading a bull to the sacrifice (the left half entirely modern). — Then, in the Arcade: 27. Reliefs with Satyrs and griffins, once forming a trapezophorus (support of a table). 28. Large sarcophagus with dancing satyrs and Bacchantes, found in 1777 while the foundations for the sacristy of St. Peter's were being laid; 30. Sleeping nymph, a fountain-figure. Two baths of black and green basalt.

Third Corner Cabinet. Perseus, and two Pugilists, by *Canova*, formerly much overrated. — In the Arcade: (right) In the small niches: 34. Mercury; 35. Minerva. Then, 37. Sarcophagus with Bacchus and Ariadne in Naxos; to the right, 38. Relief of Diana and Ceres contending with the Titans and Giants, found in the Villa Mattei; to the left, 44. So-called *Ara Casali*, with reliefs relating to the origin of Rome; 49. Sarcophagus with battle of Amazons, in the centre Achilles and Penthesilea, bearing the features of the deceased (p. xlii).

Fourth Corner Cabinet. *53. *Mercury*, formerly regarded as an Antinous; 1. 55. Relief of a procession of priests of Isis. — Then in the Arcade: (right) 61. Sarcophagus with Nereids with the arms of Achilles; on it the *Torso of a Nereid. — We next enter the —

XI. Vestibule of the Belvedere (comp. ground-plan, p. 307), forming an approach to the Museo Pio-Clementino, which was formerly entered in this direction. The first section of it is the —

ATRIO ROTONDO. In the centre a *Basin of marble (pavonaz-zetto). To the left, under No. 7, is a cippus with relief of a Diadumenus, or youth placing a fillet round his head, which conveys an idea of the famous statue of *Polyclethus* (p. xxxi). On the balcony is an ancient *Vane, found in 1779 near the Colosseum. — To the left is the —

ATRIO DEL MELEAGRO. In the centre a *Statue of Meleager, of

the imperial period, found about 1500 outside the Porta Portese. Left, 21. Colossal bust of Trajan; above it a late relief, showing the decline of art. — We now return through the Atrio Rotondo to the —

ATRIO QUADRATO. In the centre of the first hall is the celebrated **Torso of Hercules*, executed, according to the inscription, by *Apollonius* of Athens, who probably lived in the 1st cent. B.C.; it was found in the 16th cent. near the theatre of Pompey (p. 205). 'In their admiration of the torso, which has been extolled by Winckelmann in one of his famous odes, all critics are agreed; but many conflicting opinions have been expressed regarding the action intended to be portrayed. Formerly it was usually supposed that Hercules had been grouped with a figure standing in front of him (perhaps Hebe or Auge); another conjecture was that he stood alone, leaning on a staff grasped with both hands on his left side; while the most recent view is that he was playing on the lyre'. — Opposite the window is the **Sarcophagus of L. Corn. Scipio Barbatus*, great-grandfather of the illustrious Africanus, and consul B.C. 298, of peperine-stone, with a remarkable inscription in Saturnine verse, recording his virtues and achievements; it was found in 1780 in the tomb of the Scipios on the Via Appia (see p. 257), at the same time as that of his son L. Corn. Scipio, consul B.C. 259, and that of P. Corn. Scipio (son of Africanus), flamen dialis, whose inscriptions are built into the surrounding walls. The bust on the sarcophagus has been groundlessly regarded as the poet Ennius.

We next enter (comp. ground-plan, p. 306) the —

***Museo Chiaramonti**, arranged in one half of a corridor 22 ft. wide and 310 yds. long, which is divided by pilasters into thirty sections numbered with Roman numerals. The museum contains 300 sculptures in marble, many of them small and fragmentary.

[The door to the right leads to the *Giardino della Pigna*, to which visitors are not now admitted, containing numerous fragments of statues and reliefs. In the middle is a huge antique column, surmounted by a bronze statue of St. Peter, erected here in 1886 to commemorate the Council of 1870. On the right are a colossal *Pine-cone*, the work of a certain P. Cincius Salvius, which was placed in the middle ages in the fore-court of old St. Peter's Church, and the pedestal of the column in honour of Antoninus Pius, which stood near Monte Citorio, adorned with the Apotheosis of Antoninus and Faustina and processions of warriors. On the left is a colossal portrait-head in marble. — '*Il Boscareccio*', or the larger Garden of the Vatican, which was formerly sometimes visited hence, but is now closed to the public, extends from the Belvedere to the walls of the Leonine city, and is beautifully laid out in the Italian style. To the left of the entrance, at the base of an eminence planted with trees, stands the *Casino del Papa*, built by *Pirro Ligorio* in 1560, a garden-house richly decorated with sculptures, mosaics, and pictures.]

As the entrance was formerly at the other end, our enumeration now begins with Section XXX. Left: 733. Recumbent Hercules (freely restored). — XXIX. Left: 704. Ulysses handing the goblet to Polyphemos; 698. Cicero, from *Roma Vecchia*; 693. Wreathed head of the young Bacchus. — XXVIII. Left: 682. Colossal statue of Antoninus Pius, from Hadrian's Villa at Tivoli. — XXVII. Left:

655. Narcissus (erroneously restored); above, *644. Relief, dancing women. — XXVI. Left: 636. Hercules and Telephus. — XXV. Left: *607. Head of Neptune in Pentelie marble, from Ostia. — XXIV. Right: 591. Claudius; left, 589. Mercury; 588. Bacchus with a satyr; 587. Ganymede. — XXIII. Left: 563. Portrait-bust; above, 550. Square marble slab, with a shield of Medusa in the centre. — XXII. Right: 547. Isis; left, 544. Silenus. — XXI. Left: *513 A. Head of Venus in Greek marble, found in the Baths of Diocletian; 512. Marius (?); 510 A. Cato Major (?). — XX. Right: 497. Representation of a mill; *498. Drowsy spinster; left, *495. Bow-bending Cupid; *494. *Tiberius*, a colossal sitting figure, found in 1796 at Piperno; 493. Portrait-statue of a boy. — XIX. *729. Torso of an archaic [Penelope in a sitting posture, of finer workmanship than the better preserved statue in the Galleria delle Statue. — XVIII. Left: 450. Mercury; right, 453. Hero, restored as an emperor, with Victoria. — XVII. Right: 441. Alcibiades (?); left, 422. Demosthenes; 420. Head of Vulcan; 418. Julia, daughter of Augustus (?); *416. *Bust of the young Augustus*. — XVI. Left: 401. Augustus, 400. Tiberius sitting, both from Veii. — XV. Right: 392. Hadrian; left, *372 A. Greek relief with fragment of a rider; 369. Portrait-head; above, 360. Archaic relief, representing three draped Graces, a copy of a very famous antique work by *Socrates* (p. xxxviii), fragments of which were found in the Acropolis at Athens. — XIV. Left: 354. Minerva; 353. Nymph; right, 355, 357. Women of the family of the Rutilii, found at Tusculum; 356. Captured barbarian. — XIII. Right: 338. Boy from a group of talus-players; left, above, 300. Fragment of a shield with four Amazons, being a copy of the shield of Athene Parthenos by *Phidias*. — XII. Left: 294. Hercules, found in 1802, restored by Canova; 295. Torso, replica of the Hermes of Praxiteles; right, 296, 297. Athletes; 298. Bacchus. — XI. Right: 285. Apollo with the hind, in imitation of the archaic style; 287. Fisher-boy; left, 263, 259. Fine portrait-heads; 255. Jupiter Serapis; 254. Venus. — X. Right: 244. Colossal mask of Oceanus, used to adorn a fountain; 245. Polyhymnia; left, 241. Nymph with the infant Zeus at her breast. — IX. Right: *229. Two heads of Silenus as a double herma; under it, 230. Large cippus, Night with Death and Sleep (?); left, 197. Head of Roma (eyes modern), found at the ancient Laurentum; above, 186. Greek equestrian relief. — VIII. Right: 179. Sarcophagus of C. Julius Euhodus and Metilia Acte, with representation of the myth of Alcestis; 181. Hecate; under it, *182. Ara of Pentelie marble, with Venus and Bacchalian representations; left, **176. *Daughter of Niobe* (p. xxxii), headless, found at Tivoli, an admirable Greek work. — VII. Right, 166. Archaic Apollo; left, 144. Bearded Bacchus; above, 130. Fragment of a relief, badly executed, but with an interesting representation of the Sun and Moon as leaders of souls. — VI. Left: 122.

Diana; 121. Clio; 120. So-called Vestal, from Hadrian's Villa. — V. Right: 107. Julius Cæsar (?). — IV. Left: 63. Minerva. — III. Right: 55. Torso of Hebe; left, 29. Head of a female faun; 28. Head of a wounded Amazon. — II. Left: 16, 14. Muses. — I. Right: 13. Winter, from the sarcophagus of P. Ælius Verus; left, 6. Autumn, also from a sarcophagus; above, 2. Apollo sitting, a relief. — To the right is the entrance to the Braccio Nuovo (see below).

[The S. half of the corridor, separated from the Museo Chiaramonti by a railing, contains the GALLERIA LAPIDARIA, which is not now open to the public. It contains a collection of more than 5000 heathen and early Christian inscriptions, made by Clement XIV. and Pius VI., and extended by Pius VII.; they were arranged and built into the walls under the direction of *Gaetano Marini*, the learned founder of the modern science of Latin epigraphy. The gallery also contains ancient cippi, sarcophagi, and statues.]

The ***Braccio Nuovo**, which we next visit (see ground-plan), was constructed by *Rafael Stern* under Paul VII. in 1821. This saloon, roofed with tunnel vaulting, and lighted from above, is 77 yds. long and $8\frac{1}{2}$ yds. wide, and is embellished with fourteen ancient columns of cipollino, giallo antico, alabaster, and Egyptian granite. It contains 40 statues and about 80 busts. — Right: No. *5. Caryatide, supposed to be one of those executed by Diogenes for the Pantheon, restored by Thorvaldsen; 8. Commodus in hunting-costume with spear; 9. Barbarian head; 11. Silenus with the infant Bacchus; *14. *Augustus*, found in 1863 near Prima Porta in the villa of Livia, one of the best statues of the emperor, bearing distinct traces of painting (p. xxxviii). In front of it, on the ground, a mosaic from Tor-Marancia, Ulysses with Nereids and Scylla; 17. Statue of a physician (perhaps Antonius Musa, celebrated for his cure of Augustus), under the form of Æsculapius; 20. So-called Nerva (head modern); *23. So-called Pudicitia, from the Villa Mattei, head and right hand new; 24. So-called Pollux, in coloured marble; 26. Titus, found with the statue of his daughter Julia (No. 111, opposite) near the Lateran in 1828; 27. Medusa (also Nos. 40, 93, 110; the last in plaster) from Hadrian's temple of Venus and Roma; 31. Priestess of Isis; 32, 33. Satyrs sitting; 39. (in the centre) beautiful black vase of basalt, with masks, etc.; 41. Apollo Citharæus, found in 1885 at Marino; 44. Wounded Amazon; 47. Caryatide; 48. Trajan; 50. Diana beholding the sleeping Endymion; 53. Euripides; 60. So-called Sulla; *62. Demosthenes, found near the ancient Tusculum. Standing alone: **67. *Apoxyomenos* (scraper), an athlete cleaning his right arm with a scraping-iron, after *Lysippus* (p. xxxiii), found at Trastevere in 1849. — Then, by the second long wall: *71. *Mourning Amazon*, apparently after an older work of the best period, perhaps by *Polyclethus* (p. xxxi), arms and feet restored by Thorvaldsen; 81. Hadrian; 83. Juno, erroneously restored as Ceres (head new); 86. Fortuna with cornucopia and rudder, from Ostia; *89. So-called Hesiod. *109. *Colossal Group of the Nile*, surrounded by sixteen playing children, emblematic of the sixteen cubits which

the river rises; at the back and sides of the plinth a humorous representation of a battle of the pygmies with crocodiles and hippopotami, found near S. Maria sopra Minerva in the time of Leo X. (p. xxxiv). In the semicircular space behind it, on the right: *94. Figure of Spes, erroneously restored as Proserpine; 97A. Mark Antony; 97, 99, 101, 103, 105. Athletes; 106. Bust of the triumvir Lepidus. On the ground in this semicircle (behind the Nile) is a mosaic with the Ephesian Diana, from Poggio Mirteto. By the long wall, farther on: 111. Julia, daughter of Titus (see No. 26); *112. Head of Juno (the so-called Juno Pentini); *114. So-called *Minerva Medica*, or Pallas Giustiniani (the family to whom it formerly belonged), in Parian marble; 117. Claudius; *120. *Satyr Reposing*, after a celebrated work of *Praxiteles* (p. xxxii; a better copy in the Capitoline Museum); 123. Lucius Verus; *126. Athlete, recognised as a copy of the *Doryphorus* of *Polycleetus* (p. xxxi); 129. Domitian; *132. Mercury, restored by Canova (head ancient, but belonging to a different figure).

EGYPTIAN MUSEUM. *ETRUSCAN MUSEUM.

Open on Thurs., 9-3. Comp. Plan, p. 307.

The **Egyptian Museum** (*Museo Egizio*), the entrance to which is from the Sala a Croce Greca (p. 304), close to the steps, is below the Etruscan Museum, in the so-called *Torre de' Venti*. Pius VII. purchased the nucleus of the collection from Andrea Gaddi; and the museum was much extended by him and by Gregory XVI. It contains few objects of great interest, but may be visited for the sake of comparing Egyptian with Hellenic and Italian art (p. xl).

1st Room: Three coffins of mummies in green basalt, and two in painted wood. — 2nd R.: Statues, chiefly from Hadrian's villa at Tivoli, of Roman workmanship in the Egyptian style (p. xxxvii). *Colossal statue of Antinous, the favourite of Hadrian, in white marble. The Nile, in black marble. Fine architectural fragments, found in the precincts of the Iseum, or temple of Isis, near S. Maria sopra Minerva. — 3rd R.: *Egyptian colossal statues: (1) Mother of Ramses (Sesostris), in black granite, between (2) two lions of basalt, from the Thermæ of Agrippa, which formerly long adorned the Fontana di Termini; (3) by the exit-wall, in the centre: Ptolemy Philadelphus, to the left of him, his Queen Arsinoë, in red granite (from the gardens of Sallust). — 4th R.: Statuettes, idols, and alabaster vases. — 5th R.: Mummies, sarcophagi. Eight statues of the goddess Pasht (Isis), from the ruins of Carnac. — 6th R.: Small idols in vitreous paste. — 7th R.: Small bronzes, including a situla, or bucket-shaped vessel, used in the worship of Isis. — 8th R.: Idols and ornaments; scarabæes (stones cut in the shape of beetles), etc. — 9th R.: Papyrus MSS. — 10th R.: Coptic inscriptions, hieroglyphics, cuneiform inscriptions. Small replica of the Nile in the Braccio Nuovo (p. 315). Model of a pyramid.

Ascending as indicated at p. 305 to the passage into which the *Sala della Biga* and the *Sala dei Candelabri* (p. 305) open, and turning to the left, up a few steps, we reach on the right the entrance to the Etruscan Museum. — Comp. Ground-plan, p. 307.

The ***Museo Etrusco-Gregoriano**, founded by Gregory XVI. in 1836, occupies twelve rooms on the upper floor of the *Torre de'*

Venti, above the Egyptian Museum. It contains a number of antiquities excavated chiefly in 1828-36 in the Etruscan cities Vulci, Toscanella, and Chiusi, consisting of statues, paintings, vases, golden ornaments, and various domestic utensils in bronze, all extremely interesting as a link in the history of Italian art, and affording some insight into the habits of the almost pre-historic Etruscans (p. xl).

(To the left by the loggia, in the space before the door, is a relief of Medea; right, by the door, another with a contest of Hereules.)

I. Room: Three sarcophagi of terracotta with lifesize figures of the deceased on the covers. On the walls numerous portrait-heads in terracotta, of peculiar formation. — The II. Room is then entered to the right. One of the larger sarcophagi on the left is of travertine, adorned with an almost flat relief of a chariot with a bearded man and musicians, on which traces of painting are visible; numerous smaller cinerary urns, some of them of alabaster with mythological reliefs, from Chiusi and Volterra. — III. Room: In the centre a large sarcophagus of tufa with recumbent figure and reliefs of the murder of Clytemnestra, sacrifice of Iphigeneia, Eteocles and Polynices, Telephus and Orestes. Beyond this is a fine frieze in terracotta, discovered at Cervetri. In the corners are small and strange-looking cinerary urns in the form of houses and huts, found in the very ancient Italic (Latin) graves between Albano and Marino, some, it is said, under a layer of volcanic tufa. — IV. Room; left wall, near the entrance, fine terracotta frieze from Cervetri; relief in stucco of Jupiter, Neptune, and Pluto. Terracottas; *Mercury; in the corners, fragments of female figures with rich drapery, from Tivoli; Hercules; above, lid of an urn, with the dying Adonis, an interesting realistic work; on the wall to the right, reliefs in stucco of Venus and Adonis; on the walls reliefs, cinerary urns, architectural fragments. By the window small terracottas.

The next four rooms contain the **Collection of Vases** (p. xl). These painted vessels were partly imported from Greece, partly manufactured in Etruria itself, where Vulci, Chiusi, Volterra, Bomarzo, etc., are proved to have excelled in this branch of art. The Etruscans imitated the earlier Greek vases with black, as well as the later with red figures, often without a just appreciation of the subjects, and with an obvious preference for tragic scenes, especially murders. An exhaustive examination of the details will be undertaken by the scientific only; the most interesting objects only need be enumerated here. — I. Room: Vases of the earliest style, with figures in black, some of them from Corinth; in the centre a very ancient vessel with representations of animals. — II. Room: In the middle, Ajax with the body of Patroclus; *Achilles and Ajax playing at draughts (with the name of the manufacturer *Exekias*). To the right of the window-wall are imitations of the prize-vases of the Panathenæan Festival at Athens; under the 2nd window, two basins with archaic Latin inscriptions. At the door, a vase (No. 70) with two men with oil-vessels and the inscriptions: 'O Father Zeus, would that I were rich', and: 'It is already full and even runs over'. — III. Room: Arched corridor. *134. Hector parting from Priam and Hecuba. At the first window, Vase with three handles, with representations of a poet and six Muses. To the left, on the wall, a number of excellent vases with red figures, including *84. Vase with admirably-drawn figure of *Achilles, the pendant to which is effaced beyond recognition (*Briseis*?); 93. Minerva and Hercules (Vulci); 97. Apollo on a winged tripod. To the right, at the centre window, *103. Large vase, with whitish ground and coloured designs, representing the delivery of the infant Bacchus to Silenus; on the reverse, musicians. In the niche to the left are large vases from S. Italy, with polychrome ornamentation in gold, white, and violet. Adjacent a humorous representation of Jupiter and Mercury's visit to Alcmena. Near the exit, a vase with ancient fracture and repairs. — The IV. Room contains a large collection of graceful and delicately painted goblets. The cabinet contains small vases, some of them of irregular form. On the wall above are copies of paintings in a tomb at Vulci, showing that Etruscan art was at this period completely Hellenised. Below, as the imperfectly-interpreted inscriptions

appear to indicate, is a historical scene, an adventure of Mastarna (Servius Tullius) and Caelius Vibenna, besides mythological representations (Cassandra, Achilles slaying the victim for the funeral sacrifice of Patroclus). The glass-cases contain ancient glass vessels, many of which are noticeable for their fine workmanship and colouring.

We now return to the sixth room, in order thence to reach the — IX. Room on the right, where **Bronzes** of every description, domestic utensils, weapons, ornaments, jewellery, etc., are arranged. By the wall to the right the statue of a warrior, with Umbrian inscription, found at Todi in 1835. On the wall as far as the window, helmets, shields, mirrors with engraved designs. By the right window an oval **Cista* of bronze from Vulci, with Amazon battles in embossed work, which when found contained articles of the female toilet. By the exit, Boy with a bird, in bronze.

Passing through a door on the right, we next enter the X. Room, or CORRIDOR, where water-pipes and several small bronzes are preserved.

[The XI. Room (sometimes closed) contains all kinds of vases (some of the most ancient of which are engraved with geometrical patterns), as well as copies of **Tomb Paintings** from Corneto and Vulci, invaluable in the study of early Italian art. The most ancient style (down to about B.C. 450) is represented by the paintings on the narrow sides of the saloon (excepting the scene over the door), which somewhat resemble early-Greek designs, but are ruder and more destitute of expression. The next stage (after B.C. 450) is exemplified by the designs on the long walls, where the progress is traced which the Etruscans had made in the art of drawing and in their ideas of the human figure, under the influence of the Greeks; at the same time Etruscan peculiarities are observable, especially in the heads, which are all in profile. These paintings, like the preceding, also represent games and dances performed in honour of the dead. The third and fully-developed period is represented by the picture, over the door, of Pluto and Proserpine (the latter full-face), which may probably be regarded as coeval with those in the 8th room. For economy of space several rows of these paintings are here exhibited one above another, but in the tombs each wall was embellished with a single row only. It is interesting to observe the gradual expansion of the colour-scale. The visitor should also notice that the paintings were intended to be seen by an artificial light, and hence the garlands, plants, and bronzes are painted blue instead of green.]

We now return to the 9th room, where, immediately to the right, by the windows, is a glass-cabinet with votive objects, found at the mineral springs of Vicarello, near the Lago di Bracciano (p. 391; chiefly gold and silver goblets); bronze vessels, rings, polished stones. In the centre of the room a cabinet with objects excavated at Pompeii in presence of Pius IX., including an equestrian **Relief* in marble. The turning glass-cabinet in the centre contains golden **Ornaments*; in the upper section are arranged those found in 1836 in the tomb of the Regolini-Galassi at Cervetri (p. 393), in the lower similar objects from other Etruscan tombs. These show the great skill and taste in workmanship of this kind to which the splendour-loving Etruscans had attained, and the chains, wreaths, rings, etc., afford models which are rarely equalled by Roman jewellers of the present day (see Castellani, p. 117). Many of the objects, however, are not of Etruscan origin, but were manufactured for export in Phœnician or Carthaginian workshops, from Assyrian and Egyptian models. Of this kind are the three silver dishes plated with gold and adorned with embossed scenes in the upper part of the cabinet (resembling those of the Treasury of Praeneste, p. 157), and the gold ornaments to the right and left (breastplate, bracelets, etc.), with embossed ornamentation or fine granulated work. Opposite the 2nd window is a bronze statuette of a boy with a bulla and Etruscan inscription. Then a brazier with tongs and poker. Opposite the 3rd window is a second, but less perfect *cista*, with engraving. By the wall a restored biga. Adjacent a large arm in bronze, of admirable workmanship, found at Civit  Vecchia along with the dolphin's tail to the right of the biga and the spear on the wall behind; all three fragments belonged to a colossal figure of an emperor in the guise of Neptune. Beyond, a bust of a man and several mirrors with designs. In the cases, small bronzes. By the fourth

wall: candelabra, kettles, shields. The four-wheeled censer and the brazen bed in front of it, both of great antiquity, were found in the above-mentioned grave of the Regolini-Galassi at Cervetri (ca. 600 B.C.). By the wall near the door: large bronze plates like shields, with heads in relief in the middle, used as decorations for the ceilings and doors of the graves. — In the XII. Room, on the left, is an imitation of an Etruscan tomb, with three burial recesses, vases, etc.; at the entrance two lions from Vulci. The cabinet in the centre contains bronzes from Veii; by the window small ornaments and objects in glass. Also several Chinese curiosities.

C. Library.

The Library and the Museum of Statuary may be conveniently visited in succession as they are open on the same days and at the same hours. ENTRANCE for readers in the Cortile di S. Damaso, for visitors by the glass-door at the bottom of the staircase to the Sala a Croce Greca (comp. p. 304; visitors knock). Comp. Plan, p. 276.

At a very early period the popes began to collect documents and thus gradually formed the **Archives**, which are mentioned for the first time under Damasus I., and were preserved in the Lateran. After various losses, caused especially by the migration to Avignon, and frequent change of locality, the library is now finally established in the Vatican in eleven rooms, in addition to the great library-hall. Over the door is the inscription: *Paulli Papae V. Archivium*. The Archives comprise a large number of the most interesting and important documents, especially of the middle ages, registers of the papal acts, letters of the popes from Innocent III. down to Sixtus V. in 2016 volumes, and correspondence with nuncios and foreign nations.

Besides this collection of documents, the popes possessed their private libraries. Nicholas V. instituted a public **Library**, with 9000 vols., and appointed *Giovanni Tortelli* as the first librarian.

The library was neglected and dispersed by his successors. SIXTUS IV. was the first to revive the institution; he assigned a locality under the Sistine Chapel for the collection, appointed *Platina* (1475) director, and set apart definite revenues for its maintenance. Thus endowed, it increased steadily, and the allotted space became more and more inadequate to its requirements, until in 1588 SIXTUS V. caused the present magnificent edifice to be erected by *Domenico Fontana*, intersecting the great court of Bramante. To this ever-increasing collection several considerable libraries have been added by purchase or donation, some of which are catalogued and preserved separately. In 1623 the Elector Maximilian presented to the Pope the *Bibliotheca Palatina* of Heidelberg, when the town was taken in the Thirty Years' War; and in 1657 the *Bibl. Urbina*, founded by Duke Federigo da Montefeltro, in 1690 the *B. Reginensis*, once the property of Queen Christina of Sweden, and in 1746 the *B. Ottoboniana*, purchased by Alex. VIII. (Ottobuoni), were added. Most of the MSS. carried off by the French were restored in 1814.

The Vatican Library now contains upwards of 26,000 MSS., of which about 19,000 are Latin, 4000 Greek, and 2000 Oriental. Of the last a printed catalogue has been published (1756-59), and continued by Cardinal Mai. There are in all about 200,000 printed books, of which a catalogue has also been made. The principal librarian is a cardinal, at present *Pitra*, who in ordinary business is represented by the under-librarian, *Abbate Cozza*, and two custodians. The usefulness of the library is circumscribed by the numer-

ous holidays on which it is closed. It is not available on more than 200 days in the year (from the middle of Nov. to the middle of June), and then only for 4 hrs. daily (8-12). Permission to use it is best obtained through the traveller's consul or by private letters of introduction, the applicant stating the branch of study contemplated.

Visitors first enter (by the glass-door, mentioned at p. 304, opposite the staircase leading to the Museum of Statuary) a long CORRIDOR below the Galleria dei Candelabri, divided into several sections. — Section I: *Museo Profano*: To the right, by the door: **Bronze Head of Augustus*, one of the finest extant portrait-busts of that emperor; left, on the table, a small, finely executed head of Venus. The closed cabinets contain beautiful ancient and modern ornaments, etc.; e.g. in the 2nd cabinet (left), Oriental bronzes and articles in gold, hair found in an ancient tomb, etc. — At the entrance to the next room, or section, are two porphyry columns from the Thermæ of Constantine, on each of which are carved the figures of two kings. — The frescoes of scenes from the lives of Pius VI. and Pius VII. possess little interest. — The following rooms contain the *Bibliotheca Ottoboniana*, the *Bibliotheca Regimensis*, and the MSS. of the Vatican library. — For the continuation of the corridor, see below.

We now turn to the left and enter the GREAT HALL, 77 yds. long, 16 yds. wide, and 29 ft. high, supported by 6 buttresses, constructed by Fontana and paved with marble by Pius IX. (immediately to the left is the entrance to the Archives). The paintings (of the 17th cent.) are in bad taste. By the walls and round the pillars are 46 small cabinets containing the MSS., the most celebrated of which are exhibited in glass-cases: celebrated palimpsest of the Republic of Cicero, Dante with miniatures by *Giulio Clovio*, the ritual of Card. Ottobuoni, breviary of King Matthias Corvinus; MSS. of the Greek New Testament (5th cent.), of Virgil (5th cent.), and Terence (the so-called 'Bembinus', of the 4th cent.); also autographs of Petrarch and Tasso. Also a number of gifts presented to the popes: Sèvres candelabrum presented by Napoleon I. to Pius VII.; a cross of malachite, from Prince Demidoff; two vases of Berlin porcelain, presented by Fred. William IV.; vase of Sèvres porcelain, presented by Charles IX.; vase of Scottish granite, presented by the Duke of Northumberland to Card. Antonelli; font, in Sèvres porcelain, in which the Prince Imperial (d. 1879) was baptised, presented by Napoleon III. to Pius IX.; malachite vase, presented by Emp. Nicholas to Gregory XVI.; three Sèvres vases, a gift of Marshal MacMahon to Pius IX.; large vase of oriental alabaster, presented by the Khedive Ibrahim Pasha of Egypt to Pius IX.; vases of Berlin porcelain, presented by King William I. of Prussia, afterwards German Emperor; huge block of malachite, from the Grand-duke Constantine of Russia. — In the adjoining *Reading Rooms* are suspended the portraits of the cardinal-librarians, framed papyrus-scrolls, and a facsimile of the two columns from the Triopium of Herodes Atticus on the Via Appia, with an imitation of ancient Attic characters, the originals of which are in Naples.

We now retrace our steps through the Great Hall to the *Corridor*, the continuation of which is also divided into sections. The two first sections contain the MSS. of the Palatine and Urbino libraries. In the first, over the entrance, is represented the Interior of SS. Apostoli; over the egress, Interior of the old church of St. Peter; in the second, over the entrance, the Erection of the Vatican Obelisk by Fontana (see p. 277); over the egress, St. Peter's, according to Mich. Angelo's design. In the third section, quattrocentists and oriental MSS.; by the sides of the egress, two ancient portrait-statues, 1. the orator Aristides, r. Lysias. — We next enter the —

Museum of Christian Antiquities (superintendent, *Commendatore Giov. Batt. de Rossi*). The 1st Room contains curiosities from the catacombs: lamps, glasses, bottles, gems, statuettes, pictures, altar-pieces, crosses, etc., the most interesting of which are preserved under glass. Second case on the right: several fine diptychs and triptychs in ivory. — The 2nd Room, the *Stanza de' Papiri*, with ceiling-paintings by *Raph. Mengs*, is filled with documents on papyrus of the 5th-8th cent., found at Ravenna. — The glass-

cabinets of the 3rd Room contain a large number of small pictures of the 13th-15th cent., unfortunately not distinctly visible. On the wall of the egress, on the right, a Russian painted calendar in the form of a cross, of the 17th cent.; next to it a large cross of rock-crystal, on which the Passion is represented, by *Valerio Vicentino*, presented by Pius IX. The handsome carved priedieu of Pius IX. is of French workmanship. The adjoining room, formerly the CHAPEL OF PIUS V., adorned with frescoes by *Giorgio Vasari*, and containing a *Cabinet of Coins* (not shown) which was seriously pillaged in 1797 and 1849, contains a conspicuous work in stained glass, by M. H. Schmitz of Aix-la-Chapelle, representing Pius IX. in his papal robes. In this and the following room are also deposited the numerous richly-bound addresses which Pius IX. received in the course of his reign. — To the right in the third room is the entrance to a collection of —

Ancient Pictures. On the floor, ancient mosaics. On the right wall: Phædra and Scylla; above, Ulysses and Circe; then the so-called **Aldobrandine Nuptials*, one of the finest ancient pictures in existence, found in Rome in 1606; next to it, to the left, Warrior in armour, found at Ostia in 1868; above it, Ulysses encountering the Læstrygones; to the left, by a door, Ship being loaded, found at Ostia in 1867. By the window, oriental gold and silver trinkets and plate, presented by the Emperor of Siam to Pius IX., with his photograph. To the left and right of these: Myrrha and Pasiphaë. By the long wall, farther on: the spies of Ulysses among the Læstrygones; below, a chariot with Cupids; to the right, sacrificial procession in front of a statue of Artemis; to the left, a boat mounted on a waggon. Then, Ulysses in the infernal regions; below it, an unknown female figure and **Canace*. The six mythological figures of women celebrated for their misfortune in love are from Torre di Marancia. The representations from the Odyssey were found on the Esquiline. — An adjacent cabinet contains a collection of *Ancient Tile-stamps and Majolica*, recently transferred from the papal villa at Castel Gondolfo.

The so-called **Appartamenti Borgia*, occupied by the printed books, and adorned with interesting paintings, are shown by special permesso only, to be obtained from *Monsignor Ciccolini*, one of the prefects of the library. We first enter the so-called TORRE BORGIA (p. 283), two small rooms, the first of which is adorned with ceiling-paintings by *Giovanni da Udine* and *Perino del Vaga*. The paintings on the spandrels and the prophets and sybils in the lunettes are ascribed (probably wrongly) to *Pinturicchio*. In the second room are twelve apostles and prophets. The decorations in both rooms are much damaged. — We descend a few steps, and enter the HALL OF THE LIBERAL ARTS: Astrologia (above the window), Grammatica, Dialectica, Rhetorica, Geometria, Arithmetica, *Musica. — In the III. ROOM: on the rear-wall, St. Catharine's disputation before the Emperor Maximinus; on the entrance-wall, *SS. Anthony the Abbot and Paul the Hermit in the Theban desert; Meeting of Mary and Elizabeth; above the window, Martyrdom of St. Sebastian; on the exit-wall, Susanna, St. Barbara; on the ceiling, Legend of Osiris (the Apis bull is a reference to the arms of the Borgia family). — IV. ROOM. On the rear-wall, Annunciation and Nativity; on the entrance-wall, Adoration of the Magi, Resurrection; above the window, Ascension; on the exit-wall, Pentecost, *Assumption of the Virgin. — The last large SALOON, containing CARDINAL MAR'S LIBRARY, is adorned with paintings and stucco-work by *Giov. da Udine* and *Perino del Vaga*, in bad preservation.

The *Studio dei Mosaici*, or *Papal Manufactory of Mosaic*, is under the gallery of the inscriptions; entrance in the left angle of the farther side of the Cortile di S. Damaso (p. 286). Permessi obtained at the Segretaria, comp. p. 124. Numerous hands are employed here in copying celebrated pictures for churches, etc. The material used is a kind of coloured glass, of which there are 10,000 different shades. — The papal Armoury and the Mint (*La*

Zecca; now in the hands of government) near the Vatican contain a few objects of interest, *e.g.* all the papal coins from the time of Hadrian I., and most of the dies since Martin V.

The Lungara.

The Borgo is connected with Trastevere by the VIA DELLA LUNGARA, $\frac{3}{4}$ M. in length, constructed by Julius II. The Borgo is quitted by the *Porta di S. Spirito* (Pl. I, 7; p. 276), begun by Antonio da Sangallo the Younger, and occupying nearly the same site as the old Gate of the Saxons. — To the right, immediately to the S., the steep Salita di S. Onofrio, passing through the gate which closes the new Passeggiata, ascends in 5 min. to —

***S. Onofrio** (Pl. II, 7), on the slope of the Janiculum, erected about 1430 by *Niccolò da Forca Palena* in honour of the Egyptian hermit Honuphrius; adjoining it is a monastery of the order of St. Jerome. The church and monastery are preceded by a colonnade of eight columns; in the lunettes are three frescoes from the life of St. Jerome by *Domenichino* (Baptism, Chastisement, Trance). If the church is closed, visitors ring (r.) at the door of the monastery ($\frac{1}{2}$ fr.).

LEFT SIDE. The 1st Chapel contains the tomb of the poet Torquato Tasso, who died in this monastery in 1595; the monument was erected by Pius IX. in 1857, the statue is by *De Fabris*. In the 2nd chapel, the tombstone of the linguist Card. Mezzofanti (d. 1849). — RIGHT SIDE. The 2nd chapel contains a Madonna, altar-piece by *Ann. Carracci*. At the end of the right wall: monument of Archbp. Sacchi (d. 1505); in the lunette St. Anna teaching the Madonna to read, by *Pinturicchio*. The TRIBUNE contains restored frescoes, the upper attributed to *Peruzzi*, the lower to *Pinturicchio*, probably both by *Peruzzi*.

The *Monastery* contains, in a passage on the first floor, a **Madonna with the donor, a fresco by *Leonardo da Vinci*, which has unfortunately been much injured by retouching (the attitude of the raised arm of the child, for example, has been entirely spoiled). The cell is still shown in which Tasso resided, when about to receive the laurels on the Capitol, and in which he died, 25th April, 1595. It contains his bust in wax, taken from the cast of his face, his portrait (fresco by Balbi, 1864), autograph, etc. — The new *Passeggiata Margherita*, described at p. 330, intersects the former convent-garden. On the hill-slope, to the left, near some cypresses, are the remains of an oak (destroyed by lightning in 1842), under which Tasso was in the habit of sitting. Admirable *View.

In the LUNGARA, on the left, is the *Ospizio de' Pazzi* (Pl. I, II, 7), a large lunatic asylum erected by Pius IX.

Farther on, to the left, is a chain-bridge (Pl. II, 10; toll 5 c.); on the opposite bank rises S. Giovanni dei Fiorentini (p. 207). Opposite the bridge, in the Lungara, is the extensive *Palazzo Salviati* (Pl. II, 7), with a handsome court of the 16th cent., now a '*Collegio Militare*' (cadet academy). The adjacent garden, converted in 1837 into a *Botanical Garden* (visitors ring at the small door on the right), contains rare and beautiful trees and plants.

Farther on in the Lungara, about $\frac{3}{4}$ M. from the Porta S. Spirito and opposite the Pal. Corsini (p. 324), is the —

****Villa Farnesina** (Pl. II, 11; adm., see p. 123), an exceedingly pleasing Renaissance edifice erected in 1506 by *Bald. Peruzzi* for the papal banker Agostino Chigi, an enthusiastic admirer of art and patron of Raphael (see pp. 147, 192). It became the property of the Farnese family in 1580, and now belongs to the ex-king of Naples. The garden, extending to the Tiber, has been greatly curtailed by the recent alterations made in the course of the river.

The ceiling of the principal room on the ground-floor, which is entered direct from the garden, was designed by *Raphael* (1518-20), and decorated by *Giulio Romano*, *Francesco Penni*, and others of his pupils, with twelve illustrations of the ****MYTH OF PSYCHE**, which are among the most charming creations of the master (comp. p. lvi). The hall was originally open, but is now enclosed by windows for the protection of the pictures.

The series of illustrations begins on the left end-wall, and is continued on the wall opposite the entrance. Raphael adhered to the charming fable of Apuleius, which may be briefly told as follows. A certain king has three daughters, of whom Psyche, the youngest, excites the jealousy of Venus by her beauty. The goddess accordingly directs her son Cupid to punish the princess by inspiring her with love for an unworthy individual (1). Cupid himself becomes enamoured of her, shows her to the Graees (2), and carries her off (this is the best preserved of the paintings). He visits her by night only, warning her not to indulge in curiosity as to his appearance. Psyche, however, instigated by her envious sisters, disobeys the injunction. She lights a lamp, a drop of heated oil from which awakens her sleeping lover. Cupid upbraids her, and quits her in anger. Psyche wanders about, filled with despair. Meanwhile Venus has been informed of her son's attachment, imprisons him, and requests Juno and Ceres to aid her in seeking for Psyche, which both goddesses decline to do (3). She then drives in her dove-chariot to Jupiter (4), and begs him to grant her the assistance of Mercury (5). Her request is complied with, and Mercury flies forth to search for Psyche (6). Venus torments her in every conceivable manner, and imposes impossible tasks on her, which, however, with the aid of friends she is enabled to perform. At length she is desired to bring a casket from the infernal regions (7), and even this, to the astonishment of Venus, she succeeds in accomplishing (8). Cupid, having at length escaped from his captivity, begs Jupiter to grant him Psyche; Jupiter kisses him (9), and commands Mercury to summon the gods to deliberate on the matter (ceiling-painting on the right). The messenger of the gods then conducts Psyche to Olympus (10), she becomes immortal, and the gods celebrate the nuptial-banquet (ceiling-painting on the left). In this fable Psyche obviously represents the human soul purified by passions and misfortunes, and thus fitted for the enjoyment of celestial happiness.

Below the spandrels, twelve Cupids with divine attributes. The garlands enclosing the different paintings are by *Giovanni da Udine*. — The frescoes, having suffered from exposure to the atmosphere, were retouched by *Maratta*. The blue ground, which was originally of a much warmer tint, as is apparent from the few portions still unfaded, was most seriously injured. The whole nevertheless produces a charming and brilliant effect owing to the indestructible beauty of the designs. The felicity with which the scenes have been adapted to the unfavourable spaces is also remarkable.

The smaller apartment adjoining the principal hall, which was also once an open Loggia, contains a second mythological picture by *Raphael*, which is no less charming than the Psyche series, and

even far surpasses them in point of execution: ***GALATEA*, borne across the sea in a conch, and surrounded by Nymphs, Tritons, and Cupids, painted entirely by the master's own hand in 1514. The *Ceiling of this room was decorated and painted by *Baldassare Peruzzi*.

Ceiling-pictures: Perseus and Diana. The hexagonal spaces of the spandrels contain gods of the planets and mythological scenes. In the lunettes were afterwards added scenes from the *Metamorphoses*, the first Roman work of *Seb. del Piombo*. The colossal head in the lunette on the left lateral wall is said to have been drawn by *Michael Angelo* in charcoal, whilst waiting for *Dan. da Volterra* who was also engaged here, but is more probably by *Peruzzi*. The painted stucco-work is very deceptive.

In the corner of the entrance wall, to the left of *Galatea*, *Seb. del Piombo* painted the *Polyphemus*, afterwards almost entirely obliterated, and badly restored. — The landscapes are erroneously attributed to *G. Poussin*.

The restorations which the two rooms have recently undergone have only been partly successful.

The upper floor of the *Farnesina*, to which, however, visitors are not admitted except by special introduction, also contains celebrated frescoes: the Marriage of Alexander with Roxana, and the Family of Darius before Alexander, by *Sodoma* (painted after 1520; p. lvi).

Opposite is the **Palazzo Corsini* (Pl. II, 11), formerly the property of the *Riarii*, purchased by *Clement XII.* for his nephew *Card. Neri Corsini* in 1729, and altered by *Fuga*. In the 17th cent. it was occupied by *Queen Christina of Sweden*, who died here, 19th April, 1689. In 1884 the palace was purchased by government and assigned to the *Accademia de' Lincei*, or Royal Academy of Science. A double staircase ascends from the principal portal to the 1st floor, where the PICTURE GALLERY is situated (adm., see p. 123). Among a great number of mediocre and inferior works are a few pictures of rare merit. Catalogues in each room.

1st Room. 1, 5. *Bloemen (Orizzonte)*, Landscapes; 2, 4. *Locatelli*, Landscapes. This room also generally contains a small Holy Family by *Battoni*. By one of the walls a well-preserved ancient sarcophagus with sea-gods, from *Porto d'Anzio*.

2nd Room. 4. *Bassano*, Holy Family; 12. *Eliz. Sirani*, Madonna in a glory; 15. *G. Poussin* (?), Landscape; 17, 19. *Berchem* (?), Landscapes with cattle; 20. *Lod. Carracci*, Pietà. A *Madonna by *Carlo Dolci* is also generally here. On a table stands the **Corsinian Vase* in silver, with the Purification of Orestes in chased work. On the walls, a number of ancient heads, some of them interesting. To the right is the —

3rd Room: 1. *Guercino*, Ecce Homo; *4, 5. *Peters*, Sea-pieces; 9. *Andrea del Sarto*, Madonna; 17. *Caravaggio*, Madonna; *23. *Both*, Evening landscape; 26. *Fra Bartolommeo*, Madonna, resembling Raphael's Madonna Canigiani; 43. *Saraceni*, Martyrdom of two saints; 44. *After Raphael*, Julius II.; 50. *After Titian*, Philip II. of Spain (original at Naples); 55. *Dutch School*, Kitchen-scene; 63. *Conca*, Adoration of the Magi; 61. *Vasari*, Holy Family; 52. *Saraceni*, Vanity; 84. *Borgognone*, Cavalry skirmish; 88. *C. Dolci*, Ecce Homo.

4th Room: *11. *Guido Reni*, Herodias; 16. *G. Reni*, Madonna; 22. *Baroccio*, Christ and Mary Magdalene; 27. *Lod. Carracci*, Heads as studies; 35. *Parmeggianino*, Four heads; *Maratta*, 40. Portrait of his daughter, 43. Madonna; 44. *After Dürer*, Hare; 47. *Poelenburg* (?), Landscape with the judgment of Paris, after Raphael; also eleven small pictures from military life, erroneously attributed to *Callot*. Ancient marble chair with reliefs, found near the Lateran.

5th Room, in which *Christina of Sweden* is said to have died: Ceiling-decorations of the school of the *Zuccheri*. 2. *Perino del Vaga*, Holy Family;

12. *Carlo Dolci*, St. Agnes; *14. *Maratta*, Annunciation; 20. *Lanfranco*, Polyphemus and Ulysses; 23. *Franc. Albano*, Madonna; 44. *Marc. Venusti*, Holy Family, designed by Michael Angelo; 50. *Salv. Rosa*, Card-players; 51. *Marc. Venusti* (?), Sculptor. — In this room also is an ancient *Mosaic*, representing two restive oxen, with the plough and driver.

6th Room, containing an interesting collection of portraits, most of which are worthy of notice: *43. *German Master* (not Dürer), Cardinal; 19. *Holbein* (?), Portrait of a man, much retouched; *20. *G. Romano*, Monsgr. Ghiberti; *22. *Rembrandt* (?), Old woman; 23. *Giorgione* (?), Portrait of a man; 26. *Spanish School*, Portrait; *32. *Van Dyck*, Portrait; *34. Nativity of Mary, after Dürer's woodcut; 47. *Rubens*, Portrait; 50. *Titian*, Card. Alex. Farnese, freely retouched.

7th Room: *13. *G. Poussin*, Landscape; 21. *L. Giordano*, Christ as a boy in the Temple; *22, *23, *24. *Fra Angelico*, Descent of the Holy Ghost, Last Judgment, Ascension; 30. is erroneously attributed to *Titian*; 31, 32. *N. Poussin*, Landscapes.

8th Room: 6. *Claude Lorrain* (?), Landscape; *7. *G. Poussin*, Landscape; 10. *Polidoro da Caravaggio*, History of Niobe, design in the form of a frieze; 11. *N. Poussin*, Holy family; 12. *Erc. Grandi*, St. George; 13. *Guido Reni*, La Contemplazione; *15, 21, 23. *G. Poussin*, Landscapes; 24. *Guercino*, St. Jerome; 25. *Ribera*, St. Jerome; *40. *Murillo*, Madonna. — The adjoining CABINET contains pictures of the older Florentine and Sienese schools, most of them of little value, and badly preserved. 23. *Gher. Starnina*, Madonna; 26. *Spagna*, Madonna.

9th Room: 2. *Teniers*, Interior of a stable; S. *Lod. Carracci*, Pietà, sketch of No. 20 in the 2nd R.; 9. *Velazquez*, Innocent X. (copy of the picture in the Pal. Doria, p. 159); *28, 29. *Salv. Rosa*, Battles; 30. *Giorgione* (?), Female heads; 36. *Titian* (?), Portrait; 49. *Gherardesca da Siena*, Madonna.

The *Library* of this palace (adm., see p. 116; entrance by the principal portal; traverse the open corridor to the right, and ascend to the 1st floor), founded by Card. Neri Corsini, is one of the largest in Rome. It contains numerous MSS. and books of great value, and one of the most extensive collections of *Engravings* in the world.

The *Corsini Garden* now belongs to the municipality (see p. 330).

At the S. end of the Lungara stands the **Museo Torlonia** (entrance Vicolo Corsini 5), containing the most extensive collection of antiquities in Rome after those at the Vatican and the Capitol (unfortunately closed at present). The collection, which includes objects of almost every epoch of Græco-Roman art, consists chiefly of the contents of the former Galleria Giustiniani, of a number of works formerly in the Villa Albani, and of the yield of Prince Torlonia's excavations at Porto and elsewhere. It occupies a series of parallel corridors and the adjoining rooms, and is divided into compartments, distinguished by Roman numerals. Catalogue by *P. E. Visconti*.

1st CORRIDOR (Comp. I-X). 4. Venus with the eestus; 19. Isis; 20. Bes, an Egyptian deity; *24. Head of an athlete (in the style of Lysippus); 25. Athlete restored as Hercules (in the style of Polykletus); 30. Lysias (?); 33. Isocrates; 43. Herod Agrippa; 44. Juba II. of Mauretania(?); 47. Venus Anadyomene; 49. Aristotle; *50. Head of Hypnos, the god of sleep; 60. Leda and the swan.

2nd CORRIDOR (Comp. XI-XX). *64. Sitting figure of Livia, admirable in attitude and in the disposal of the drapery (comp. the statue No. 77 and the Agrippina in the Capitoline Museum); 63. Carneades; 65. Zeno; *67. Alcibiades; 68. Latona with the twins Apollo and Diana; 72. Tiberius as a hero, statuette; *77. Sitting portrait-figure of a woman, an excellent Greek work, perhaps representing Olympias, the mother of Alexander

the Great (head, etc., skilfully restored); *82. So-called Philosopher of Ruspoli; *86. Head of Hermes (in the style of Praxiteles); 91. Alexander the Great; 101. Nymph; 116. Two wrestling satyrs, an interesting example of the numerous skilful restorations in this collection, the only ancient parts being the body of one combatant and the head and a piece of the base of the other; 117. Statue of the orator Hortensius, found in his villa at Laurentum.

3RD CORRIDOR (*Comp. XXI-XXX*). 118. Cæsar; *133. Old fisherman, a very realistic work; 137. Muse; 141. Draped statue, restored as Niobe; 146. Venus Euploëa (the goddess of navigation), found at Porto; 150. Base of a candelabrum, with relief of the dancing Horæ; 151, 157. Satyr and Hermaphrodite; 154. Telesphorus (the god of healing), in rosso antico; 161. Sophocles; 163. Homer; 164. Augustus, sitting figure.

4TH CORRIDOR (*Comp. XXXI-XXXIII*). 167. Fragment of a group, representing Scylla devouring one of the companions of Ulysses (wrongly restored as Milo of Croton in combat with a wild animal); 173. Euterpe; 174. Cupid and Psyche. — We now return to Comp. XXX. and pass thence into the —

1. Room (*Comp. XXXIV-XXXIX*). *183. Minerva; 189. Trajan, 192. Claudius, colossal busts; 202. Tiberius, statue; 228-236. The Muses; 237. Apollo Musagetes. — We now return to the right into the —

5TH CORRIDOR (*Comp. XL-XLII*). 240. Female draped statue, corresponding to No. 290 and restored as Niobe; 249. Claudius; 250. Neptune. — From here we proceed in a straight direction into the —

11. Room (*Comp. XLIII*). *225. Germanicus, bronze statue found at Arci (the ancient Cures), in the Sabine Mts.; 267. Caput Africæ, with an elephant's head as helmet (used as an architectural ornament). — We now return through Comp. XLII into the —

6TH CORRIDOR (*Comp. XLIV-XLVII*). 290. Draped female statue (*comp. No. 240, above*), restored as Irene with the young Plutus, after the celebrated work of Cephisodotus (now in Munich); 294, 296. Heads of Medusa; *297. Large shallow vase with Bacchanalian scenes; *298. Minerva (adjacent, casts of the Vatican and Capitoline Minervas).

7TH CORRIDOR (*Comp. XLVIII-LI*). 301. Melpomene in the costume of a tragic actress; 308. Marsyas; 309. Kneeling youth (perhaps Ganymede in combat with the eagle, or one of the children of Niobe), restored as a falling warrior; 310. Youthful Nero.

8TH CORRIDOR (*Comp. LII-LV*). *232. Diadumenos, or youth binding a fillet on his brow; 343. Pompey.

9TH CORRIDOR (*Comp. LVI-LIX*). 355. Wrestler. — We now return to Comp. XL. To the right is Comp. LX. with portrait-busts of emperors and others. — To the left, the —

III. Room (*Comp. LXI*). 374. Silenus, a fountain-figure; 375. Aurora; *377. Hercules with the apples of the Hesperides, a Greek relief; 379. Game-dealer, a large tomb-relief, with three verses of Virgil at the top (*Aen. I, 607-609*); 383. Shallow vase with reliefs of the labours of Hercules. — The door in front leads to the —

IV. Room (*Comp. LXII-LXIX*). 387. Captive barbarian; 388. Hercules and Telephus; 389. Sleeping Ariadne; 392. Bacchus and Silenus; 395. Large sarcophagus with representation of a wedding; 397, 398. Antinous; *402. Plotina, wife of Trajan; 407. Antinous; 401, 404. Domitian; 406. Ptolemy Philadelphus; 402. Ceres; 414. Sarcophagus with reliefs of the different periods of life. — To the right, the —

ROOM OF THE SARCOPHAGI (*Comp. LXX*). 416. Triumph of Bacchus; 420, 422. Deeds of Hercules; 423. Apollo and Marsyas. In the middle, 426. Cupid in a chariot drawn by two boars (in black marble). — *Comp. LXXI*. 427. River-god, in black marble; 423. Roman tax-collecting; 430. Harbour of Ostia; 431. Ship, three reliefs found at Porto; 433. Tomb-relief in the Greek style; 434. River-god, in basalt. — To the right CAMERA DEGLI ANIMALI (*Comp. LXXII*). 438. Ram carrying Ulysses out of the cave of Polyphemus. — We now return through Comp. LXXI to *Comp. LXXIII*. 459. Alto-relief, called Medea and Jason, but perhaps Hercules and the Hesperides. — We then pass through Comp. X. to

Comp. LXXIV. 463, 464. Apollo and Marsyas; 466. Hermaphrodite; 467. Vase with marine deities. — To the right, *Comp. LXXV,* *470, 473, 476, *477, 480. Athletes. — We now return through *Comp. LXXIV* into the —

ROOM OF THE ARCHAIC SCULPTURES (*Comp. LXXVI*). 481. Spes; 482. Priestess; 483. Diana of the Ephesians; 485. Canephora (Caryatide) of similar type to those at the Villa Albani (p. 339). — *490. Vesta, formerly in the Giustiniani collection, possibly an original Greek work, from some temple of the goddess. No other extant example conveys so true an impression of the solemn dignity that distinguished the representations of the gods in the lofty period of Greek art (Friedrichs). — 498. Venus; 501. Apollo; 503. Cybele. — We return through *Comp. LXXIV* to the —

GALLERY OF IMPERIAL BUSTS, arranged in chronological order. This series of busts, most of which have been identified with the aid of coins, is one of the richest collections of the kind. The following are specially interesting either for their excellence or their rarity: 514. Livia; 515. Mæcenas; 516. Agrippa; 533. Galba; 545. Hadrian; 552, 553. Marcus Aurelius; 556. Lucius Verus; 569. Caracalla; 571. Geta; 588. Papienus Maximus; 611. Helena Fausta.

Numerous architectural fragments of all kinds have been built into the walls of the adjoining COURT and GARDEN.

A little to the S. of the Museo Torlonia the Via della Lungara is terminated by the *Porta Settimiana* (Pl. II, 11), a gate in the older wall of Trastevere. — The *Via Garibaldi* and the *Via de S. Maria della Scala* begin here; see pp. 328 and 331.

Trastevere.

The *Janiculum* (275 ft.) rises to a commanding height near the river, and was on that account chosen by the ancient kings of Rome as the site of a castle, which they connected with the city lying opposite to it by a double wall. The hill was at length annexed to the city by Augustus as a 14th quarter, which he named the *Regio Transtiberina*. The banks of the Tiber here were bordered with handsome villas, but the quarter always retained the character of a suburb, and was much frequented by foreigners, particularly by Jews, who formed a community here down to the beginning of the 16th cent. (*comp. p. 203*). Trastevere is now inhabited almost exclusively by the working classes, among whom many well-built and handsome persons of both sexes will be observed. The inhabitants of Trastevere maintain that they are the most direct descendants of the ancient Romans, and their character and dialect differ in many respects from those of the citizens of other quarters.

Trastevere is connected with the city by four bridges, the most N. of which is the **Ponte Sisto** (Pl. II, 11), constructed under Sixtus IV., in 1474, on the site of the *Pons Valentiniani*, built in 366 A. D. by Symmachus, prefect of the city. The bridge affords a good view of the river and of the important works constructed to control the stream.

The frequent inundations of the Tiber, occasioned by the insignificant fall in the lower part of its course and by its sudden increase of volume after heavy rain in the mountain-homes of its numerous affluents (sometimes multiplying it tenfold) have long been a source of anxiety to the citizens and authorities. After the great inundation of 1870, during which the water rose 56 ft. above the ordinary water mark at the Ripetta, a

commission was appointed by government, to report on the possibility of improvements. This body recommended a thorough purification and deepening of the channel, careful regulation of the drains emptying themselves into the river, and the widening of the channel at certain specified points. The works began in 1876 with the widening of the channel opposite the Farnesina and below the Ponte Sisto, and are now almost complete on the right bank as far as the Ponte Rotto (p. 250), though on the left and the lower part of the right bank much has still to be done.

To the right the *Via di Ponte Sisto* leads in 3 min. to the broad *VIA GARIBALDI* (Pl. II, 11, 12), a little on this side of the *Porta Settimiana* (see p. 327), by which we now ascend to the left. After 5 min. the street reaches a small piazza, whence, to the right, a steep road ascends direct to the *Acqua Paola* (see p. 329.) The road passes the new Spanish Academy, an institution resembling the French (p. 149), on the hill to the right, and ascends in windings to S. Pietro in Montorio, the *Acqua Paola*, *Porta S. Pancrazio*, and *Villa Pamphili*. About 50 paces from the above-mentioned small piazza, beyond the memorial-tablet, a path to the right, flanked with oratories, and ascending in steps, also leads to the church.

S. Pietro in Montorio (Pl. II, 12), erected in 1500 for Ferdinand and Isabella of Spain by *Baccio Pintelli* (?), on the spot where St. Peter is said to have suffered martyrdom, stands on the slope of the *Janiculum*, 197 ft. above the sea-level. The campanile and tribune were almost entirely destroyed during the siege of 1849. If the church is closed, visitors ring at the door on the right (25-50 c.).

RIGHT SIDE. The *1st Chapel was decorated by *Seb. del Piombo* with frescoes from Michael Angelo's drawings: Scourging of Christ (of which there is a small duplicate in the Gall. Borghese), adjoining which are St. Peter on the left and St. Francis on the right; on the ceiling the Transfiguration; on the exterior of the arch a prophet and sibyl. The 2nd Chapel (Coronation of Mary on the arch) was painted by pupils of Perugino. The altar-piece of the 5th Chapel, Conversion of St. Paul, is by *Vasari*. — The High-Altar was once adorned by Raphael's Transfiguration (p. 301). — **LEFT SIDE.** The last chapel contains an altar-piece by *Daniele da Volterra* (?), Baptism of Christ; in the 4th Chapel an Entombment by a Dutch master; in the 3rd, an altar-piece and ceiling, by pupils of Perugino; in the 2nd, sculptures of the school of Bernini; in the 1st, St. Francis by *G. de' Vecchi*. By the wall near the door, tomb of St. Julian, Abp. of Ragusa, by *G. A. Dosio*, 1510.

In the court of the monastery rises the **Tempietto*, a small circular building with sixteen Doric columns, erected in 1502, from *Bramante's* designs, on the spot where the cross of St. Peter is supposed to have stood. A chapel in the interior contains a statue of St. Peter, and below it is a second chapel, with an opening in the floor indicating the spot which the cross is said to have occupied.

The piazza in front of the church commands a magnificent **VIEW* of Rome and the environs, for the orientation of which this point is admirably adapted (comp. annexed Panorama, from which the omission of the unimportant new erections will be no disadvantage). The most important places are enumerated here from right to left. To the S. is the Tiber, which is crossed by the iron bridge of the railway to *Civita Vecchia*; beyond it the extensive basilica of S. Paolo Fuori le Mura. Then part of the city-wall, in front of



S. Pietro

Monte Mario
S. Onofrio S. Maria del Rosario Osp. di S. Spirito Villa Mellini
Giardino Corsini

S. Giovanni de' Fiorentini Monte Rizzano Castello S. Angelo
Palazzo Corsini

Monte Soratte
Pal. detto la Farnesina

Chiesa nuova S. Maria della Scala

Piazza del popolo Palazzo Farnese
Passeggiata al Pincio S. Agnese a P. Navona
Palazzo Tarnese S. Carlo al Corso

Villa Medici Sapienza
M. Leonessa S. Andrea d. Valle
Villa Ludovisi S. Ignazio
Pantheon S. Trinità de' Pellegrini
S. Trinità de' Monti Piazza Colonna


S. Angelo Gesù M. Gennaro
Monte Quirinale Monticelli
Pal. Quirinale Pal. di Venezia

Torre di Nerone
Stazione di Strada Terrena S. Maria in Campitelli
Colonna Trajana

Monte Gianicolo

Monte Pincio

PANORAMA DI ROMA
preso da S. Pietro



M. Velino Tivoli S. Lorenzo in Miranda (l. di Anagnino) Coliseo S. Crisogono S. Giovanni in Laterano Palestrina S. Stefano Rotondo Colonna S. Maria in Cosmedin S. Anastasia Villa Mills S. Cecilia Villa Mattei Rocca Priora Fabbrica de Tabacchi Monte Porzio S. Sabina Osped. di S. Michele Frascati S. Alessio Grotta Ferrata Rocca di Papa S. Maria del Priorato M. Cavo Marino Sep. d. Cecilia Metella Porta Portese Cast Gandolfo Porta S. Paolo e P. di Cestio S. Cosimato Cimet. de Protestanti

Monte Esquilino S. Maria in Trastevere Monte Palatino Monte Celio Monte Aventino

SUOI CONTORNI,
Montorio.



it the Monte Testaccio (adjoined by the new quarter to the S.W. of the Aventine), the pyramid of Cestius, and the Porta S. Paolo. The Tiber, which flows between us and Monte Testaccio, is not visible hence. On the Aventine rise the three churches of S. Maria del Priorato, S. Alessio, and S. Sabina. Beyond are the Alban Mts., with Mte. Cavo (3130 ft.) on the right, and Frascati on the left. On the Caelius, the Villa Mattei and S. Stefano Rotondo, above which, on the extreme spur of the Alban Mts., is Colonna; between this and the Sabine Mts., near Palestrina, the heights of the Abruzzi. Then the Palatine, with the ruins of the palaces of the emperors and the cypresses of the Villa Mills, above which rise the statues on the façade of the Lateran. Next, the Colosseum, the three huge arches of the basilica of Constantine; then the Capitol with the German Archaeological Institute, the Pal. Caffarelli, the tower of the senatorial palace, parts of the façade of the Capitoline Museum, and of the church of Araceli; the two domes with the campanile above these belong to S. Maria Maggiore on the Esquiline. The finely shaped, double-peaked mountain in the extreme distance is the Monte Velino (8165 ft.), which rises to the N. of the Lago di Fucino. Farther on, near the cypresses, the extensive royal palace on the Quirinal, in front of which, near a light-coloured dome, rises Trajan's column; more towards the foreground the church del Gesù with its dome, beyond which is the M. Gennaro (4160 ft.). Then on the Pincio, the most N. of the Roman hills, the light Villa Medici, and to the right of it S. Trinità de' Monti, rising with its two towers above the Piazza di Spagna. Nearer, not far from the Tiber, rises the Pal. Farnese with its open loggia. To the right of it, the spiral tower of the Sapienza; farther to the right, part of the dome of the Pantheon, concealed by the dome-church of S. Andrea della Valle, to the right of which the column of M. Aurelius in the Piazza Colonna is visible. Again to the left, on the height, are the wall and the Passeggiata of the Pincio with the two dome-churches of the Piazza del Popolo. Then, near the river, the Chiesa Nuova; beyond it the indented outline of Soracte (2250 ft.). On this side of the Tiber rises the castle of S. Angelo; beyond it, the heights of Baccano. By the chain-bridge is the dome-covered church of S. Giovanni de' Fiorentini. Farther off, M. Mario with the Villa Mellini; lastly, at the extreme angle to the left, rises the dome of St. Peter's. In Trastevere, at the foot of the hill, is the church of S. Maria in Trastevere, the light-coloured campanile to the right of which belongs to S. Cecilia.

If we descend from S. Pietro in Montorio in a straight direction, traverse the Vicolo della Frusta to the right, and then the Via de' Penili to the left, we reach the Piazza di S. Maria (p. 330).

The Via Garibaldi, which continues to ascend the hill beyond S. Pietro in Montorio, leads in 2 min. to the *Acqua Paola* (Pl. II, 12), the ancient *Aqua Trajana*, which was supplied by the

Lago di Bracciano (p. 391), upwards of 30 M. distant. The aqueduct was restored by *Fontana* and *Maderna* in 1611 under Paul V., who decorated the great fountain with marble columns from the Temple of Minerva (p. 239). The granite columns were brought from the vestibule of the old church of St. Peter; the massive basin was added by Innocent XII. — A monument to Garibaldi is to be erected in the new gardens to the left.

The Via Garibaldi leads on hence to the *Porta S. Pancrazio* and the *Villa Doria-Pamphilj* (see p. 355).

Immediately to the N. of the Acqua Paola is the entrance to the ***Passeggiata Margherita** (Pl. II, 7, 8, 9), opened in 1884, and embracing the former garden of the Palazzo Corsini (p. 325). This promenade is continued along the summit and slope of the Janiculum (p. 327) to S. Onofrio (p. 322). The broad carriage-road which traverses the gardens ends at the Porta di S. Spirito (p. 322). From the Acqua Paola to S. Onofrio is an easy walk of 15-20 minutes. The ***VIEWS** of the city and the Campagna, especially fine at sunset, almost excel in their variety the view from S. Pietro in Montorio.

At the S. end of the Via di Tor Argentina (Via di Mortella, p. 202) the Tiber is spanned by the iron **Ponte Garibaldi** (Pl. II, 14, 15), built in 1885-88. The length of the bridge is 150 yds. (of the openings on each side of the central pier 180 ft.), the breadth 65 ft.

At the Trastevere end of the bridge is the small **PIAZZA DI S. CRISOGONO**, which is traversed by the *Via della Lungaretta*, the main street of Trastevere. The church of **S. Crisogono** (Pl. II, 15) is a basilica with aisles, a portico, and straight beams, of the 12th century. Last restoration in 1624.

The **INTERIOR** is interesting on account of its fine old mosaic pavement, and ancient columns, particularly the two of porphyry supporting the arch of the choir, which are the largest in Rome. The ceiling-paintings of the transept are by *Arpino*. The mosaic on the wall of the tribune represents the Madonna between SS. Chrysogonus and James. Fine carved stalls of 1866.

In the Contrada Monte di Fiore, to the E. of the Piazza S. Crisogono, an *Excubitorium* of the VII. Cohort of the *Vigiles*, i.e. a station of the Roman firemen (p. 132), was excavated to a depth of about 30 ft. in 1866-67.

A modern flight of steps descends to a small mosaic-paved court-yard, with a well in the centre, a chapel with mural paintings (right), and several rooms, on the walls of which are numerous rude inscriptions of the beginning of the 3rd cent. (see 1½ fr.).

After 5-6 min. we reach the **PIAZZA DI S. MARIA** (Pl. II, 15, 12), with a fountain and the church of —

***S. Maria in Trastevere**, which is said to have been founded by Callistus I. under Alexander Severus, on the spot where a spring of oil miraculously welled forth at the time of the birth of Christ. It is mentioned for the first time in 499, was re-erected by Innocent II. about 1140, and consecrated by Innocent III. in 1198. The present


vestibule was added by *C. Fontana* under Clement XI. in 1702. In front are mosaics of Mary and the Child, on each side the small figure of a bishop (Innocent II. and Eugene III.) and ten virgins, eight of whom have burning, and two extinguished lamps, a work of the 12th cent., largely restored in the 14th (comp. p. xlviii). The mosaics on the gable above are modern. The vestibule contains the remains of two Annunciations, one attributed to *Cavallini*, but now entirely repainted, and numerous inscriptions. The church has recently been restored.


The INTERIOR contains twenty-two ancient columns of unequal sizes. Some of the capitals were formerly decorated with heathen deities, but these were removed when the church was restored in 1870. The fine pavement is laid with porphyry, verde antico, and other marbles, in the style known as *Cosmato* work (comp. p. xlvii). The ceiling, decorated with richly-gilded stucco, was designed by *Domenichino*. The oil-painting on copper in the centre, a Madonna surrounded by angels, is by the same master. Immediately to the right of the entrance to the NAVE is an elegant tabernacle by *Mino da Fiesole*. The chapels contain little to detain the traveller. The TRANSEPT is reached by an ascent of seven steps, adjoining which is the inscription *Fons olei*, indicating the alleged site of the spring of oil. In the transept on the left are the tombs of two Armellini and an ancient relief of the Virgin and saints. Opposite is an altar erected to St. Philip and St. James by Card. Philip of Alençon; r. his tomb (d. 1397); l. tomb of Card. Stefaneschi (d. 1417), with recumbent figure by *Paolo Romano*. — The MOSAICS in the TRIBUNE belong to different periods. Above, on the arch, are the older ones, dating from the 12th cent.: the Cross with Alpha and Omega, under the symbols of the Evangelists; r. and l. Isaiah and Jeremiah. On the vaulting Christ and the Virgin enthroned; l., St. Callistus, St. Lawrence, Innocent II.; r., St. Peter, St. Cornelius, Julius, Calepodius. The lower mosaics are ascribed by Vasari to *Pietro Cavallini*, a master of the transition period from the Cosmas family to Giotto, and have been restored by Camuccini. They represent the 13 lambs and scenes from the life of Mary; in the centre of the wall a mosaic bust of Mary with St. Peter, St. Paul, and the donor Stefaneschi (1290). — The SACRISTY contains a Madonna with SS. Rochus and Sebastian, ascribed to Perugino, and a fragment of ancient mosaic (ducks and fishermen, the former admirable).

The *Via di S. Maria della Scala*, beginning to the N.W. of S. Maria in Trastevere, leads past the church of *S. Maria della Scala* to the *Porta Settimiana* (p. 327) and the beginning of the *Via Garibaldi* (p. 328). — The *Via di S. Francesco a Ripa* leads to the S.E. from the Piazza S. Maria in Trastevere to (6 min.) the church of *S. Francesco a Ripa*, see p. 332.

From the island in the Tiber (p. 204), we cross the temporary wooden bridge beside the *Ponte Cestio* to the *Lungaretta* (p. 330), the E. continuation of which, the *Via Lungarina*, is undergoing alterations to adapt it for an approach to the new iron bridge at the Piazza Bocca della Verità (p. 248). At present the traffic passes through the *Via della Luce*, *Via Anicia*, and other narrow and dirty side-streets. From the iron bridge the *Via de' Vascellari* and its prolongation, the *Via di S. Cecilia*, lead to —

***S. Cecilia in Trastevere** (Pl. II, 15), originally the dwelling-house of the saint, which was converted into a church by Urban I., restored by Paschalis I., and entirely rebuilt by Card. Franc. Acquas-





THIRD SECTION.

ENVIRONS OF ROME.

1. The Campagna.

The vast CAMPAGNA DI ROMA, bounded on the N. by the Ciminian Forest, on the W. by the sea, and on the E. by the Apennine chain of the Sabina, affords an ample field for a number of the most interesting excursions. The mountains with their picturesque outlines, and the wild and deserted plain, covered in every direction with imposing ruins, chiefly of ancient origin, present attractions of the highest order, to which years of study might fitly be devoted.

The Campagna, which was once covered by the sea, owes its origin to powerful volcanic agency; lava and peperine are of frequent occurrence, and the red volcanic tufa is seen everywhere. A great number of ancient craters may be distinguished, the most important of which are the lakes of the Alban Mts., the lake of Bracciano, the lake of Vico in the Ciminian Forest, and the crater of Baccano. The historical associations connected with this plain are, however, of still higher interest than its natural features. The narrow strip of land which stretches between the Alban Mts. and the Tiber towards the sea is the ancient LATIUM, which victoriously asserted its superiority over the Etruscans on the N., the Sabines on the E., and the Volscians on the S., subsequently effected the union of the Italian peninsula, and finally acquired supremacy over the whole world. Once a densely peopled land, with numerous and prosperous towns, it is now a vast and dreary waste, of which barely one-tenth part is furrowed by the ploughshare. In May, when the malaria begins to prevail, herdsmen and cattle retire to the mountains, while the few individuals who are compelled to remain behind are rendered miserable by continual attacks of fever. The cause of this change dates from so remote a period as the last centuries of the republic, when the independent agricultural population was gradually displaced by proprietors of large estates and pastures. This system inevitably entailed the ruin of the country, for a dense population and a high degree of culture alone can avert the malaria, which is produced by defective drainage and the evap-

oration of stagnant water in the undulating and furrowed volcanic soil. In the middle ages the evil increased. The popes repeatedly endeavoured to promote the revival of agriculture, and the Italian government has continued their policy, but such attempts cannot be otherwise than abortive as long as the land is occupied by farms and pastures on a large scale. An entire revolution in the present system, energetically and comprehensively carried out, will alone avail to restore the prosperity of the land. The large estates are usually let to *Mercanti di Campagna*, or contractors on a large scale. These entrust the management of the land to a *Fattore*, or bailiff, who resides at the *Tenuta* or *Casale*, as the farm-house is called. The system of tillage and the agricultural implements used are of a very primitive character.

After several hours' sight-seeing in churches and galleries visitors in Rome will find it a pleasant relief to spend the latter part of the afternoon at the *VILLAS* (*Borghese*, *Albani*, *Doria-Pamphilj*, etc.) situated just beyond the gates. Excursions to the Campagna proper, however, generally require at least half-a-day. Those whose residence in Rome is sufficiently prolonged should make the excursions in the plain in winter, and those among the mountains in the warmer season. In the height of summer excursions in the plain should be avoided as much as possible.

As far as the gates, and for $\frac{1}{2}$ M. or more beyond them, the roads are dull and uninteresting from being flanked by lofty walls. A cab should therefore be taken at least as far as the gate. *Fares*, see Appx.; *Carriages* and *Saddle-horses* for the Campagna, see p. 119.

The traveller is particularly cautioned against the risk of taking cold, owing to the great and sudden change of temperature which generally takes place about sunset. Lying or sitting on the ground in winter, when the soil is extremely cold in comparison with the hot sunshine, is also to be avoided. In crossing the fields care should be taken to avoid the formidable herds of cattle, especially in spring; and the same remark sometimes applies to the dogs by which they are watched when the herdsman is absent. Predatory attacks on travellers are of rare occurrence, but enquiry as to the state of the country is by no means superfluous (p. xvi). Ladies should never undertake expeditions to the more solitary districts without escort; and even the masculine traveller should arrange his excursion so as to regain the city shortly after sunset.

The excursions are enumerated according to the order of the gates from N. to E. and S. (comp. the annexed Map, on a scale of 1:60,000). Those who wish minuter details should consult the admirable maps of the Italian Ordnance Survey, some of which are on a scale of 1:25,000 and others of 1:50,000. For a careful study of the topography of the neighbourhood *Nibby's 'Dintorni di Roma'* (3 vols., Rome, 1849) is indispensable.


From the Porta del Popolo.

TRAMWAY to *Ponte Molle*, 2 M., starting just outside the gate (25 c.). One-horse carr. about 2 fr. — From *Ponte Molle* to *Acqua Acetosa* $1\frac{1}{4}$ M. — From *Ponte Molle* to *Prima porta* $3\frac{1}{2}$ M. (one-horse carr. about 10 fr.).

Porta del Popolo (Pl. I, 15, 18), see p. 146. On the right, just outside the gate, is the entrance to the —

**Villa Borghese* (Pl. I, 18, 21; adm., p. 122), founded by *Card. Scipio Borghese*, nephew of Pius V., and afterwards enlarged by the addition of the Giustiniani gardens. The beautiful and extensive grounds, containing several ancient statues and inscriptions, form a favourite promenade. Most visitors will prefer to make the excursion







sion by carriage (cabs admitted), as benches to rest on are few and far between.

On entering, we follow a footpath which skirts the carriage-road on the right, and leads through an *Egyptian Gateway* (8 min.). Farther on we pass a grotto with antique fragments (left). After 4 min. the road divides. Following the left branch (as to the other, see below), which leads through an *Artificial Ruin* with two columns, we observe on the left the private gardens of the prince, and farther on reach an imitation of a *Ruined Temple*. Turning to the right here, we come in 10 min. to a circular space with a *Fountain*. (Or this spot may be reached by the first broad path to the right beyond the columns, leading through an avenue of evergreen oaks to a small temple, and thence to the left, through another avenue.) From this point the road leads in 5 min. to the Casino, to which also beautiful, shady footpaths lead from the left of the fountain.

If we proceed straight from the above-mentioned bifurcation of the path, we observe on the left, after 3 min., the remains of *Raphael's Villa*, and in 3 min. more an arch with a *Statue of Apollo*, whence the road turns to the left and leads to the Casino.

The CASINO (adm., p. 123), which was handsomely restored by Marc. Ant. Borghese in 1782, formerly contained one of the most valuable private collections in existence, which was purchased by Napoleon I. and sent to the Louvre. Prince Borghese, however, has founded a new *Museum* here, which contains several objects of great interest, though some of the most important have been temporarily removed to private apartments to which entrance is not permitted.

Ground-Floor. 1. VESTIBULE: Two candelabra; on the narrow walls two reliefs, probably from the triumphal arch of Claudius which once stood in the Corso near the Pal. Sciarra. Several sarcophagi; one of them, to the left by the wall of the egress, with a harbour, lighthouse, and ships.

II. SALOON ('Salone'), with ceiling-painting by *Mario Rossi*. On the floor, mosaics, discovered in 1835 near the Tenuta di Torre Nuova, with gladiatorial and wild beast combats. Left wall: 3. Colossal head of Isis; 4. Dancing Faun, under it a Bacchic relief; 5. Colossal head of a Muse (?). Long wall: 7. Tiberius; 8. Meleager; 9. Augustus; above, a raised relief of a horseman (M. Curtius?); *10. Priestess; 11. Bacchus and Ampelus. Right wall: 14. Hadrian, 16. Antoninus Pius (colossal busts); under No. 15 a Bacchic relief. Entrance-wall: 18. Diana.

III. ROOM (1st to the right). In the centre: *Juno Pronuba, found near Monte Calvi. Left wall: 4. Ceres. Opposite the entrance: 8. Relief, Sacrificial prayer (of Hesiod?) to Cupid; *11. Relief, Rape of Cassandra. Right wall: 16. Draped statue. Entrance-wall: 20. Greek tomb-relief.

IV. ROOM. In the centre: Amazon on horseback contending with two warriors. Entrance-wall: 2. Pan; 4. (and 17, opp.) Sarcophagus with the labours of Hercules; on the cover, Reception of the Amazons by Priam; 6. Head of Hercules; 7. Pygmy. On the left wall: 9. Herma of Hercules. Wall of the egress: 15. Hercules in female attire. Window-wall: 21. Venus; 23. Three-sided ara with Mercury, Venus, and Bacchus.

V. ROOM. In the centre: Apollo. Left wall: 3. Scipio Africanus. Following wall: 7. Head of a Mænad or Bæchante; 8. Melpomene; 9. Genre-group; 10. Clio. Right wall: 14. Lueilla, wife of L. Verus. Entrance-wall: 18. Polyhymnia.

VI. ROOM: 'Gallery' with modern busts of emperors in porphyry. In the centre a porphyry bath, said to have been found in the mausoleum of

Hadrian; 3. Diana, restored as a Muse; 8. Diana; 22. Bacchus; 24. *Itérna* of Bacchus, the head of bronze, the pedestal of coloured alabaster; *29. *Hérma* of a Satyr in basalt; 32. Bronze statue of a boy. The figures of *Æneas* bearing *Anchises*, *Apollo* and *Daphne*, and *David* with the sling are early works of *Bernini*.

VII. Room, with columns of *giallo antico* and porphyry; on the floor ancient mosaics. Left wall: *2. Boy with bird; 3. *Bacchus*; *4. Captive boy. Wall of the egress: 7. Recumbent *Hermaphrodite*; 9. *Sappho* (doubtful); 10. *Tiberius*. Entrance-wall: *13. Roman portrait-bust (said to be *Domitius Corbulo*); *14. Head of a youth, perhaps *Meleager*; 15. Boy with a piteher, a fountain-figure; *16. Female bust.

VIII. Room. Left wall: 2. *Athene*; 4. *Apollo* (archaistic style). Following wall: 6. Figure from a tomb; 7. *Candelabrum* with *Ilecate*. Right wall: 8. *Nymph*; 10. *Leda*. Entrance-wall: 15. *Æsculapius* and *Telesphorus*.

IX. Room. In the centre: *Satyr on a dolphin, a fountain-figure, the model of the *Jonah* in *S. Maria del Popolo* attributed to *Raphael* (p. 148); 3. *Isis*; 4. *Paris*; 8. Female statue, inaccurately restored as *Ceres*; 10. Gipsy-woman (17th cent.); 13. *Venus*; 14. Female figure (archaistic); *16. *Bacchante*; 18. *Satyr*; 19. *Hadrian*; 20. *Satyr*.

X. Room. *1. Dancing *Satyr*, wrongly restored (he originally played on a flute); 2. *Ceres*; 3. *Mercury* with a lyre; 4. Dancing *Satyr*; 8. *Satyr*, after *Praxiteles*; 9. *Pluto* with *Cerberus*; 14. *Periander*; 19. *Bacchus* enthroned. Fine ceiling-paintings by *Conca*.

The upper floor is closed at present.

The ROAD FROM THE PORTA DEL POPOLO TO THE PONTE MOLLE, the ancient *Via Flaminia*, is at first flanked by garden-walls. After 1/2 M. a road diverges to the right to the *Villa di Papa Giulio* ('*Vicolo dell' Arco Oscuro*', see below). At one corner of this road rises the *Casino di Papa Giulio*, a Renaissance edifice attributed to *Jac. Sansovino* and *Bald. Peruzzi*, but probably not erected till 1550 or later. — The road to the Promenade on the *Monti Parioli* also diverges to the right.

This fine new promenade, called the *Parco Regina Margherita*, was opened in 1889. On the slope of the *Monti Parioli* the remains of the *Basilica of St. Valentine*, dating from the 4th cent., were excavated in 1888. Behind is the entrance to its catacombs. The promenade leads along the ridge of the hill, commanding beautiful views, then descends to the *Tiber* near the *Acqua Acetosa* (p. 337; thence back to the *Villa Albani* and *Porta Pineiana*, see p. 172), follows the course of the river as far as the *Forte Antemne*, and ends at the *Via Salara* (p. 341).

To the right, farther on, is *S. Andrea*, founded by *Julius III.* in commemoration of his deliverance from the Germans in 1527, erected by *Vignola* in an admirable Renaissance style. A little on this side of the bridge, to the right, is a second *Chapel of St. Andrew*, erected by *Pius II.* on the spot where he met the head of *St. Andrew*, when brought hither from the *Peloponnesus* in 1462.

We then cross the *Tiber* by the **Ponte Molle**, which was constructed on the foundations of the ancient *Pons Milvius*, built by the *Censor M. Æmilius Scaurus* in B.C. 109. The four central arches are antique. The last thorough restoration took place in 1805. when the superstructure in the form of a triumphal arch, designed by *Valadier*, was added.

Beyond the *Ponte Molle* are several osterie at the tramway-terminus (p. 334). The road divides. The branch to the left is the *Via Cassia*, (see p. 389); that to the right, near the river, is the *Via*

Flaminia; while to the extreme left is the road coming from the *Porta Angelica* (see below).

From the *VIA FLAMINIA*, a road diverges to the left, after about 35 min., to the *Val di Pussino*, with a picturesquely situated 'tenuta'. To the right of the road are the ruins of an ancient tomb, named *Tor di Quinto*. Adjacent is the new race-course. About 3 M. from the *Ponte Molle* the *Via Flaminia* crosses the *Valchetta*, a brook descending from *Veii*, the ancient *Cremera*, where the *Fabii* sustained their well-known defeat. Beyond the *Tiber* lies *Castel Giubileo*, the ancient *Fidenæ* (p. 341). About 1 M. farther on the road reaches the *Casale di Prima Porta*, with the ruins of the imperial *Villa of Livia*, or *Ad Gallinas*, where the statue of *Divus Augustus* (p. 313) was found in 1863. A room with *Mural Paintings, representing a garden with trees, plants, and birds, in excellent preservation, is particularly interesting ($\frac{1}{2}$ fr.). — Not far from *Prima Porta* is a station of the ancient road, called *Saxa Rubra*; here, in the plain by the river, *Maxentius* was defeated in 312 by *Constantine* fighting under the sign of the cross ('*labarum*'). *Maxentius* was drowned in the *Tiber* at the *Ponte Molle*.

Pedestrians may return from the *Ponte Molle* either by the *Acqua Acetosa* or by the *Villa Madama*. The road to the former, commanding fine views of the *Sabine Mts.* and of *Mt. Soracte* on the left, diverges to the E. from the high-road on the left bank of the *Tiber*, immediately beyond the bridge. It follows the river-bank and reaches ($1\frac{1}{2}$ M.) the *Acqua Acetosa*, which is also passed by the new promenade of the *Parco Regina Margherita* (p. 336). The mineral spring which rises here is much esteemed. The well-house, designed by *Bernini*, was erected under *Alexander VII.* in 1661, and restored in 1712.

By the road leading hence immediately to the right towards the town, passing between vineyards, we reach (1 M.) the *Arco Oscuro*, a long vaulted gateway, and beyond it an open space, on the left side of which rises the *Villa di Papa Giulio*, erected by *Vignola* for *Julius III.*, long in a dilapidated state but lately restored and arranged as a museum for the interesting objects discovered at *Falerii* (p. 67).

On the *GROUND FLOOR* are two rooms with richly-decorated ceilings by *Taddeo Zuccaro*, and the court with its fountain also deserves notice. — *UPPER FLOOR*. Room I: Rude clay vessels and large wooden coffins (made out of hollowed trees) from the deepest parts of the excavations. Middle Room: Vases, partly of Grecian workmanship, partly rude native imitations; beautiful terracotta ornaments and figures from a temple, tomb-inscriptions in the *Faliscan dialect*, painted on tiles, etc. The ceiling-paintings are views of *Rome* in the 16th century.

The '*Vicolo dell' Arco Oscuro*' leads hence back to the ($\frac{1}{4}$ M.) high-road (p. 336).

From the *Ponte Molle* a road leads on the right bank of the *Tiber* straight to the *Porta Angelica* (comp. Pl. I, 8), from which, after $\frac{3}{4}$ M., a road diverges to the right to ($\frac{1}{2}$ M.) the *Villa Madama*, situated on the N. slope of the *Monte Mario*, and about 2 M. from the *Porta Angelica*. The villa was erected by *G. Romano* from *Raphael's* designs for *Card. Giulio de' Medici*, afterwards *Clement VII.*, and subsequently came into possession of the *Princess Margaret*, daughter of *Charles V.*, from whom it derives its name (comp. p. 192).

It next belonged to the Farnese family, and then to the kings of Naples. The building is in a very dilapidated condition. It contains a picturesque, overgrown fountain-basin, and a fine *Loggia with mouldings and half-effaced frescoes by *Giulio Romano* and *Giovanni da Udine*. Beautiful view. (Fee $\frac{1}{2}$ fr.)

Monte Mario was anciently named *Clivus Cinnae*, in the middle ages *Monte Malo*, and its present name is derived from Mario Mellini, the owner in the time of Sixtus IV. of the *Villa Mellini* on the summit. This villa is now included in the *Forte Monte Mario*, and visitors are not admitted.

By the high-road issuing from the *Porta Angelica* (comp. Pl. I, 8), and running to the N.W., the *Villa Mellini* and the fort are about 2 M. from Rome (omn. hourly; No. 25, p. 2 of the Appendix). If we follow the road for $\frac{3}{4}$ M. more, passing the church of *S. Onofrio* (on the right), and then take the field-road leading back towards the left, we reach the *Valle dell' Inferno*, a deep ravine overgrown with cork-trees, over which we obtain a charming peep of the dome of S. Peter's, framed by the Alban Mountains.

From the *Porta Salara*.

From the *Porta Salara* to the *Ponte Salaro*, 2 M. — From the *Ponte Salaro* to the *Villa Spada* (Fidenæ), $2\frac{1}{2}$ M.

The *Porta Salara* (Pl. I, 27), which, like the *Porta Pia* (p. 341), was seriously injured by the bombardment of 20th Sept., 1870, has been restored. The removal of its two towers brought to light a well-preserved ancient monument in 'peperino', resembling that of *Bibulus* (p. 163).

The *Via Salara* (Pl. I, 27), a very ancient road, quits Rome by the bank of the Tiber and then turns towards the country of the Sabines. On this road, to the right, $\frac{1}{3}$ M. from the gate, is the —

***Villa Albani**, founded in 1760 by Card. Aless. Albani, built by *C. Marchionne*, and embellished with admirable works of art. Napoleon I. sent 294 of the statues to Paris, which on their restitution in 1815 were sold there by Card. Giuseppe Albani, in order to avoid the cost of transport; some of them now adorn the Glyptothek at Munich. The villa was purchased in 1866 by Prince Torlonia (d. 1886), to whose heirs it now belongs.

Three paths bordered with hedges diverge from the entrance (comp. p. 122); that in the centre leads to a *Circular Space* with a column in the middle, and then to a TERRACE with a fountain whence a comprehensive survey is obtained: to the left is the *Casino* with the galleries on each side; opposite is the so-called *Bigliardo*, a small building flanked with cypresses; on the right in the crescent is the 'Caffè'.

I. CASINO. Ground Floor. VESTIBULE. In the six niches: 54. *Tiberius* (?); 59. *L. Verus*; 64. *Trajan*. Farther on, on the other side of the staircase in the vestibule mentioned below: 72. *M. Aurelius*; 77. *Antoninus Pius*; 82. *Hadrian*. In the centre, 61. Sitting female figure (*Faustina*); 66. Circular Ara with *Bacchus*, *Ceres*, *Proserpine*, and three *Horæ*; 74. Another with female torch-bearer and the Seasons; 79. Sitting female figure (perhaps the elder *Agrippina*). By the pillars on the left and right are hermæ: by the first on the right, 52. *Hermes*; by the 5th on the left, 68.

Female, and on the right, 67. Male double herma; by the 7th on the right, 80. Euripides. — We now return to the beginning of the Vestibule and enter the ATRIO DELLA CARIATIDE, to the left: 16, 24. Two canephoraë, found between Frascati and Monte Porzio (baskets new). In the centre, 19. Caryatide, by the Athenians *Criton* and *Nicolaus* (the names engraved on the back of the vessel), found in 1766 near the Cæcilia Metella; on the pedestal, 20. so-called "Capaneus struck by lightning. In the GALLERY adjacent, on the left: hermaë; the third to the right, 45. Seipio Africanus; to the left, 29. Epieurus.

From the vestibule we pass through a small ante-room on the left to the STAIRCASE. In front of the staircase (left), 9. Roma sitting on trophies (relief). Adjacent, 11. Relief of a butcher's shop. On the staircase, reliefs: on the first landing, (r.) 885. Death of Niobe's Children; (l.) 889. Philoctetes in Lemnos (?); third landing, above, 898, 899. Dancing Bæchantes.

Upper Floor (when closed, visitors ring; $\frac{1}{2}$ fr.).

I. SALA OVALE. In the centre, 905. Apollo on the tripod, with his feet on the omphalos. To the left of the door, 906. Statue of a youth by *Strophanos*, a pupil of Pasiteles. Opposite: *915. Cupid bending his bow, perhaps a copy of Lysippus. — On the right —

II. GALLERIA GRANDE, the principal saloon (on the ceiling Apollo, Mnemosyne, and the Muses, painted by *Raph. Mengs*). In the niches of the entrance-wall: *1012. Pallas, and 1010. Zeus. Reliefs (over the door): 1004. Apollo, Diana, Leto in front of the temple of Delphi (archaistic choragic victory relief). Then to the right, 1013. A youth with his horse, from a tomb near Tivoli; left, 1018. Antoninus Pius with Pax and Roma. The eight fragments of mosaic at the sides of this door and that of the balcony, and in the four corners, are for the most part antique. — By the left wall: 1020. Two women sacrificing; to the right, 1007. Dancing Bæchantes. By the window-wall: 1005. Hercules and the Hesperides; 1009. Dædalus and Icarus. Beautiful view from the balcony.

TO THE RIGHT of the principal saloon: III. First Room. Over the chimney-piece: *1031. Mercury bringing Eurydice back from the infernal regions, an Attic relief of a period soon after that of Phidias, an exquisite example of the noble simplicity for which ancient art is so justly celebrated. By the entrance-wall, (r.) *1034. Theophrastus; window-wall, (l.) 1036. Hippocrates; wall of the egress, (r.) 1040. Socrates. — IV. Second Room. Wall of the entrance, on the right: 35. *Pinturicchio* (?), Madonna with SS. Laurence and Sebastian on the left, St. James and the donor on the right; to the left of the entrance, 45. Lunette by *Cotignola*: Dead Christ with mourning angels. Right wall: 36. *Niccolò Alunno*, Altar-piece: Madonna and Saints (1475). Wall of the egress: *37. *Pietro Perugino*, a picture in six sections: Joseph and Mary adoring the Infant Christ, Crucifixion, Annunciation, Saints (1491). — V. Third Room. Wall of the entrance, (r.) 49. *Van der Werff*, Descent from the Cross. Right wall: 55. *Van Dyck*, Christ on the Cross. Opposite the entrance, 59. *Salaino*, Madonna.

TO THE LEFT of the principal saloon: VI. First Room. Over the chimney-piece, *994. the celebrated Relief of Antinous, from the Villa of Hadrian, the only sculpture brought back from Paris in 1815. Entrance-wall: *997. Shepherdess playing the flute. — VII. Second Room. To the left of the entrance: 980. Archaic Greek relief from a tomb. Left wall: *985. Greek relief in the best style, a group of combatants, found in 1764 near S. Vito. Below it: 988. Procession of Hermes, Athene, Apollo, and Artemis (archaistic style). By the window to the left, 970. Archaic statue of Pallas, found near Orte; on the right, 975. Archaic Venus. Wall of egress, on the left: Greek tomb-relief (half of it modern). — VIII. Third (corner) Room: 21. *Holbein* (?), Portrait, 1527; 20. *Raphael*, Fornarina, a copy; *48, *17. *Giulio Romano*, coloured designs (in oils, on paper) for the frescoes from the myth of Psyche in the Pal. del Tè at Mantua. The cartoons of Domenichino, and several other pictures formerly here, have been removed to a room on the lower floor, which is at present closed. — IX. Fourth Room. In front of the window: *965. Æsop, perhaps after *Lysippus*, the head beautifully executed. In the niche in the entrance-wall, 952. Apollo Sauroctonus, after *Praxiteles*. Opposite, 933. Farnese Hercules, a small copy in bronze. Window-wall on the right, (r.) 942. Small statue of Diogenes. Exit-wall, (l.) *957. Small

relief of the Apotheosis of Hercules; on the pillars at the sides a record of his exploits is inscribed (resembling the *Tabula Iliaca* in the Capitol, p. 220). — X. Room with pictures of inferior value. — XI. Room with tapestry.

Returning to the oval saloon, we again descend to the —

Ground Floor, and inspect the other wing of the vestibule. Here, at the extremity to the left, corresponding to the *Atrio della Cariatide*, is the: I. *ATRIO DELLA GIUNONE*. 91, 97. two Canephore; 93. So-called Juno. — II. *GALLERY*. In the niches, *103. Bacchante with Nebris; *106. Satyr with the young Bacchus. Some of the herms by the pillars are fine, but arbitrarily named. — In a straight direction: III. *STANZA DELLA COLONNA* (generally closed, fee 25 c.). Antique columns of variegated alabaster, found in the *Marmorata*. On the left, *131. Sarcophagus with the Nuptials of Peleus and Thetis; above, four sarcophagus-reliefs; on the left, 135. Hippolytus and Phædra; over the egress, 139. Rape of Proserpine; on the right, 141. Bacchanalian procession; over the entrance, 140. Death of Alcestis. — IV. Passage: Bearded Bacchus (archaistic). — V. *STANZA DELLE TERRACOTTE*. By the left wall, close to the entrance: 146. Greek tomb-relief; 147. Greek votive relief. Beyond the door: 157. Love-sick Polyphemus and Cupid; 161. Diogenes and Alexander. Opposite the entrance, 164. Dædalus and Icarus, in rosso antico. Below, 165. Ancient landscape-picture. On the right wall, 171. Mask of a river-god; to the left of it, 169. Bacchus pardoning captive Indians; to the right of the mask, and on the entrance-wall, several fine reliefs in terracotta. — VI. Room. In the centre, Leda with the swan. — VII. Room. Above the entrance-door, Bacchanalian procession of children, from Hadrian's Villa, in pavonazetto, or speckled marble; left, statue of a recumbent river-god; right, Theseus with the Minotaur, found near Genzano in 1740. — VIII. Room. Relief in the first window to the left, the God of Sleep. — The exit here is generally closed.

An avenue of oaks, flanked with *cippi* (tombstones), leads from the last-named apartments of the Casino to the —

II. **BIGLIARDO**, containing a few unimportant antiques, and to the —

III. **CAFFÈ**. In the semicircular HALL, to the left: 594. Herma of Alcibiades; (l.) 604. Statue of Mars; 610. Chrysippus; 612. Apollo reposing; 628. Caryatide. Farther on, beyond the entrance to the saloon: (l.) on a detached column, 721. Homer. Adjacent, 725. Caryatide; (r.) by the 3rd pillar, 737. Mask of Poseidon. Obliquely opposite, (l.) 744. Archaic Greek portrait-head, Pericles (?), or perhaps Pisistratus; (l.) 749. Statue, called Sappho, perhaps Ceres. — We now return to the middle of the hall and enter the ANTE-ROOM. Here, in the section to the right, 711. Iris; (l.) 706. Theseus with Æthra, perhaps a sarcophagus-relief. In the section to the left, 641. Marsyas bound to the tree; (l.) 639. Relief of Venus and Cupid. Also several statues of comic actors. — In the SALOON (25-50 c.), in the niche to the left of the door, 662. Libera with a fawn. Below, 663. Mosaic with meeting of seven physicians or mathematicians. Corresponding to the latter, to the right of the door, 696. Mosaic, liberation of Hesione by Hercules. To the right of the balcony-door, 688. Ibis, in rosso antico; 684. Atlas, bearer of the Zodiac; (l.) 678. Boy with comic mask; 676. Colossal head of Serapis, in green basalt.

Before entering the hall of the Caffè, we may descend a flight of steps to the left, leading to its basement. Fragments of sculpture are here built into the walls, and a few Egyptian statues are placed in a hall. In the centre: Ptolemy Philadelphus, in gray granite; (r.) the cat-headed goddess Pasht; (l.) statue of a king, in black granite; a sphinx. On a fountain in front of the hall: reclining Amphitrite; on the left and right two colossal *Hermæ of Tritons.

The GARDEN also contains many antique statues, among which the colossal busts of Titus on the left, and Trajan on the right, below the terrace in front of the Casino, deserve mention.

We may now return by the avenue of evergreen oaks, which is entered by an arch at the end of the left gallery of the Casino. In

the centre of the avenue is a colossal bust of the German antiquarian *Winckelmann*, a friend of Card. Albani, the founder of the villa, by *E. Wolff*, erected by order of Lewis I. of Bavaria. — An annexe of the villa, in the Via Salara, contains a *Collection of Plaster Casts*, formed by Prince Torlonia (admission on Frid. only, after 12 noon).

The *Via Salara* passes other lofty houses farther on, some of which are still unfinished. About $\frac{1}{2}$ M. beyond the Villa Albani a broad road diverges to the left to the new *Parco Regina Margherita* (to the *Acqua Acetosa* about 1 M., p. 337). Still $\frac{1}{2}$ M. farther on is the *Osteria di Filomarino*, whence a fine view may be obtained, especially towards evening, of S. Agnese and S. Costanza. On the hill to the left, now crowned by the *Fortezza Maggiore Antenne*, lay *Antennae*, which was destroyed by Romulus. Thence to the banks of the Tiber several avenues are to be laid out in connection with the new promenade and continued on the E. as far as the *Via Nomentana*.

The *Via Salara* reaches the *Anio* about 2 M. from the city-gate. The **Ponte Salaro** over the *Anio*, several times destroyed and renewed, and again blown up during the invasion of Garibaldi in 1867, has preserved little of the original structure. — Beyond the bridge is an ancient tomb, built over in the middle ages.

About 5 M. from the gate is the *Villa Spada*. From this point to the height on the right extended the ancient *Fidenae*, the ally of Veii against Rome, and only subdued after protracted struggles. Few traces of the ancient city are now recognisable. The fortress lay close to the river, on the hill which is now occupied by *Castel Giubileo* (6 M. from Rome; p. 68). The summit (265 ft.) affords a beautiful and extensive *View. The castle was erected by Boniface VIII. in 1300, a year of jubilee (hence the name).

The road continues to skirt the river in the plain, and 11 M. from Rome reaches the *Scannabechi*, the ancient *Allia*, on which the Romans were signally defeated by the Gauls, B.C. 390. The railway-station of *Monte Rotondo* (p. 68) is 2 M. farther on.

From the Porta Pia.

From the *Porta Pia* to *S. Agnese* about $\frac{1}{4}$ M. (omnibus No. 18, p. 2 of the Appendix); thence to *Ponte Nomentano* and *Mons Sacer*, to which point most travellers will extend their walk, also $\frac{1}{4}$ M.

The *Porta Pia* (Pl. I, 27, 30), famous in the annals of 1870, was begun by Pius IV. from designs by Michael Angelo in 1564. On 20th Sept., 1870, the Italians directed their bombardment chiefly against this gate, and soon effected a breach at the side of it, through which they entered the city. The damage has since been repaired. On the outside, to the left, a memorial tablet, bearing the names of 33 soldiers of the Italian army who fell on the occasion, marks the place where the breach was made. To the right of the gate is the old *Porta Nomentana*, walled up since 1564, which led to Nomentum

(p. 343). — A new suburb is springing up outside the gate, like that adjoining the *Via Salara* (see p. 341).

Following the main road, the ancient *Via Nomentana*, past the *Villa Torlonia* (on the right; no admittance), we reach, on the left, $1\frac{1}{4}$ M. from the gate, —

***S. Agnese Fuori le Mura**, a church founded by Constantine, over the tomb of St. Agnes, and still retaining many characteristics of an early-Christian basilica (p. xlv). It was re-erected by Honorius I. in 625-38, altered by Innocent VIII. in 1490, and restored by Pius IX. in 1856. The principal festival, on 21st Jan., is the 'blessing of the lambs' from whose wool the archiepiscopal robes are woven.

We enter by a gateway, where, to the right, is the entrance to the residence of the canons, with remnants of old frescoes in the corridor of the 1st floor, dating from 1454, and including an Annunciation. In the Court, through a large window to the right, we observe a fresco painted in commemoration of an accident which happened to Pius IX. on 15th April, 1855. The floor of a room adjoining the church, to which his Holiness had retired after mass, gave way, and he was precipitated into the cellar below, but was extricated unhurt. On the farther side of the court, on the right, is the entrance to the church, to which a STAIRCASE with 45 marble steps descends. On the walls of the staircase are numerous ancient Christian inscriptions from the catacombs.

The INTERIOR is divided into nave and aisles by 16 antique columns of breccia, porta santa, and pavonazzetto, which support arches. Above the aisles and along the wall of the entrance are galleries with smaller columns. The *Tabernacle* of 1614, borne by four fine columns of porphyry, covers a statue of St. Agnes, in alabaster, a restored antique. In the tribune, **Mosaics*, representing St. Agnes between Popes Honorius I. and Symmachus, dating from the 7th cent., and an ancient episcopal chair. 2nd Chapel on the right: Head of Christ in marble, a mediocre work of the 16th cent.; also a beautiful inlaid altar; above it a *Relief of SS. Stephen and Lawrence, of 1490. In the left aisle, over the altar of the chapel, a fine old fresco, Madonna and Child. — The *Catacombs*, to which there is an entrance in the left aisle, are shown by the sacristan, from whom lights are also obtainable (1 fr.; see p. 361).

Leaving the covered flight of steps which descends to S. Agnese, and descending to the right, we reach —

S. Costanza (if closed, apply to the custodian of S. Agnese, $\frac{1}{2}$ fr.), originally erected as a monument by Constantine to his daughter Constantia, but converted into a church in 1256. The dome, 70 ft. in diameter, is borne by 24 clustered columns of granite. A few fragments only of the vestibule and the wall of the central part of the edifice now exist. In the tunnel-vaulting of the aisle are **Mosaics* of the 4th cent. with genii gathering grapes, in the ancient style, but bearing traces of decline. The porphyry sarcophagus of the saint, formerly in one of the niches (now in the Vatican Museum, Sala a Croce Greca, p. 305), is similarly adorned. In a niche, Christ as the ruler of the world with SS. Peter and Paul, and again in the opposite niche with St. John. — The *Coemeterium Ostrianum*, $\frac{1}{4}$ M. from this point, see p. 363.

About $2\frac{1}{2}$ M. from the gate, the road crosses the *Anio* by the **Ponte Nomentano**, an ancient bridge which has been frequently restored, surmounted by a tower. This road is also bordered with

ancient tombs. Beyond the bridge is a hill, conjectured to be the *Mons Sacer* rendered famous by the Secession of the Plebs (at its foot an osteria). View from the top.

About 4 M. farther are the *Catacombs of Alexander* (p. 363).

A little beyond the Catacombs, a road to the right diverges to *Palombara* (p. 374). — The road to the left leads to *Mentana*, a village belonging to the Borghese family, near the ancient *Nomentum*, 14 M. from Rome, where a battle between the Garibaldians and the French and Papal troops took place on 3rd Nov., 1867 (p. 68). The district is extremely bleak at places, but affords beautiful views of the slopes of the Sabine Mts. From *Mentana* to *Monte Rotondo* 2 M., at the foot of which the railway-station of the same name is situated (p. 68).

From the Porta S. Lorenzo.

Tramway from the Piazza delle Terme to S. Lorenzo, see *Tramway-line* No. 2, p. 3 of the Appendix. *Omnibus* from the Piazza della Consolazione viâ the Forum Romanum; see *Omnibus-route*, No. 17. — *Steam Tramway* to Tivoli, see p. 374.

The *Porta S. Lorenzo* (Pl. II, 31) stands on the site of the ancient *Porta Tiburtina*, which led to Tivoli. The gateway, constructed by Honorius against an arch, over which, according to the inscription, passed the three aqueducts Marcia, Tepula, and Julia, is now shut.

The road, the ancient *Via Tiburtina*, starts from an opening in the wall to the S.E. of the gate. It is bounded by walls, and does not afford views of the Sabine Mts. until the church is reached, $\frac{3}{4}$ M. from the gate.

The basilica of ***S. Lorenzo Fuori le Mura** occupies the spot where Constantine founded a church on the burial-place of St. Lawrence and St. Cyriaca. In 578 it was rebuilt by Pelagius II. This ancient edifice, which was entered from the E., was entirely remodelled by Honorius III. (1216-27), who added the present nave to the apse, and transferred the façade with the porch to the W. end. An angle formed by the outer walls shows where the new part was added. Under Nicholas V. and Innocent X., and lastly under Pius IX. in 1864-70, the church underwent extensive alterations, and is now at least partly freed from disfiguring patchwork. S. Lorenzo is a patriarchal church, and one of the seven pilgrimage-churches of Rome (p. 135). Festival, 10th August.

In the piazza in front of the church is a *Column* with a bronze statue of St. Lawrence. In 1864 the *Façade* was embellished with paintings resembling mosaic, representing the founders and patrons of the church: Pelagius II., the Emp. Constantine, Honorius III., Pius IX., Sixtus III., and Hadrian I. The vestibule is borne by six ancient columns, above which is an architrave with mosaics (St. Lawrence and Honorius III.); it contains retouched frescoes of the 13th cent., two tombs in the form of temples, and two rude Christian sarcophagi. The door-posts rest on lions.

The *Interior* consists of two parts. The anterior **LATER CHURCH**, which chiefly dates from HONORIUS III., consists of nave and two aisles, separated

by 22 antique columns of granite and cipollino of unequal thickness. On the capital of the 8th column on the right are a frog and a lizard, and it is therefore supposed, but without authority, to have been brought from the colonnade of Octavia, where two sculptors Batrachus (frog) and Saurus (lizard) are said to have adopted this method of perpetuating their names. Above the plain entablature rises a wall recently adorned with frescoes by *Fraccassini* (on the right, history of St. Lawrence; on the left, that of St. Stephen), and the gaudily-painted open roof. The pavement, in opus Alexandrinum, dates from the 12th cent. (p. xlvii). Under a mediæval canopy to the right of the entrance is an ancient *Sarcophagus with a representation of a wedding, in which in 1256 the remains of Card. Fieschi, nephew of Innocent IV., were placed. In the nave are the two elevated ambones, that to the *right (p. xlv) for the gospel, near which is a wreathed candelabrum for the Easter candle, that to the left for the epistle (12th cent.). On the triumphal arch are modern paintings (resembling mosaics) of the Madonna and saints. At the extremity of the N. aisle a flight of 12 steps, on the left, descends to a chapel and the catacombs.

Adjoining this building of Honorius on the E. is the **OLDER CHURCH**, erected by PELAGIUS, the pavement of which lies 3 ft. lower. The raised central space, to which seven steps ascend on each side of the Confessio, dates from the time of Honorius, who converted the nave of the older church into a choir with a crypt by laying a pavement halfway up the columns, and caused the aisles to be filled up. The rubbish has been recently removed, and the original level of the aisles exposed to view. The church of Pelagius, a basilica with aisles in the style of S. Agnese Fuori (the only two examples of churches with galleries at Rome), was originally entered at the opposite (E.) end. Twelve magnificent fluted columns of pavonazzetto with Corinthian capitals (those of the two first are formed of trophies, on the benches in front of them are mediæval lions) support the *Entablature, which consists of antique fragments and bears a gallery with graceful smaller columns. On the triumphal arch, of which this is the original front, are restored mosaics of the time of Pelagius II.: Christ, right SS. Peter, Lawrence, and Pelagius; left SS. Paul, Stephen, and Hippolytus. The canopy dates from 1148. The dome is modern. By the wall at the back is the handsome episcopal throne. — We now descend the flight of steps leading from the prolongation of the aisles of the anterior church to the aisles of the church of Pelagius. The nave of the old church has now been partly converted into a crypt, as above mentioned. In the vestibule is the *Tomb of Pius IX.* (d. Feb. 7, 1878), whose body was transferred hither in 1881 from its temporary resting-place in St. Peter's. The monument, which according to the injunctions of the deceased pope is of the plainest character, consists of a marble sarcophagus in a niche like those in the catacombs.

The handsome old ***Cloisters** (*Chiostro*; generally closed; apply to one of the monks to the right in the sacristy) contain numerous fragments of sculptures and inscriptions built into the walls; in the corner to the right of the principal entrance is the lid of a sarcophagus adorned with the triumphal procession of Cybele.

Adjoining the church is the **Campo Verano**, an extensive church-yard, consecrated in 1837, and repeatedly enlarged since; the upper part commands a beautiful view of the mountains and the Campagna. By the entrance are colossal figures of Silence, Charity, Hope, and Meditation. Among the numerous handsome monuments are one commemorating the Battle of Mentana, erected in 1870, and another (with statue) to the poetess Erminia Fua-Fusinato (d. 1876). On the whole, however, the cemetery is less interesting than those in several other Italian towns. Fine view of the mountains and the Campagna from the higher part of the cemetery, reached by several flights of steps.

From the Porta Maggiore.

Two high-roads issue from the *Porta Maggiore* (Pl II, 35; p. 180): to the left the *Via Prænestina* and to the right the *Via Labicana*.

The ancient *Via Praenestina*, or *Palestrina* road, to the left, is little frequented, but, as the city is left behind, commands beautiful views of the mountains. About 1 M. from the gate the vineyard-walls cease. Numerous ruins of tombs on the right indicate the direction of the ancient route, which, lying higher, affords a freer view than the present lower level of the road, and may be reached by crossing the fields. About $2\frac{1}{2}$ M. from the city-gate is the **Tor de' Schiavi**, the scanty ruins of an extensive villa of the time of Diocletian.

First, to the left of the road, is a *Hexagonal Structure*, almost entirely fallen to decay. A column in the centre and the additional erection on the summit, both mediæval, impart a grotesque appearance to the place. — Farther on is a *Circular Building* with niches and dome, used in the middle ages as a church, with now nearly obliterated frescoes; below, entered from the back, is a vault supported by strong pillars in the centre. Both these buildings are supposed to have belonged to baths. Among the extensive ruins on the right of the road are a few *Columbaria*.

The *Via Collatina*, diverging here to the left, skirts the *Acqua Vergine* and leads to ($9\frac{1}{2}$ M.) *Lunghezza* (p. 373). — Beyond this point the *Via Prænestina* offers little of interest, except the continuous view of the mountains.

On the *Via Prænestina*, $3\frac{1}{2}$ M. from the gate, are the ruins of *Tor tre Teste* and *Tor Sapienza*, the so-called *Villa of the Gordiani*. About $3\frac{1}{2}$ M. farther on the road crosses the *Fosso di Ponte di Nona* by an ancient bridge of seven arches. Near the *Osteria dell' Osa*, 2 M. farther on, to the left of the road, is the site of the ancient *Gabii*, on the bank of the drained *Lago di Castiglione*. Some ruins are visible near the conspicuous tower of *Castiglione*, the most interesting of which are the hewn stone remains of the celebrated temple of *Juno Gabina*.

At the *Osteria dell' Osa* the ancient *Via Prænestina* turned to the right towards (6 M.) *Gallicano* (see below), but the modern road bends to the N.E. and forks at the foot of the mountain, the left arm leading to the *Via Tiburtina*, which it reaches at the *Ponte Lucano* (p. 374), the right arm, passing *Corcolle* and *Passerano*, to *Gallicano* (10 M. from the *Osteria dell' Osa*). The ancient and modern roads unite just before the last-named place at the *Osteria di Cavamonte*, the name of which recalls the cutting, 65 ft. deep, made for the old road in the tufa rock. The *Aqua Claudia* passes over it. The road finally leads past the monastery of *S. Paslore* to ($5\frac{1}{2}$ M.) *Palestrina* (p. 353).

The road leading to the right from the *Porta Maggiore*, the ancient *Via Labicana*, now called *Via Casilina*, is more frequented than the preceding, and is traversed thrice a week by a 'vetturino'. On this road, $1\frac{3}{4}$ M. from the gate, are situated the remains of the octagonal *Tomb of the Empress Helena*, whose sarcophagus found here is now preserved in the Vatican (p. 305). The building, which has been fitted up as a small church (*SS. Pietro e Marcellino*; catacombs, see-p. 363), is named **Torre Pignattāra** from the 'pignatte', or earthenware vessels used for the sake of lightness in the construction of the vaulting, as was customary during the empire, but

is otherwise uninteresting. Torre Pignattara is a station on the steam-railway to Marino (p. 367).

About 8 M. from the gate, near the *Ponte della Catena*, is a modern aqueduct, the *Acqua Felice* (p. 347). Farther on, to the left, are remains of the arches of the ancient *Aqua Alexandrina*. A lake ('il Laghetto'), now drained, to the left of the road, at the foot of the *Monte Falcone*, is supposed to be the famous *Lake Regillus*, where the Romans defeated the Latins (B. C. 496). — On an isolated eminence, 15 M. from Rome, lies *Colonna*, beyond which, nearer the lofty *Monte Compatri*, lay the ancient *Labicum*. — The road gradually ascends to the *Osteria di S. Cesareo*, a thatched cottage to the left (good wine), beyond which it forks. The branch to the right leads *viâ Lagnano* (recently erroneously renamed *Labico*) to (6 M.) *Valmontone* (p. 382); the left branch leads to (4½ M.) *Palestrina* (p. 383).

From the Porta S. Giovanni.

From the gate to the *Tombs* 2¼ M.; thence to *S. Urbano* ¾ M. (p. 351). Driving is practicable as far as the tombs. Custodian on the spot from noon to sunset, except in summer (fee ½ fr.; for a party 1-1½ fr.). — From this point we may cross the meadows to *Porta Furba* (½ M.), and thus combine the two excursions. Those who are driving should order their carriage to meet them at *Porta Furba*.

Porta S. Giovanni, see p. 273, and comp. Pl. III, 33, 36. — The ancient **Via Latina** diverged from the *Via Appia* outside the *Porta Capena*; the now closed *Porta Latina* in the wall of Aurelian was destined for its point of issue (p. 256). Like the *Via Appia* and the other roads emerging from Rome, it was bordered by tombs on both sides, several of which, interesting especially on account of their decorations, were excavated in 1862.

We follow the road to Albano (the *Via Appia Nuova*), commanding beautiful views, in a straight direction. At the *Trattoria Baldinotti* the road to the left leads to *Frascati* (p. 364). The high-road is followed as far as the second milestone (1.) of the present route, immediately beyond which we quit it by a road leading to the left to the ancient *Via Latina*, passing the remains of the old road, with two **Ancient Tombs**, which may be reached by carriage.

The 1st TOMB, *Tomba dei Valerii*, to the right of the road, with the two recently-restored Roman pilasters, consisted of an anterior court and subterranean tomb, over which rose the now re-erected sacellum with two columns. The interior of the chamber is decorated with interesting *Reliefs in stucco, sea-monsters, nymphs. and genii.

The 2nd TOMB, *Tomba dei Pancratii*, under a shed opposite, contains in its single chamber landscapes framed in stucco *Ornaments and four stucco reliefs (Judgment of Paris, Alcestis, Priam and Achilles. Hercules playing the lyre before Bacchus and Minerva). The 'Pancratii' were one of the burial societies common in the 3rd and 4th cent., but the plan and arrangements of the tomb prove that it dates from the 2nd century.

The other tombs are interesting only for their tile ornamentation (Corinthian pilaster-capitals and cornices).

In the immediate vicinity the foundations of a *Basilica*, dedicated to *St. Stephen* in the 5th cent., have been excavated. It is now surrounded by a wall, of which the custodian of the tombs keeps the key.

From the *Via Appia Nuova*, ¼ M. farther, a road diverges to the cold mineral-baths of *Acqua Santa*, passes the circus* of *Maxentius* and *S. Urbano*, and leads to the *Via Appia* near the Catacombs of *Callistus* (pp. 361, 348). The *Osteria del Tuvolato*, on the *Via*

Appia Nuova, $\frac{1}{4}$ M. farther on, is a station on the Marino tramway (p. 367).

PORTA FURBA. This excursion of 2-3 hrs. is pleasanter than many others, as the view is obstructed by walls for short distances only (carriage thither from the gate and back, 3-4 fr.).

From *Porta S. Giovanni* we follow a straight direction for 5 min. (see p. 346), and at the Tratt. Baldinotti we take the Frascati road to the left, which farther on is crossed by the railway to Civit  Vecchia. To the left runs the unbroken series of arches of the *Acqua Felice*, and in front of them occasionally appear the *Aqua Claudia* and *Marcia*, running one above the other. The *Acqua Felice*, about 13 M. long, completed by Sixtus V. (Felice Peretti) in 1585, and afterwards frequently restored, begins at the base of the Alban Mts. near Colonna (two-thirds subterranean), and terminates in the Piazza S. Bernardo (p. 168). The *Aqua Marcia*, 56 M. long, constructed by the Pr tor Q. Martius Rex in B.C. 146, and restored in 1869, enters the city by the *Porta Pia*, and brings a supply of water from the Sabine Mts., which is considered the purest in Rome. Over it flows here the *Aqua Claudia*, erected in A.D. 50 by the Emp. Claudius, extending from Subiaco, a distance of 59 M. — To the right, a view of the *Via Appia* with the tomb of *C cilia Metella*.

About 2 M. from the gate we reach the so-called **Porta Furba**, an arch of the *Acqua Felice*, under which the road leads. An exquisite *View is enjoyed here of the Campagna and the Alban Mts., and a little farther on, the Sabine Mts. also come in sight. Below runs the railway to Naples and Frascati. — About 2 min. from the *Porta Furba*, the **Osteria del Pino* stands by the pine on the right. — About $\frac{1}{2}$ M. beyond it rises the *Monte del Grano*, with a tower, which commands a magnificent *PANORAMA. A long shaft leads to an ancient circular tomb-chamber in the interior of this hill, where the so-called sarcophagus of Alexander Severus (p. 217) was found.

From the Porta S. Sebastiano.

The excursion to the *VIA APPIA* by carriage, including halts, requires 3-3 $\frac{1}{2}$ hrs. (one-horse carr. to Casale Rotondo and back, 9-10 fr.). Good walkers will take 4 $\frac{1}{2}$ -5 hrs.: from the arch of Constantine to *Porta S. Sebastiano*, $\frac{1}{4}$ M.; from the gate to the *Catacombs of St. Callistus*, $\frac{1}{4}$ M.; thence to the beginning of the excavated part of the ancient *Via Appia*, 1 M.; to the *Casale Rotondo*, 2 M. more. — The traveller is recommended to drive as far as the *Catacombs of Callistus* (2 $\frac{1}{2}$ fr.), a visit to which is conveniently combined with this excursion, and to walk thence to the *Casale Rotondo* and back. — Or he may take a tramway-car (Tramway-line No. 2, p. 3 of the Appendix) at about 11 a.m. from the *Piazza delle Terme* as far as *S. Lorenzo fuori*, change there to the steam-tramway for S. Marino, alight at *Le Capannelle* (p. 367, 1 fr. 20 c.), and proceed thence to (1 $\frac{1}{2}$ M.) *Casale Rotondo*. It is not advisable to adopt this route in the reverse direction, as there is no waiting-room at *Le Capannelle*, and the trains run very irregularly.

The route by the *Via di Porta S. Sebastiano* to the *Porta S. Sebastiano* (Pl. III, 28), and the ruins and buildings situated near it, are described at pp. 254 et seq.

The ***Via Appia**, the military road constructed by the censor Appius Claudius Cæcus (in B.C. 312), led by the ancient *Porta Capena*, near the church of S. Gregorio (p. 258), to Capua, whence it was afterwards extended to Beneventum and Brundisium. In 1850-53 it was excavated as far as the 11th milestone, where it is now intersected by the railway to Albano. Even at the present day the Via Appia merits its proud ancient title of the 'queen of roads'. It affords perhaps the finest of all the nearer excursions in the Campagna. Shortly after leaving the city, we enjoy a magnificent prospect, embracing the Campagna, the ruins of the aqueducts, and the mountains, while numerous ancient tombs are situated on each side of the road. Very few of the latter are preserved intact; but the remains of others have been carefully restored, so as to convey an idea of their architecture and decorations.

The road descends from the *Porta S. Sebastiano* by a declivity corresponding with the ancient *Clivus Martis*, and after 4 min. passes under the railway to Civit  Vecchia. It then (3 min.) crosses the brook *Almo*, where ruins of tombs are observed on both sides. The Via Ardeatina now (5 min.) diverges to the right; and on the left stands the small church of **Domine Quo Vadis**, so named from the legend that St. Peter, fleeing from the death of a martyr, here met his Master and enquired of him, 'Domine quo vadis?' to which he received the reply, 'Venio iterum crucifigi'; whereupon the apostle, ashamed of his weakness, returned. A copy of the footprint which Christ is said to have impressed on the marble is shown here.

On the Via Ardeatina, about $4\frac{1}{2}$ M. from the gate, lies the picturesque *Cecignola*, with an old tower; the castle and garden were added by Paul V. and Leo XII.

By a small circular chapel, about a hundred paces beyond the church, a field-road diverges to the left, to the Caffarella Valley (see p. 351). The road now ascends, being hemmed in for the next $\frac{1}{2}$ M. by monotonous walls. To the left, in the *Vigna Vagnolini*, are considerable remains of the largest ancient *Columbarium* yet discovered. Its three apartments, of which that to the left is now used as a dwelling, and that in the centre as a wine-cellar, were capable of containing 5000 urns. Charming view hence of the valley of the Caffarella and the Via Latina.

To the right, No. 33, $1\frac{1}{4}$ M. from the gate, is the entrance to the *Catacombs of St. Callistus* (p. 361), furnished with an inscription, and shaded with cypresses.

Farther on the road again divides. The arm to the left, the 'Via Appia Pignatelli', is the new road which leads to S. Urbano (p. 351) and the baths of Acqua Santa (p. 352), and unites near Le Capannelle (p. 347; $2\frac{1}{2}$ M. from the bifurcation) with the high-road to Albano.

We follow the branch of the road to the right, the 'Via Appia Antica', descend past the entrance (on the left, No. 37, *Vigna Randanini*) of the *Jewish Catacombs* (p. 363), and reach the church of S. Sebastiano, situated $1\frac{1}{2}$ M. from the gate. This church has from

a very early period been one of the seven churches frequented by pilgrims, being erected over the catacombs where the remains of so many martyrs reposed. Mention of it is first made in the time of Gregory the Great. The form was originally that of a basilica, but in 1612 it was altered by *Flaminio Ponzio* and *Giovanni Vasanzio*. The portico is supported by six ancient columns of granite.

The 1st CHAPEL on the right contains the original 'footprint of Christ' on stone. The last chapel on the right was designed by *C. Maratta*. Over the HIGH ALTAR is a painting by *Innocenzo Tacconi*, a pupil of Annibale Carracci. The second chapel on the left contains a good statue of St. Sebastian, designed by *Bernini* and executed by *Giorgini*. A staircase on the left, by the egress, descends to the CATACOMBS (p. 363).

Immediately before we come to the church, the *Via delle Sette Chiese* diverges to the right, intersecting the *Via Ardeatina* after 10 min., and in 4 min. more reaching the recently excavated remains of the *Basilica of St. Petronilla*, or of *SS. Nereo ed Achilleo* (see p. 362). Thence to S. Paolo Fuori 11½ M., see p. 352.

Continuing to follow the *Via Appia* we come to a large gateway on the left, which we pass in order to reach the ***Circus of Maxentius**, situated on the left side of the road. The circus, which is 350 yds. long, and 86 yds. broad, was constructed in 311, and is now sufficiently excavated to show the arrangement of the structure, which was designed for chariot-races.

Facing the *Via Appia* was an extensive portico, and behind it one of the principal *Entrances*, with another opposite to it in the semicircle which terminated the building (on the branch of the road mentioned at p. 348). At the sides were other gates, of which the first on the right is supposed to be the *Porta Libitina*, by which the dead were carried out. On each side of the first-mentioned main entrance were the *carceres*, or barriers. The chariots starting hence had to perform seven times the circuit of the course, which was formed by the seats of the spectators and the *spina*, a wall erected longitudinally in the centre of the arena, and embellished with statues and obelisks, one of which last now stands in the Piazza Navona (p. 190). At the ends of this wall stood the *metae*, or goals. The *spina* was placed somewhat obliquely, for the purpose of equalising the distance as much as possible to those starting in different positions, and for the same reason the *carceres* are in an oblique line. The spectators sat on ten surrounding tiers of steps, on which about 18,000 persons could be accommodated. It is worthy of remark that pottery has been used in the formation of the tiers of seats.

The ruins of a circular building near the circus, on the *Via Appia*, are supposed to be a *Temple of Romulus*, the son of Maxentius, who died young, and in whose honour the circus was perhaps also constructed.

The road again ascends, and, in 35 min. from the *Porta S. Sebastiano*, leads us to the ***Tomb of Cæcilia Metella**, which forms so conspicuous an object in the views of the Campagna. It is a circular structure, 65 ft. in diameter, which, as well as the square pedestal, was originally covered with travertine. The frieze which runs round the building is adorned with wreaths of flowers and skulls of oxen, from which last the tomb is sometimes called *Capo di Bove*. On a marble tablet facing the road is inscribed: *Cæciliae Q. Cretici Filiae Metellae Crassi*, i.e. to the daughter of Metellus Creticus, wife of the younger Crassus, son of the triumvir. The interior, now al-

most entirely filled up, contained the tomb-chamber of the deceased. In the 13th cent. the Caetani converted the edifice into the tower of a stronghold, and furnished it with battlements. To this extensive castle, which subsequently passed through various hands, and was destroyed under Sixtus V., belong the picturesque ruins of a palace adjacent to the tower, and a church opposite. — A little beyond the tomb the 'Via Metella' diverges to the left (see p. 352).

As far as this neighbourhood extends a lava-stream which once descended from the Alban Mts. and yielded paving material for the ancient road. The more interesting part of the Via now begins; the ancient pavement is visible in many places, the road is skirted on both sides by continuous rows of ruined tombs, and the view becomes more extensive at every step. On the left are perceived the adjacent arches of the Aqua Marcia and the Aqua Claudia, the latter now partly converted into the modern Acqua Felice (comp. p. 347). The houses on the roadside gradually cease, and $2\frac{1}{4}$ M. from the city-gate, beside the osteria of the *Vigna Savi*, we reach the entrance (indicated by a notice on a house to the right) to the excavated part of the Via Appia, flanked beyond this point by a constant succession of tombs. Many of these contain reliefs and inscriptions worthy of note. The scenery continues to be strikingly beautiful. On the right is the *Fortezza Appia Antica*, an outwork of the new fortifications of Rome.

About $1\frac{1}{4}$ M. from the Vigna Savi, on the left, is a 'casale' built within the walls of an ancient church, which is called *S. Maria Nuova*. Beyond it lie the extensive ruins named *Roma Vecchia*, which appear to have belonged to a spacious villa of the Quintilii. Several of the chambers were employed as baths. Then, on the right, are two conical tombs, overgrown with trees, commanding an extensive view of the barren Campagna. Close by is an *Ustrinum*, or place used for cremations, surrounded by a wall of peperine.

A large tomb on the left, the site of which is now occupied by a small farm, $\frac{3}{4}$ M. from S. Maria Nuova, is named the *Casale Rotondo*. It may be ascended for the sake of the fine view (25 c.; often closed). The lofty building on the left, 7 min. from the Casale Rotondo, is also an ancient tomb, on which the Arabs and Normans erected a tower, named *Tor di Selce* (tower of basalt).

The Via Appia from the Tor di Selce to Albano ($7\frac{1}{2}$ M.) is less interesting. Among the tombs may also be mentioned, on the left, 2 M. beyond Tor di Selce, the circular *Torraccio*, or *Palombaro*. At the 11th milestone the road is crossed by the railway, a little beyond which is the *Osteria delle Fraticchie*, where the old road and the Via Appia Nuova unite. On the left side of the road Clodius once possessed a villa; to the right in the valley lay *Bovillae*, a colony of Alba Longa, with a sanctuary of the Gens Julia, where the remains of a theatre and circus may still be traced. Remains of walls and tombs are seen on both sides of the road. A large square structure, about 33 ft. in height, with three niches, was long erroneously regarded as the tomb of Clodius. The road ascends. The high ground here commands a fine survey of the Campagna, the sea, and Rome. Near the gate of Albano, at the 14th milestone, on the left, is the so-called Tomb of Pompey (p. 369).

TEMPLE OF THE DEUS REDICULUS. GROTTTO OF EGERIA. S. URBANO. — From the Arch of Constantine to *Domine Quo Vadis* about 2 M., thence to S. Urbano $1\frac{1}{4}$ M. (thus far driving is practicable); from this point across the fields to the *Via Appia Nuova* and *Via Latina* $1\frac{1}{2}$ M.; back to the *Porta S. Giovanni* $2\frac{1}{4}$ M. — Or from S. Urbano to the ancient *Via Appia*, reaching it not far from the tomb of Cæcilia Metella, $1\frac{1}{4}$ M.

At the small chapel beyond the church of *Domine quo Vadis* (p. 348) we take the field-road, which is very muddy after rain, to the left, leading for $\frac{1}{2}$ M. between hedges. On reaching the open fields, we follow the road descending to the left to the mill. Near the latter is situated the so-called **Temple of the Deus Rediculus**, a Roman tomb of Hadrian's time, on an ancient road which formerly issued from the now closed *Porta Latina* (comp. p. 346). The building has been assumed by some, but without authority, to be a temple erected by the Romans, after the retreat of Hannibal, to the deity who 'turned back' the Carthaginians. The front, facing the N., was approached by a flight of steps; the entrance to the tomb is in the left side-wall. One side is ornamented with hexagonal pilasters in niches, the whole being an excellent example of skilful brick architecture. The interior (25 c.) contains two stories with groined vaulting.

Returning hence to the road, we ascend the valley of the *Almo*, or *Caffarella*. The hill (with the 'Grove of Egeria') forming the termination of the valley is conspicuous. The carriage-road along the brook is at present closed by a fence, at the point where the path to the *Tenuta* diverges to the left. We may either climb the fence or make a detour by the hill to the right to S. Urbano (see below). Farther on, where the road to Urbano ascends to the right, we follow the path by the brook. This path leads to the so-called **Grotto of Egeria**, which was sought for here owing to a misinterpretation of a passage of Juvenal, and a confusion between the Aurelian and the Servian walls. The 'grotto' is a *Nymphæum*, originally covered with marble, the shrine of the brook *Almo*, which now flows past it in an artificial channel, and was erected at a somewhat late period. A niche in the posterior wall contains the mutilated statue of the river-god, standing on corbels from which water used to flow. The niches in the lateral walls were also once filled with statues.

The footpath now passes a small, but formerly more extensive wood on the hill, commanding an admirable view of the *Campagna* and the *Alban Mts.*, where, according to the account of the *ciceroni*, Numa is said to have held his interviews with the nymph Egeria.

To the right (N.), opposite us, is situated **S. Urbano**, a Roman tomb of the time of the Antonines, long regarded as a temple of Bacchus, and recognised from a distance by its red brick walls. It seems to have been converted into a church in the 11th cent., from which period the paintings date.

The edifice was provided with a portico borne by four Corinthian columns, which was probably walled up during the restoration in 1634, on which occasion the flying buttresses were also added.

The INTERIOR is adorned with paintings between the Corinthian

pilasters, restored under Urban VIII., but interesting on account of their origin. They were executed, according to an inscription on the Crucifixion over the door, by a certain *Bonizo* in the year 1011. On the posterior wall is Christ on a throne imparting blessings; also scenes from the lives of Christ, St. Urban, and St. Cecilia. — A staircase, now walled up, is said to lead to the catacombs.

To the W. of S. Urbano is the (2 min.) 'Via Appia Pignatelli' (p. 348), which leads to the right to the (9 min.) Via Appia Antica and to the left to the (2 min.) Circus of Maxentius, which we may traverse, in order to reach the Via Appia below the Tomb of Cæcilia Metella (p. 349).

In the other direction the pedestrian from S. Urbano may cross the fields to the 'Via Metella', which leads from the tomb of Cæcilia Metella to the tombs on the Via Latina (p. 346); or, traversing the fields beyond the Via Metella, he may proceed past the *Baths of Acqua Santa* to the *Osteria del Tavolato* (station of the tramway to Marino mentioned at p. 367; comp., however, the remark on Le Capannelle at p. 347).

From the Porta S. Paolo.

From the Piazza Bocca della Verità (p. 249) to the *Porta S. Paolo*, 1 M.; thence to the church of *S. Paolo Fuori*, $1\frac{1}{2}$ M.; to the *Tre Fontane*, $1\frac{1}{2}$ M. more. — A digression to the three churches on the Aventine (pp. 252, 253), Monte Testaccio, and the Pyramid of Cestius (pp. 251, 252), may conveniently be made from the route to the Porta S. Paolo. — TRAMWAY direct to S. Paolo Fuori from the Piazza Montanara (tramway-line No. 5, p. 3 of the Appendix; between Piazza Montanara and Piazza di Spagna, omnibus-line No. 24, p. 2 of the Appendix).

Porta S. Paolo (Pl. III, 16), see p. 252. — A few hundred paces from the gate the road is crossed by the railway to Fiumicino and Cività Vecchia. About midway to the church of S. Paolo a small chapel on the left indicates the spot where, according to the legend, St. Peter and St. Paul took leave of each other on their last journey. Before we reach the church, the pleasant *Via delle Sette Chiese* diverges to the left at an acute angle to S. Sebastiano on the Via Appia, 2 M. distant; comp. p. 349.

***S. Paolo Fuori le Mura**, founded in 388 by Theodosius and Valentinian II. on the site of a small church of Constantine, was completed by Honorius and was restored and embellished by many of the popes, especially Leo III. Prior to the great fire of the night of 15th July, 1823, this was the finest and most interesting church at Rome. It was a basilica with double aisles and open roof; and the architrave was supported by eighty columns of pavonazzetto and Parian marble, adorned with busts of the popes. It contained numerous ancient mosaics and frescoes, and in the Confessio the sarcophagus of St. Paul, who, according to tradition, was interred by a pious woman named Lucina on her property here. The front towards the Tiber was approached by a colonnade, and early in the middle ages an arcaded passage connected it with the city.

Immediately after the fire, Leo XII. began the work of restora-

tion, which was presided over by *Belli*, and afterwards by *Poletti*. The transept was consecrated by Gregory XVI. in 1840, and the whole church by Pius IX. in 1854, on the occasion of the meeting of the Council. The plan and the dimensions are the same, but for slight divergences, as those of the original building, with which, however, the gorgeous decoration is somewhat inconsistent. The chief façade, with a portico borne by splendid monolithic columns of Simplon granite, is turned towards the Tiber. The mosaics on the upper part of it, representing Christ with SS. Peter and Paul, in the symbolical style of the early Christians, with the four great prophets below them, were executed by F. Agricola and Consoni, in the papal mosaic manufactory (1875). — The chief church festivals take place on Jan. 25th, June 30th, and Dec. 28th.

The *Interior (130 yds. in length, 65 yds. in width, 75 ft. in height), with double aisles and a transept, is entered by the portico on the N. side (or from the road at the E. end, by a side-door adjoining the campanile, and through the vestibules mentioned below). The ceiling of the nave, which is richly coffered instead of being open, or entirely flat, like that of the early-Christian basilicas, is borne by 80 columns of granite from the Simplon.

The imposing effect of the vast dimensions and the valuable materials of the church is best perceived from the W. end of the nave, a little on one side. The two yellowish columns of oriental alabaster at the entrance, as well as the four of the canopy of the high-altar, were presented by the Viceroy of Egypt, and the malachite pedestals by the Emp. Nicholas of Russia. Above the columns of the nave and aisles, and in the transept, is a long series of *Portrait Medallions* of all the popes in mosaic (each 5 ft. in diameter). Between the windows in the upper part of the NAVE are representations from the life of St. Paul by *Gagliardi*, *Podesti*, *Consoni*, *Balbi*, etc. The windows of the external aisles are filled with stained glass (Apostles and Fathers of the church, with their names surrounded with glories). On the sides of the approach to the transept are the colossal statues of SS. Peter and Paul; the **Confessio*, or shrine, is richly decorated with red and green marble from Greece.

The CHANCEL ARCH is adorned with *Mosaics* of the 5th cent., executed by order of Galla Placidia, sister of Honorius and Arcadius: Christ with the 24 Elders of the Revelation. On the side next the transept: Christ in the centre, left St. Paul, right St. Peter. — Under the arch is the HIGH-ALTAR, with a *Canopy by *Arnolfo del Cambio*, the architect of the cathedral of Florence, and his assistant *Pietro* (1285). — In the TRIBUNE **Mosaics* of the beginning of the 13th cent.: in the centre Christ, with Pope Honorius III. at his feet; on the right SS. Peter and Andrew, on the left SS. Paul and Luke. Under these are the Apostles and two angels. Below them is the modern episcopal throne. — The LEFT TRANSEPT contains the (1st) CHAPEL OF ST. STEPHEN, with a statue of the saint by *Rinaldi*, and two pictures (Stoning of St. Stephen, by *Podesti*, and the Council of high-priests, by *Coghetti*). (2nd) CAPPELLA DEL CROCIFISSO: in front of the mosaic below it, Ignatius Loyola and his adherents pronounced the vows of their new order, 22nd April, 1541. — On the right, adjoining the Tribune, the (1st) CAP. DEL CORO, designed by *C. Maderna*, was spared by the fire. (2nd) CAP. DI S. BENEDETTO, with his statue by *Tenerani*. — By the narrow walls of the TRANSEPT: to the left, altar with the Conversion of St. Paul by *Camuccini* and the statues of St. Romuald by *Stocchi*, and St. Gregory by *Laboureur*; to the right, altar with the Coronation of the Virgin by *Podesti*, and statues of SS. Benedict and Theresa by *Baini* and *Tenerani*. Easter candlebrum by *Niccolò de Angiolo* and *Pietro Vassulletto*, with scenes from

the life of Christ, and ornamentation of animal forms and foliage, in fine workmanship of the 12th century.

In a straight direction from the right transept is the entrance to the monastery (see below); to the left we pass through several chapels containing some ancient but freely restored frescoes, and reach a VESTIBULE with a colossal statue of Gregory XVI., and a few frescoes and ancient mosaics rescued from the fire. The most interesting mosaics are the half-figures of SS. Peter and Paul, dating from about the 5th century. In this room is the side-entrance to the church beside the campanile mentioned above, and to the right is the entrance to the Sacristy, which contains several good oil-paintings. Over the door the Scourging of Christ (by *Signorelli* ?), on the right a Madonna with SS. Benedict, Paul, Peter, and Justina. Also four single figures of the same saints. In a room beyond the sacristy is a sitting marble figure of Pope Boniface IX., an interesting work of the beginning of the 15th century. A closed cabinet here contains the bronze door of the ancient basilica, executed at Constantinople in 1070 by order of the consul Pantaleon; in spite of injuries inflicted by fire and thieves, it still retains much of its former magnificence. It is adorned with scenes from sacred history inlaid in silver.

The MONASTERY attached to the church belonged to the Benedictines from 1442 to our own time, but has recently been secularised and declared a 'monumento nazionale'. It is shown by an official in uniform (ring; no fee). The beautiful *Cloisters (*Chiostro*) of the 12-13th cent. (p. xlv) are inferior to those of the Lateran alone. According to the mosaic inscription round the wall they were commenced by *Petrus de Capua*, Abbot of St. Paul's, 'arte suū' (1193-1208), and completed under John V. (1208-41); the decoration is perhaps by *Petrus Vassallettus*, a master in this kind of work (comp. p. 267).

On the walls are numerous heathen and early-Christian inscriptions from the catacombs, and a few fragments of ancient and mediæval sculptures, among them a large sarcophagus with the history of Apollo and Marsyas. Other parts of the convent contain numerous early-Christian inscriptions and medallions of popes from the old basilica; the latter perhaps date from the beginning of the 5th cent., but have been repainted and are on the whole of little iconographic value.

The main road leads on in a straight direction and (7 min. beyond the church) divides at the *Osteria del Ponticello*: on the right the ancient *Via Ostiensis* diverges to Ostia (p. 394), and on the left the *Via Laurentina* leads in 25 min. to the —

Abbadia delle Tre Fontane (*ad aquas Salvias*), which was almost deserted on account of the unhealthiness of the situation and was made over in 1868 to French Trappists. Owing to extensive plantation of the rapidly-growing Eucalyptus the sanitary condition of the place is said to have improved. The name is derived from the legend that the apostle Paul was executed here, and that his head was observed to make three distinct leaps, corresponding to which there welled forth three different fountains. The court surrounding the three churches is approached by an archway bearing traces of painting, which is supposed to have belonged to an earlier church of John the Baptist (visitors ring; 25c.).

SS. Vincenzo ed Anastasio, the largest of the churches, a basilica in the ancient style, founded by Honorius I., and restored in 1221 by Honorius III., as the inscription to the left of the choir records, has lately

again undergone restoration. It has retained many mediæval peculiarities, and in particular the marble windows over the nave. The portico bears traces of paintings, including the portrait of Honorius III.

To the right of this is the second church, the circular **S. Maria Scala Coeli**, so called from the 'vision' here vouchsafed to St. Bernard, to whom Innocent III. had presented the monastery, of a heavenly ladder, on which angels were conducting to heaven the persons whom his prayers had released from purgatory. In its present form the church dates from the close of the 16th century. The tribune contains good mosaics by *F. Zuccaro*: the saints Zeno(?), Bernard, Vincent the deacon, and Anastasius(?), who are revered by Clement VIII. and Card. Aldobrandini, the finisher of the church.

The third church, **S. Paolo alle Tre Fontane**, stands on the spot where the apostle is said to have been beheaded, and contains the three springs already mentioned. In the centre is an antique mosaic representing the four seasons, found in Ostia, and presented by the Pope in 1869. By the spring to the right stands the column of white marble to which St. Paul is said to have been bound at the time of his execution. The present edifice dates from 1599.

Before leaving, the visitor is conducted to the distilling-room, where a glass of Eucalyptus liqueur is offered to him (see 50 c.).

The hills above the abbey, which are honeycombed with puzzolana pits, command delightful views. Close by is a large penitentiary.

From the Porta S. Pancrazio.

The Via Garibaldi leads in 5 min. from the *Acqua Paola* (p. 329) to the **Porta di S. Pancrazio** (Pl. II, 9), on the summit of the Janiculum (275 ft.), adjoining the ancient *Porta Aurelia*. It was stormed by the French under Oudinot in 1849, but restored in 1857 by Pius IX. From the *Osteria di Belvedere*, to the right, outside the gate, we have a picturesque view of St. Peter's, which seems to close the vista at the end of a verdant valley. Close by are several other osterie. The surrounding summer-houses and the church and monastery of *S. Pancrazio*, $\frac{1}{4}$ M. to the left, were also seriously damaged in 1849. The church was erected by Symmachus about the year 500, but has been frequently restored. — In a straight direction we reach the entrance to the —

***Villa Doria Pamphilj** (Pl. II, 9; admission, see p. 123), planned by *Algardi*, and skilfully adapted to the undulating character of the ground, at the instance of Prince Camillo Pamphilj, nephew of Innocent X., and now the property of Prince Doria. It is sometimes called by the Italians *Belrespiro*, and the grounds are the most extensive and perhaps the pleasantest near Rome.

On entering, we follow the carriage-road, which passes under a triumphal arch, and leads in windings (8 min.) to the entrance of the Casino, in a reserved part of the garden. On the right is a terrace with a *View of M. Mario and St. Peter's, between which the horizon is bounded by Mte. Soracte, and a part of the Campagna.

To obtain admission to the CASINO, built by *Algardi*, we ring at the gate opposite the terrace. The walls are adorned with reliefs (chiefly from ancient sarcophagi) and statues. The stairs ascend to

the PLATFORM of the villa, commanding a fine *Panorama of the grounds and environs. The sea, to the S.W., is said to be visible in clear weather (fee $\frac{1}{2}$ fr.).

Leaving the Casino, we next visit the **Columbaria* under the trees to the right, discovered in 1838, and situated on the ancient *Via Aurelia*. One of them is well-preserved, and contains some interesting paintings (Prometheus delivered by Heracles, Death of the children of Niobe, etc.). Apply for admission to the custodian of the Casino.

The flight of steps by the Casino descends to the flower-garden, where the camellias are particularly fine.

The carriage-road by which we reached the Casino turns to the left and skirts a meadow, carpeted in spring with anemones (in the centre an altar, with representations of seven gods, and Antoninus Pius holding one of the Penates). After 5 min., where the road turns to the right, a beautiful *View is obtained of the Alban Mts. and the Campagna; it then winds past a celebrated grove of pines and leads along the bank of a (10 min.) pond with swans to the (5 min.) fountain by which it is supplied. The Casino may now be regained either by the direct path, or by the carriage-road, which leads in 4 min. to the hothouses (r.), and the pheasantry (l.), with its beautiful silver-pheasants. On the roadside (l.), 50 paces farther, a monument was erected by Prince Fil. Andr. Doria in 1851 to the memory of the French who fell in 1849 and were interred here.

The Catacombs.

Ancient and Christian Rome seem to be separated by a wide chasm, if the modern appearance of the city alone be regarded. The most ancient churches having disappeared, or being concealed beneath a modern garb, the earliest Christian monuments of any importance are several centuries later than the last Roman structures. This interval is satisfactorily filled up by the *Catacombs*; or burial-places of the early Christians. — Most travellers will be satisfied with a visit to the *Catacombs of St. Callistus*, and perhaps those of *St. Agnese* (both shown daily, except in midsummer; comp. pp. 361, 342). On 22nd Nov. the Catacombs of Callistus are illuminated and open to the public. Information as to admission to the other catacombs may be obtained of the custodians of the Callistus Catacombs.

Scientific visitors may apply for additional information to *Commendatore Giov. Batt. de Rossi*, Piazza Aracœli 17, upper floor.

I. HISTORY OF THE CATACOMBS. The term 'Catacombs' is modern, having been extended from those under S. Sebastiano, to which the topographical name '*ad catacumbas*' was anciently applied, to the others also. The early Christians gave their burial-places the Greek name of *Coemeteria*, i. e. resting or sleeping-places, probably with reference to the hope of the resurrection. The Roman law, frequently re-enacted during the empire, prohibiting the interment of the dead, or even their ashes, within the precincts of the city, was of course binding on the Christians also. We accordingly find their burying-places situated between the 1st and 3rd

milestones beyond the Aurelian wall, to which Rome had extended long before the construction of the wall itself.

While the European nations had become accustomed to dispose of their dead by cremation, the Egyptians and the Jews retained the practice of interment as being more in harmony with their views on the subject of a future state. The prevalence of similar views among the Christians gave rise to the excavation of subterranean passages, in the lateral walls of which apertures were made for the reception of the corpses, Burial-places of this description are to be found at Naples, Syracuse, Chiusi, Venosa, in Alexandria (in Egypt), and elsewhere, as well as at Rome.

It was formerly supposed that the early Christians used ancient arenaria, or pits of puzzolana earth, for this purpose, and extended them according to requirement, but this theory, as well as the belief that the different catacombs were all connected, has been refuted by modern investigation. These subterranean passages are proved to have been excavated almost solely for the purposes of Christian interment, in the soft strata of tufa (tufo granolare), of which most of the hills near Rome consist, and which is rarely employed for building purposes. The hard tufa used for building, and the puzzolana, which when mingled with lime yields the celebrated Roman cement, have been penetrated in a few exceptional cases only.

The Roman Catacombs took their rise from *Family Tombs*, which were named after their original proprietors, such as those of *Lucina*, *Pontianus*, and others. The approaches to these vaults were everywhere wide and conspicuous, without any indication of attempt at concealment. The oldest belong to the first century of our era, while the most recent date from the first half of the 4th century. In the 3rd century the *Church* began to establish burial-places of its own and to take the management of those already existing; and this supervision seems soon to have embraced all the Christian burial-places. Each district was presided over by a presbyter.

During the 3rd cent. the persecuted Christians frequently sought refuge in the Catacombs; but they were sometimes followed into their subterranean places of refuge, or there arrested or slain. Peace was at length restored to the Church and security to the Catacombs by Constantine the Great's edict of Milan. Throughout the 4th cent. interments here were customary, but they became rarer towards the beginning of the 5th, and were soon entirely discontinued, as it then became usual to inter the dead near the churches. The last three Catacombs appear to have been constructed by Pope Julius in 336-47.

The Catacombs, however, as well as the tombs of the martyrs, still enjoyed the veneration of pilgrims and the devout. As early as 370 Pope Damasus caused numerous restorations to be made, and the most important tombs to be furnished with metrical inscriptions; apertures for light were constructed, to facilitate the access of visitors, and the walls at a comparatively late period decorated with

paintings, which differ materially from those of the earliest Christians in subject and treatment. During the frequent devastations undergone by the city, however, the Catacombs were also pillaged and injured, the first time on the occasion of the siege by the Goths in 537, and afterwards during the siege by the Lombards in 755, when they suffered still more seriously. 'The invaders ransacked the burial-places of the martyrs with pious zeal, searching for the bones of saints, which they deemed more precious than gold, and giving them arbitrary names, carried them home in hope of selling them at a great price. That a skeleton was found in Roman soil was sufficient warrant to them for attributing miraculous virtue to it, and thus it probably happened that the greatest sinners buried in the catacombs frequently had their remains exhumed and revered as as those of saints' (Gregorovius). After these different plunderings the Catacombs were restored by John III. (560-73) and Paul I. (757-68); but the transference of the remains of the martyrs to the altars of the city had already taken place in the most wholesale manner. In 609, when Boniface IV. consecrated the Pantheon as a church, he caused twenty-eight waggon-loads of the bones of 'saints' to be disposed beneath the altar; and an extant inscription records that no fewer than 2300 corpses of 'martyrs' were buried in S. Prassede on 20th July, 817. Hadrian I. (772-95) and Leo III (795-816) also made attempts to preserve the Catacombs from ruin, but the task was abandoned by Paschalis I. (817-24), after whose time the Catacombs gradually fell into oblivion, those under S. Sebastiano alone remaining accessible to the visits of pilgrims.

At length we find traces of renewed visits to a few of the catacombs towards the close of the 15th cent. partly by pilgrims, and partly by members of the Roman academy of the humanists, but the scientific exploration did not begin until fully a century later. In 1578 some workmen accidentally discovered an ancient Cœmeterium near the Via Salara, and from that period the subject began to excite general and permanent interest; and the Roman church has since then regarded the supervision of *Roma Sotterranea* as a point of honour. The pioneer of the scientific examination of the Catacombs was *Antonio Bosio* of Malta, who devoted thirty-six years of his life to the task, but his '*Roma Sotterranea*' was not published till 1632, three years after his death. His researches, although afterwards followed up by other scholars, were at length threatened with oblivion, but within the last twenty or thirty years he has been worthily succeeded by the Jesuit *Marchi* and the able brothers *De Rossi*, *Michele*, the geologist, and *Giovanni Battista*, the archæologist. The last has begun to publish the result of his indefatigable labours in a Collection of Ancient Christian Inscriptions (1st vol. 1861), in a work entitled '*Roma Sotterranea*' (1st vol. 1864, 2nd vol. 1867, 3rd vol. 1877), and in the '*Bullettino di Archeologia Cristiana*' (1863 et seq.). Comp. also p. 128.

II. THE ARRANGEMENT OF THE CATACOMBS was originally extremely simple. Narrow passages, $2\frac{1}{2}$ ft. in width, and afterwards even less, were excavated and furnished with *loculi*, or recesses in the sides, of the length of the body to be interred. These niches were placed one above the other, as many as three and more being sometimes thus disposed, and when the body was interred they were closed with tablets of marble, or occasionally of terracotta, which were either left plain, or merely recorded the name of the deceased, with the addition '*in pace*'. The older inscriptions are sometimes in Greek, but the later always in Latin. This change illustrates the progress of Christianity from the position of an alien creed to that of the accepted religion of a native and national community. Important inscriptions are now united in the great collection in the Lateran (p. 271), while the niches are generally empty in consequence of the mania for relic-hunting, already mentioned, which even during the present century is not entirely extinct. The practice is now being introduced of leaving all the monuments in the places in which they are found.

The increase of the community and the transformation of burial-places originally intended for families and their co-believers into public cemeteries could not fail to affect the external arrangements of the Catacombs. By degrees they were extended; the passages became narrower and higher, or rose in several stages, sometimes as many as five, one above another. Catacombs originally distinct were connected by means of new excavations, and the complicated nature of these alterations and extensions is still apparent to the observer. These operations were carried out by a regular society of *Fossores* (or diggers), who ceased to exist only when the use of the catacombs was discontinued. Altered times and circumstances naturally exercised an influence on the appearance of the catacombs. They originally differed little from similar heathen localities; and the use of sarcophagi, instead of interment in the rock without other receptacle, was not uncommon, while other distinctions between the burial of the rich and that of the poor were also sometimes made. In most cases the bodies were wrapped in cloth, on their breast was laid the consecrated bread of the sacrament, and various ornaments and memorials were interred along with them. Adjacent to the slabs which closed the niches were frequently placed earthen lamps, partly as symbols of the resurrection, and perhaps also for practical purposes, just as lamps had always been much used in the heathen observance of worshipping the dead.

The system of monotonous passages was sometimes broken by the introduction of larger chambers, which were used as *cubicula*, or family burial-places, and were private property. Lastly we also find chambers that were set apart for the celebration of divine worship; but these all date from the 4th cent., when they were fitted up for the celebration of ecclesiastical festivals in honour of the

martyrs, which came into vogue at that period. The ordinary services, however, were performed in the private dwelling-houses in the city, and not in the Catacombs, as has been erroneously supposed.

III. THE DECORATION OF THE CATACOMBS is one of their most interesting features. Christian art in origin could, of course, be but an application of ancient precepts to the new objects and conceptions introduced by the new religion. The paintings and sculptures of the Catacombs are therefore in no respect different in style from contemporaneous works, and with them shared in the precipitate and almost total degradation of art. The best frescoes belong to the end of the 1st and beginning of the 2nd century. With the general decline of the Roman empire in the 3rd and 4th century, artistic forms became distorted and unpleasing, and in the case of decorative works there is no difference in style between Christian and heathen art, especially during the earlier periods.

On the other hand, a peculiar significance in the choice and treatment of the subjects is observable from the earliest period. Comparatively few *historical* paintings are met with, and these have no other object in view than the illustration of some simple fact from Jewish or Christian lore. Once the Madonna and Child by themselves are observed (Catacombs of Priscilla); generally they are accompanied by the Magi, varying in number, who present their offerings, as in the Catacombs of St. Callistus, Domitilla, and Priscilla. Scenes of martyrdom do not occur earlier than the 5th century.

The great majority, however, of the paintings represent scenes *symbolical* of the doctrines and hopes of Christianity. That of most frequent recurrence is the *Resurrection*, typified either by the raising of Lazarus, who appears at a door wrapped in his grave-clothes, while Christ, represented beardless, stands before it with a wand, or by the history of Jonah sitting under the gourd, the prophet swallowed by the whale, and his final escape. The Good Shepherd also frequently appears, with the lost sheep on his shoulders, and sometimes surrounded by lambs. Abraham's Sacrifice, Noah in the Ark, and the Hebrew Children in the fiery furnace belong to the same category. Daniel in the lions' den is another favourite subject, and he is generally represented with his hands raised in prayer, an attitude in which the deceased themselves are often depicted ('orantes'). The Miracles of Christ also recur frequently. In the 'sacrament-chapels' of the Callistus Catacombs we also meet with representations of *Baptism*, in realistic style, and the *Last Supper*, treated symbolically. The fish, too, by a kind of acrostic, formed an important Christian symbol, as the Greek *ἰχθῦς* (fish) consists of the initial letters of: *Ἰησοῦς Χριστὸς Θεοῦ Υἱὸς Σωτήρ* (Jesus Christ the Saviour, Son of God). All these subjects and many others, especially the traditions of the Old Testament which contain a typical reference to New Testament history (such as Moses smiting the rock), recur continually in the paintings of the Catacombs.

and in the sculptures on the ancient Christian sarcophagi. The inscriptions corresponding to these were, as already mentioned, of a very simple description down to the middle of the 3rd cent., after which they become more lengthy, and contain more elaborate ejaculations of grief and hope. — For purpose of study, the collections of pictures, inscriptions, and sarcophagi in the Christian museum of the Lateran (p. 270) will be found indispensable.

The Catacombs extend around the city in a wide circle, the majority, however, being concentrated between the Via Salara, the Via Nomentana, the Via Latina, the Via Appia, and the Via Ostiensis. Upwards of forty different Catacombs, varying greatly in extent, and only partially accessible, have been discovered. That of Callistus alone has been thoroughly excavated. According to Michele de Rossi's careful calculations, they cover an area of 615 acres. In order, however, to form an accurate idea of their extent, it must be borne in mind that the passages run one above another, as many as five being sometimes thus disposed. The highest of these lie 22-25 ft. below the surface of the earth, while the lowest are 40-50 ft. deeper. If the whole of these subterranean passages were placed in a continuous line, their total length would be about 545 English miles. The most important of the Catacombs only need be enumerated here, and of these the most instructive are the —

***Catacombs of St. Callistus** on the Via Appia, $1\frac{1}{4}$ M. beyond the Porta S. Sebastiano (p. 348). On entering the vigna in which they are situated, we perceive a small brick building with three apses. This having been identified by Giov. de Rossi as the ancient *Oratorium S. Callisti in Arenariis*, he induced Pius IX. to purchase the ground, and his investigations were speedily rewarded by most important discoveries. Admission to the catacombs (1 fr.) is paid at an adjoining cottage. Three Trappist monks, absolved from the vow of silence, act as guides, and provide lights. The Oratorium contains inscriptions and reliefs from the catacombs, a plan of this city of tombs, and copies of the most important mural paintings. The present entrance to the catacombs immediately adjoins this building. A passage with tombs is traversed,* and the **Camera Papale*, or *Cubiculum Pontificium*, a chamber of considerable dimensions, is soon reached on the left, containing the tombs of several popes (Anteros, Lucius, Fabianus, and Eutychianus); originally also that of Sixtus II., who died as a martyr in the Catacombs in 258. In front of the central wall is a long metrical inscription in honour of those interred here, composed by Pope Damasus about the close of the 4th cent., and engraved in elegant and decorated characters invented specially for the purpose by Furius Dionysius Philocalus, the secretary of that pope. Outside the entrance, on both sides, a great number of inscriptions have been scratched by devout visitors of the 4th-6th centuries. We next enter a *Chamber, open above, which once contained the *Tomb of St. Cecilia*, whose

remains are now in the church of S. Cecilia in Trastevere (p. 331). On the wall here are several Byzantine paintings of the 7th-8th cent. : St. Cecilia, St. Urban, and a head of Christ. The walls of the aperture for light bear traces of other frescoes. On St. Cecilia's Day (22nd Nov.) mass is celebrated here, on which occasion the chapel and the adjoining chambers are illuminated and open to the public. In the sides of the passages near these chapels are several chambers known as 'sacrament chapels', which are adorned with symbolical representations of the communion, baptism, and other scenes of the kind already mentioned. Then follow the *Tomb-Chamber of Pope Eusebius* (309-11), with an old copy of an inscription by Damasus, and another with two sarcophagi still containing the remains of the deceased, one of them preserved in a mummy-like form, the other-almost entirely destroyed. The *Tomb of Pope Cornelius* (251-52) originally belonged to the separate cemetery of *Lucina*.

The **Catacombs of SS. Nereus and Achilleus, or of Domitilla**, near the Catacombs of Callistus, on the Via delle Sette Chiese (p. 349), contain the greatest number of inscriptions (upwards of 900), and are among the earliest foundations of the kind, vying in antiquity with the Crypts of St. Lucina, and the Catacombs of St. Priscilla. Domitilla is said to have been a member of the imperial house of the Flavii. In two of the five ancient entrances are frescoes of the beginning of the 2nd cent., representing genii in the Pompeian style, figures of the Good Shepherd, Daniel, and others of the earliest type. In the centre of the catacomb is the large and nearly quadrangular *Basilica of St. Petronilla*, who, according to the legend, was the daughter of St. Peter. The basilica, built in the second story of the catacomb, projects with its roof into the open air. On the column of a canopy is represented the martyrdom of St. Achilleus in relief, perhaps the earliest work of the kind (5th cent.). Everything else is in a ruined condition, but the church has recently been partly restored. It was used from the 5th to the 8th cent. only.

The **Catacombs of St. Prætextatus**, on the Via Appia towards S. Urbano (p. 351), contain decorations similar to those of the station of the Vigiles at Trastevere (p. 337). In the burial chapel of Vibia here are still to be seen gnostic heretical representations (Hermes as conductor of the dead, etc.).

The **Catacombs of St. Priscilla** lie on the Via Salara, $13\frac{1}{4}$ M. from the gate (p. 338). The oldest part consists of a square chamber, called the 'Cappella Greca', owing to its Greek inscription, which contains interesting paintings of the 3rd century. Farther on, among the decorations of the ceiling, are a Madonna and the Child, with Joseph, the oldest Madonna in existence, dating from the latter half of the 2nd century. Coloured inscriptions on tiles, of the earliest and simplest type, are also occasionally found here.

The **Catacombs of S. Agnese**, under the church of S. Agnese Fuori le Mura (p. 342), are destitute of painting, but are to a great extent still in their original condition. They are shown by the sacristan without a permesso. — About $\frac{1}{4}$ M. beyond the church is another catacomb, called the *Coemeterium Ostriatum*, which contains numerous family burial-places.

The **Catacombs of S. Sebastiano**, below the church of that name on the Via Appia (see p. 348), the only burial-places of the kind which continued to be visited in mediæval times, have been almost entirely deprived of their enrichments. One chamber recently excavated is interesting on account of the portrait of a Christian gladiator which adorns it. — In the vicinity are the —

Jewish Catacombs, in the *Vigna Randanini* (p. 348; adm. 1 fr.), which were excavated about the 3rd century. They rather resemble the catacombs of Naples than the other Roman catacombs. The inscriptions are exclusively Greek and Latin. The most frequently recurring symbol is the seven-branched candelabrum. Two chambers are enriched with decorative paintings, in which, contrary to the Mosaic law, figures of animals are depicted. A sarcophagus here bears traces of gilding.

The **Catacombs of SS. Peter and Marcellinus**, near Torre Pignattara (p. 345), are among the most extensive. The ceiling of a lofty chapel bears an Enthroned Christ, with St. Paul on the right, and St. Peter on the left, with four saints below, quite in the style of the earliest mosaics. Other frescoes, such as two scenes of Agapæ (love-feasts), belong to the 3rd century. The representation is often very realistic. A very fine cœmeterial glass, with a design of the Temple of Jerusalem in gilt outline, was found in these catacombs in 1883.

The **Catacombs of St. Pontianus**, situated in the Vigna di S. Michele, $\frac{1}{2}$ M. from the Porta Portese (to the right before the Strada di Monte-verde), are excavated in the breccia of Monte Verde. At the foot of a staircase descending into it is a basin with water, serving as a baptistery. On the wall beyond is the Baptism of Christ (with a stag near the Jordan), above a large cross in the later style. Above the staircase are two large medallions with heads of Christ of the 6th and 9th (?) centuries.

The **Oratorio of S. Alessandro**, 6 M. from the Porta Pia (p. 341), in the Tenuta del Coazzo is a long, half-subterranean building, the very poor masonry of which is well preserved in the lower part. According to an inscription on the altar, this was the tomb of a certain Alexander, perhaps the bishop of that name. The oratory is surrounded with lofty passages still containing undisturbed tombs.

Catacomb of St. Generosa, see p. 393.

2. The Alban Mountains.

The *Alban Mountains*, $12\frac{1}{2}$ M. to the S.E. of Rome, form a volcanic group with several extinct craters, two of which are occupied by the *Alban Lake* and the *Lago di Nemi*. *Monte Cavo* (3145 ft.) is the highest summit. On the N. slope of the group lies *Frascati*, and on the E. slope *Albano*, both of which have been surrounded since the most ancient times with the country-houses of wealthy Romans. The greenish-grey tufa, known as *peperino*, which is quarried near Albano, is a favourite building stone. *Alban Wine* was praised by Horace and is still much esteemed. The great natural beauty of the scenery here has always made these mountains a favourite resort of visitors from Rome. The inhabitants have preserved

many of their peculiarities, though the famous costume of the Alban women is seldom seen except on Sundays and holidays.

PLAN OF EXCURSION, 1½ day. 1st Day: afternoon train from Rome to *Frascati* or *Albano*, the only places where there are good inns; in the evening visit *Tusculum* from *Frascati*, or *Castel Gandolfo* from *Albano*. — 2nd Day: walk from *Frascati* in 2½ hrs., or drive by the high-road (one-horse carr. about 8 fr.), to *Rocca di Papa* (p. 372); ascend *Monte Cavo* (p. 372), ¾ hr.; descend to *Nemi* (p. 371), in 1¼ hr., and walk thence to *Genzano* (p. 370; ¾ hr.), *Ariccia* (p. 370; ½ hr.), and *Albano* (p. 368; ¼ hr.). This excursion may be made in the reverse order from *Albano*, the traveller, however, proceeding from *Rocca di Papa* to *Frascati* by a footpath (2½ hrs.) passing *Tusculum*. The *Grotta Ferrata* is interesting mainly on account of the frescoes by *Domenichino* (p. 367); this part of the mountains as far as *Marino* and *Rocca di Papa* offers least in the way of scenery. — The excursion from *Albano* to *Monte Cavo*, returning by *Nemi*, *Genzano*, and *Ariccia* (6-7 hrs.) may be accomplished in a single day; and *Frascati* and its neighbourhood may be visited in the course of one afternoon. In this case the night need not be spent out of Rome.

Those who have plenty of time, and do not object to an occasional deviation from the direct route, will have no difficulty in finding their way with the aid of the map and following directions. When GUIDES (about 3 fr. a day) are made use of, a precise programme of the excursion should be agreed upon beforehand, as they are apt to cut the journey short to the traveller's disadvantage. In spring and autumn WALKING in this district will be found pleasant; but in the warmer months the traveller will find it convenient to follow the native custom of using DONKEYS (about 6 fr. per day, including driver). CARRIAGES may be hired at *Frascati* and *Albano*, but the most interesting routes are only practicable for pedestrians and riders. The charges are as high as at Rome (25-30 fr. per day).


FRASCATI AND ITS NEIGHBOURHOOD.

RAILWAY FROM ROME TO FRASCATI, 15 M., in 48 min. (fares 2 fr. 75, 1 fr. 90, and 1 fr. 25 c.; return-tickets, comp. p. xix). — Journey to (8¾ M.) stat. *Ciampino*, see p. 368. The train to *Frascati* gradually ascends. The station lies immediately below the *Piazza*, where the high-road to Rome begins.

Frascati. — *ALBERGO DI FRASCATI (branch of the Alb. Milano in Rome), in the *Villa Zuccala*, R. 2½, B. 1¼, lunch 2½, D. 4 fr.; *ALBERGO DI LONDRA, in the piazza. — On the left, at the entrance to the town, in the *Via Romana*, *Trattoria del Sole*. Near the piazza, the *Nuova Trattoria della Ripresa*, well spoken of, kept by *E. Filipponi*, best rooms on the 1st floor. Good wine at the *Nuova Trattoria di Cipoletta*, in the street to the left of the church. — Lodgings easily obtained in the *Villas Piccolomini*, *Falconieri*, *Muti*, and others (single rooms 30-40 fr., 3-4 rooms about 100 fr. per month).

A visit to the *Villas*, which are always open to the public, and to *Tusculum*, takes 2½-3 hrs., the best route being by *Villa Aldrobrandini* and *Ruffinella* in going, and by *Camaldoli* and the *Villas Mondragone* and *Taverna* in returning. *Guides* and *Donkeys*, necessary only when time is limited, 2-3 fr.

Frascati, in a cool and healthy situation, on the slope of the mountains, with its beautiful, shady, and well-watered villas, is a favourite summer-resort of foreigners as well as natives. The ancient *Tusculum* having been destroyed by the Romans in 1191, this town (with 7000 inhab., incl. environs), which is insignificant and comparatively modern, sprang up on the ruins of a former villa, overgrown with underwood (*frasche*), from which it derives its name.



At the S.W. entrance to the town, which is reached by the high-road from Rome (and also from the station) in a wide curve, lies the *Villa Conti*, with fountains and beautiful points of view, the property of the Duca Torlonia. — In the piazza, which is embellished with a pretty fountain, rises the cathedral of *S. Pietro*, erected in 1700 under Innocent XII. To the left of the high-altar is a memorial-tablet to Charles Edward, the young Pretender, grandson of James II., who died at Frascati on 31st Jan., 1788. — The more ancient cathedral of *S. Rocco* dates from 1309.

From the piazza we ascend the street (Corso Vittorio Emanuele) to the right, past the cathedral of *S. Pietro* and the donkey-station. Above the town, on the left, rises the *Villa Piccolomini*, once the residence of the learned Cardinal Baronius (d. 1607).

Farther on we reach, on the right, the handsome **Villa Aldobrandini*, erected by *Giacomo della Porta* for Card. Pietro Aldobrandini, nephew of Clement VIII., and now the property of the Borghese. The palace contains paintings by the Cavaliere d'Arpino. The grounds are adorned with cascades and beautiful oaks, and the views are very extensive, especially from the roof of the semi-circular building.

The road to Tusculum next passes the *Capuchin Church* (1 M. above the town, containing a few pictures), and soon reaches the entrance to the **Villa Ruffinella*, or *Tusculana*, of the 16th cent., formerly the property of Lucien Bonaparte, afterwards that of King Victor Emmanuel, and now belonging to Prince Lancelotti. In Nov., 1818, Lucien was attacked and robbed here, an event admirably described in Washington Irving's 'Adventure of the Artist'. The celebrated *Villa of Cicero* (the 'Tusculanum') is generally believed to have occupied this site. Inscriptions and antiquities found in the neighbourhood are shown.

The other villas lie on the height to the E. of Frascati. The nearest is the *Villa Taverna* and a little farther on is the *Villa Mondragone*, erected by Cardinal Altemps under Gregory XIII., both the property of the Borghese, surrounded by delightful gardens and points of view. The latter is now occupied by the Jesuits as a school. — Above the Villa Taverna is situated the *Villa Falconieri*, the oldest in Frascati, planned by Cardinal Ruffini before the year 1550, and erected by Borromini, possessing pictures by C. Maratta and others, and shady gardens. — On the height to the E. lies the suppressed monastery of *Camaldoli*, founded by Pope Paul V.

From Villa Ruffinella (ascending to the right from the palace) a shaded, and partly ancient road, leads to the site of the venerable town of **Tusculum**, the foundation of which is traditionally ascribed to Telegonus, the son of Ulysses and Circe, the birthplace of the elder Cato and a favourite residence of Cicero. In the middle ages the ancient castle on the summit of the hill was occupied by a

warlike race of counts, who were generally in league with the emperors against the Romans. The latter, having been signally defeated in the reign of Frederick I. in 1167, retaliated by dismantling the castle in the pontificate of Cælestine III., in 1191. Nothing therefore now remains of the ancient Tusculum but a heap of ruins.

In ascending from the Villa Ruffinella, we soon obtain a view of the *Amphitheatre*, outside the town-walls (longer diameter 77 yds., shorter 57 yds.; arena 52 yds. by 31 yds.), which is called by the guides *Scuola di Cicerone*. The so-called *Villa of Cicero*, excavated in 1861 by Prince Aldobrandini, is next reached. On the right is the ancient *Forum* and the **Theatre* (about 3 M. above Frascati), excavated, as an inscription records, in presence of Maria Christina, dowager Queen of Sardinia, on the occasion of the arrival of Gregory XVI., 7th Oct., 1839, and remarkably well preserved. At the back is a *Piscina*, or reservoir, in four compartments. The guides generally propose to return from this point, as the path to the castle is rough and hardly practicable for donkeys.

The **Castle* (arx) lay on an artificially hewn rock, now surmounted by a cross, 174 ft. above the ancient town (an ascent of about $1\frac{1}{4}$ hr. from the piazza). Two gateways and the direction of the walls are still traceable. Magnificent **VIEW* from the top (2220 ft.). On the right are Camaldoli and Monte Porzio; farther distant the Sabine Mts., with Tivoli and Monticelli; then Soracte and the Ciminian Mts.; towards the sea the broad Campagna with its aqueducts, Rome, and the dome of St. Peter's; to the left, the Alban Mount (M. Cavo), Castel Gandolfo, Marino, and Grotta Ferrata.

Descending from the theatre and turning to the right, we observe a fragment of the old wall, and adjoining it a very ancient **Reservoir* of peculiar construction, formed of massive blocks, and vaulted in an almost pointed arch. We now take the longer way back by Camaldoli, and the villas Mondragone, Taverna, and Falconieri (see p. 365).

The ROAD FROM FRASCATI TO PALESTRINA, $15\frac{1}{2}$ M. (comp. Maps, pp. 364, 382), especially the first half, is beautiful, but destitute of shade. From the N.E. corner of the town the road leads past the lower entrance to the Villa Mondragone, which is approached by an avenue of cypresses. Farther on are the ruined vaults of an ancient villa, arbitrarily said to have belonged to Cato. After 2 M. the road passes (r.) the olive-clad hill on which *Monte Porzio* (1530 ft.) is picturesquely situated; $1\frac{1}{2}$ M. farther it reaches *Monte Compatri* (1745 ft.), with a château of the Borghese. We do not enter the village, but pass the approach to it, and descend by a somewhat rough road, passing a washing-trough. Near a (1 M.) considerable group of trees we turn to the right, and close to ($\frac{1}{3}$ M.) a small chapel with an image of the Madonna, again ascend to the right. About 2 M. farther the broad road leads us to the high-road from Rome (*Via Labicana*, *Strada di Palestrina*); and following the latter for $\frac{3}{4}$ M. we reach the *Osteria S. Cesario* (p. 346).

Two routes lead from Frascati to ($2\frac{1}{2}$ M.) GROTTA FERRATA: the carriage-road to Marino, and the shorter route by a path through the wood, diverging, below the Villa Torlonia, to the left from the street which leads to the railway. (In descending, keep to the left;

$\frac{1}{4}$ hr. farther, where the path divides, turn to the left; and also to the left 5 min. farther, at the entrance to the wood.)

Grotta Ferrata, a Greek monastery of the Basilians, was founded by St. Nilus under Otho III. in 1002. In the 15th cent. it was the property of Card. Giul. della Rovere, afterwards Pope Julius II., who fortified it with moats and towers. Of the old *Church* nothing now remains but the vestibule, with (r.) a beautiful statue of the Madonna. The Portal, with arabesques and a Greek inscription, dates from the 11th cent.; over the door are mosaics of the Saviour, the Madonna, and St. Basil. The present church, built by Cardinal Guadagni in 1754, contains nothing worthy of mention.

INTERIOR. From the right aisle we enter the CHAPEL OF ST. NILUS, decorated with *Frescoes from the life of the saint by *Domenichino* in 1610 (p. lix), restored in 1819 by V. Camuccini. At the entrance of the chapel, on the left, is represented the meeting of the saint with Otho III.; the attendant in green, holding the emperor's horse, is *Domenichino* himself; to the right to the horse, Guido Reni is also represented in a green costume, and behind him Guercino. The boy in front of the horse, with blue eap and white feather, bears the features of a girl of Frascati to whom the artist was attached. On the right St. Bartholomew arrests the fall of a column, and saves the lives of the workmen. At the altar on the left, St. Nilus heals a boy possessed by an evil spirit with oil from a lamp of the Madonna. On the right, the Madonna presenting a golden apple to St. Nilus and St. Bartholomew. In the lunette, Death of St. Nilus. Outside the chapel, St. Nilus calming a storm by which the harvest is endangered; the saint kneeling before the cross. On the ceiling, the Annunciation.

A monument of Cardinal Consalvi, who died as abbot of Grotta Ferrata in 1824, and several ancient sculptures are shown in the handsome *Abbey*. The small Madonna over the altar is by Ann. Caracci; a bust of *Domenichino* is by Teresa Benincampi, a pupil of Canova. Fairs held here on 25th March and 8th Sept. attract numerous peasants from the neighbourhood, as well as strangers from Rome.

About 2 M. farther S., and reached either by a footpath or by the high-road, is **Marino** (*Trattoria del Tramway*, at the fountain), a small town famous for its wine, and picturesquely situated on a spur of the Alban Mts., 1320 ft. in height, the site of the ancient *Castrinonemum*. It lies about 3 M. from the railway-station of Marino, mentioned at p. 368. In the middle ages it was a stronghold of the Orsini, who defended themselves here against their enemies, particularly the Colonna's; but the latter captured Marino under Martin V. in 1424, and still possess it. The town contains a *Corso* (the principal street), a *Fountain*, and a *Cathedral* dedicated to St. Barnabas. The church of *La Trinità*, to the left of the *Corso*, contains a Trinity by Guido Reni. In the church of the *Madonna delle Grazie*, St. Rochus by *Domenichino*. In the *Cathedral* a badly-preserved St. Bartholomew by Guercino.

Marino is connected with Rome by a steam-tramway (4-5 times daily in 1 $\frac{1}{4}$ hr.; fares 2 fr. 40, 1 fr. 95, 1 fr. 30 c.). Intermediate stations: *Sassone*, *Campino* (p. 368), *Le Capannelle* (p. 347), *Il Tavolato* (p. 347), *Torre Pignataro* (p. 341), and *Portonaccio* (p. 371). The terminus at Rome is outside the Porta S. Lorenzo, where the tramway to Tivoli also starts.

From the town of Marino a shady road, commanding extensive views, leads through the *Parco di Colonna*, the well-wooded valley of the *Aqua Ferentina*, a brook often mentioned in history as a rallying-point of the Latins, to the Alban lake, and by Castel Gandolfo to ($3\frac{3}{4}$ M.) Albano (see p. 369).

ALBANO AND ITS NEIGHBOURHOOD.

FROM ROME TO ALBANO. — RAILWAY TO CECCHINA (Rome and Naples Railway), 18 M., in 35-50 min. (fares, express 3 fr. 65, 2 fr. 55 c.; ordinary train 3 fr. 30, 2 fr. 30, 1 fr. 50 c.; through ticket to Albano 4 fr. 10, 2 fr. 90, 1 fr. 90 c., return 6 fr. 40, 4 fr. 55, 2 fr. 95 c.). The line emerges from the city-walls to the left of the Porta Maggiore. On the right the arches of the *Acqua Felice*, partly upon and partly beside the remains of the ancient *Aqua Claudia*; then the tombs of the *Via Appia*. To the left the Sabine and Alban Mts.; at the foot of the latter, Frascati (p. 364) is a conspicuous object. At ($8\frac{3}{4}$ M.) *Ciampino* the line to Frascati diverges to the left (p. 364; the tramway-station mentioned at p. 367 is about $\frac{3}{4}$ M. from the railway; no path). — $10\frac{1}{2}$ M. *Marino*; above the town (p. 367), on the mountain, is *Rocca*, adjoining which on the right rises Monte Cavo with the white monastery walls. The train then passes through a cutting. To the left, on the olive-clad hill, appears Castel Gandolfo, immediately beyond which Albano and Ariccia, connected by a viaduct, are visible in the distance. — 18 M. *Cecchina*, the station for Albano and Genzano.

FROM CECCHINA TO ALBANO (and to Nettuno, p. 398), $2\frac{1}{2}$ M., steam-tramway in 20 min. (fares 80, 60, and 40 c.). The tramway, however, does not always run in connection with the trains. Walkers take 1 hr. between Cecchina and Albano. — The tramway follows the high-road. The ruins of *Castello Savelli* soon appear on the right; *La Torre*, or *Torretta*, on the left. A magnificent view of Ariccia is then obtained, with the ancient castle (p. 370) on the right, and the imposing viaduct on the left, and farther to the left, Albano; to the right, by the entrance to the town, stands the *Villa Boncompagni*. The tramway stops in the Piazza Umberto.

Albano. — VILLE DE PARIS, Palazzo Feoli, R. 3 fr., dear; ROMA, at the end of the town, near the bridge leading to Ariccia; EUROPA, or *Posta*, R. 2 fr., café on the ground-floor; RUSSIA, at the Porta Romana.

Ristorante Salustri in the Piazza Umberto; the landlord procures bedrooms for visitors. — *Café* in the Corso.

Those who desire to make the tour mentioned at p. 364, viâ *Palazzuola* and *Rocca di Papa* to Monte Cavo and back by *Nemi*, *Genzano*, and *Ariccia* (6-7 hr.), must turn to the right on their arrival in Albano, cross the Piazza, take the first turning to the left in the *Via Appia*, and ascend to the Capuchin convent. — The walk through the *Galleria di Sotto* to *Castel Gandolfo*, and back by the *Galleria di Sopra* requires about 1 hr., and may sometimes be added to the above tour before the departure of the last train.

Albano, officially *Albano Laziale* (1250 ft. above the sea), a

small town with 6500 inhab. (incl. suburbs), situated on the ruins of the villa of Pompey and of the *Albanum* of Domitian, is mentioned as early as 460 as the seat of a bishop, and again in the 11th cent. in the contests of the popes with the citizens of Rome. In the 13th cent. it belonged to the Savelli, from whom it came into the possession of the papal government in 1697. The lofty site and beautiful environs of Albano attract many visitors in summer, but it is not entirely exempt from fever. It is an excellent centre for a number of interesting excursions.

Above the station is the little Piazza Umberto, skirted by the Via Appia, which forms the S.W. boundary of the town. In the upper part of the town, which stretches up the side of the hill, between the monastery of *S. Paolo* and the loftily-situated *Capuchin Monastery* (to the right from the Piazza, then the first turning to the left), lay an *Amphitheatre*, the scanty remains of which are seen from the road. The church of *S. Maria della Rotonda* stands on the foundations of an ancient circular temple. The ruins in the street of Gesù e Maria are supposed to be the remains of baths.

In front of the N.W. entrance to the town, to the right of the Via Appia, rise the remains of a large tomb, called without authority the *Tomb of Pompey*. The avenue, diverging to the right by this tomb, is known as the *Galleria di Sotto*, see below. — On the S.E. side of the town, to the right on the road to Ariccia (to the left of the ancient road), stands another ancient **Tomb* in the Etruscan style, consisting of a massive cube, originally surmounted by five obtuse cones, of which two are still standing. It was formerly regarded as the tomb of the Horatii and Curiatii, and now, with no better reason, as that of Aruns, a son of Porsenna, who was killed near Ariccia.

About $1\frac{1}{4}$ M. to the N.W. of Albano lies *Castel Gandolfo*, which is reached by two shady avenues of beautiful evergreen oaks: the so-called **Galleria di Sopra*, or 'upper gallery', beginning at the Capuchin monastery above Albano, and affording fine views of the lake; and the *Galleria di Sotto*, beginning near the tomb of Pompey at the N.W. entrance to the town, passing the *Villa Barberini* and Castel Gandolfo, and leading to ($3\frac{3}{4}$ M.) Marino (p. 367).

Castel Gandolfo, the seat of the Savelli in the middle ages, has belonged to the Popes since 1596. It is an insignificant place with a large *Papal Palace*, erected by Urban VIII. from designs by *Carlo Maderna*, and splendidly situated high above the Alban lake. The *clâteau* (now a convent) was formerly a favourite summer-resort of the popes, and enjoys the privilege of exterritoriality.

The ***Lake of Albano** (965 ft. above the sea-level, 490 ft. deep), about 6 M. in circumference, is the crater of an extinct volcano, of sombre and melancholy aspect, although its banks are well cultivated. It is fed by abundant subterranean springs, and is drained by a very ancient *Emissarium* which issues below Castel Gandolfo.

The path to the ancient *Emissarium* descends steeply from the *Galleria di Sopra* a little before the village is reached, but the custodian must first be summoned from the village (fee 1 fr.; for a party more in proportion). The descent occupies nearly $\frac{1}{4}$ hr., and the whole inspection about 1 hr. The *Emissarium*, an imposing work, was constructed according to tradition by the Romans in B.C. 397, during the siege of Veii, when the lake rose to an unusual height, but it is probably of still more remote origin. It is hewn in the solid rock. At the entrance is a large stone building resembling a nymphæum. The channel is 7-10 ft. in height, and issues $\frac{3}{4}$ M. below Albano by the village of *La Mola*, where the water is used as a motive power for mills, descending thence to the Tiber. The custodian floats lighted pieces of candle on boards down the stream, in order to give visitors an idea of its length (about 1300 yds.).

From Albano to Palazzuola, and thence to the top of Monte Cavo, see p. 372.

About $\frac{3}{4}$ M. to the S.E. of Albano lies Ariccia. Beyond the Etruscan tomb mentioned at p. 369, the road crosses the imposing **Viaduct* which connects Albano with Ariccia, erected by Pius IX. in 1846-53, 334 yds. in length, and 192 ft. in height, consisting of three series of arcades of six, twelve, and eighteen arches respectively, one above the other. To the right we obtain a view of the extensive plain as far as the sea; to the left we observe the **Park of the Palazzo Chigi*, a mansion built by Bernini. This park, containing fine old timber, is kept in as natural a condition as possible. Permission to visit it should be obtained from the porter or gardener in the palace (fee $\frac{1}{2}$ -1 fr.).

Ariccia (*Caf  * in the piazza), a small village, frequently attracts visitors in summer on account of the proximity of the woods. The women of Ariccia and Genzano are famed for their beauty. The ancient *Aricia*, which belonged to the Latin League, lay towards the S., in the *Valle Aricciana* (980 ft.), an extinct crater below the modern town, while the latter occupies the site of the ancient *Arx* or citadel. It was the fifth station on the *Via Appia*, which runs towards Genzano on massive and still visible substructures, at the foot of the modern town. (A circuit of $\frac{1}{2}$ hr. by the valley, instead of the direct route from Albano to Ariccia, is interesting.) In the middle ages Ariccia came into the possession of the Savelli, and in 1661 was purchased by the Chigi, who are still the proprietors of the place.

The beautiful and shady new road from Ariccia to Genzano at first leads a little to the left and crosses four viaducts, which command fine views. After $\frac{1}{2}$ M. it passes *Galloro*, formerly a Jesuit church. At the 17th milestone, about $\frac{3}{4}$ M. farther, the road divides; the branch to the left descends to a Capuchin monastery and to the Lake of Nemi (below is a partly ancient road to Nemi); that in the middle leads through an avenue to the Palazzo Cesarini (see below); and that to the right descends to the town.

Genzano, a town with 5000 inhab., loftily situated above the S.W. bank of the Lago di Nemi, is also much visited in summer, but there are no good inns, and intermittent fever is not uncommon

here. In the piazza, opposite the fountain, is the **Trattoria della Grotta Azzurra*, the landlord of which can procure sleeping-quarters in an adjoining house (bargain desirable). The wine of Genzano is esteemed. The place presents no attraction beyond its fine situation. The best **View* of the lake is from the garden of the *Palazzo Cesarini*, which slopes rapidly towards the water (entrance to the left, opposite the palace; admission granted on application at the palace). — At Genzano, on the 8th day after Corpus Christi (but not every year), is held the famous *Infiorata di Genzano*, or flower-festival, consisting of a procession through a street carpeted with flowers, followed by fireworks and merry-makings.

The ***Lago di Nemi* (1065 ft.) is an extinct crater, about 3 M. in circumference, and like the Alban lake, which lies 100 ft. lower, is of considerable depth (330 ft.), and is also drained by an artificial emissarium. The water is beautifully clear, and rarely ruffled by wind. The precipitous lava-slopes of the crater, 330 ft. in height, are carefully cultivated. In ancient times it was called the *Lacus Nemorensis*, and sometimes the 'Mirror of Diana', from a temple, of which substructures have been discovered below Nemi, and from a nemus, or grove sacred to that goddess, whence the present name is derived. This exquisite lake is the gem of the Alban Mts.

From Genzano to Nemi $2\frac{1}{2}$ -3 M.; by the Palazzo Cesarini we follow the road to the right, through the town, and past the church of SS. Annunziata. The pleasant road skirts the upper margin of the lake, affording several fine views. — A footpath descends to the lake from SS. Annunziata, and ascends again near the mills below Nemi.

Nemi is a small mediæval town with an ancient fort. The inn (*Trattoria Desantis*, tolerable, bargaining advisable) possesses a small verandah which commands a delightful **VIEW* of the lake and the castle of Genzano, of an old watch-tower beyond them, and of the extensive plain and the sea.

From Nemi to the ($1\frac{1}{2}$ hr.) Monte Cavo (p. 372) a guide is necessary on account of the intricacy of the forest-paths ($1-1\frac{1}{2}$ fr.). Albano is a little farther distant.

Monte Cavo.

The ascent of Monte Cavo may be accomplished in about $3\frac{1}{4}$ hrs. from *Frascati*, in about $2\frac{3}{4}$ hrs. from *Albano*, and in about 2 hrs. (with guide) from *Nemi*. The traveller had better take refreshments with him; the monks are very civil, but the food (merely wine, bread, and cheese, $\frac{1}{2}$ -1 fr.) and sleeping accommodation (for gentlemen) which they offer are exceedingly poor.

FROM FRASCATI TO ROCCA DI PAPA is a distance of about 5 M. which on account of the ascent represents a walk of not less than $2\frac{1}{2}$ hrs. The day's journey indicated at p. 364 may be lightened by taking a carriage to Rocca di Papa (p. 372). The road diverges to the left from the road to Marino, at a point a little more than halfway (comp. the Map). Rocca di Papa may also be reached

from Tusculum (p. 365) direct in $1\frac{1}{2}$ hr. by field and forest-paths (guide desirable, 1- $1\frac{1}{2}$ fr.).

The ROUTE FROM ALBANO TO ROCCA DI PAPA leads to the right at the above-mentioned Capuchin convent, where the Galleria di Sopra begins to the left. Fine view of the lake. Where the road forks we keep to the left, in the direction of the lake, even when the path seems to descend steeply. In about 1 hr. we reach the suppressed Franciscan monastery of **Palazzuola**, dating from the 13th cent., and situated above the E. margin of the lake. The garden contains a curious rock-tomb in the Etruscan style, about which little is known. — Above the monastery, on the narrow space between the base of Monte Cavo and the Alban Lake, once lay in a prolonged line, as its name indicates, the city of *Alba Longa*, of which no traces now remain. It will be observed, however, that the rocks in the direction of Palazzuola have been hewn perpendicularly, in order to render the town more impregnable.

The foundation of Alba Longa belongs to a prehistoric period, and tradition has attributed it to Ascanius, the son of Æneas. It was the ancient capital, and the political and religious centre, of the Latin League, but was destroyed at an early period by its younger rival on the banks of the Tiber, after which, however, the ancient festivals of the League on the Alban Mt. still continued to be celebrated here.

Rocca di Papa lies 3 M. farther on, the route passing through wood. We follow the most beaten path (which keeps to the right, along a fence, at the fork, about 1 M. from Palazzuola), and avoid those on the left, leading to Marino and Grotto Ferrata.

Rocca di Papa (2645 ft.; *Caffè dell' Aurora*, in the upper part of the town; the two *Trattorie* very poor), a favourite summer-resort of the Romans, with numerous villas, lies on the slope of the great extinct crater of *Campo d'Annibale*, so named from the unfounded tradition that Hannibal once pitched his camp here during his campaign against Rome. The garrison of Rome occupies summer-quarters here in July, August, and September.

In order to reach the summit of Monte Cavo we turn to the right on the rim of the crater, which is reached by a walk of 15-20 min. through the steep streets of the town, and ascend the well-preserved and shady *Via Triumphalis*, an ancient road, paved with basalt, once traversed in triumphal procession by the generals to whom the Senate refused a triumph at Rome. From two open spaces, about three-quarters of the way up, a better *View than from the top is obtained of Marino on the right, the Lago d'Albano, Ariccia with the viaduct, Genzano, the Lago di Nemi, and Nemi itself.

On the summit of the **Monte Cavo** (3145 ft.), the ancient *Mons Albanus* (an ascent of $\frac{3}{4}$ hr. from Rocca di Papa), stood the venerable sanctuary of the Latin League, the *Temple of Jupiter Latiaris*, where the great sacrificial festival of the *Feriae Latinae* was celebrated annually. Its ruins, 82 yds. long and 38 yds. wide, with columns of white and yellow marble, were in tolerable preservation till

1783, when Cardinal York, the last of the Stuarts, converted them into a *Passionist Monastery*. A portion only of the ancient foundations is preserved on the S.E. side of the garden-wall.

The **VIEW from several different points is incomparable. It embraces the sea, the coast from Terracina to Cività Vecchia, the Volscian and Sabine Mts., Rome and the Campagna with a number of towns and villages, and below the spectator the beautiful Alban Mts. The distant view, generally obscured by mist, is seen to the best advantage immediately before sunrise, after sunset, or when a passing shower has cleared the atmosphere.

From Nemi to Monte Cavo, see p. 371; the descent, through wood, takes 1-1 $\frac{1}{4}$ hr. A guide is almost indispensable, especially when the traveller is hurried and wishes to avoid deviations.

3. The Sabine Mountains.

That chain of the Apennines which descends abruptly and bounds the Roman plain on the E., named Sabine Mts. from the ancient inhabitants, is full of interest for lovers of the picturesque. The formation of these mountains is limestone, differing entirely from that of the volcanic Alban Mts., and their height is much greater, attaining to 4200 ft. As a rule the INNS are good, though plain, but enquiry as to charges should be made beforehand; usual charge for board and lodging 5-6 fr., and $\frac{1}{2}$ fr. gratuity.

Those whose time is short must be satisfied with a visit to Tivoli, which was a favourite summer-resort of the Romans in the time of Horace. A fine day in April or May, when the vegetation is at its freshest, is the best time for this excursion. Those who are indifferent to the saving effected by taking return-tickets may go by railway and return by steam-tramway (or vice versâ). — If several days are devoted to the Sabine Mts., and they are well worth it, the following tour may be made, ending with Tivoli, the culminating point: 1st day, from Rome by early train to *Valmontone* (p. 382) or to *Frascati* (p. 364), and thence by diligence or on foot to *Pa-lestrina*; in the afternoon, walk or drive to *Olevano*; 2nd, to *Subiaco*; 3rd, to *Tivoli*; 4th, back to Rome. The whole trip may be accomplished by carriage (not always to be had, however, except at Tivoli), but some of the excursions at least should be made on foot or on donkey-back. The public conveyances are not recommended when ladies are of the party, in which case a private carriage should be hired. Tivoli affords the best summer-quarters, but Subiaco and Olevano are also pleasant.

From Rome to Tivoli.

1. RAILWAY, 25 M., in 1 $\frac{1}{2}$ hr. (return-fares 4 fr. 55, 3 fr. 20, 2 fr. 5 c.). This route is more picturesque than that of the steam-tramway (see p. 374). Trains start from the *Principal Station* at Rome.

Outside the city-walls the railway crosses the steam-tramway to Marino (p. 367). On the right appears the ruined *Tor de' Schiavi* (p. 345). — 5 $\frac{1}{2}$ M. *Cervara*, the grottoes near which used to be celebrated for the artists' festivals held in them. — 7 $\frac{1}{2}$ M. *Salone*. — 9 $\frac{1}{2}$ M. *Lunghezza*, the ancient *Collatia*, a 'tenuta' belonging to the Duca Strozzi, with an old baronial castle, prettily situated in the well-wooded valley of the *Teverone*.

13 M. **Bagni**, the station for the sulphur-baths of *Acque Albule*, the Roman *Aquae Albulae*, which were much frequented in ancient times, and were again fitted up for the reception of patients in 1879-80 (handsome Curhaus; swimming-baths for ladies and gentlemen; 68° Fahr.).

The railway next crosses the high-road to Tivoli. To the right fine view of the road and of the railway-viaducts farther on, with the mountains in the background. — 16 M. *Monte Celio*, formerly called *Monticelli*, said to occupy the site of the ancient *Corniculum* and now belonging to the Borghese family. — 20½ M. *Palombara* is situated on an isolated hill, with a château of the 14th cent. belonging to the Savelli family. — View of the Campagna to the right; in front, Tivoli, with the beautiful cypresses of the Villa d'Este. Beyond two tunnels and two viaducts we enjoy a *View to the right of Le Cascatelle (p. 378) and the town. A short and a long tunnel follow. — 25 M. *Tivoli*, the station of which is outside the Porta S. Angelo.

2. STEAM TRAMWAY, 18 M., in 2¼ hrs. (fares 2 fr. 50, 1 fr. 85 c., return 3 fr., 2 fr. 20 c.). This is the most convenient route for a visit to Hadrian's Villa. The steam-cars start outside the Porta Lorenzo, for which a horse-car in connection leaves the *Piazza Venezia* (Via Nazionale 131) ½ hr. before their departure, running viâ the *Piazza delle Terme* (tramway-lines 1 and 2. p. 3 of Appx.; through-tickets to Tivoli may be obtained at the *Piazza Venezia*). Those who drive to the steam-tramway should dismiss their cab at the Porta S. Lorenzo to avoid paying the extra-mural tariff (see Appx.). — Travellers with through-tickets are allowed to break their journey in order to visit Hadrian's Villa, which takes about 2 hrs. There is no osteria at the Villa, so that visitors must either bring provisions with them, or postpone luncheon until they reach Tivoli. Those who intend to walk from the Villa to Tivoli, as suggested at p. 377, should certainly bring luncheon.

The high-road, along which the steam-tramway runs, quits Rome by the Porta S. Lorenzo (p. 343), passing the church of that name on the right. It then crosses a bridge over the railway. The first halting-place is *Portonaccio*, where the line to Marino diverges on the right (p. 367). The road, which is generally identical with the ancient *Via Tiburtina*, crosses the *Anio*, here called the *Teverone*, by the *Ponte Mammolo* (station, 4 M.). The river rises on the mountains near Filettino, passes Subiaco, Vicovaro, and Tivoli, where it forms the celebrated cascades, and falls into the Tiber at the Ponte Salaro (p. 341). The bridge is said to be named after Mammæa, the mother of Alexander Severus. To the right an undulating district with ancient towers.

7 M. *Settecamini*. — 12½ M. *Bagni*, station for *Acque Albule* (p. 373). — In the vicinity are the quarries of *Lapis Tiburtinus*, or travertine, which furnished building-material for ancient and for modern Rome, for the Colosseum and for St. Peter's alike. In ½ hr. more the *Anio* is crossed by the *Ponte Lucano* (station, 14½ M.), near which is the well-preserved *Tomb of the Plautii*, dating from the early empire, and resembling that of Cæcilia Metella (p. 349).

Beyond the Ponte Lucano we see on the right two pillars, which are supposed to mark the ancient entrance to Hadrian's Villa; one is adorned with reliefs.

15½ M. *Villa Adriana* (no osteria in the vicinity; see above). We follow the road which ascends gradually from the station, turn

to the right at a ($\frac{1}{4}$ min.) finger-post, and soon reach the ($\frac{1}{4}$ hr.) present entrance of the villa. A fine avenue of cypresses leads to the lower *Casa della Guardia*, where tickets are sold (1 fr.).

The *VILLA OF HADRIAN, which with its magnificent grounds occupies an area of several square miles, dates from the later years of the far-travelled emperor (d. 138 A.D.). Hadrian, as his biographer Spartian relates, 'created in his villa at Tivoli a marvel of architecture and landscape-gardening; to its different parts he assigned the names of celebrated buildings and localities, such as the Lyceum, the Academy, the Prytaneum, Canopus, the Stoa Pæcile, and Tempe, while in order that nothing should be wanting he even constructed a representation of Tartarus'. After the death of its founder little use seems to have been made of this gigantic construction, which does not again appear in history till the period of the Gothic invasions, when it served Totila as a fortress (544 A.D.) and suffered great injury. During the following centuries the ruins afforded valuable building material for the churches and palaces of Tivoli. At the beginning of the Renaissance a profitable search for works of ancient art was instituted here, and from the 16th cent. to the present day the ruins have furnished an almost inexhaustible series of works of art, including many of the principal treasures of the Vatican, Capitoline, and other museums. Unfortunately, however, the destruction of the buildings kept pace with the search for treasures of art. In 1871 the Italian government purchased the Villa from the family of the Braschi.

The Roman archæologists have tried to identify the extant ruins with the buildings mentioned by Spartian in the passage cited above, and though it is often doubtful we here follow the usual terminology.


Adjoining the watchman's hut is the so-called *Teatro Greco*, of which the foundations of the stage and the rows of seats are still distinguishable. Skirting the posterior wall of the stage, we then ascend through an avenue of cypresses to the *Pæcile*, an imitation of the *στοὰ ποικίλη*, or painted porch, at Athens. Of this huge colonnade, 250 yds. long and 110 yds. wide, nothing now remains but the N. wall and a few fragments of the parallel arcades. In the centre of the space enclosed by the colonnade traces have been discovered of a large oblong *Water Basin*. As the natural plateau of the hill was not capacious enough to receive so extensive a building, it has been enlarged on the W. and S.W. by gigantic substructures, which contain three stories of vaulted chambers, accessible through an entrance on the S. side of the square (Pl. 1). These chambers, generally called *Le Cento Camerelle*, are supposed to have been occupied by the imperial guards or slaves. — At the N.E. corner of the square is the entrance to the *Sala dei Filosofi*, with niches for statues. From it we enter a *Circular Building* (Pl. 3) containing a water-basin and an artificial island adorned with columns; this is usually described as a *Natatorium* or swimming-bath, but it is more probably a *Nymphæum*. To the E. of this building, at a somewhat higher elevation, is a rectangular court, the left side of which is occupied by the so-called *Library* (Pl. 4). To the N. lay a *Garden*. A corridor, on the left side of which was a fine vestibule, leads N.E. to a room supposed to have been a *Triclinium*, commanding a fine view of Tempe, Tivoli, and the mountains. Hence we proceed to the S. (right), through a plantation, to the *Doric Peristyle* (Pl. 5), and to a large

rectangular space known as the *Giardino*. Some of the finest mosaics (now in the Vatican, p. 309) were found in the adjoining rooms (*Triclinio*, Pl. 6). On the E. side of the *Giardino* is the *Æcus Corinthius* (Pl. 8), a hall the ends of which are occupied by large semicircular recesses. In front of the N. recess are two small fountain-basins. To the right is the *Basilica*, with 36 marble pillars and remains of a magnificent marble flooring, recently excavated for the second time. On the W. it is adjoined by a room with an *exedra*, in which is an elevated basis or platform; this is supposed to be the throne-room. — We now return to the *Æcus Corinthius*, and on quitting it turn to the right. The following rooms also belong to the state-apartments. Beyond an octagonal vestibule we enter the so-called *Piazza d'Oro*, a court surrounded with a colonnade of 68 columns, alternately of Oriental granite and cipollino, of which the bases alone are now *in situ*. The costly material of the decorations found here in the excavations of the 18th cent. gave rise to the name. On the S.E. side of the *Piazza d'Oro* is a room surmounted with a dome, with a semicircular apse, containing water-works and a fountain.


We now return to the *Giardino*, skirt its S. side, and follow the path leading to the S. past a handsome semicircular *Exedra* (Pl. 10), with a water-basin, to the *Quartiere dei Vigili*, a lofty building supposed to have been occupied by soldiers or by imperial officials. Farther on is a large block of buildings facing the W. We pass through a *Cryptoporticus* and enter a suite of rooms from which we overlook the *Stadium*. On leaving this building we proceed to the S. along the substructures. In the middle of the space which they enclose are the *Thermæ*, with remains of tasteful stucco ornamentation. To the left as we leave the *Thermæ* opens the *Valley of Canopus*, artificially cut in the tufa rock. 'Canopus', says Strabo, 'is a town 120 stadia from Alexandria, named after the steersman of Menelaus, who is said to have died here, and containing a highly-revered temple of Serapis . . . Troops of pilgrims descend the canal from Alexandria to celebrate the festivals of this goddess. The neighbourhood of the temple swarms day and night with men and women, who spend the time in their boats dancing and singing with the most unbridled merriment, or find accommodation in the town of Canopus and there prosecute their orgies'. Hadrian constructed the canal, with the temple in the background, and also numerous small chambers, where he caused festivals to be celebrated in the Egyptian manner. At the end of the valley is a large and well-preserved recess, with a fountain, beyond which was a system of subterranean halls, terminating in a cella with a statue of Serapis. Many of the works of art in the Museo Egizio in the Vatican (p. 316) were discovered here.


[The Canopus is the last part of the Villa usually visited by travellers. The more distant parts, to the S., now occupied by private owners, are more difficult to reach and to identify. About 4 min. from the Canopus, a square building with a modern tower (fine view) is known as the *Torre di Timone* (see lower part of Plan). To the S.E. lies the *Academy*, a reproduction of the celebrated grove at Athens. Farther to the S.E. is the *Odeum*, with the remains of a stage and rows of seats. To the E. of the Odeum is a construction called the *Inferi*, supposed to be the *Tartarus* mentioned by Spartian. A ravine (*Valley of the Styx*), 220 yds. long and 20 yds. wide, is hewn in the tufa rock and connected with two subterranean passages. To the S. lies an extensive *Cryptoporticus*, in the form of a trapezium. Still farther to the S. are the ruins of an *Aqueduct*, and a colonnade supposed to be the *Lyceum*. The extensive ruins on the *Colle di S. Stefano*, to which the name of *Prytaneum* has been attached, perhaps belonged to a private villa.]

Returning from the Canopus and passing in front of the above-mentioned *Thermæ*, we reach a second series of *Baths*, not yet easily accessible. We then return to the *Stoa Pæcile*, pass through the door in the N. wall, and reach the cypress avenue leading to the exit. — On our way back we have an opportunity of enjoying the grateful shade of the grove below the *Giardino* (see Plan) and the view of Tivoli and the Vale of Tempe.



1. Ingresso alle canerelle.
2. Aedicula
3. Natatorium
4. Biblioteca
5. Peristilio dorico
6. Triclinio
7. Ospedale
8. Oecus Corinthius
9. Exedra verso T
10. Exedra del Gio





Pedestrians on their way to (1 hr.) Tivoli keep straight on at the finger-post mentioned at p. 375, pass under the tramway, and reach the town at the *Porta del Colle*, or lower gate. [About one-half of the time otherwise required for a visit to the Cascatelle may be saved by turning to the left about $\frac{3}{4}$ M. before reaching the gate, at the factory in the so-called Villa of Mæcnas, crossing the Ponte dell' Acquoria, and thence making the tour described at p. 378 in the reverse direction.] — The tramway-line makes a wide curve to the S.E., ascends steeply through olive-groves past the station of ($16\frac{1}{2}$ M.) *Regresso*, and ends at the (18 M.) *Porta S. Croce*.

Tivoli. — REGINA, in the piazza, clean, R. 2, D. $3\frac{1}{2}$ -4 fr.; SIBYLLA, beautifully situated near the temples, with view, not dear if bargain be made, pens. per week 49 fr.; VESSILLO D'ITALIA. PACE, both unpretending. *Donkeys and Guides* (superfluous) to the waterfalls 1 fr. (3-4 fr. are generally demanded at first). Beggars are numerous and importunate.

Tivoli, the *Tibur* of antiquity, existed, according to tradition, as a colony of the Siculi long before the foundation of Rome. In B.C. 380 Camillus subjugated Tibur along with Præneste, after which it formed a member of the league of the Latin towns allied with Rome. Hercules and Vesta were the deities chiefly revered at Tibur. Many of the Roman nobles, including Mæcnas, and the emperor Augustus himself, founded beautiful villas here; under Hadrian the splendour of the place attained its climax; and in the middle ages it participated in the fate of Rome. In 1460 Pius II. founded the citadel on the ruins of the amphitheatre. The modern town (7500 inhab.), with its narrow streets, lighted by electricity since 1887, offers few attractions beyond its charming situation. It is moreover somewhat damp and windy, especially in spring.

From the piazza we proceed straight to a small piazza near the bridge, by which the high-road to Vicovaro, Subiaco, etc. (p. 381) crosses the Anio above the falls. The Vicolo della Sibylla here leads to the left to the inn of that name (on the right), in the court of which stands the fine *TEMPLE OF THE SIBYL, a circular edifice, surrounded by a colonnade of 18 Corinthian columns, 10 of which are preserved. This temple, called by other authorities that of *Vesta*, or of *Hercules Saxanus*, was used as a church in the middle ages, to which period the round niche in the interior belongs. The door and windows contract at the top. It stands on a rock above the waterfalls, of which it commands an admirable *VIEW. — Close to the Alb. Sibylla is a small piazza with another fine old temple of oblong shape, with 4 Ionic columns in front, supposed to have been dedicated to *Tiburtus*, or to the *Sibyl*. Until 1884 it was incorporated with a church.


The ruins visible from the projecting rock near the temple of the Sibyl to the right, were caused by an inundation in 1826, which carried away part of the village. To prevent the recurrence of a similar disaster, two shafts were driven through the limestone-rock of *Mte. Catillo*, 290 and 330 yds. long respectively, to draw off part of the water of the Anio. In 1834 the river was admitted to its new

channel, in presence of Gregory XVI., by the engineer *Folchi*, and a **New Waterfall* of imposing appearance, about 330 ft. in height, was thus formed (to the left of a spectator at the temple of the Sibyl). Two ancient bridges and several tombs were discovered on this occasion.

The present entrance to the falls is by an iron gate beyond the Ponte Gregoriano, to the right (see Plan, 'Ingresso'). Admission $\frac{1}{2}$ fr., Sun. free; guide for the round of the falls ('giro') 1 fr. — On entering we first turn to the left (straight on, in the direction of the ends of the two tunnels, is the arch of an ancient bridge in 'opus reticulatum'), pass through an archway below the road, and follow the margin of the valley, enjoying a view of the two temples on the left. We then reach a *Terrace* planted with olives, whence we obtain a charming **View* of the temple of the Sibyl, above us, and of the new waterfall below. Passing through a door, which a custodian opens (fee), we may proceed to the fall and the entrance of the two tunnels by which the Monte Catillo is penetrated (see above; 372 paces long; to persons inclined to giddiness the walk by the roaring stream is not recommended). — From the terrace we follow the footpath descending to the valley; halfway down, near some cypresses, a path diverges to the right, at first ascending a few steps and then descending to a *Platform* of masonry, immediately above the new fall. — We now return to the path, which descends at first in zigzags and afterwards in steps. We descend to the lowest point to which it leads, and finally mount a flight of stone steps, wet with spray, to the fantastically-shaped **Sirens' Grotto*. — From the grotto we return to the point where the paths cross, and ascend the path on the other side of the valley to a *Gallery* hewn in the rock. At the end of the gallery the path again divides; that in a straight direction leads across a wooden bridge to the *Grotto of Neptune*, which was formerly the channel of the main branch of the Anio. The new works drew off the greater part of the water from this channel, but the fall is still very fine. — We now return to the gallery and follow the path to the left, ascending in zigzags to the exit near the temples (10-15 c.).

The *Via delle Cascatelle*, the road issuing to the left from the *Porta S. Angelo*, skirts the slopes above the right bank of the Anio, between fine olive-trees. It affords beautiful views of Tivoli and its waterfalls, especially from ($\frac{3}{4}$ M.) the first and ($\frac{1}{2}$ M. farther) the second terrace, whence also are seen the smaller waterfalls below the town, known as *Le Cascatelle*.

It is usual to turn here. Visitors who wish to return by another route may continue to follow the same road. About $\frac{1}{4}$ M. farther, various ancient ruins, said to be the remains of a villa of Quintilius Varius, are seen near the small church of *S. Maria di Quintiliolo*. A '*Villa of Horace*', although the poet never had one at Tibur, is also pointed out by the guides. From S. Maria we cross the meadows between old olive-trees, and in about 20 min. reach a road descending in a few minutes to the left to the *Ponte dell' Acquoria*, by which we cross the Anio. On the left bank of the river we ascend the hill to the left, partly by an ancient pavement,





and join the road from Rome. Here, to the left, are the colonnades, which have long been visible from the opposite bank, of the so-called *Villa of Maecenas*, where an iron manufactory and the motors for the electric lighting of the town are now established. On the other side of the road is an ancient circular building, known by the curious name of *Tempio della Tosse*, or 'temple of the cough', probably a tomb of the *Turcia*, or *Tuscia* family. From this point to the *Porta del Colle* of Tivoli about $\frac{1}{2}$ M.

Hurried visitors may omit the walk on the Cascatelle road, especially if they arrive or depart by railway; but no one should fail to visit the beautiful **Villa d'Este*, to the W. of the town (sometimes closed). The entrance adjoins the church of S. Francesco. The Villa, one of the finest Renaissance structures of the kind, was erected by *Pirro Ligorio* in 1549 for Card. Ippolito d'Este, and presented by the Duke of Modena to Card. Hohenlohe. In the casino are frescoes by Fed. Zuccari and Muziano (damaged). The garden contains terraces (best seen from the cypress plateau with the fountains), grottoes with cascades, densely-shaded avenues, magnificent groups of trees, and charming points of view.

The *Villa Braschi*, founded by Pius VI., and the *Terrace* of the *Jesuits' College* near the *Porta S. Croce* (steam-tramway station) also afford magnificent views of the Campagna and Rome.


THE ASCENT OF MONTE GENNARO from Tivoli takes 5-6 hrs., and the excursion there and back occupies a whole day. Guides at Tivoli ask 5-6 fr., those at S. Polo, which the traveller may reach unaided, 2-3 fr. A luncheon-basket should be provided, including something to drink, as there is little water on the mountain. We quit Tivoli by the *Porta S. Angelo*, and follow the high-road nearly as far as the railway-station of S. Polo (see below). At this point a new road diverges to the left, leading along the mountain-slopes in $1\frac{1}{2}$ hr. to the lofty (2340 ft.) village of *S. Polo de' Cavalieri*. The real ascent now begins (guide necessary), the last part being very fatiguing. On the summit stands a rude pyramid of stone, which has been used for trigonometrical surveys.

Monte Gennaro (4160 ft.), one of the highest peaks of the Sabina, is familiar to the eye of every visitor to Rome. The view from the top is very extensive, comprising the coast from Mte. Circeo as far as the lake of Bracciano, the broad plain with innumerable villages, from the Volscian and Alban Mts. as far as Soracte and the Ciminian Forest; then the Apennines, as far as the snowy peaks of the central range. — The descent may be made to *Rocca Giovine* and through the *Valley of the Licenza* (p. 380), but the night-quarters are very poor.

From Tivoli to Subiaco.

25 M. RAILWAY (continuation of line from Rome to Tivoli) to (11 M.) *Cinetto Romano* in about 50 min. (fares 2 fr. 5, 1 fr. 40, 90 c.). DILIGENCE thence twice a day to (14 M.) *Subiaco*, in connection with the trains. To Subiaco walkers should allow 4-5 hrs. — A pleasant route for pedestrians to Subiaco (7-8 hrs., guide necessary) leads along the left bank of the Anio, ascends the lonely valley of the Empiglione, and finally traverses a hilly region. — Carriage from Tivoli to Subiaco, 20 fr. (or more) and fee.

The railway-station of Tivoli lies outside the *Porta S. Angelo* (p. 378). The train follows the right bank of the *Anio*, to the left of the road, the ancient *Via Valeria*, and the *Acqua Marcia*. Fine view of the green valley to the right. — 3 M. *S. Polo*; the village (see above) lies $2\frac{1}{4}$ M. to the left of the station. Two tunnels. — 5 M. *Castel Madama*; the conspicuous village (1460 ft.) lies high up



Subiaco (*La Pernice*, pleasant for a long stay, pension 6 fr.) is a small town (6000 inhab.) of mediæval appearance, commanded by a castle which was formerly often occupied by the popes. It was the ancient *Sublaqueum*, situated in the territory of the *Æqui*, and is now the capital of the Comarca. It sprang up on the grounds of an extensive villa of Nero, which was embellished by three artificial lakes, the '*Simbruina stagna*' of Tacitus (Ann. 14, 22), which were destroyed by an inundation in 1305, and have given the village its name. On the left side of the Anio, opposite the monastery of S. Scolastica, are seen walls and terraces of the time of Nero, who, according to Tacitus, narrowly escaped being struck by lightning while dining here.

The environs are delightful, and the far-famed monasteries (closed 12-3 p. m.) are very interesting. Guide unnecessary. The excursion takes about 3 hrs., and affords a succession of beautiful views. We follow the main street which intersects the town, upwards of $\frac{1}{2}$ M. in length, and afterwards ascends the right bank of the Anio. About $\frac{3}{4}$ M. from the last houses of the suburb of S. Martino, before the road crosses the gorge by the lofty bridge, a path supported by masonry ascends to the left, passing several chapels, and leading to the ($\frac{1}{4}$ hr.) three —

***MONASTERIES OF S. SCOLASTICA.** The first was founded in 530 by St. Benedict, who retired to this spot, and took up his abode as a hermit in one of the grottoes, now converted into chapels (*Il Sagro Speco*). The monastery was afterwards confirmed in its possessions by Gregory I. and his successors. In the 7th cent. it was destroyed, in 705 it was rebuilt, and it is now entirely modern. In 1052 a second monastery was erected, and a third was added in 1235 by the Abbot Landus. (If time is limited the monasteries should be visited in returning from the *Sagro Speco*.)

The **FIRST MONASTERY** (entrance to the right in the passage, beyond the anterior court) possesses a few antiquities; by the fountain a sarcophagus with Bacchic scenes, fine columns, etc., probably found during the erection of the building. The monastery formerly had a library containing valuable MSS. In 1465 the Germans Arnold Pannartz and Conrad Schweinheim printed here the first book published in Italy, an edition of Donatus, which was followed by Lactantius, Cicero, and Augustine (1467), of which copies are still preserved here (comp. p. 199).

The **SECOND MONASTERY**, dating from 1052, is one of the earliest specimens in Italy of the pointed style. The court contains a quaint relief and two mediæval inscriptions.

The **THIRD MONASTERY**, of 1235, has an arcaded court with mosaics.

The *Church of S. Scolastica*, originally founded by Benedict VII. in 975, was completely modernised in the 18th cent., and now contains nothing worthy of note, excepting the fine carved choir-stalls.

An ascent of 25 min. from S. Scolastica brings us to *S. Benedetto*, or *Il Sagro Speco*, built against the rock, overtopped by a huge mass of stone, and shaded by oaks.

The first corridor contains scenes from the lives of St. Benedict and his sister St. Scholastica, painted in 1466. We then descend to two chapels, adorned with paintings of the Madonna, Massacre of the Innocents, etc., which were executed in 1219 by the otherwise unknown master *Con-*

xolus (earlier than Cimabue). The grotto of St. Benedict contains the statue of the saint by *Bernini* (?). The walls are decorated with venerable paintings.

The GARDEN of the monastery is well stocked with beautiful roses. They were, according to tradition, originally thorns, cultivated by St. Benedict for the mortification of the flesh, but converted into roses by St. Francis when he visited the monastery in 1223.

Having returned to the high-road after visiting the monasteries, we may cross the Anio by the bridge, and return to the town by a footpath on the right.

By the high-road, which is mentioned at p. 384, Olevano (p. 384) is about 10 M. distant.

From Rome to Palestrina.

RAILWAY (Rome and Naples line) to (35 M.) *Valmontone* in about $1\frac{3}{4}$ hr. (fares 6 fr. 45, 4 fr. 55, 2 fr. 90 c.). The express trains do not stop at *Valmontone*. DILIGENCE thence twice daily, in connection with the trains, to (1 hr.) *Palestrina* and ($1\frac{3}{4}$ hr.) *Genezzano*, proceeding once daily (morning) to Olevano.

The COACH from Rome to Palestrina (6 hrs.; comp. p. 345) offers no inducements to the traveller. But the stage between *Frascati* and *Palestrina* (p. 366) may be advantageously made either on foot, or on donkey-back (4 hrs.), or by carriage. *Comp. the Maps, pp. 382, 380.*

From Rome to *Cecchina* (*Albano*), see p. 368. — To the right, rising abruptly from the sea, is the *Monte Circello* (1800 ft.), and nearer us rise the Volscian Mts. — 20 M. *Cività Lavinia*. The insignificant town lies $1\frac{1}{2}$ M. from the station, on a W. spur of the Alban Mts. It is the ancient *Lanuvium*, which was celebrated for its worship of Juno Sospita. A few remains of her temple have recently been found. At the W. end of the town are considerable remains of the ancient walls, built of massive blocks of peperine, and also the pavement of a street skirting the walls. In the piazza, a sarcophagus and several fragments from tombs and villas in the neighbourhood.

$25\frac{1}{2}$ M. **Velletri** (**Loc. Campana*, **Gallo*, each with a trattoria), the ancient *Velitrae*, a town of the Volscians, which became subject to Rome in B. C. 338, famous for its wine, lies picturesquely on a spur of the *Monte Artemisio*, $\frac{1}{4}$ M. from the station. The town (8000 inhab.), with its narrow and crowded streets, is the seat of the bishop of Ostia. The loggia of the *Palazzo Lancelotti*, in the piazza, commands an extensive view. In 1883 a *Column of Victory* was erected in the new *Cemetery*, where Garibaldi successfully encountered the Neapolitan troops on May 19th, 1849. — From Velletri to the Volscian Mts., see p. 386.

The railway continues to run towards the E., between the Alban and the Volscian Mts. — 30 M. *Ontanese*.

35 M. *Valmontone*, a small town, with a handsome château belonging to the Doria-Pamphilj, on an isolated volcanic cone, is the starting-point of the diligence to the Sabine Mts., Palestrina, Genezzano, and Olevano. — Railway hence to Naples, see *Baedeker's Southern Italy*.



Palestrina is $5\frac{1}{2}$ M. distant, a walk of $1\frac{3}{4}$ -2 hrs. The view of the mountains is the only point of interest on the road.

Palestrina, a small, closely-built town, with steep and dirty streets, lies most picturesquely on the hillside. On arriving, the traveller should ask a boy to take him to the unpretending **Inn* of the *Vedova Anna Bernardini*, Via delle Concie 1 (about 5 fr. per day).

Palestrina, the Roman *Praeneste*, one of the most ancient towns in Italy, was captured by Camillus, B.C. 380, and was thenceforth subject to Rome. In the civil wars it was the chief arsenal of the younger Marius, and after a long siege was taken and destroyed by Sulla, who afterwards rebuilt it in a magnificent style as a Roman colony. Under the emperors it was a favourite resort of the Romans on account of its refreshing atmosphere, and it is extolled by Horace (Carm. iii, 4, 22) together with Tibur and Baiae. A famous *Temple of Fortune* and an *Oracle* ('sortes Prænestinæ', Cic. Div. ii, 41) attracted numerous visitors. In the middle ages Palestrina was long the source of sanguinary conflicts between the powerful Colonnas and the popes, the result of which was the total destruction of the town in 1436. The territory was purchased in 1630 by the Barberini, who still own it. — The great composer *Giovanni Pierluigi da Palestrina* (1524-94), director of the choir of St. Peter's, was born here.

The town stands almost entirely on the ruins of the temple of Fortuna, which rose on vast terraces, surrounded by a semicircular colonnade, and occupied the site of the Palazzo Barberini. On entering the town we observe the lowest of these terraces, constructed of brick. The precise plan of the ancient building cannot now be ascertained. The arcades with four Corinthian half-columns in the piazza near the cathedral, now converted into a wine-cellar, appear to have belonged to the second terrace. The *Grottini*, as the interior of these foundations is called, may be examined in the Barberini garden (in the Corso), but more conveniently in autumn than in spring, when they are often filled with water. The garden contains statues and inscriptions. — From the Corso we ascend in about 10 min. to the *Palazzo Barberini*, which rests almost entirely on these ancient substructures, and deserves a visit (fee $1\frac{1}{2}$ -1 fr.).

It contains a large *Mosaic*, probably executed in the reign of Domitian, representing scenes from the Nile, with numerous animals and figures in Egyptian and Greek costume. It was found near the cathedral. The burial chapel of the palace contains the design of a Pietà by Michael Angelo.

The ancient **Walls* of Palestrina, of which various fragments are visible, exhibit four different systems of building, from the Cyclopean mode of heaping huge blocks of stone together, to the brick-masonry of the empire. Two walls, of which that to the N. is the best preserved, connected the town with the citadel (*Arx*) on the summit of the hill, now *Castel S. Pietro*, consisting of a few poor houses. A somewhat fatiguing path ascends from the Palazzo Barberini in $1\frac{1}{2}$ hr., for which, however, the noble prospect from the summit (2545 ft.) amply compensates. The vast Campagna, from which the dome of St. Peter's rises, is surveyed as far as the sea; to the right rise Soracte and the Sabine Mts., then the Alban range; to the left is the valley of the Sacco, bounded by the Volscian Mts. The picturesque, half-dilapidated *Fortezza*

was erected by the Colonnas in 1332. The door is opened on application ($\frac{1}{2}$ -1 fr.); the approach is uncomfortable, but the view from the interior is particularly fine.

The ruins of the *Villa of Hadrian*, where the beautiful Antinous Braschi, in the Rotonda of the Vatican (p. 306) was found, are near the church of *S. Maria della Villa*, $\frac{3}{4}$ M. from the town. In the forum of the ancient Praeneste, in 1773, was found the calendar of Verrius Flaccus, now in the Pal. Vidoni at Rome (p. 198). The excavations at Palestrina have always yielded a rich harvest; the so-called cistæ, or toilet-caskets, including the celebrated Ficoronian (p. 156), were almost all found here.

The distance from Palestrina to Tivoli viâ Zagarolo and Passerano is about 15 M.

From Palestrina to Subiaco viâ Olevano.

FROM PALESTRINA TO OLEVANO, about 11 M., diligence in $2\frac{1}{2}$ hrs. (one-horse carriage 8-10 fr.); comp. p. 382. Walkers require about 4 hrs. — FROM OLEVANO TO SUBIACO, about $9\frac{1}{2}$ M., a drive of $2\frac{1}{2}$, a walk of about 4 hrs. (comp. p. 382). — *Comp. the Maps, pp. 382, 380.*

The road, which is a continuation of that from Rome (see p. 382), passes below Palestrina and runs towards the E.; it is interesting also for pedestrians. To the left, and before us, rise the Sabine Mts., to the right the Volscian, and behind us the Alban Mts. Beyond a seven-arched bridge across the *Fiume di Cave* we reach (2 M.) *Cave*, a village with 2000 inhab., the property of the Colonna's. The road pursues a straight direction, and soon passes the church of the *Madonna del Campo*, 2 M. beyond which a road to Genazzano diverges to the left.

Genazzano, a pleasant little town with 3000 inhab., is famed for its richly-endowed pilgrimage-chapel of the *Madonna del Buon Consiglio*, which attracts crowds of devotees in their picturesque costumes on festivals of the Virgin. We may now return to the high-road, or proceed through the valley direct to Olevano by a picturesque, but rugged route.

The road farther on again crosses two bridges, beyond the second of which, the *Ponte d'Orsino*, it divides; the branch to the left leads to Olevano, that to the right to Paliano. The former road at first gradually ascends, and then describes a long curve, causing Olevano to appear much nearer than it really is.

Olevano (**Alb. di Roma*, outside the town, clean, R. $2\frac{1}{2}$, pens. $38\frac{1}{2}$ fr. per week), a mediæval place, containing traces of an ancient wall, with about 3500 inhab., the property of the Borghese, lies most picturesquely on the slope of a hill, and is commanded by the ruins of an ancient castle. The interior of the town, with its narrow and dirty streets, presents no attraction. The top of the hill commanding the town affords a splendid *View, especially fine towards evening. To the right are visible the barren summits of the Sabine Mts., with Civitella, S. Vito, Capranica, and Rocca di Cave; then the narrow plain, bounded by the Alban and Sabine Mts. In the distance lies Vellëtri. Nearer is Valmontone with its château, situated on a hill; then Rocca Massima, Segni, and Paliano. Towards the S. stretches the valley of the Sacco, until lost to view. The town with its ruined castle forms a charming foreground. The inn, *Casa*

Baldi, on the top, formerly a well-known resort of artists, has much deteriorated. — On the left of the road to *Civitella* is the *Serpentara*, a fine grove of oaks, saved from destruction by the subscriptions of artists for that purpose.

FROM OLĒVANO TO SUBIACO, three beautiful routes (comp. Map, p. 380).

1. The high-road, which diverges from the Tivoli road to the right, 2 M. below Olevano, before reaching *Civitella*, is the shortest (12 M.) and most convenient (on foot 4 hrs., by carr. 2½ hrs.). Beyond the bridge over the Anio, almost at the end of the route, ¼ hr. before Subiaco is reached, a path to the right diverges to the monasteries (p. 381).

2. The route via *Civitella*, *Rocca S. Stefano*, and *S. Francesco*, the most beautiful (5 hrs.), must, like the following, be traversed on foot, or on the back of a donkey (which the landlord procures; 3 fr., and as much more to the attendant). From the *Casa Baldi* by the above-mentioned road we reach *Civitella* in ¼ hr., a poor village lying on an isolated peak in a barren, mountainous district. Owing to its secure situation it was inhabited even in ancient times, but its former name is unknown. The fragments of a fortification which commanded the narrow approach on the W. side, constructed of large masses of rock, are still visible. From the farther end of the village a beautiful view of the valleys and mountains towards Subiaco is enjoyed. Archæologists should not omit to follow the wall to the left from this gate (although a rough walk), in order to inspect the remains of the very ancient *Wall, constructed of rough-hewn blocks, by which this, the less precipitous side of the mountain, was guarded. The path then leads by *Rocca S. Stefano* and *S. Francesco* into the valley of the Anio, and to Subiaco, a beautiful route the whole way.

3. The third route (5-6 hrs., guide necessary), the longest, and in some respects the most fatiguing, but also highly interesting, leads via *Rojate* and *Affile*. *Rojate* is a small village. *Affile*, a place of more importance, boasts of a few relics of ancient walls and inscriptions. From this point to *Subiaco* (p. 381) we follow the high-road (see above).

4. The Volscian Mountains.

Railway from Rome to Velletri (from which Cori is most conveniently reached), 26 M., in 1½ hr. (fares 4 fr. 75, 3 fr. 35, 2 fr. 15 c.; express, 5 fr. 25, 3 fr. 70 c.). From *Velletri* to *Cori* diligence twice daily in ½ hrs. (2 fr.). — From *Rome* to *Segni*, 40½ M., railway in ¼-2½ hrs. (fares 7 fr. 35, 5 fr. 15, 3 fr. 35 c., or 8 fr. 10, 5 fr. 70 c.); the place, however, lies ½ M. from the station (diligence). — About ½ days may be advantageously devoted to this region, as follows: afternoon train to *Velletri*, and diligence thence to *Cori*. 2nd day, excursion to *Norma* and *Ninfa* (not advisable in summer, see p. 387) and back to *Cori*; 3rd day, to *Velletri*, railway to *Segni*, returning to *Rome* in the evening.

The Volscian mountain-range, which attains an elevation of 5000 ft., is


separated on the E. from the principal chain of the Apennines by the valley of the Sacco, and on the N. from the Alban Mts. by a narrow depression; it extends to the S. as far as the Bay of Gaeta, and on the W. is bounded by a dreary and in some places marshy plain adjoining the sea. This district was anciently the chief seat of the Volsci, but was at an early period subjugated by the Romans and Latinised. Its towns, picturesquely rising on the slopes, still bear many traces of the republican epoch of Italy, which add great interest to the natural attractions of the scenery. Hitherto these mountains have seldom been visited, partly on account of the pooriness of the inns (except at Cori), and partly owing to their former reputation as a haunt of bandits.


From Rome to *Velletri*, see p. 382. — The ROAD FROM VELLETRI TO CORI, 10 $\frac{1}{2}$ M., especially the first part, traversing a dreary plain, is uninteresting. To the right lies the (3 $\frac{1}{2}$ M.) *Lago di Giulianello*, an extinct crater. Beyond the poor village of *Giulianello* (6 M. from Velletri) the mountain-slopes become more attractive. About 2 $\frac{1}{2}$ M. farther on, at the chapel of the *Madonna del Monte*, a road to the left diverges to the upper part of the town of Cori. The road to the right, descending to the lower part of the town, concealed among olive-plantations, is preferable.

Cori. — *Locanda di Filippuccio*, at the gate, poor; *Albergo dell' Unione*, farther up, better. — *Guide*, to save time, 1 $\frac{1}{2}$ -1 fr. — Two Horses to Norma and Ninfa, with mounted guide, about 12 fr., incl. Sezze about 18 fr.

Cori is the ancient *Cora*, which claimed to have been founded by the Trojan Dardanus or by Coras and was at an early period a member of the Latin League. Even in antiquity it consisted of an upper and a lower town. The remains of the ancient walls, constructed of huge polygonal blocks, are still considerable. During the empire it still prospered, but its name afterwards fell into oblivion. In the early part of the middle ages it seems to have been wholly deserted, but in the 13th cent. it was rebuilt by the Conti di Segni and fortified with a wall, the greater part of which is still extant. Pop. 6200. Tobacco is largely cultivated in the neighbourhood.

The 'Via Pelasga', skirting a portion of the ancient wall, ascends from the piazza to the upper town. Following this, we reach first the church of *S. Oliva*, which is built on ancient foundations and possesses antique columns and two-storied cloisters. Beside the church is a fragment of the ancient wall in unusually good preservation; and farther up some scantier remains. Adjoining the church of *S. Pietro* is the portico of a **Temple*, generally called the *Temple of Hercules*, but perhaps dedicated to the three Capitoline deities, Jupiter, Juno, and Minerva. The statue of Minerva which now adorns the fountain in the Palace of the Senators in Rome (p. 211), and which has been restored as Roma, is believed to have been found here. The cella of the temple is incorporated with the church of *S. Pietro*; but 8 columns of the Doric colonnade, with a frieze of travertine bearing traces of stucco decoration, are preserved. The inscription, recording the erection of the edifice by the *dumviri*, or chief magistrates of the place, dates from the time of Sulla. *View hence over the town towards the sea, and of the plain with the isolated M. Cir-







ceio. Within the church (opened on application; 25 c.) is an ancient marble urn, used as a font.

We now descend to the Via S. Salvatore, where two admirably executed **Corinthian Columns* are still standing. On the epistyle above is part of the ancient inscription, and another part is preserved in a fragment built into the wall of the Casa Moroni. From these it appears that the columns belonged to a *Temple of Castor and Pollux*. They probably were the two in the centre of six columns on the front of the temple. — Still lower down, in the Vicolo di Pozzo Dorico and the Piazza Pizzitonico, are the remains of the substructures of some large cisterns.

Near the *Porta Ninfesina* is another large fragment of the earliest polygonal wall. Outside the gate is a deep ravine, spanned by the ancient *Ponte della Catena*, constructed of blocks of tufa. The solidity of the arch with its double layers of masonry is best appreciated when surveyed from below.

FROM CORI TO NORMA (about $7\frac{1}{2}$ M.) a road leads across the plain, and another route is by a narrow bridle-path over the mountains, generally skirting a steep slope. The latter leads in about 3 hrs. riding to the ruins of **Norba**, which became a Latin colony, B.C. 492, and was captured and destroyed by the troops of Sulla during the civil wars. The well-preserved wall, in the polygonal style, was $1\frac{1}{2}$ M. in circumference, and several towers and a gateway are still traceable. In $\frac{1}{4}$ hr. more the small mountain-village of **Norma** (*Locanda*, poor) is reached. On the road below it lie the remains of the mediæval town of ***Ninfa**, surrounded by a marsh which has been the cause of its abandonment. The ivy-clad ruins date mainly from the 12th and 13th cent. and include a palace, a monastery, a church with faded frescoes, and several streets. In summer the malaria makes a visit to Ninfa unadvisable, while the crops also render a closer investigation of the ruins impracticable.

FROM NINFA TO SEZZE, $3\frac{1}{2}$ hrs. The road diverges to the left from the Sermoneta road at the *Abbey of Valvisciolo* (abbey-church of the 13th cent.), and leads through a beautiful wooded valley, below *Bassiano*. It then traverses a well-cultivated region, with *Monte Semprevisa* (5035 ft.), the highest summit of the Volscian Mts., on the left.

Sezze (*Locanda Nazionale*, in the piazza, unpretending) is the ancient *Setia* of the Volscians, a Roman colony after 382 B.C., and frequently mentioned in the Italian wars up to the time of Sulla. Under the empire its name was remembered only on account of its wine, which Augustus preferred even to Falernian. Considerable remains of its ancient walls have been preserved; they are built of massive polygonal blocks, but with more attention to horizontal courses than was the case at Cori. The rough rusticated work here is an unusual feature in ancient town-walls, which in most other examples are carefully smoothed. A massive substructure in the same style, below (to the right) the entrance of the town, has been arbitrarily named *Tempio di Saturno*. — A diligence runs daily from Sezze to *Foro Appio*, in connection with the diligence between Velletri and Terracina.

FROM SEZZE TO PIPERNO, $9\frac{1}{2}$ M., carriage-road (bridle-path shorter; mule 3 fr., in $2\frac{1}{2}$ hrs.). On the *Monte Tresi* (1640 ft.), between these two

routes, are the ruins of a town destroyed in the 16th cent. by the inhabitants of Sezze.

Piperno (*Locanda della Rosetta*, tolerable) was founded early in the middle ages by refugees from the ancient Volscian town of *Privernum*, remains of which may be seen on the road to Frosinone, near the streamlet Amaseno. The *Cathedral*, in the picturesque piazza, was built in 1233 and modernised in the interior in 1782. — An interesting excursion (1½ hr.; carr. there and back 6 fr.) may be made hence to the Cistercian convent of *Fossanuova*, where St. Thomas Aquinas died in 1274 while on his way to the Council of Lyons. The convent-church, built about 1225, with rectangular choir and a rectangular tower over the crossing, is one of the earliest examples of Italian Gothic. It has recently been restored. The cloisters, chapter-house, and refectory are also interesting. One of the rooms contains a relief of St. Thomas Aquinas, by Bernini. — From Piperno to *Frosinone*, diligence in 3½ hrs. (fare 2½ fr.), starting at 4 a.m.; see *Baedeker's Southern Italy*.

SEGNI is the first railway-station beyond *Valmontone* (p. 382). From the station we take about 2 hrs. to ascend to the town. We skirt the slopes of the mountains enclosing the valley of the Sacco; to the left, on a solitary hill below us, is the picturesque *Gavignano*, the birthplace of Innocent III. The remains of the old walls of Segni and the *Porta Sarracinesca* come into sight on the height rising above a lateral valley to the left. The last part of the way ascends in numerous windings.

Segni (*Loc. di Gaetanino*), the ancient *Signia*, said to have been colonised by the Romans under Tarquinius Priscus, lies on a mountain-slope (rising to a height of 2300 ft.), in a secure position, with fine views of the valley and the towns of the Hernici. The present town (6000 inhab.) occupies the lower half of the old site.

Ascending through the streets, we reach the church of *S. Pietro*, standing on the foundations of an ancient temple, the walls of which consist of rectangular blocks of tufa, with two courses of polygonal masses of limestone below. A cistern near the church is also of the Roman epoch. The **Town Walls*, in the massive polygonal style, 1¼ M. in circumference, are to a great extent well preserved. From *S. Pietro* we follow an easy path to the summit of the hill, which is indicated by a cross; fine view of the town and the valley of the Sacco. Hence we follow the wall, passing a small sally-port at the N. angle, to the half-buried *Porta in Lucino*. Farther on, on the slope of the N.W. spur, is the curious **Porta Sarracinesca*, apparently built before the discovery of the arch principle, as a substitute for which the lateral walls gradually approach until they meet at an angle. From this point we may follow the footpath along the slope, which passes a large washing-bench and descends to the lower gate.

From Segni a fine but fatiguing mountain-path leads to Norma in 6 hrs. (horse and guide 5 fr.); Montelanico may be included.

The station of Segni is 4-5 M. from Anagni. Regarding this and other towns of the Hernici, see *Baedeker's Southern Italy*.

5. Etruscan Towns.

That part of the Roman Campagna which extends N. from the Tiber to the Ciminian Forest and the mountains of Tolfa was the Southern Etruria of antiquity. Originally occupied by a tribe akin to the Latins, then conquered by the Etruscans, it was finally, after the protracted contests with which the first centuries of the annals of Rome abound, reconquered and Latinised. The fall of the mighty Veii, B.C. 396, mainly contributed to effect this memorable change. Excursions are frequently made to the remains of the Etruscan tombs at Cervetri and Veii. Malaria is unfortunately very prevalent throughout this whole district.

VEII.

An excursion to *Veii* takes one day (carr. there and back about 25 fr.). Pedestrians should drive at least as far as the Tomba di Nerone ($4\frac{1}{2}$ M., fiacre 4 fr.), or La Storta ($8\frac{1}{2}$ M.). Provisions for the journey should be carried from Rome, as the tavern at Isola is extremely poor.

From Rome to the *Ponte Molle*, see p. 334 et seq. By the Osteria, where the Via Flaminia diverges to the right, we follow the VIA CASSIA, gradually ascending to the left. The district soon becomes desolate, but fine views are enjoyed of the Alban and Sabine Mts., Mt. Soracte, and the lateral valleys. About $4\frac{1}{2}$ M. from Rome, on a dilapidated pedestal to the left, stands a sarcophagus, erroneously called the *Tomb of Nero*. The long inscription (at the back, facing the ancient road) expressly records that the monument, which dates from the 2nd cent. after Christ, was erected by *Vibia Maria Maxima* to the memory of her father P. Vibius Marianus and her mother Regina Maxima. — An ancient route, somewhat shorter than the modern, diverges here to the right to Veii, but as it is not easily traced the high-road is preferable.

$8\frac{1}{2}$ M. *La Storta* (Inn), anciently the last post-station on the route to Rome. One mile beyond it the road to Isola Farnese diverges to the right; $\frac{1}{2}$ M. farther on we take the road to the right, that on the left leading to *Formello*.

Isola Farnese, a poor village, belonging to the Rospigliosi, numbering about 100 inhab., owes its foundation to the security of its site, and was a place of some consequence in the middle ages. We engage a guide here ($1-1\frac{1}{2}$ fr., bargaining necessary) to conduct us to the site of *Veii*, which is interesting and picturesque; but the ruins are scanty.

Veii was one of the most powerful of the Etruscan cities. After contests protracted for centuries, which at first centred round *Fidenæ* (p. 341), the frontier-stronghold of the Etruscans on the S. bank of the Tiber, and after manifold vicissitudes and a long siege, the city was taken by Camillus in B.C. 396. Its circumference, which may still be traced, was $5\frac{1}{2}$ M. After its capture it fell to decay, and was repopled by Cæsar with Romans; but this colony scarcely occupied one-third of the former area. Excavations here have led to the discovery of inscriptions, statues, and the columns mentioned at p. 154.

The ancient site of the city was a triangle between two brooks, which united with each other farther down, viz. the *Fosso dell' Isola*, washing the N.E. base of the hill of Isola, and the *Fosso di Formello* or *di Valca* (the ancient *Cremera*), flowing from N. to S. The

ancient citadel (*Arx*), now the *Piazza d'Armi* or *Cittadella*, occupies a separate plateau at the confluence of the brooks, connected with the site of the town by a narrow isthmus only.

A visit to the principal points takes 2-3 hrs. We descend from *Isola* to the N.W. to the *Fosso dell' Isola*, which forms a pretty waterfall beside the mill (*molino*). — Thence we proceed to the *Ponte Sodo*, a tunnel hewn in the rock, through which flows the *Fosso di Formello*. Then to the *Grotta Campana*, a rock-tomb discovered in 1842, with two interior chambers, the wall-paintings in which date from a high antiquity. The skeletons which were found on the benches when the tomb was opened rapidly crumbled into dust on the admission of air. A few remains of armour and clay vessels are still extant. — We now recross the *Fosso di Formello* to the *Porta Spezieria* (drug-shop), with remains of a columbarium, the recesses of which explain the name. On the hill above are some singularly well-preserved remains of the fortifications, a gate, and a street paved with lava. — We may either follow the hill or the valley of the *Fosso di Formello* to the S. to the above-mentioned *Piazza d'Armi*, which commands a fine view. To the N. is the conspicuous *Tumulus of Vaccareccia*, crowned with battlements. — We return from the piazza to *Isola*, in the rocks near the entrance to which are numerous sepulchral niches.

Walkers may descend the valley of the *Cremera* from the *Piazza d'Armi* and in about 2 hrs. strike the *Via Flaminia* (p. 337), about 6 M. from Rome. The camp of the *Fabii*, whose whole family was destroyed by the *Veientes*, lay about $1\frac{1}{2}$ M. from the *Piazza d'Armi*.

GALERA.

Galera, 15 M. from Rome, may be visited on the way to Bracciano, or by carriage (about 25 fr.), in one day from Rome. Provisions necessary.

About $\frac{1}{2}$ M. beyond *La Storta* (p. 389) the *Via Clodia* diverges to the left from the *Via Cassia*, which leads to Viterbo (p. 69). We follow the *Via Clodia*, the old pavement of which is seen at intervals. On the roadside is the entrance to the subterranean conduit of the *Acqua Paola*, which descends from the lake of Bracciano (p. 326). On the left, about 5 M. from *La Storta*, appears the church of *S. Maria di Cesareo*; $\frac{1}{2}$ M. farther is the *Osteria Nuova*, where the carriage may be left. The land here is well-watered, and occupied by several large farms. A path to the left in the direction of these, then turning to the right, leads in $\frac{1}{2}$ hr. to the ruins of *Galera*. The town sprang up in the middle ages near the ancient *Careiae*, and was at first governed by powerful nobles; in 1226-1670 it belonged to the Orsini. At the beginning of the present century the inhabitants were driven from the place by malaria. It stands on an abrupt tufa-rock, around which flows the *Arrone*, the outlet of the Lake of Bracciano. The walls are of the 14th and 15th centuries. Two churches with their towers, the palace of the Orsini, and many houses are recognisable, all densely overgrown with ivy and creepers.

BRACCIANO.

24½ M. from Rome: *Vetturino* several times weekly from the Piazza of the Pantheon, in 5-6 hrs. (fare 4 fr.), returning next day. In May and June, the bathing-season at Vicarello, the traffic is brisker. — Bracciano is 9½ M. from Cervetri (p. 392).

Beyond the Osteria Nuova (p. 390) the *Arrone* is soon reached. A road to the right then diverges to Anguillara (see below), situated on the lake. The country continues dreary. About 3 M. before Bracciano is reached, the *Lake of Bracciano* becomes visible, with *Trevignano* and *Rocca Romana*, the highest point (2020 ft.) of the surrounding range of hills. The lake, the *Lacus Sabatinus* of antiquity, is 20 M. in circumference, and lies nearly 500 ft. above the sea-level. Its form and the heights encircling it indicate that it was once a crater. It is famed for its eels and abundance of fish, and the slopes are well-cultivated, the upper parts being wooded, but malaria is prevalent.

Near Bracciano the road divides: the upper branch, to the left, leads to the Capuchin monastery; the other to the right, to the town.

Bracciano (*Loc. Piva*, a fair second-class inn), a modern town with 3000 inhab., possesses a picturesque castle of the 15th cent., and several iron-works in the vicinity. The **Castle*, erected by the Orsini, now the property of Prince Odescalchi, is very interesting, and its towers and fortifications convey a good idea of the character of a mediæval stronghold. It is said on this account to have riveted the attention of Sir Walter Scott far more powerfully than the ruins of antiquity. The interior, still inhabited, contains nothing worthy of note. The **View* from the tower, extending over the beautiful lake to Trevignano and Anguillara, with Soracte and the Sabine Mts. in the background, is remarkably fine.

A pleasant excursion may be made from Bracciano to *Trevignano* (6 M.). The road skirts the lake. After 1¾ M. a path ascends to the left to the (¼ hr.) old church of the martyrs SS. Marco, Marciano, and Liberato, erected, as the inscription states, on the site of an ancient villa named *Pausilypon*, and affording a fine view. In the vicinity stood *Forum Clodii*, from which inscriptions and other relics are preserved. Pedestrians may regain the road to Vicarello by another forest-path. — *Vicarello* is 4 M. from Bracciano. The baths, ¾ M. from the road, with a hot sulphureous spring, are the *Aquæ Apollinæ* of antiquity. A proof of the estimation in which they were held was afforded in 1852 by the discovery of great numbers of coins and votive offerings, most of which are now in the Museo Kircheriano (p. 156; others in the Vatican, p. 318). Owing to the malaria, the bathing season is not prolonged beyond the early part of summer. — By the road are seen many remains of 'opus reticulatum', belonging to villas of the imperial epoch. *Trevignano*, occupying the site of the Etruscan town of *Sabate*, which fell early into oblivion, formerly the property of the Orsini, now that of the Conti, is a poor village. Roman remains very scanty. In the principal church two pictures of the school of Perugino. The ruined castle above the village commands a fine view; its destruction was due to Cæsar Borgia.

A bridle-path leads hence in 1½ hr. to *Sutri* (p. 73), another in about 3 hrs. to *Anguillara*, the ancestral seat of the once powerful counts of that name. If the wind be favourable it is preferable to cross the lake from Trevignano by boat. From Anguillara to Bracciano an uninteresting route of 6-6½ M.; the tour of the lake may thus be made in one day.

CÆRE.

Cervetri, the ancient *Caere*, may be visited from Rome in one day. The first train should be taken as far as Palo (p. 7; express in 1 hr., fares 6 fr., 4 fr. 20 c.; slow train in 1¾ hr., 5 fr. 45, 3 fr. 80, 2 fr. 45 c.); thence in 1¼ hr. to Cervetri, where a stay of 5 hrs. may be made, leaving time to regain Rome by the afternoon or evening train. At Palo a carriage may be obtained from the coach-hirer Francescone.

It is necessary to inform the Sindaco of Cervetri of the intended visit a day or two beforehand, as otherwise the custodian with the key may not be forthcoming. After two or three days of rain the graves are filled with water.

Cervetri (**Café-Restaurant*, near the gate, moderate; the landlord provides guides and carriages to the tombs), the *Caere* of antiquity, originally named *Agylla* (Phœnician, 'circular city'), a place of very remote origin, afterwards became subject to the Etruscans, and carried on an extensive commerce from its harbours *Pyrgos* (S. Severa) and *Alsion* (Palo). At the same time it always maintained friendly relations with Rome, and in B.C. 351 it was incorporated with the Roman state. It was a prosperous place in the reign of Trajan, and continued to flourish down to the 13th cent., at the beginning of which it was abandoned by its inhabitants, who founded *Cere Nuovo*, 3 M. distant, the present *Ceri* (with not more than 50 inhab.). A number of them, at an uncertain date, afterwards returned to *Cære Vetere*, whence the name *Cervetri*. The present town (600 inhab.) occupies but a small part of the site of the ancient city, which was 3 M. in circumference. The interest of this locality was greatly increased by the discovery of numerous tombs in 1829, and the excavations are still prosecuted. In the middle ages Cervetri was surrounded with a battlemented wall, and had, as now, only one entrance. Part of the walls and several towers are still well-preserved and give a picturesque air to the town, especially on the N.E. side, where the old baronial château is situated.

Some of the TOMBS are clustered together and hewn in the rock, while others stand alone in conical mounds or tumuli. They are not nearly so well preserved as those of Corneto (p. 5), and hardly a trace of painting remains. The more important may be visited in 3-4 hrs., with a guide (see above; 1 pers. 2 fr., 2 pers. 3 fr., a party in proportion). Most of them lie on the hill opposite the town, and separated from it by a gorge.

1. GROTTA DELLE SEDIE E SCUDI, so called from two seats and several shields hewn in the rock, consists of an ante-room and five chambers. 2. GROTTA DEL TRICLINIO, with faded paintings representing a banquet. 3. GROTTA DELLA BELLA ARCHITETTURA, with two chambers, supported by pillars. 4. GROTTA DELLE URNE, with three marble sarcophagi. 5. GROTTA DELLE ISCRIZIONI, or DE' TARQUINII, with two chambers, borne by pillars, contains numerous inscriptions with the name of *Tarchnas* (Lat. *Tarquinius*), thus apparently corroborating the tradition that the Roman kings were of Etruscan origin. 6. GROTTA DEI BASSORILIEVI, excavated in 1850, the best preserved and most interesting of all. At the head of the flight of steps are two lionesses as guardians of the tomb. The two pillars supporting the roof, and the walls above the niches are decorated with various bas-reliefs of instruments, weapons, and objects of domestic life, partly in stucco, partly hewn in the tufa-rock, and mostly painted.

On the road to Palo lies: *7. GROTTA REGOLINI GALASSI, opened in 1829, a tomb of great antiquity and now very dilapidated. The roof is vaulted by means of the gradual approach of the lateral walls to each other, instead of on the arch-principle. The yield of this tomb, now in the Gregorian Museum, was very considerable, consisting of a bed, a four-wheeled chariot, shields, tripods, vessels of bronze, an iron altar, figures of clay, silver goblets, and golden trinkets once worn by the deceased, all found in the small chambers to the right and left of the vaulted passage. — Fully $\frac{1}{2}$ M. from this is situated another tomb, opened in 1850, and still containing the vases, vessels, and other objects then discovered.

Besides these, there are many other tombs (e.g. *Grotta Torlonia*, the first chamber of which contains 54 recesses for the dead).

6. The Sea-Coast of Latium.

Communication with the sea was of far greater importance to ancient than to modern Rome, and its former facility contributed much to the proud rank held by the mistress of the world. Vast harbours and other structures were accordingly founded at the estuary of the Tiber. The coast was a favourite resort of the wealthy Romans, as the numerous villas testify; but it is now desolate, and is skirted by a broad belt of forest (*macchia*), where the malaria in summer is peculiarly pestilential. Lofty sand-hills, extending to the S. beyond the Pontine Marshes, bound the whole coast.

PORTO. FIUMICINO.

FROM ROME TO FIUMICINO, 21 M., railway in $1\frac{1}{4}$ hr. (3 fr. 85, 2 fr. 70, 1 fr. 75 c.; there and back, including a bath in the sea, 4 fr. 80, 3 fr. 75 c.).

The railway describes a circuit round the town (p. 7). $5\frac{1}{2}$ M. *Stazione di S. Paolo* (outside the Porta Portese). — $9\frac{1}{2}$ M. *Magliana*. Close to the station, on the hill to the right, is the *Vigna Ceccarelli*, the site of the sacred *Grove of the Arvales*. The corporation of the Twelve Arvales was of very ancient Latin origin, having been founded, according to tradition, by the sons of Acca Larentia ('mother of the Lares'), the foster-mother of Romulus. The society was entirely remodelled by Augustus and became a privileged order, consisting of the relations and friends of the emperor.

Excavations have been carried on here since 1866, and records of the society during the imperial period, engraved on stone, have been found. The ancient foundations on which the Casino of the vigna rests belong to the circular temple of the *Dea Dia*, which lay in the middle of the grove. In the plain below the grove (on the other side of the road) there are remains of a rectangular building, with a hall enclosed by rows of columns. — Higher up the hill lay an ancient Christian burial-place, where remains of an oratory of Pope Damasus have been discovered. Adjacent is the entrance to the *Catacombs of St. Generosa*. They are of small extent and of remarkably primitive construction, but are in excellent preservation and merit a visit.

About $\frac{1}{2}$ M. farther on, betwixt the road and the river, is situated the ruinous hunting-château of *La Magliana*, with pleasing Renaissance details, once a favourite retreat of Innocent VIII., Julius II., and Leo X., and now the property of the convent of S. Cecilia (frescoes in the Palazzo dei Conservatori, p. 215).

14 M. *Ponte Galera*, see p. 7. Our line now quits the Leghorn railway (R. 1) and continues to run westwards.

19 M. **Porto** was founded in A. D. 103 by the Emp. Trajan (*Portus Trajani*), as the harbour constructed by Claudius as a substitute for that of Ostia, which had become choked up by the

deposits of the Tiber, had soon shared the same fate. Trajan also formed a new canal here (*Fossa Trajani*), which now forms the main arm of the Tiber. Trajan's seaport, which lay close to the sea, and soon attracted the commerce of Rome, is now 2 M. distant from it; and the delta formed by the river is estimated to advance 13 ft. annually. The present town consists of the *Cathedral of S. Rufina* (a modernised edifice of the 10th cent.), an episcopal *Palace*, with inscriptions and antiquities, and a *Villa of Prince Torlonia*. The harbour of Trajan, a large octagonal basin, surrounded by magazines, is now a shallow lake only. In the meadows to the N. of this, the extent of the harbour of Claudius is still traceable.

21 M. **Fiumicino** (*Locanda*) is a modern place. The castle, erected in 1773 close to the sea, is now $\frac{1}{2}$ M. distant from it. The tower commands a fine view. — The train runs hence, $\frac{1}{2}$ M. farther, to the new *Stabilimento Bagni*, or bath-establishment.

The *Isola Sacra*, situated between the two arms of the river, was so named at a very early period, either from having been the site of a heathen temple, or from having been presented by Constantine to the Church. Numerous herds of cattle are pastured here, against which travellers must be on their guard, especially in spring. A guide is therefore desirable. In dry weather visitors may walk across the island from Fiumicino to Ostia in $\frac{1}{2}$ hr.

OSTIA.

15 M. from Rome. Two-horse carriage there and back 25-30 fr., fee 2-4 fr.; the drive to Castel Fusano must be expressly stipulated for. A supply of provisions should be taken, and the beautiful cella of the temple, or the woods at Castel Fusano may be selected as resting-place. The osteria at Ostia is poor, and there is no inn at Castel Fusano. The points of interest may be seen in 3-3 $\frac{1}{2}$ hrs. — From Ostia to Fiumicino, see above; ferry at Torre Boacciana.


From the *Porta S. Paolo* to the *Osteria del Ponticello*, where the Via Laurentina diverges to the left, see pp. 352-354. — The road to Ostia leads to the right and runs not far from the Tiber. At the (9 $\frac{1}{2}$ M.) *Osteria di Malafede* a road diverges to the left to (4 $\frac{1}{2}$ M.) *Castel Porziano*, a royal hunting-lodge, on the site of the ancient *Vicus Augustanus* (thence to Tor Paterno, 5 M., see p. 396). The road next traverses the hills of Decima, and then a growth of underwood (*Macchia di Ostia*), beyond which a fine view of Ostia, 2 M. distant, is obtained. A short distance from the village an embankment carries us across the *Stagno di Ostia*, which has yielded salt since the period of the kings.

Ostia, a poor village with scarcely 100 inhab., was founded by Gregory IV. in 830, several centuries after the destruction of the ancient town. Under Leo IV. (847-56) the Saracens sustained a signal defeat here, which Raphael has represented in the Stanze. Julius II. (1503-13), when Cardinal della Rovere, caused the fort to be erected by *Giul. da Sangallo*. The town lost its importance when Paul V. re-opened the right arm of the Tiber at Porto in 1612.

The pleasing church of *S. Aurea*, attributed to Baccio Pintelli,

was erected under Julius II. The *Castello* contains an extensive but comparatively uninteresting collection of inscriptions and relics from the excavations. The most important object is a large marble *Ara*, with reliefs relating to the foundation of Rome. The hill on which the *Castello* stands affords a good view.

The Ostia of antiquity, founded by Ancus Martius, extended westwards along the Tiber, from the present village, as far as *Torre Boacciana*. It was a large commercial town, and though in the reign of Augustus it lost some of its importance through the choking up of the harbour by the Tiber, it afterwards regained its influential position. The inhabitants belonged to numerous nationalities and various religions; Christianity also was introduced here at an early period. The bishopric of Ostia, according to some accounts,



was founded by the Apostles themselves, and is still regarded with great veneration by the Romish clergy. Monica, the mother of St. Augustine, died here.

At the entrance to the town (r.) is a plain osteria, where the custodian is to be found (fee for the excursion 2-3 fr.). The *Tombs*, which extend in a line beyond the *Porta Romana* of the *Ancient Town*, are reached in 5 min. from the gate. Most of the reliefs found here are now in the Lateran (p. 269). In 3 min. the gate of the old town is reached. Where the road forks, we ascend slightly to the right to the (5 min.)**Forum*, excavated in 1880-81, a square structure, each side of which was 265 ft. long, and which was surrounded with colonnades. The portico on the S. contained marble columns, the others brick columns encased in stucco. At a later period the colonnades were divided into a series of small chambers (best seen at the S.E. corner), which served as the offices of various Collegia or guilds, such as the lumberers who conveyed timber to Rome and the boatmen of Terracina. In the centre of the forum is the substructure

of a *Templum 'in antis'*, 80 ft. long and 35 ft. wide. The walls are in a very ruinous condition and have been almost entirely stripped of their marble lining, while the altar has experienced a similar fate. Adjoining the S. colonnade of the forum is the rear-wall of the **Theatre*, of which considerable remains of both stage and auditorium are extant. This edifice, built in the early imperial period, perhaps by M. Agrippa, was restored by Septimius Severus in 196-7, and again, in a very imperfect and hasty manner, in the 4th or 5th century. Numerous marble bases with inscriptions, brought from the forum at the last restoration, may be seen below the seats in the central corridor and in other parts of the building. Farther to the W. rises a handsome and conspicuous **Temple*, which at the beginning of the present century was the only visible relic of ancient Ostia. The cella, of admirable masonry, is well preserved; the threshold consists of a single block of African marble, 16 ft. in length. The vaulted substructions contain the receptacles for the sacred vessels (*favissae*). Farther to the S. is the shrine of the *Magna Mater*, excavated in 1869, an irregular quadrangular structure with a colonnade on each side, where the statue of Atthis mentioned at p. 270, was found. — We now retrace our steps and follow the street leading straight from the back of the temple to the river. This street, 50 ft. in width, was flanked with rows of pillars, behind which were shops and private houses; it is the most extensive construction of the kind which now remains to us. At the modern house we diverge to the left and skirt the Tiber to (10 min.) the **Baths*, which are of moderate size; the positions of the furnace, swimming-basin, hot-bath (*caldarium*), etc., are traceable.

Proceeding towards the road on the Tiber, we arrive in 5 min. at a *Store Chamber*, with thirty earthen jars for keeping wine, oil, and grain, imbedded in the floor. Then, 2 min. farther, are much more extensive *Baths* with a palæstra, etc., probably erected by Antoninus Pius; a large mosaic pavement in the principal hall represents the intricacies of the labyrinth. Adjacent is a small *Mithraeum*, with an inscription on the mosaic pavement. — On the roadside, just beyond the baths, are remains of arches of tufa and travertine of the republican era, which probably belonged to a harbour. In $\frac{1}{4}$ hr. more we reach the road leading from the E. side of the town to *Laurentum*, where a number of graves and columbaria have been discovered. Thence back to Ostia, $\frac{3}{4}$ M.

A carriage-road leads from Ostia to (2 M.) **Castel Fusano*, situated in the midst of a beautiful pine-forest. It was erected by the Marchese Sacchetti in the 16th cent., and fortified against pirates, and is now the property of the Chigi, who leased it in 1888 to the royal family. A pleasant road, with an ancient pavement of basalt, leads hence to the sea, $1\frac{1}{2}$ M. distant.

From Castel Fusano to *Tor Paterno*, a farm near the ancient Laurentum, 6 M. Thence with guide to ($4\frac{1}{2}$ M.) *Pratica*, an insignificant village on the site of the ancient *Lavinium*.

About 6 M. from Pratica and 11 M. from Albano lies **Ardea**, the ancient capital of the Rutuli, one of the few towns of Latium which even in the time of the Roman emperors were avoided on account of the malaria. Early deserted for this reason, Ardea has preserved, especially in its fortifications, a more antique appearance than any other Latin town. The wretched modern village (150 inhab.) occupies the site of the old citadel on a hill with artificially precipitous sides. There are remains of massive walls of different periods at various places; and two ramparts with ditches, several hundred yards long, like the wall of Servius at Rome.

ANZIO.

Railway to *Cecchina*, below Albano, see p. 368. Steam-tramway thence to *Anzio* in 1 hr. (fares 3 fr. 50, 2 fr. 50, 1 fr. 75 c.; through-ticket from Rome to Anzio 6 fr. 60, 4 fr. 60, 3 fr. 15 c., return 9 fr. 50, 6 fr. 65, 4 fr. 50 c.).

Anzio. — **Hotels:** ALBERGO DELLE SIRENE, large new house midway between Anzio and the Villa Borghese; ALBERGO MILANO, in the Piazza. *Ristorante Turchetto*, in the town. — **Private Apartments** in the season at many of the new villas.



1:50,000 1 Kilometri

Carriage with one horse to Nettuno for 1-3 pers. 1 fr., each addit. pers. 20 c. more. — Omnibus 25 c.

Boats in the harbour, 1-3 pers. 1½ fr. per hr., each additional person ½ fr. more. — During the season small steamboats ply on Sun. to Astura and Tor Caldara (to the N.).

The little fishing-town of *Porto d'Anzio*, or simply *Anzio*, as it has recently become customary to call it, a favourite resort of the Romans during the bathing-season (June, July, and August), in spite of its liability to fever, occupies the site of the ancient *Antium*.

Antium, the capital of the Volsci, and a prosperous seaport at an early period, the place where Coriolanus sought refuge when banished from Rome in B. C. 490, was compelled in 468 to succumb to the Romans. In 338, when all the Latins were conquered, Antium received a Roman colony, and was thus permanently united with Rome. Extensive villas were erected here towards the end of the republic. Cicero possessed an estate at Antium, the tranquillity and charms of which he highly extols (Att. iv. 8). The emperors also, especially those of the Julian house (Caligula, Claudius, Nero), built country-houses here; and though at a later period Antium seems to have been surpassed in popularity by Baiae

and the places on the bay of Naples, the temple of Fortune, mentioned by Horace (Carm. I. 35), where oracular responses were given, existed until the latest era of paganism. The place was entirely deserted in the middle ages, but in the 16th cent. it began to be rebuilt. The present town dates almost wholly from the period after the restoration of the harbour by Innocent XII. (1698).

The tramway-terminus lies close to the Piazza, and a few paces from the harbour. The latter is small, and as it opens to the S., is in continual danger of being sanded up. The remains of an ancient mole may be seen opposite, in the direction of Nettuno, near the new bathing-establishment.

A pretty walk leads to the *Arco Muto*, turning to the right from the lighthouse (*Faro*) and descending to the beach beyond a solitary column. The promontory is pierced with antique passages, belonging to a large villa, which was, perhaps, built by one of the emperors. Picturesque view of the ruin-strewn beach. The Apollo Belvedere (and probably the Diana of Versailles also) was found here.

Close by the town itself is the *Villa Albani*, commanding pretty views from its neglected grounds; we reach it by ascending from the Piazza, crossing the rails in the Via della Capitale, and then turning to the right. Opposite the entrance is the *Villa Corsini* or *Mencacci* (usually inaccessible). Continuing along the Via della Capitale and ascending the hill straight in front, we come upon the remains of an antique wall. Fine survey of the town and sea.

The TRAMWAY FROM ANZIO TO NETTUNO (see below; in 7 min., fares 35, 20 c.) follows the high-road (1½ M.). Adjoining the railway signal-box No. 31 is the side-entrance to the —

**Villa Borghese* (main entrance opposite the Casino generally closed), which is surrounded by fine shady trees. When occupied by the family the villa can be visited only with a special permesso, to be obtained at the Pal. Borghese (p. 184) in Rome. The casino is said to occupy the site of the ancient Arx; and fragments of columns, capitals, and other remains have been found here at various points. An alley of trees (*Olmata*) ascends from the S. exit of the villa to the little *Casino Soffredini*, which affords one of the finest views of Anzio and Nettuno. — From the gate of the villa to Nettuno, ⅓ M.

Nettuno (*Trattoria della Ferrovia*), which depends for its interest on its picturesque situation, is said to have been once a settlement of the Saracens. The native costume of the women is picturesque, but it is now worn only on holidays. — A coast-road leads from Nettuno to (7½ M.) *Astura*, where there are numerous remains of Roman villas, and where Cicero also once possessed a villa. A tower, connected with the mainland by a bridge, belonged to a castle in which prince *Conradin of Swabia* sought refuge with *Jacopo Frangipani* after the Battle of Tagliacozzo. The latter, however, delivered him up to Charles of Anjou, who caused him to be beheaded at Naples.

List

of the most important Artists mentioned in the Handbook, with a note of the schools to which they belong.

Abbreviations: A. = architect, P. = painter, S. = sculptor; ca. = circa, about; Bol. = Bolognese, Ferr. = Ferrarese, Flor. = Florentine, Fr. = French, Lom. = Lombard, Rom. = Roman, etc.

The Arabic numerals enclosed within brackets refer to the art-notice throughout the Handbook, the Roman figures to the Introduction.

- Agoracritos*, Greek S., pupil of Phidias, ca. 436-424 B.C. — (xxxii).
Albani (*Albano*), *Franc.*, Bol. P., 1578-1660.
Alberti, *Leon Batt.*, Flor. A., 1405-72. — (xlix. 92).
Alcamenes, Greek S., pupil of Phidias, ca. 430-398 B.C. — (xxxii).
Alfani, *Domenico di Paris*, Umbr. P., 1483-1553. — (48).
Algardi, *Al.*, Bol. S., A., 1592-1654.
Allegri, *Ant.*, see *Correggio*.
Allori, *Aless.*, Flor. P., 1535-1607.
—, *Cristofano*, Flor. P., 1577-1621.
Ahuino, *Niccolò (di Liberatore) da Folligno*, Umbr. P., ca. 1430-1502. — (48. 79).
Amerighi, see *Caravaggio*, *Mich.*
Ammanati, *Bart.*, Flor. A., S., 1511-92.
Angelico da Fiesole, *Fra Giov.*, Flor. P., 1387-1455. — (63).
Anguissola, *Sofonisba*, Crem. P., 1539-1625.
Apelles, Greek P., 356-308 B.C. — (xxxiii).
Arnolfo del (di) Cambio, see *Cambio*.
Arpino, *il Cavaliere d' (Gius. Cesari)*, Rom. P., ca. 1560-1640. — (lviii).
Bandinelli, *Baccio*, Flor. S., 1493-1560.
Barbarella, *Giorgio*, see *Giorgione*.
Barbieri, see *Guercino*.
Barili, *Ant.* and *Giov.*, Sien. wood-carvers, first half of 16th cent. — (23).
Barna or *Berna*, Sien. P., d. 1381. — (23).
Baroccio, *Federigo*, Rom. P., imitator of *Correggio*, 1528-1612. — (97).
Bartoli, *Taddeo*, see *Taddeo*.
Bartoto, *Domenico di*, see *Domenico*.
Bartolommeo della Porta, *Fra*, Flor. P., 1475-1517.
Bassano, *Franc. (da Ponte)*, father of *Jacopo*, Ven. P., 1548-91.
—, *Jacopo (da Ponte)*, Ven. P., 1510-92.
Batoni, *Pompeo*, Rom. P., 1708-1787.
Bazzi, *Giov. Ant.*, see *Sodoma*.
Beccafumi, *Domenico*, Sien. P., 1486-1551. — (23).
Bellini, *Giovanni*, Ven. P., 1426-1516.
Benvenuto di Giovanni, Sien. P., d. 1517. — (23).
Berchem (*Berghem*), *Claas Pietersz*, Dutch P., 1620-1683.
Berettini, *Pietro*, see *Cortona*.
Bernardo Rossellino, Flor. A., 15th cent.
Bernini, *Giov. Lorenzo*, Rom. A., S., 1589-1680. — (lix).
Boedas, Greek S., son of *Lysippus*. — (xxxiii).
Bologna, *Giov. da*, or *Giambologna* (*Jean de Boullogne* of Douai), S., 1524-1608.
Bonfigli, see *Buonfigli*.
Bonifacio (*Bonifazio*) *the Elder*, d. 1540, *the Younger*, d. 1553, *the Youngest*, ca. 1555-79, Ven. P.
Bonvicino, see *Moretto*.
Bordone, *Paris*, Ven. P., 1500-70.
Borgognone, *Ambrogio*, *da Fossano*, Mil. P., 1455? - 1524? .
Borromini, *Franc.*, Rom. A., S., 1599-1667. — (lviii).
Botticelli, *Aless.* or *Sandro*, Flor. P., 1446-1510. — (xlix).
Bramante, *Donato*, A., 1444-1514. — (li. — Comp. also the Index, under 'Rome').
Bril, *Paul*, Flem. P., 1556-1626.
Bronzino, *Angelo*, Flor. P., 1502-72.
Buonarroti, see *Michael Angelo*.
Buonfigli (or *Bonfigli*), *Benedetto*, Umbr. P., ca. 1420-c. 1496. — (48).
Buontalenti, *Bern.*, Flor. A., 1536-1608.
Cagnacci (*Canlassi*), *Guido*, Bol. P., 1601-1681.
Caliari, *Paolo*, see *Veronese*.
Cambiasso, *Luca*, Gen. P., 1527-85.
Cambio, *Arnolfo del (di)*, Flor. A., S., 1240-1311.
Campagna, *Girolamo*, Ven. S., pupil of *Jac. Sansovino*, 1552-1623.

- Camuccini, Vinc.*, Rom. P., 1773-1844.
Canatetto (Antonio Canale), Ven. P., 1697-1768.
Canova, Antonio, S., 1757-1832.
Caprina, Amadeo or Meo del, Rom. A., d. 1501.
Caravaggio, Michelangelo Amerighi da, Lomb. and Rom. P., 1569-1609. — (lviii).
 —, *Polidoro Caldara da*, Rom. P., 1495-1543.
Cardi, Luigi, see *Cigoli*.
Carpi, Girol. da, Ferr. P., 1501-68.
Carracci, Agostino, Bol. P., 1558-1601.
 —, *Annibale*, brother of Agostino, Bol. P., 1560-1609. — (lviii).
 —, *Lodovico*, Bol. P., 1555-1619.
Carrucci, see *Pontorno*.
Cavattini, Pietro, Rom. P. and mosaicist, 14th cent. — (xlviii).
Cellini, Benvenuto, Flor. S. and goldsmith, 1500-72.
Cepisodotus the Elder, Greek S. (perhaps father of Praxiteles). — (xxxii).
 —, *the Younger*, Greek S., son of Praxiteles. — (xxxii).
Cignani, Carlo, Bol. P., 1628-1719. — (89).
Cigoli (Luigi Cardi da), Flor. P., 1559-1613.
Cimabue, Giov., Flor. P., 1240?-1302?.
Claude le Lorrain (Gellée), French P., 1600-82.
Clovio, Don Giulio, P. of miniatures, pupil of Giul. Rom., 1498-1578.
Cornelius, Peter v., Germ. P., 1783-1867. — (lix).
Correggio (Antonio Allegri da), Parm. P., 1494?-1534.
Cortona, Pietro (Berettini), da, Flor. A., P., 1596-1669. — (46).
Cosmati, the, Rom. S. and mosaicists, 13th cent. — (xlvii).
Credi, Lorenzo di, Flor. P., 1459-1537.
Cresti, Dom., da Passignano, Flor. P., 1560-1638.
Crivelli, Carlo, Ven. P., ca. 1468-93.

Dolci, Carlo, Flor. P., 1616-86.
Domenichino (Domenico Zampieri), Bol. P., 1581-1641. — (lviii).
Domenico di Bartolo, Sien. P., middle of 15th cent. — (23).
Donatello (Donato di Niccolò di Betti Bardi), Flor. S., 1386-1466.
Dosso Dossi, Ferr. P., ca. 1479-1545 (46?).
Duccio di Buoninsegna, Sien. P., ca. 1285-1320. — (23).
Dyck, Ant. van, Antwerp P., 1599-1641.

Euphranor, Greek S. and P., 375-335 B.C. — (xxxii).

Eusebio di S. Giorgio, Umbr. P., ca. 1500. — (48).
Euthykrates, Greek S., son of Lysippus. — (xxxiii).
Eutychides, Greek S., pupil of Lysippus. — (xxxiii).

Fabrizio, Gentile da, see *Gentile*.
Federighi, Ant., Sien. A., S., ca. 1420-90.
Ferrari, Gaudenzio, Milan. P., 1481-1549.
Fiammingo, Arrigo, of Malines, Rom. P., d. 1601.
Fiesole, Fra Giovanni Angelico da, see *Angelico*.
 —, *Mino da*, Flor. S., 1431-84.
Filarete, Ant., Flor. A., d. 1465? — (1).
Fiorenzo di Lorenzo, Umbr. P., ca. 1472-1521. — (48).
Fontana, Carlo, Rom. A., 1634-1714. (lviii).
 —, *Domenico*, Rom. A., 1543-1607. — (lvii).
 —, *Giov.*, brother of Domenico, Rom. A., 1540-1641.
Fonte, Jac. detta, see *Quercia*.
Francesca, Piero detta (Pietro di Benedetto), Umbr. Flor. P., b. 1423, d. after 1509. — (39. 56. 97).
Francesco di Giorgio, Sien. A., S., P., 1439-1502. — (22).
Francia, Francesco (Franc. Raibolini), Bol. P., 1450-1517.
Francucci, Innoc., see *Imola*.
Fredi, Bartolo di, Sien. P., ca. 1330-1409. — (23).
Fuga, Ferdinando, Rom. A., 1699-1780.
Fungai, Bernardino, Sien. P., d. 1516. — (23).
Furini, Franc., Flor. P., 1600-49.

Gaetano, Scip., Neap. P., 16th cent.
Galilei, Alessandro, Flor. A., 1691-1737.
Garbo, Raffaellino del (R. Capponi), Flor. P., ca. 1466-1524.
Garofalo (Benvenuto Tisio), Ferr. P., 1481-1559.
Gatta, Bartol. della, Flor. P., d. 1491.
Gentile da Fabriano, Umbr. P., 1360?-1440?. — (48).
Gerino da Pistoja, Umbr. P., first half of 16th cent. — (48).
Ghiberti, Lor., Flor. S., 1378-1455.
Ghirlandajo, Dom. (Dom. Bigordi), Flor. P., 1449-94. — (xlix).
 —, *Ridolfo (R. Bigordi)*, son of Dom., Flor. P., 1483-1561.
Giambologna, see *Botogna, Giov. da*.
Gimignani, Giacinto, Tuscan P., 1611-1681.
Giocondo, Fra, Veron. A., 1435-1515.
Giordano, Luca, surnamed *Fapresto*, Neap. P., ca. 1632-1705.

- Giorgione (Giorgio Barbarella)*, Ven. P., 1477?-1511.
- Giottino*, Flor. P., pupil of Giotto. — ().
- Giotto (di Bondone)*, Flor. P., A., S., 1276-1337. — (xlviii. 76).
- Gozzoli, Benozzo*, Flor. P., pupil of Fra Angelico, 1420-97.
- Guercino, il (Giov. Franc. Barbieri)*, Bol. P., 1590-1666. — (lviii).
- Guido da Siena*, Sien. P., 13th cent.
- Ibi, Sinibaldo*, Umbr. P., first half of 16th cent. — (48).
- Ictinus*, Greek A., 5th cent. B.C. — (xxx).
- Imola, Innocenzo da (Inn. Francucci)*, Bol. P., 1494?-1550?
- Laippus*, Greek S., pupil of Lysippus. — (xxxiii).
- Landini, Taddeo*, Flor. S., d. 1594.
- Lanfranco, Giov.*, Lomb. and Rom. P., 1580?-1647.
- Laurana, Luciano*, of Dalmatia, A., 15th cent.
- Le Brun, Charles*, French P., 1619-1690.
- Leochares*, Greek S., middle of 4th cent. B.C. — (xxxii).
- Leonardo da Vinci*, P., S., A., 1452-1519.
- Licinio, Bernardino*, P., pupil of Pordenone, ca. 1524-42.
- , *Giov. Ant.*, see *Pordenone*.
- Ligorio, Pirro*, Rom. A., d. 1580.
- Lippi, Filippino*, Flor. P., 1458-1504. — (xlix).
- , *Fra Filippo*, father of Filippino, Flor. P., 1412-69. — (82).
- Lombardo, Girolamo*, Ven. S., 16th cent.
- Longhi, Luca*, P., Ravenna, 1507-80.
- Lorenzetti, Ambrogio*, Sien. P., d. 1348? — (23).
- , *Pietro*, Sien. P., d. 1348? — (23).
- Lorenzetto, Martino (di Lodovico Campanajo)*, Flor. A., S., 1494-1541.
- Lorenzo di Pietro*, see *Vecchietta*.
- Lotto, Lorenzo*, Ven. P., 1480?-1554?
- Luca Thome*, Sien. P., second half of 14th cent. — (23).
- Luini, Bernardino*, Milan. P., 1470?-1530?
- Lunghi, Mart., the Elder*, Rom. A., 16th cent.
- , *Onorio*, Rom. A., son of the preceding, 1569-1619.
- , *Mart., the Younger*, son of the last, d. 1637.
- Luti, Bened.*, Flor. P., 1666-1724.
- Lysippus*, Greek S., 4th cent. B.C. — (xxxii).
- Maderna, Carto*, Rom. A., 1556-1629. — (lviii).
- Maderno, Stefano*, Lomb. Rom. S., 1571-1636.
- Majano, Benedetto da*, Flor. A., S., 1442-97.
- , *Giuliano*, Flor. A., 1432-90.
- Manni, Giannicola di Paolo*, Umbr. P., d. 1544. — (48).
- Mantegna, Andrea*, Pad. P., 1431-1506.
- Maratti (Maratta)*, Carlo, Rom. P., 1625-1713.
- Marcantonio Raimondi*, engraver, ca. 1488-1527.
- Marchionne, Carlo*, Rom. A., S., 1704-1780.
- Margaritone*, P. and S., of Arezzo, 1236?-1313. — (39).
- Mariano, Lor. di*, surnamed *il Marzina*, Sien. S., 1476-1534.
- Martini, Simone (Sim. di Martino)*, Sien. P., 1283-1344. — (23).
- Masaccio (Tommaso Guidi)*, Flor. P., 1401-28?. — (38).
- Matteo (di Giovanni) da Siena*, Sien. P., 1435-95. — (23).
- Mazzolini, Lodov.*, Ferr. and Bol. P., 1481- ca. 1528.
- Mazzuola, Franc.*, see *Parmeggianino*.
- Melozzo da Forlì*, Umbr.-Tuscan P., 1433-1494. — (xlix. 89).
- Memmi, Lippo*, Sien. P., d. 1356. — (23).
- Menelaus*, Rom. S. of the time of Augustus. — (xxxvi).
- Messina, Antonetto da*, P., b. after 1410, d. ca. 1493.
- Michael Angelo Buonarroti*, A., S., P., 1475-1564. — (li, lii. — Comp. also the Index under 'Rome').
- Mnesicles*, Greek A., 5th cent. B.C. — (xxx).
- Mocchi, Franc.*, Tuscan S., 1580-1646.
- Mota, Francesco*, Rom. P., 1612-1666.
- Montetupo, Raff. da*, Flor. S., ca. 1505- ca. 1570.
- Montorsoli, Fra Giov. Ang.*, Flor. S., ca. 1506-63.
- Moretto da Brescia (Alessandro Bonvicino)*, Besc. P., 1498-1555.
- Morone, Franc.*, Veron. P., 1473 or 1474-1529.
- Moroni (Morone)*, Giov. Batt., Besc. P., 1510?-1578.
- Mosca, Smeone, da Seltignano*, S., 1493-1554.
- Murillo, Bartolomé Estéban*, Span. P., 1617-1682.
- Muziano, Girol.*, of Brescia, P., 1530-1592.
- Myron*, Greek S., 5th cent. B.C. — (xxx).
- Netti, Ottaviano*, Umbr. P., d. 1444. — (48. 51).
- Nucci, Avanzino*, Umbr. P., 1552-1629.
- Oderisi of Gubbio*, miniature-painter, 1240-1299. — (47. 55).

- Oggionno, Marco da*, Milan. P., pupil of Leonardo, 1470?-1540?.
- Orcagna (Andrea di Cione)*, Flor. A., S., P., 1308?-1368?.
- Overbeck, Joh. Friedr.*, Germ. P., 1798-1869.
- Pacchia, Girolamo del*, Sien. P., 1477-ca. 1535. — (23).
- Pacchiarotto, Giac.*, Sien. P., 1474-1540. — (23).
- Palladio, Andr.*, Ven. A., 1518-80.
- Palma Giovane (Giovine), Giac.*, Ven. P., 1544-ca. 1628.
- *Vecchio, Giac.*, Ven. P., 1480-1528.
- Palmerucci, Guido*, Umbr. P., 1280-1345?. — (53).
- Palmezzano, Marco, da Forlì*, Flor. P., 1490-1530.
- Parmeggianino or Parmigianino (Franc. Mazzuola)*, Parm. P., 1503-1540.
- Pasiteles*, Græco-Rom. S., 72-48 B.C. — (xxxvi).
- Passignano*, see *Cresti*.
- Pellegrino Pellegrini (Tibaldi)*, Bol. A., P., 1527-91.
- Penni, Franc. (il Fattore)*, Flor. P., 1488-1528. — (lvii).
- Perino del Vaga*, see *Vaga*.
- Perugino, Pietro (Pietro Vannucci)*, Umbr. P., 1446-1524. — (xlix. 48. 61).
- Peruzzi, Baldass.*, Sien. and Rom. A., P., 1481-1536. — (lvii. 23).
- Phidias*, Greek S., 500-430 B.C. — (xxxi).
- Pintelli, Baccio*, Flor. A., S., ca. 1472-1490. — (xlix).
- Pinturicchio (Bernardino Betti)*, Umbr. P., 1454-1513. — (xlix. 48).
- Piombo, Sebast. del*, see *Sebastiano*.
- Pippi*, see *Romano*.
- Pisanello*, see *Pisano, Vittore*.
- Pisano, Giov.*, Pis. A., S., son of Niccolò, d. 1320. — (22).
- , *Giunta*, Pis. P., first half of 13th cent.
- , *Niccolò*, Pis. A., S., d. 1278. — (22).
- , *Vittore (Pisanello)*, Ver. P., ca. 1455.
- Podesti, Franc.*, modern Rom. P. — (lix).
- Polidoro*, see *Caravaggio*.
- Pollajuolo, Ant.*, Flor. A., S., P., 1429-98.
- , *Piero*, Flor. S., P., 1441-89?.
- Polycletus*, Greek S., 5th cent. B.C. — (xxxi).
- Polygnotus*, Greek P., 480-430 B.C. — (xxxi).
- Pomaranccio (Circignani)*, Rom. P., end of 15th cent.
- Ponte, Franc., Jac. da*, see *Bassano*.
- Pontormo, Jacda (Carrucci)*, Flor. P., 1494-1557.
- Ponzio, Flaminio*, Rom. A., ca. 1570-1615.
- Pordenone, Giov. Ant. (G. A. Licinio da P.)*, Ven. P., 1483-1539.
- , see also *Licinio, Bernardino*.
- Porta, Bart. della*, see *Bartolommeo*.
- , *Giac della*, Lomb. A., S., 1541-1604.
- , *Giov. Batt. della*, Rom. S., 1539-94.
- , *Guglielmo della*, Lomb. S., d. 1577.
- Poussin, Gaspard (G. Dughet)*, French P., 1613-75.
- , *Nicolas*, French P., 1594-1665.
- Pozzo, Andrea, Jesuit*, P., A., 1642-1709.
- Praxiteles I.*, Greek S., ca. 364 B.C. — (xxxii).
- Provenzale, Marcello*, Rom. mosaicist, d. 1639.
- Quercia, Jac. della (or J. della Fonte)*, Sien. S., 1374-1438. — (22).
- Raffaello dal Colle*, Rom. P., 1490-1540. — (lvii. 56).
- Raphael Santi da Urbino*, P., A., 1483-1520. — (liii. 97. Comp. also the Index under 'Rome').
- Raibolini*, see *Francia*.
- Raimondi*, see *Marcantonio*.
- Reni, Guido*, Bol. P., 1574-1642. — (lviii).
- Ribera*, see *Spagnoletto*.
- Ricciarelli*, see *Volterra, Daniele da*.
- Rinaldi, Antonio*, Rom. A., 16th cent.
- Ristoro, Fra*, Flor. A., d. 1283. — (xlviii).
- Robbia, Andrea della*, Flor. S., 1435-1528.
- , *Giov. della*, son of Andrea, Flor. S., ca. 1530).
- , *Luca della*, Flor. S., 1400-82.
- Robusti*, see *Tintoretto*.
- Romanelli, Giov. Franc.*, Rom. P., 1610?-1662.
- Romano, Giulio (G. Pippi)*, Rom. P., A., 1492-1546. — (lvii).
- , *Paolo*, Rom. S., first half of 15th cent.
- Roncalli, Rom. P.*, second half of 16th cent.
- Rondinello, Niccolò*, Ven. P., 16th cent.
- Rosa, Salvator*, Neap. P., 1615-73.
- Rosselli, Cosimo*, Flor. P., 1439-1507. — (xlix).
- Rossellino (Bern. di Matteo Gambarelli)*, Flor. A., S., 1409-90. — (19.22).
- Sacchi, A.*, Rom. P., 1598?-1661. — (lix).
- Salaino, Andr.*, Milan. P., pupil of Leonardo, ca. 1495-1515.
- Salimbeni, Ventura*, Sien. P., 1557? 1613.

Salviati, Franc., Flor. P., 1510-1563.
Sammicheli, Michele, Ver. A., 1484-1554.
Sangallo, Antonio da, the Elder, Flor. A., 1450?-1534.
 —, *Antonio da, the Younger*, Flor. A., 1485-1546. — (lvii).
 —, *Francesco da*, son of Giuliano, Flor. S., 1494-1576.
 —, *Giuliano da*, brother of Antonio (the Elder), Flor. A., 1445-1516.
San Gimignano, Vincenzo da, Rom. P., 1490?-1529?
Sano di Pietro (di Domenico), Sien. miniature painter, 1406-1481.
Sansovino, Andrea (Contucci), Flor. S., 1460-1529. — (42).
 —, *Jac. (J. Tatti)*, Ven. A., 1477-1570.
Santi, Giov., father of Raphael, Umb. P., ? 1450-94. — (97).
 —, *Raffaello*, see *Raphael*.
Saraceni, Carlo, surnamed *Veneziano*, Ven. and Rom. P., 1585-1625.
Sarto, Andrea del, Flor. P., 1487-1531.
Sassoferrato (Giov. Batt. Salvi), Rom. P., 1605-85. — (lix. 109).
Scarsellino, Ippol., Ferr. P., 1551-1621.
Schiavone (Andr. Meldolla), Ven. P., 1522-82.
Schidone, Bart., Mod. P., d. 1615.
Scopas, Greek S., ca. 390-350 B.C. — (xxxii).
Sebastiano del Piombo, Ven. and Rom. P., 1485-1547.
Sermoneta, Girol. Sicciolante da, Rom. P., d. 1580.
Signorelli, Luca, Tusc. P., 1441-1523. — (xlix. 17. 43. 63.)
Sisto, Fra, Flor. A., d. 1289. — (xlviii).
Sódoma, il (Giov. Ant. Bazzi), Sien. and Lomb. P., ca. 1473 (not 1480)-1549. — (lvi. 23. 17).
Solario, Andrea (da Milano), Lomb. P., ca. 1448-1530?
Spada, Lionello, Bol. P., 1556-1622.
Spagna (Giov. di Pietro), Umb. P., ca. 1507, d. before 1530. — (48).
Spagnoletto (Gius. Ribera), Span. Neap. P., 1588-1656.
Specchi, Aless., Rom. A. and engraver, d. 1710.
Spinello Aretino, Flor. P., pupil of Giotto, 1318-1410. — (39).
Stephanus, Græco-Rom. S., 1st cent. B.C. — (xxxvi).
Subleyras, Pierre, French P., 1699-1749.
Taddeo (di) Bartoli, Sien. P., 1362-1422?. — (23).

Tamagni, Vinc., see *San Gimignano*.
Tempesta, Ant., Rom. P., 1637-1701.
Teniers, David, the Younger, Antwerp P., 1610-1690.
Tibaldi, see *Pellegrino Pellegrini*.
Tiberio d'Assisi, Umb. P., 16th cent. — (48).
Timarchides, Greek S., son of Praxiteles. — (xxxii).
Tintoretto, il (Jac. Robusti), Ven. P., Ven. P., 1518-94.
Tisi, Benv., see *Garofalo*.
Titian (Tiziano Vecellio da Cadore), Ven. P., 1477-1575.
Torrili, Jacobus, Rom. mosaicist, second half of 13th cent.
Tribolo (Nicc. Pericoli), Flor. S., 1485-1550.

Uccelli, Paolo, Flor. P., 1397-1475. — (97).
Udine, Giov. (Nanni) da, Ven. Rom. P., 1487-1564. — (lvii).

Vacca, Flaminio, Rom. S., second half of 16th cent.
Vaga, Perino del (Pier. Buonaccorsi), Rom. P., 1500-1547. — (lvii).
Valsoldo, Rom. S., second half of 16th cent.
Vanni, Franc., Sien. P., 1563?-1609.
 —, *Lippo*, Sien. P., 14th cent. — (23).
Vannucci, Pietro, see *Perugino*.
Vanvitelli, Lodov., Rom. P., A., 1700-73.
Vasari, Giorgio, Flor. P., A., and writer on art, 1512-74. — (39).
Vecchietta (Lorenzo di Pietro), Sien. S., A., P., 1412-80. — (23).
Vecellio, Tiziano, see *Titian*.
Velazquez (Diego V. de Silva), Span. P., 1599-1660.
Venusti, Marcello, P., d. ca. 1570.
Veronese, Paolo (P. Caliari), Ven. P., 1528-88.
Vignola (Giacomo Barazzi), A., 1507-73. — (lviii).
Vinci, Leonardo da, see *Leonardo*.
Vite, Timoteo della (Tim. Viti), Umb. Rom. P., 1467-1523. — (97).
Volterra, Daniele da (D. Ricciarelli), Flor. P., 1509-66. — (10).

Zampieri, see *Domenichino*.
Zuccherro (Zuccaro), Federigo, Rom. P., 1560-1609. — (lviii).
 —, *Taddeo*, Rom. P., 1529-68.

INDEX.

- Abete, Monte dell'** 11.
Acqualagna 101.
Acqua Acetosa 337.
 — **Felice** 168. 346. 347.
 — **Marcia** 347.
 — **Paola** 390.
 — **Santa** 346.
 — **Vergine** 152. 345.
Acque Albule 371.
Adriana, Villa 374.
Æsis 108.
Æthalia 12.
Afile 385.
Agosta 380.
Agylla 392.
Albacina 108. 109.
Alba Longa 372.
Alban Mountains, the 363.
Albano 368.
 —, **Lago di** 369.
Albano Laziale 364. 368.
Albanum 368.
Albarese 3.
Albegna 3.
 —, **river** 3.
Albinia 3.
Allerona 61.
Allia 341.
Almo, brook 348. 351.
Alsion 392.
Alsium 7.
Alviano 61.
Amelia 87.
Ameria 87.
Amiata, Monte 18.
Amone 88. 89.
Ancona 102.
Anemo 83.
S. Angelo (near Grosseto) 18.
 — **in Vado** 101.
Angliari 56.
Anguillara 391.
Anio, river 341. 342. 371.
Anio novus 180.
Ansa, the 92.
S. Ansano in Dofana 37.
Ansciano, Mte. d' 57.
Ansedonia 4.
Antemnæ 341. 336.
Antico, Monte 18.
Anticoli 380.
S. Antimo 17.
Antium 397.
Anzio, or Porto d'Anzio, 397.
Apennines, the 102. etc.
Appia Antica, Fortezza 350.
 —, **Via** 348.
Aqua Alexandrina 346.
 — **Claudia** 347.
 — **Ferentina** 367.
 — **Marcia** 347. 379.
Aquæ Albulæ 373.
 — **Apollinares** 391.
 — **Salviæ** 354.
 — **Tauri** 7.
Arbia 16.
 —, **river** 17. 22. 37.
S. Arcangelo 91.
Arco Muto 398.
 — **Oscuro** 337.
Ardea 397.
Arezzo 38.
Argentario, Monte 3.
Ariccia 370.
Aricciana, Valle 370.
Ariminum 92.
Ariminus 94.
Arno, river 42.
Arretium 38.
Arrone, river 4. 7. 390. 391.
Artemisio, Monte 382.
Aruns, Tomb of 369.
Arvales, Grove of the 393.
Asciano 16.
Ascoli 88.
Asdrubale, Monte d' 93.
Assino, the 57.
Assisi 75.
Astagno, Monte 102.
Astura 398.
Attidium 109.
Attigliano 66.
Augustanus, Vicus 394.
Augustus, Bridge of 87.
Auximum 105.
Bachetona, La 11.
Badia del Furlo 101.
 — **of S. Severo** 65.
Bagnaia 71.
Bagni 373.
Bagno a Morbo 8.
Bagnorea 69.
Balneum Regis 69.
Balze, Le 11. 56.
Baschi 66.
Bassano Teverino 66.
 —, **Lake of** 66.
Bassiano 387.
Bastia 74.
Bedesis 89.
Belcaro 37.
Belrespiro, Villa 355.
Belvedere, Osteria di 355.
S. Benedetto 90.
 — (**convent near Su-
biaco**) 381.
S. Bernardino 99.
Bertinoro 90.
Betolle 42.
Bevagna 80.
Bibbiena 42.
Bieda 73.
Bisentina 66.
Blera 73.
Bolsena 65.
 —, **Lago di** 66.
Bomarzo 67.
Borghese, Villa 334. 398.
Borghetto 67.
Borgo dei Magazzini 12.
 — **di S. Marino** 94.
 — **S. Sepolcro** 56.
Bovillæ 350.
Bracciano 391.
 —, **Lago di** 391.
Branca 59.
Bruna, river 2.
Buche de' Saracini, Le 11.
Bucine 38.
Bulicame 72.
Buonconvento 17.
Burano, river 101.
Carcina 1.
Cære 7. 392.
Cæsena 90.
Caffarella, brook 351.
Cagli 101.
Calcs 101.

- Calle 101.
 Callori, S. Maria Assunta di 16.
 Calvo, Monte 57.
 Camaldoli 365. 42. 94.
 Camerino 108.
 Camerinum Ubrorum 108.
 Campagna di Roma 306. 7.
 Campana, Grotta 390.
 Campello 81.
 Campiglia 1.
 Campo d'Annibale 372.
 — Reggiano 57.
 Camuscia 43.
 Candigliano, river 101.
 Canoscio 57.
 Cantalupo 380.
 Canterano 380.
 Cantiano 101.
 Capalbio 4.
 Capanne, Monte 12.
 Capannelle, Le 347. 367.
 Capo di Bove 349.
 Capoliveri 12.
 Caporciano 11.
 Capraja 12.
 Caprarola 73.
 Carceri, Eremo delle 78.
 Careie 390.
 Carsulæ 56.
 Casale del Fontanile 69.
 — di Prima Porta 337.
 — Rotondo 350.
 Cascade delle Marmore 86.
 Casentino, the 42.
 Casino di Terra 8.
 Cassia, Via 69. 336. 389.
 Castagneto 1.
 Castel d'Asso 72.
 — Bolognese 88.
 — Durante 56.
 — S. Elia 74.
 Castelfidardo 105.
 Castel Fiorentino 13.
 — Fusano 396.
 — Gandolfo 369.
 — Giubileo 68. 341.
 — di S. Lco 94.
 — Madama 379.
 — del Piano 18.
 — S. Pietro 81.
 — Planio 109.
 — Porziano 394.
 — Raimondo 108.
 — Savelli 368.
 — Todino 56.
 Castellaccio 72.
 Castellum Axia 72.
 Castelnuovo 8.
 Castelnuovo dell' Abbatte 17.
 Castiglione 345.
 — Fiorentino 43.
 — del Lago 59.
 — d'Orcia 18.
 — della Pescaja 2.
 — Teverino 66.
 —, Palude di 3.
 —, Promontory of 2.
 Castrimœnium 367.
 Catillo, Monte 377.
 Cattolica, La 94.
 Cava, La, di Caporciano 11.
 Cave, Fiume di 384.
 Cavi 384.
 Cavo, Monte 371.
 Ceccarelli, Vigna 393.
 Cecchina 368.
 Cechignola 348.
 Cecina 1. 8.
 —, river 1. 8.
 Cellole 16.
 Celsa 36.
 Centum Cellæ 6.
 Cerboli 12.
 —, Monte 8.
 Cere nuovo 392.
 Cerfone, the 56.
 Ceri 392.
 Certaldo 13.
 Cervara 380. 373.
 —, Grottoes of 373.
 Cervetri 392.
 Cesano, river 101.
 S. Cesareo, Osteria di 346.
 Cesena 90.
 Cesi 87.
 Cetinale 37.
 Cetona 61.
 —, Monti di 20.
 Chiana, river 16. 18. 42. 60.
 Chianciano 20.
 Chiaravalle 108.
 Chiarone 4.
 Chiascio, river 59. 74. 101. 109.
 Chienti, the 107.
 Chiusi 60. 20.
 —, Lake of 20.
 Chiusure 16.
 Ciampino 367. 368.
 Ciminius, Mons 73.
 Cineto Romano 379.
 Cinigiano 18.
 Circello, Monte 382.
 Citerna 56.
 Città di Castello 56.
 — della Pieve 61.
 Cività Castellana 67.
 — Lavinia 382.
 Civitanova, Porto 107.
 Cività Vecchia 6.
 Civitella 385.
 Clanis 43.
 Clitumnus 80. 81.
 Clivus Cinnæ 338.
 Clusium 60.
 Collatia 373.
 Colle 13.
 — di Val d'Elsa 11. 14.
 — del Poetello 380.
 — Salvetti 1.
 Collescipoli 87.
 S. Colomba 36.
 Colonia Fideus Julia Arretium 38.
 — Julia Hispellum 79.
 — Julia Senensis 21.
 — Junonia 67.
 — Nepensis 74.
 Colonia 2. 346.
 —, near Grosseto 2.
 —, Parco di 361.
 Compatri 366.
 Compiobbi 37.
 Conca, river 94.
 Conero, Monte 105.
 Cora 386.
 Corcolle 345.
 Cori 386.
 Corneto (Tarquinii) 4.
 Corniculum 374.
 Corrignaleto, Monte 380.
 Corsignano 20.
 Corsini, Villa 398.
 Cortona 43.
 Cosa 4.
 Costacciaro 101.
 S. Costanza 342. xlv.
 S. Costanzo 55.
 Cremera, the 337. 389.
 Crustumius rapax 94.
 Cures 68.
 Digentia 380.
 S. Donato 11.
 S. Donnino 13.
 Dorica Ancon 102.
 Durante, Castel 56.
 S. Edistio 68.
 Egeria, Grotto of 351.
 S. Egidio, Alto di 45.
 Elba 12.
 Ellera 46.
 Elsa, river 13.
 Emissarium of the Lago Albano 369.
 — of the Lago di Nemi 371.
 Empoli 13.
 Ercole, Port' 3.
 Esino, river 102. 108.
 Etruscan Towns 389. 72.
 S. Eugenio, Abbazia di 37.
 Eugubium 58.

- Fabriano 109.
 S. Facondino 109.
 Faenza 88.
 Falconara 87. 102. 108.
 Falcone, Monte 346.
 Falconieri, Villa 365.
 Falerii 67.
 Falerium Novum 67.
 Fano 99.
 Fanum Fortunæ 99.
 — Vacunæ 380.
 — Voltumnæ 69.
 Fauglia 1.
 Faventia 88.
 Ferentinum 69.
 Ferento 69.
 Ferrata, Grotta 364. 367.
 —, Osteria della 380.
 Ficulle 61.
 Fidenæ 389. 341.
 Figline 38.
 Filomarino, Osteria di 341.
 Fiora, river 4.
 Fiumicino 394. 7.
 —, river 91.
 Florence 94.
 Foggia 105.
 Foglia, river 94. 96.
 Fojano 42.
 Foligno 79.
 Follonica 2.
 Fontanile, Casale del 69.
 Fonte degli Oratini 380.
 Forlì 89.
 Forlìmpopoli 90.
 Formello 389.
 —, Fosso di 387.
 Formica, island 2.
 Forum Cassii 72.
 — Clodii 391.
 — Livii 89.
 — Popilii 90.
 — Sempronii 101.
 Fossanuova 388.
 Fossato 59. 101. 109.
 Fossa Trajani 394.
 Fosso di Formello 389.
 — dell' Isola 389.
 — di Ponte di Nona 345.
 — di Valca 389.
 Fossombrone 104.
 S. Francesco (Sabine Mts.) 385.
 — (Fojano) 42.
 Frascati 364.
 Frassinetto 43.
 Fratocchie, Le 350.
 Fregene 7.
 Frosinone 388.
 Fulginium 79.
 Furbara 7.
 Furlo Pass 101.
 Gabii 345.
 Galera 390.
 S. Galgano 37.
 Gallese 67.
 Gallicano 345.
 Gallinas, Villa ad 337.
 Galloro 370.
 Gambettola 91.
 Gavignano 388.
 Gavorrano 2.
 S. Gemine 56.
 Genazzano 384.
 Genga, La 109.
 Gennaro, Monte 379.
 Genzano 370.
 S. Giacomo 81.
 Giano, brook 109.
 Giglio 13.
 S. Gimignano 14.
 S. Giovanni 38.
 — d'Asso 17.
 — di Ponte allo Spino 37.
 S. Girolamo, convent 11.
 Giove, Monte 100.
 Giovi 42.
 Giulianello 386.
 —, Lago di 386.
 Giuncano 84.
 S. Giustino 56.
 Gonfolina, the 13.
 Gordiani, Villa of the 345.
 Gorgona 12.
 Gradara 96.
 Granaiole 13.
 Grano, Monte del 347.
 Gran Sasso d'Italia 105.
 Gravisca 5.
 Grosseto 3.
 Grotta Campana 390.
 — Ferrara 367.
 — d'Orlando 74.
 Grotto of Egeria 351.
 Gualdo Tadino 109.
 Guasco, Monte 102.
 Gubbio 57.
 Hadrian's Villa 374.
 Helvia Ricina 107.
 Hispellum 79.
 Horace, Villa of 378.
 Horta 67.
 Igilium 13.
 Iguvium 58.
 Ilva 12.
 Imola 88.
 Imperiale, Villa 96.
 Incisa 38.
 Inferno, Valle dell' 338.
 Inghirami Villa 11.
 Interamna 85.
 Isaurus, river 94.
 Isola Farnese 389.
 — Maggiore 46.
 — Minore 46.
 — Polvese 46.
 — Sacra 394.
 Jesi 108.
 Jupiter Apenninus, Temple of 101.
 Jupiter Latiaris, Temple of 372.
 Labico 346.
 Labicum 346.
 La Cava di Caporciano 11.
 Lacus Albanus 369.
 — Ciminus 73.
 — Nemoensis 371.
 — Prelius 3.
 — Sabatinus 391.
 — Trasimenus 45.
 — Vadimonis 67.
 — Vulsiniensis 66.
 Ladispoli 7.
 La Genga 109.
 — Magliana 393. 7.
 — Mola 370.
 Lago Zolforeo 8.
 Lanuvium 382.
 Larderello 8.
 La Storta 389.
 Laterina 38.
 Latium 333.
 La Tolfa 7.
 Laurentum 396.
 Lavinium 396.
 Le Balze 11. 56.
 Le Vene 81.
 Licenza 380.
 —, river 379. 380.
 Livia, Villa of 337.
 Loreto 105.
 Lucignano 18.
 Luco, Monte 84.
 Lucretilis, Mons 380.
 Lugnano 346.
 Lunghezza 373.
 Maccarese 7.
 —, Stagno di 7.
 Macchia di Ostia 394.
 Macerata 107.
 Madonna del Buon Consiglio 384.
 — del Calcinajo 43.
 — del Campo 384.
 — delle Case 380.
 — del Monte 386.

- Madonna del Sasso 42.
 Mæcenæ, Villa of 379.
 Magazzini, Borgo dei 12.
 Magione 46.
 Magliana 7. 393.
 Magliano 67.
 Malafede, Ost. di 394.
 S. Mama 42.
 Mandela 380.
 Marano, river 94.
 Marches, the 88.
 Marciana 12.
 Marecchia, river 91. 92.
 94.
 Maremme, the 1. 2.
 S. Maria degli Angeli 75.
 — Assnnta di Callori 16.
 — di Cesareo 390.
 — delle Grazie 42. 84.
 — del Monte 91.
 — della Quercia 71.
 — di Quintiliolo 378.
 — dei Servi 61.
 — della Villa 84.
 S. Marinella 7.
 Marino 367. 368.
 S. Marino 94.
 Mario, Mte. 338.
 S. Marmi 9.
 Marmoraja 36.
 Marmore, 85.
 —, Cascade delle 86.
 Marotta 101.
 Marrana, the 255.
 Marta, river 4. 5.
 Martana 66.
 S. Martino al Piano 101.
 Massa Marittima 2.
 Massi, Monte 11.
 Matelica 108.
 Meloria 12.
 Mentana 68. 343.
 Metaurus 101.
 Mevania 80.
 S. Mezzano, Villa 38.
 Mignone, river 6.
 Milvius, Pons 336.
 S. Miniato dei Tedeschi 13.
 Mola, La 370.
 Mondragone, Villa 365.
 Moline 96.
 Mons Albanus 372.
 — Ciminus 73.
 — Lucretilis 380.
 — Sacer 343.
 Montalcino 17.
 Montalto 4.
 Montarozzi 5.
 Monte dell' Abete 11.
 — Amiata 18.
 — Antico 18.
 — Aperto 22.
 — Argentario 3.
 Monte Artemisio 382.
 — d'Asdrubale 101.
 — S. Bartolo 96.
 — Capanne 12.
 — Catillo 377.
 — Catini 11.
 — Cavo 371.
 Montecchio 43.
 Monte Cerboli 8.
 — Celio 374.
 — Ciminio 73.
 — Circello 382.
 — Compatri 366.
 — Conero 105.
 — Corona 57.
 — Corrignaletto 380.
 — Cristo 13.
 Montefalco 80.
 Montefiascone 69.
 Montefiorentino 55.
 Monte Gennaro 379.
 — Giove 100.
 — del Grano 347.
 — Guasco 102.
 — Luco 84.
 Montelupo 13.
 Monte Maggiore 56.
 Montemarciano 102.
 Monte Mario 338.
 — Massi 11.
 — Nero 1.
 — Oliveto Maggiore 16.
 — Pescali 3. 18.
 — Petrarà 101.
 — Porzio 366.
 Montepulciano 18.
 —, Lago di 20.
 Monte Riggioni 16.
 — Romano 73.
 — Rosso 109.
 — Rotondo (near Rome) 68. 341. 343.
 — — (near Volterra) 8.
 — Sansavino 42.
 Montesanto 107.
 Monte Semprevisa 387.
 — Somma 84.
 — Subasio 78.
 — Trevi 387.
 Montevarchi 38.
 Monti di Cetona 20.
 Montone, river 89.
 Montone Monte Castelli 57.
 S. Mustiola a Torri (Val di Merse) 37.
 Nar 87.
 Narni 87.
 Nemi 371.
 —, Lago di 371.
 Nepete 74.
 Nepi 68. 74.
 Nequinum 87.
 Nera, river 56. 85.
 Nera Montoro 87.
 Nero, Mte. 1.
 Nero's Tomb 389.
 Nettuno 398.
 Ninfa 387.
 Nocera 109.
 Nomentum 343.
 Norba 387.
 Norchia 73.
 Norma. 387.
 Nuceria 109.
 Olevano 384.
 Ombrone, river 3. 13. 16.
 Ontanese 3-2.
 Oratini, Fonte degli 380.
 Orbetello 3.
 Orcia, river 18.
 Orciano 1.
 Orcle 73.
 S. Oreste 68.
 Orlando, Grotta d' 74.
 Orte 67. 87.
 Orvieto 61.
 Osa, river 3.
 Osimo 105.
 Osservanza, L' 36.
 Osteria di Belvedere 355.
 — delle Capannacce 374.
 — delle Capannelle 346.
 — di Cavamonte 345.
 — S. Cesareo 346.
 — della Ferrata 380.
 — di Filomarino 341.
 — del Fornaccio 374.
 — delle Fraticchie 350.
 — di Malafede 394.
 — Nuova 390.
 — dell' Osa 345.
 — del Pino 347.
 — del Ponticello 354. 394.
 — del Tavolato 346. 367.
 — della Volte 37.
 Ostia 394.
 —, Macchia di 394.
 —, Stagno di 394.
 Otricoli 67.
 Padule 59.
 Paganico 18.
 Paglia, river 61.
 Palazzo 109.
 — del Pero 56.
 Palazzolo 109.
 Palazzuola 372.
 Palestrina 383.
 Palidoro 7.
 Palmajola 12.
 Palo 7.

- Palombara 343. 374.
 Palombaro 374. 350.
 Panicale 60.
 S. Paolo, Stazione di 393.
 Papa Giulio, Casino of 336.
 — —, Villa of 337.
 Papigno 86.
 Parco di Colonna 368.
 Parioli, Monti 336.
 Passerano 384. 345.
 Passignano 46.
 Passo di Correse 68.
 S. Pastore 345.
 Pausilypon 391.
 Pellegrino 109.
 Pentapolis Maritima 92.
 Perugia 46.
 S. Agnese 52.
 S. Agostino 51.
 S. Angelo 52.
 Antiquarian Museum 52.
 Arco di Augusto 51.
 Baglioni, Villa 55.
 S. Bernardino, Oratorio 53.
 Biblioteca Pubblica 51.
 Botanic Garden 52.
 Cambio, Coll. del 49.
 Cathedral 51.
 Cemetery 55.
 Chiesa Nuova 53.
 Collegio del Cambio 49.
 Corso Cavour 54.
 — Vannucci 49.
 S. Costanza 55.
 S. Domenico 54.
 Episcopal Palace 51.
 S. Ercolano 54.
 Fonte Maggiore 51.
 S. Francesco dei Conventuali 53.
 House of Perugino 53.
 S. Lorenzo 51.
 Madonna della Luce 53.
 Maestà della Volte 51.
 Meniconi, Gallery 55.
 Monaldi, Gallery 55.
 Museum 52.
 Necropolis 55.
 Pal. Antinori 51.
 — Baldeschi 49.
 — del Capitano del Popolo 53.
 — Gallenga 51.
 — del Podestà 51.
 — Pubblico 49.
 Passeggiata Pubblica 55.
 Perugino, House of 53.
- Perugia :
 Piazza Danti 51.
 — del Duomo 49.
 — Fortebraccio 51.
 — del Municipio 51.
 — del Sopramuro 53.
 — Vitt. Emanuele 49.
 Picture Gallery 50.
 S. Pietro de' Casinensi 54.
 Pinacoteca 50.
 Porta Marzia 53.
 — S. Pietro 54.
 Prefettura 49.
 Romualdi, Collection 55.
 Sciri (Scalzi), Torre delle 53.
 S. Severo 52.
 Statue of Julius III. 51.
 University 52.
 Volumnii, Sepolcro de' 55.
- Perugia 47.
 Pesa, river 13.
 Pesaro 94.
 Petrarca, Monte 101.
 Pianosa 12.
 Picenum 105.
 Piediluco 85.
 —, Lake of 87.
 Pienza 20.
 Pietralata 101.
 Pietralunga 57.
 Piombino 2.
 Piperno 388.
 Pisaurum 94.
 Pisciattello, the 91.
 Planasia 12.
 Plautii, Tomb of the 374.
 Poggibonsi 13.
 Poggio alla Croce 11.
 — Mirteto 68.
 Polenta 90.
 Polimartium 67.
 S. Polo 379.
 Pomarance 8.
 Pompey, Tomb of 369.
 Ponente, Lago di 7.
 Pons Milvius 336.
 Pontassieve 37.
 Ponte dell'Acquoria 378.
 — della Badia 4.
 — a Botte 101.
 — della Catena 346.
 — Centesimo 110.
 Pontedera 8.
 Ponte a Elsa 13.
 — Felice 62.
 — Galera 7. 393.
 — Ginori 8.
 — S. Giovanni 74.
- Ponte Lucano 374.
 — Mammolo 374.
 — Molle 336.
 — Nomentano 342.
 — di Nona 345.
 — d'Orsino 384.
 — Salaro 341.
 — Sodo 390.
 — del Terreno 67.
 — delle Torri 84.
 Ponticello, Osteria del 354. 394.
 Ponticino 38.
 Pontignano, Certosa di 36.
 Poppi 42.
 Populonia 2.
 Porrena 42.
 Porsenna, Mausoleum of 60.
 Porta Aurelia 355.
 — Furba 347.
 — Libitina 349.
 — Spezieria 390.
 Porto 393.
 — d'Anzio 397.
 — Civitanova 107.
 — Clementino 6.
 — Ercole 3.
 — Ferrajo 12.
 — Longone 12.
 — S. Stefano 3.
 Portonaccio 367. 374.
 Portus Trajani 6. 393.
 Porzio, Mte. 366.
 Potenza, river 107. 108.
 Potenza-Picena 107.
 Præneste 383.
 Pratica 396.
 Pratovecchio 42.
 Prima Porta, Casale di 337.
 Privernum 388.
 Pupluna 2.
 Pussino, Val di 337.
 Pyrgos 7. 392.
- S. Quirico 17.
- Ranza 11.
 Rapolano 18.
 Rassinia 42.
 Ravenna 88. 94.
 Recanati 107.
 Regillus, Lake 346.
 Regresso 377.
 Riccione 94.
 Rignano, on the Arno 38.
 Rimini 91.
 Rio Castello 12.
 — Falisco 74.
 — Marina 12.
 Riparbella 8.

Rocca 363.

- Canterano 380.
- S. Casciano 90.
- di Cave 384.
- Giovine 379. 380.
- Maggiore 78.
- Massima 384.
- di Papa 372.
- Romana 391.
- S. Stefano 385.
- Strada 18.
- S. Rocco 380.
- Rojate 385.
- Roma Vecchia 350.
- Romena, castle 42.

ROME 111.

- Abbadia delle Tre Fontane 354.
- Accademia di Francia 149.
- di Belle Arti 184.
- de' Lincei 324.
- di S. Luca 238.
- Acqua Acetosa 337.
- Felice 163. 346. 347.
- Marcia 166. 347.
- Paola 329.
- Santa 346. 352.
- Vergine 152. 345.
- S. Adriano 238.
- Ædes Castoris 226.
- Ærarium publ. 227.
- S. Agata in Suburra 170.
- S. Agnese 190.
- fuori le Mura 342.
- S. Agostino 189. xlix.
- Albergo dell' Orso xlix.
- Aldobrandine Nuptials 321.
- S. Alessio 253.
- S. Alfonso de' Liguori 181.
- All Saints, Ch. of 150. 119.
- Alpine Club, Italian 118.
- Alta Semita 166.
- Amazon after Polycletns 315.
- American Church 119. 169.
- Amphitheatrum Castrense 273.
- Flavian 234.
- Anaglyphs 229.
- S. Anastasia 250.
- S. Andrea 336.
- delle Fratte 151.
- al Quirinale 173.
- della Valle 198. lix.

ROME :

- St. Andrew, Chap. of 336.
- Anfiteatro Umberto I. 184.
- S. Angelo, Castello 274.
- Custode 151.
- in Pescaria 204.
- Anglo-American Club 119.
- Anio Novus 180.
- S. Anna, Chapel of 251.
- S. Annunziata 239.
- Antinous 263. xxxvii.
- Antiquities, vendors of 117.
- S. Antonio Abbate 179.
- S. Apollinare 190.
- Apollo Belvedere 312
- Musagetes 309.
- Sauroctonus 310. 339.
- SS. Apostoli 165.
- Apoxyomenos 315. xxxiii. xxxix.
- Aqua Claudia 180. 247. 347. 272.
- Julia 179.
- Trajana 329.
- Virgo 152.
- Aquarium 179.
- Ara Pacis 153.
- Arch of Augustus 230.
- of Constantine 236.
- of Dolabella and Silenus 259.
- of Drusus 258.
- of the Fabii 231.
- of Gallienus 179.
- of the Money-Changers 248.
- of Sept. Severus 228.
- of Tiberius 227.
- of Titus 233. xxxvii.
- Archæol. Instit., British and American 117.
- —, German 221.
- —, French 205.
- Archivio Vaticano 319.
- Arco di Giano 248.
- Oscuro 337.
- de' Pantani 239.
- Arcus Argentariorum 248.
- Area Capitolina 208.
- Palatii 244.
- Ariadne (Vatican) 310.
- Armoury 321.
- Arrival 111.
- Artists' Association 116.
- Arx Capitolina 208.
- Atrium Vestæ 230.
- Auguratorium 243.

ROME :

- Augustus, Bust of 314.
- Augustus, Statue of 315. xxxviii.
- Aula Dei 266.
- Aventine, the 145. 250.
- Bakers 114.
- S. Balbina 254.
- Banca Romana 169.
- Bankers 115.
- Baptistry (Lateran) 265.
- Barcaccia, La 150.
- Barracks of the Carabinieri 276.
- S. Bartolomeo 204.
- Basilica Æmilia 223. 228.
- of Constantine 232.
- Constantiniana 266.
- Eudoxiana 182.
- Julia 226.
- Liberiana 176.
- of SS. Nereo ed Achilleo 349.
- of St. Petronilla 349. 362.
- Porcia 223.
- Sempronia 223.
- Sessoriana 181.
- di S. Stefano 346.
- Ulpia 240.
- of St. Valentine 336.
- Baths 114.
- Battistero, the 265.
- Beer 113.
- Belrespiro 355.
- S. Bernardo 169.
- S. Bibiana 179.
- Bibliography 127.
- Biblioteca Alessandrina 115. 197.
- Angelica 115. 189.
- Barberina 116. 171.
- Casanatensis 115. 196.
- Chigiana 116. 154.
- Corsiniana 116. 325.
- Vallicellana 116. 200.
- Vaticana 115. 319.
- Vittorio Emanuele 115. 156.
- Bibulus, Mon. of 163.
- Birrerie 113.
- Blind Asylum 253.
- Bocca della Verità 249.
- S. Bonaventura 233.
- Bookbinders 115.
- Books on Rome 128.
- Booksellers 115.
- Borgo 273. 145.
- S. Angelo 276.

ROME :

Borgo Nuovo 276.
 — S. Michele 276.
 — S. Spirito 276.
 — Vecchio 276.
 Botanical Garden 322.
Bramante:
 Belvedere of the Vatican 304.
 Cancelleria, Palazzo della 199.
 Cortile di S. Damaso (or delle Loggie) 287.
 Monastery Court of S. Maria della Pace 192.
 S. Lorenzo in Damaso 199.
 Pal. Giraud 276.
 St. Peter's 277.
 Tempietto 328.
 Bridges 143.
 British Academy 117.
 Bronzes, Antique 214. 318.
 —, Imitations of 117.
 Cabs, see Appx.
 Cæcilia Metella, Tomb of 349.
 Cælius, the 145. 258.
 Cairoli, Monument of the 149.
 Cafés 113.
 Calcografia Regia 117.
 Calendarium Prænestinum 198.
 Cameos 117.
 Camera de' Deputati 154.
 Campagna di Roma 333.
 Campo di Fiori 204.
 — Militare 169.
 — Vaccino 224.
 — Verano 344.
 Campus Martius 183. 145.
 Cancelleria, Pal. 199. LI.
 Candelabra, antique 305. 310.
 Capitol 208.
 —, Coll. of the 212.
 Capitoline Hill 145.
 — Museum 216.
 — Venus 221.
 — Wolf 214.
 Capo di Bove 349.
 Cappuccini 272.
 Caracalla, Thermæ of 255.
 Curcer Mamertinus 237.

ROME :

Carceri Nuovi 207.
 S. Carlo alle Quattro Fontane 170. LVIII.
 — a, Catinari 201.
 — al Corso 153.
 Carnival 121.
 Carriages 119.
 Carthusian Monastery 167.
 Casa Bartholdy 150.
 — di Crescenzo 249.
 — di Livia 243.
 — di Pilato 249.
 — Professa 198.
 — di Rienzi 249. [xlvii.
 — Tarpeia 221.
 — Zuccari 150.
 Casale Rotondo 350.
 Casino Massimi 272.
 — di Papa Giulio 336.
 — Rospigliosi 175.
 Castello S. Angelo 274.
 Catacombs 131. 356. xlv.
 — of S. Agnès 363.
 — of S. Alessandro 363.
 — of St. Callistus 361.
 — of Domitilla 362.
 — of S. Genesio 393.
 — Jewish 363.
 — of SS. Nereus and Achilleus 362.
 — of SS. Peter and Marcellinus 363.
 — of St. Pontianus 363.
 — of St. Prætextatus 362.
 — of St. Priscilla 362.
 — of S. Sebastiano 363.
 S. Caterina de' Funari 202.
 — di Siena 169.
 S. Cecilia in Trastevere 331.
 Cemetery, German 285.
 —, Jewish 250.
 —, Protestant 251.
 S. Cesareo 256.
 Cestius, Pyramid of 252.
 Chain Bridge 207.
 Chemists 115.
 Chief Attractions 125.
 Chiesa Nuova 200.
 Christian Museum 270. 320.
 Chronological Table of the Emperors and Popes 139.
 Church Festivals 119.
 Cigars 114.
 Cimitero dei Tedeschi 285.

ROME :

Circo Agonale 190.
 Circus of Caligula 273.
 — of Domitian 190.
 — Flaminius 202.
 — of Maxentius 349.
 — Maximus 250.
 Civitas Leonina 274.
 Claude Lorrain's Landscapes 159.
 S. Clemente 260. xlv. xlvii. xlviii.
 Climate 114. xxv.
 Clivus Capitolinus 227.
 — Cinnæ 338.
 — Martis 348.
 — Victoriæ 214.
 Cloaca Maxima 218. 222. 227.
 Clubs 119.
 Cœmeterium Ostrianum 363.
 Cola di Rienzi, statue of 210.
 Collections, etc. 122.
 Collegio Militare 322.
 — di Propaganda Fide 151.
 — Romano 156.
 Collegium Maroniticum 182.
 — Urbanum 151.
 Collis Hortorum 148.
 Colonacce, Le 239.
 Colonnade of the Twelve Gods 225.
 Colosseum 234.
 Columbaria 257. 315. 348. 356.
 Comitum 222.
 Concordia, Temple of 226.
 Confectioners 114.
 Conservatori, Palace of the 211.
 Consulates 111.
 Corso, the 152.
 — Vittorio Emanuele 191.
 Corte di Appello 200.
 SS. Cosma e Damiano 231. xlv.
 S. Costanza 342.
 Crescentius, House of 249.
 S. Crisogono 330.
 S. Croce in Gerusalemme 181.
 Cupid (Eros) of Praxiteles 309.
 Curia 228.
 — Hostilia 222. 238.
 — Julia 238.

ROME :

Dentists 115.
 Deputies, House of 154.
 Diadumenos Relief 312.
 Diary 125.
 Diocletian, Thermæ of 167.
 Dioscuri, group of the 210.
 Directory 112.
 Discus-thrower of Myron 190. 305. xxxi. xxxix.
 Divisions, ancient, of the city 134.
 Dogana di Terra 155.
 SS. Domenico e Sisto 170.
 Domine Quo Vadis 348.
 Dominican Monastery 253.
 Domus Augustana 242.
 — Flavia 244.
 — Livie 243.
 — Tiberiana 244.
 Doryphorus (after Polyctetus) 316. xxxi.
 Drusus, Arch of 258.
 Duration of Visit 125.
 Ecole de Rome 205.
 Egyptian Museum 316.
 S. Eligio degli Orefici 207.
 Embassies 111.
 Emporium 251.
 English Churches 119. 150. 154. 169.
 Engravings 117.
 Eros of Praxiteles 309. xxxii.
 Esquiline 145. 166.
 Ethnographical Museum 157.
 Etruscan Museum 316. xl.
 Eurysaces, Mon. of 187.
 S. Eusebio 179.
 Exchange 155.
 Excubitorium of the Vigiles 330.
 Exquilie 166.
 Farnese Gardens 242.
 Farnesina, Villa 323. lvi.
 Fasti Consulares 215.
 Fattorini Pubblici 119.
 Faustina, Temple of 231.
 Fees 114.
 Ficoronian Cista 156.
 Filippo Neri, chapel of 199.

ROME :

Filippo Neri, Oratorio di 259.
 Firewood 112.
 Flavian Palace 244.
 Fontana delle Tartarughe 202.
 — di Trevi 151.
 — del Tritone 171.
 Fontanone dell' Acqua Felice 168.
 — di Ponte Sisto 207.
 Fora of the Emperors 237.
 Fortune, Temple of 249.
 Forum of Augustus 239.
 — Boarium 248.
 — of Cæsar, or Forum Julium 239.
 — of Nerva 239.
 — Romanum 222.
 — of Trajan 240.
 — Transitorium 239.
 S. Francesca Romana 232.
 S. Francesco di Paola 183.
 — a Ripa 332.
 Franciscans, House of 182.
 Galleria Barberini 171.
 — Borghese 185.
 — Colonna 163.
 — Corsini 324.
 — Doria 158.
 — of Imperial Busts 327.
 — Lateranense 271.
 — Spada 206.
 — Tenerani 169.
 — of the Vatican 301.
 Gallienus, Arch of 179.
 Galluzze, Le 180.
 Ganymede (after Leocares) xxxii.
 Gardens of Mæcenas 182.
 — of Sallust 173.
 Garrison 122.
 Gaul, Dying 217. xxxiv.
 Genio del Vaticano (Eros of Praxiteles) 309.
 German Hospice 191.
 Gesù 197. lviii.
 — e Maria 153.
 Ghetto 203.
 Gibson's House 150.
 S. Giacomo in Augusta (degli Incurabili) 153.
 — degli Spagnuoli 191.
 S. Giorgio in Velabro 248.

ROME :

Giotto's Navicella 281.
 S. Giovanni de' Fiorentini 207.
 — in Fonte 265.
 — in Laterano 265. xlvii. lvii.
 — in Oleo 257.
 — e Paolo 259.
 — a Porta Latina 256.
 S. Giuseppe a Capo le Case 151.
 — de' Falegnami 162. 237.
 Gladiator, Dying 217. xxxiv.
 Gloves 117.
 Goethe, House of 152.
 Golden Palace of Nero 234.
 Goods Agents 117.
 Graces, the, relief by Socrates 314. xxxviii.
 Gratuities 114.
 S. Gregorio 258.
 Grotte Vaticane 284.
 Grotto of Egeria 351.
 Guercino's Aurora 173.
 Guide 116.
 Guido Reni's Aurora 175.
 Hadrian's Tomb 274.
 Hairdressers 114.
 Hercules, Torso of 313.
 Hills of Rome, Seven 145.
 History of the City of Rome 129.
 Horse Tamers (Quirinal) 173.
 Horses, Saddle 119.
 Hospice, German 191.
 Hospital, Bohemian 201.
 Hospital for Women 265.
 —, Military 276.
 Hôtel Quirinal 169.
 Hotels 111.
 Hydropathic Establishments 114.
 S. Ignazio 155. lviii.
 Ilian Tablet 220.
 Immacolata, Column of the 150.
 Inquisition 285.
 Intarsia 117.
 S. Isidoro 172.
 Isola Tiberina (di Bartolomeo) 204.
 Istituto de' Cicchi 253.
 — Tecnico 183.
 S. Ivo 197.

ROME:

Janiculum, the 327.
 Janus Quadrifrons 248.
 Jesuit Churches 155.
 197. lviii.
 — Cemetery 250.
 Juno Barberini 308.
 — Ludovisi 173.
 Keats' House 150.
 Keyhole 253.
 Laocoon 311. xxxiv.
 Lateran, the 267.
 Leonardo da Vinci's
 Madonna 322.
 Lex Regia of Vespasian 218.
 Libraries 115.
 Liceo Ennio Quirino
 Visconti 156.
 Lieux d'Aisance 114.
 Liquoristi 113.
 Livia, House of 243.
 Longara see Lungara.
 S. Lorenzo in Damaso
 199.
 — fuori le Mura 343.
 xlv. xlvii.
 — in Lucina 153.
 — in Miranda 231.
 — in Panisperna 176.
 — in Piscibus 276.
 Lotto, Direzione del
 184.
 S. Luigi de' Francesi 193.
 Lungara 322.
 Lungaretta 330. 331.
 Lungarina 332.
 Lungo Tevere 184.
 Lupercal, the (grotto)
 243.
 Madonna Lucrezia 163.
 Mæcenæ, Gardens of
 182.
 S. Marcello 153.
 S. Marco 162. xlv.
 Marcus Aurelius, Col-
 umn of 154.
 —, Statue of 210. xxxviii.
 Marforio, Statue of 216.
 Margherita, Passeggiata
 322. 330.
 S. Maria degli Angeli 167.
 — dell' Anima 191.
 — Antiqua 233.
 — in Araceli 209.
 — Aventina 253.
 — Bocca della Verità
 249.
 — in Campitelli 202.
 — dei Cappuccini 172.
 — della Concezione 172.
 — in Cosmedin 249.
 xlviii.

ROME:

S. in Domnica 259.
 — Egiziaca 249.
 — Maria di Grottapinta
 205.
 — Liberatrice 247.
 — di Loreto 241.
 — Maggiore 176. xlv.
 xlvii. xlviii.
 — ad Martyres 194.
 — Mater Dei 177.
 — sopra Minerva 195.
 — de' Miracoli 147.
 — di Monserrato 205.
 — in Monte Santo 147.
 — della Navicella 259.
 — ad Nives 176.
 — Nova 233.
 — Nuova 350.
 — dell' Orto 332.
 — della Pace 191.
 — della Pietà in Campo
 Santo 285.
 — del Popolo 147. 1.
 — ad Præsepe 176.
 — del Priorato 253.
 — Rotonda 193.
 — Scala Coeli 355.
 — in Schola Graeca 249.
 — del Sole 249.
 — Traspontina 276.
 — in Trastevere 330.
 — in Vallicella 203.
 — in Via Lata 158. 154.
 — della Vittoria 168.
 Marionettes 119.
 Marmorata, the 251.
 Marrana, the 255.
 SS. Martina e Luca 235.
 S. Martino ai Monti 182.
 Mausoleum of Augustus
 184.
 — of Hadrian 274.
 Meleager, Statue of
 312.
 Metastasio, Mon. of 153.
 Meta Sudans 234.
 Michael Angelo: li-iii.
 lix.
 Carthusian Convent,
 Court of the 167.
 Christ bearing the
 Cross 196.
 Frescoes in the Cap-
 pella Paolina 292.
 Frescoes in the Sis-
 tine Chapel 288.
 S. Giov. dei Fiorenti-
 ni 207.
 — in Laterano 266.
 Last Judgment 291.
 S. Maria degli Angeli
 167.

ROME:

Michael Angelo:
 Monument of Ju-
 lins II. 183.
 Pal. Farnese 205.
 Pedestal of the Marc.
 Aur. statue 210.
 St. Peter's 279.
 Piazza del Campido-
 glio 216.
 Pietà 282.
 —, unfinished 152.
 Prophets and Sibyls
 291.
 Statue of Moses 183.
 S. Michele, Osp. 332.
 S. Michele in Sassia 277.
 Milliarium Aureum 228.
 Minerva, Temple of 180.
 Minerva Medica 316.
 Ministers' offices:
 Education 196.
 Exterior 173.
 Finance 168.
 Interior 201.
 Public Works 154.
 War 165. 170.
 Mint 321.
 Moles Hadriani 274.
 Molossian Honnds 311.
 Mons Sacer 343.
 Monte Caprino 208. 221.
 — Cavallo 174.
 — Citorio 154.
 — Malo 338.
 — Mario 338.
 — di Pietà 206.
 — Testaccio 251.
 Monument of the Em-
 press Helena 345.
 Mosaico, Studio del 321.
 Museo Artistico-Indu-
 striale 151.
 — Kircheriano 156.
 — Profano 268.
 — delle Terme 168.
 — Torlonia 325.
 Museums, see Capitol,
 Lateran, Vatican.
 Music 116.
 Navicella, the 259.
 — (Giotto's) 231.
 S. Nereo ed Achilleo 256.
 xlv.
 Nero, Buildings and
 Statue of 231.
 Newspapers 116.
 S. Nicola in Carcere 250.
 — da Tolentino 172.
 Nile, Group of the 315.
 xxxiii.
 Niobe, Daughter of 314.
 xxxii.

ROME:

- Nome di Maria 241.
 Nymphæum 181. 245.
 Obelisks 149. 155. 166.
 173. 176. 195. 191.
 265. 277.
 Observatory 157.
 Octavia, Colonnade of
 203.
 October Festival 122.
 Oculists 115.
 S. Offizio 285.
 Omnibuses, see Appx.
 S. Onofrio (Lungara)
 322.
 — (Monte Mario) 338.
 Oratorio di S. Filippo
 Neri 259.
 Orientation 126.
 Orti Farnesiani 242.
 Ospedale di S. Spirito
 276.
 Ospizio di S. Michele
 332.
 — de' Pazzi 322.
 Osterie 113.
 Pædagogium 247.
 Painters 116.
 Palatine 145. 241.
 Area Palatii 244.
 Auguratorium 243.
 Basilica 243.
 Buildings of Tibe-
 rius 244.
 — of Sept. Severus
 246.
 Clivus Victoriae 244.
 Excavations 242.
 Farnese Gardens 242.
 Flavian Palace 244.
 Lupercal 243.
 Pædagogium 247.
 Palatium 244.
 Porta Mugionis 244.
 Private House 243.
 Septizonium 242.
 Stadium 246.
 Temple of Jupiter
 Stator 244.
 Temple of Jupiter
 Victor 243.
 Temple of Victoria
 243.
 Palazzetto Farnese 199.
 Palazzo Accoramboni
 276.
 — Albani 170.
 — Altemps 190.
 — Altieri 197.
 — Antonelli 169.
 — Barberini 170. lviii.
 — delle Belle Arti 169.
 — Bernini 153.

ROME:

- Palazzo Bolognetti 198.
 — Bonaparte 162.
 — Borghese 184.
 — Braschi 191. 201.
 — Caffarelli 209.
 — della Cancelleria 199.
 — Capranica 198.
 — Cenci-Bolognetti 202.
 — Chigi 154.
 — Colonna 152. 163.
 — of the Conservatori
 211.
 — della Consultà 173.
 — Corsini 324.
 — della Dataria 174.
 — Doria 158.
 — Falconieri 207.
 — Farnese 205.
 — Ferrajuoli 154.
 — Fiano 153.
 — Field 182.
 — Gabrielli 201.
 — Galitzin 184.
 — Giraud - Torlonia
 276.
 — del Governo Vecchio
 201.
 — Grazioli 197.
 — Hüffer 169.
 — Lancelotti 190.
 — del Laterano 267.
 — Linotta 199.
 — Madama 192.
 — Massimi alle Co-
 lonne 199.
 — Mattei 202.
 — Muti-Papazzurri 152.
 — Odescalchi 162. 166.
 — del S. Offizio 285.
 — Orsini 203.
 — Pamphilj 158. 191.
 — Pio 205.
 — Piombino 154.
 — Poli 151.
 — Regio 174.
 — Ricciardi 276.
 — Righetti 202. 205.
 — Rinuccini 162.
 — Rondinini 152.
 — Rospigliosi 174.
 — Ruspoli 153.
 — Sacchetti 207.
 — Salviati 162. 322.
 — Santacroce 206.
 — Savelli 203.
 — Sciarra-Colonna 155.
 — del Senatore 211.
 — Simonetti 158.
 — Sora 200.
 — Spada alla Regola
 205.
 — di Spagna 151.

ROME:

- Palazzo Torlonia 154.
 162. 276.
 — Vaticano 286.
 — di Venezia 182. xlix.
 — Verospi 154.
 — Vidoni 198.
 S. Pancrazio 355.
 S. Pantaleo 199.
 Pantheon 193. xxxvi.
 S. Paolo fuori le Mura
 352. xlvii.
 — alle Tre Fontane 355.
 Parco Regina Marghe-
 rita 336. 337.
 Pasquino, Piazza del
 201.
 Passeggiata Margherita
 322. 330.
 Patriarchal Churches,
 the 135.
 Passionist Monastery
 259.
 S. Paul, Ch. of 169. 119.
 Pensions 112.
 Permessi 124.
 St. Peter's 277.
 Philippine Convent 201.
 Phocas, Column of 228.
 Photographs 118.
 Physicians 114.
 Piazza Araceli 209.
 — Barberini 171.
 — Bocca della Verità
 248.
 — del Campidoglio 210.
 — Campitelli 202.
 — Campo di Fiori 104.
 — Capo di Ferro 205.
 — Capranica 195.
 — Colonna 154.
 — del Foro Trajano
 240.
 — Guglielmo Pepe 179.
 — Madama 192.
 — S. Marco 163.
 — Mignanelli 151.
 — della Minerva 195.
 — Montanara 202.
 — di Monte Citorio 154.
 — della Navicella 259.
 — Navona 191.
 — Nicosia 185.
 — dell' Orologio 201.
 — del Pasquino 201.
 — de' Pelligrini 206.
 — Pia 276.
 — di Pietra 155.
 — di S. Pietro 277.
 — Pilotta 152.
 — del Popolo 146.
 — di Porta S. Gio-
 vanni 273.

ROME:

Piazza del Quirinale 173.
 — Rustiensei 276.
 — di Spagna 150.
 — Tartaruga 202.
 — delle Terme (di Termini) 166.
 — Tor Sanguigna 190.
 — della Trinità 149.
 — della Valle 198.
 — di Venezia 162.
 — Vitt. Emanuele 179.
 S. Pietro in Carcere 238.
 — e Marellino 182.
 — in Montorio 328.
 — in Vaticano 277.
 — in Vineoli 182.
 — Vittorio Emanuele 179.
 Pincio, the 145. 143.
 Pliny's Doves 220.
 Police Office 111.
 Pons Ælius 274.
 — Æmilius 250.
 — Cestius 204. 331.
 — Gratianus 204.
 — Milvius 336.
 — Triumphalis 274.
 — Valentiniani 327.
 Ponte S. Angelo 274. 143.
 — S. Bartolommeo 143.
 — Cestio 204. 331. 143.
 — Fabricio 204. 144.
 — Garibaldi 143. 202. 330.
 — Leonino 202. 143.
 — Molle 336.
 — Nomentano 342.
 — de' Quattro Capi 204. 144.
 — di Ripetta 184. 143.
 — Rotto 250. 144.
 — Salaro 341.
 — Sisto 327. 143.
 — Umberto 184. 143.
 Popes, List of 139.
 Popular Festivals 121.
 Population 143.
 Porta Appia 258.
 — Asinaria 273.
 — Aurelia 355.
 — Capena 254. 348.
 — Furba 347.
 — S. Giovanni 273. 346.
 — Latina 256. 346.
 — S. Lorenzo 179. 343.
 — Maggiore 180. 345.
 — Mugionis 241.
 — Nomentana 341.
 — Ostiensis 252.
 — S. Panerazio 355.
 — S. Paolo 252. 352. 394.

ROME:

Porta Pia 341.
 — Pinciana 172.
 — del Popolo 146. 334.
 — Portese 332.
 — Salara 338.
 — S. Sebastiano 258. 347.
 — Settimiana 327.
 — S. Spirito 276. 322.
 — Tiburtina 343.
 Porters 119.
 Portico (Colonnade) of Octavia 203.
 — of the Twelve Gods 225.
 Post Office 118. 154.
 Præneste, Treasure of 157.
 S. Prassede 178. xlv.
 Prati di Castello 275.
 — del Popolo Romano 251.
 Prehistoric Museum 157.
 S. Prisca 254.
 Private Apartments 112.
 Promenades 126.
 Propaganda 151.
 Protestant Cemetery 251.
 — Churches 119. 160.
 Protomoteca 212.
 S. Pudenziana 175. xlv.
 Pyramid of Cestius 252.
 SS. Quattro Coronati 264.
 Quattro Fontane 170.
 Questura 111.
 Quirinal, the 145. 166.
 Railway Office 111.
 — Station 111. 166.
Raphael: liii-lvi.
 Bible of R. 300.
 Chigi Chapel 147.
 S. Eligio 207.
 Entombment 185. 187.
 Faith, Hope, and Charity 301.
 Fornarina 171.
 Frescoes in the Farnesina 323.
 Galatea 324.
 Loggie (Vatican) 299.
 Madonna di Foligno 301.
 Navagero and Beazzano 158. 161.
 St. Peter's 278.
 Prophet Isaiah 189.
 Sibyls 192.

ROME:

Raphael's Stanze (Vatican) 293.
 — Tapestry 303.
 — House (removed) 276.
 — Frescoes from the Villa 188.
 — Tomb 195.
 — Transfiguration 301.
 Reading Rooms 116.
 Regia 222. 231.
 Restaurants 112.
 Rienzi's House 249.
 Rione Monti 166.
 Ripa Grande 332.
 Ripetta, the 184.
 Ripresa de' Barberi 162.
 SS. Rocco e Martino 184.
 Roma Quadrata 241. 242. 244.
 — Vechia 350.
 Rostra 228.
 — Julia 230.
 Rotonda, La 193.
 Round Temple 249.
 S. Saba 254.
 S. Sabina 252. xlv.
 xlvii.
 Sacra Via 222. 226. 231.
 Sallust, Gardens of 173.
 S. Salvatore 236.
 Saneta Sanctorum, chapel 272.
 Sapienza, Università della 197.
 Sarcophagi, ancient xl.
 —, early Christian xlii. xlv. 270. 271.
 Saturn, Temple of 227.
 Satyr of Myron 269.
 — of Praxiteles 217. 316.
 Savings Bank 155.
 Scala Santa 272.
 — di Spagna 150.
 Schola Xantha 225.
 Scipios, Tomb of the 257.
 Scott, House of Walter 154.
 Sculptors 116.
 S. Sebastiano 348.
 Semenzaio Comunale 256.
 Seminario Romano 190.
 Septa Julia 153.
 Septizonium 242.
 Servius, Wall of 130. 168. 254.
 Sessorium 181.
 Sette Sale 181.

ROME :

Seven Churches of Rome, the 135.
 Shops 117.
 S. Silvestro in Capite 154.
 — in Lacu 248.
 — al Quirinale 175.
 Sistine Chapel 287. lii.
 S. Sisto 256.
 Sophocles, Statue of 269.
 Spagna, Scala di 150.
 Spanish Church 205.
 S. Spirito, Ospedale di 276.
 S. Spirito in Sassia 276.
 Stadium (Circus) of Domitian 190.
 — of Septimius Severus 246.
 S. Stefano delle Carrozze 249.
 — Rotondo 260.
 Strangers' Quarter 146.
 Street Scenes 122.
 Studios 116.
 S. Susanna 168.
 Tabularium 221.
 Tarpeian Rock 221.
 Teachers 116.
 Teatro Argentina 198.
 — Drammatico 170.
 Telegraph Office 119. 154.
 Tempietto 328.
 Temple of Cæsar 229.
 — of Castor and Pollux 226.
 — of Concordia 226.
 — of the Deus Rediculus 351.
 — of Divus Augustus 247.
 — of Faustina 231.
 — of Fortune 249.
 — of Hercules Victor 249.
 — of Isis 196.
 — of Juno Sospita 250.
 — of Jupiter Capitolinus 208.
 — of Jupiter Stator 244.
 — of Jupiter Victor 243.
 — of Mars Ultor 239.
 — of Mater Matuta 249.
 — of Minerva Medica 180.
 — of Neptune 155.
 — of Romulus 349.
 — of the Sacra Urbs 232.
 — of Saturn 227.
 — of Spes 250.

ROME :

Temple of Venus and Cupid 181.
 — of Venus Genetrix 239.
 — of Venus and Roma 238.
 — of Vespasian 225.
 — of Vesta 222. 230. 249.
 — of Victoria 243.
 Templum Sacræ Urbis 232.
 S. Teodoro 248.
 Testaccio, Monte 251.
 Theatres 118.
 Theatre of Marcellus 203.
 — of Pompey 205.
 Thermæ of Agrippa 195.
 — Antoninianæ 255.
 — of Caracalla 255.
 — of Constantine 165.
 — of Diocletian 167.
 — of Titus 237.
 Thorvaldsen, Statue of 170.
 Tiber, river 143. 144.
 —, Island of the 204.
 Tiberius, Buildings of 244.
 Time-Ball 156.
Titian:
 Amor Sagro e Profano 186. 188.
 Cupid 188.
 St. Dominic 188.
 Tobacco Manufactory 114. 328.
 Tomb of Bibulus 163.
 — of Cæcilia Metella 349.
 — of Hadrian 274.
 — of the Empress Helen 345.
 — of the Nasones 333.
 — of the Pancratii 346.
 — of the Scipios 257.
 — of the Valerii 346.
 S. Tommaso in Fornis 259.
 Torlonia, Museo 325.
 Torre delle Milizie 169.
 — di Nerone 170.
 Town-wall 145.
 Trajan's Column 240.
 Trajan's Forum 240. xxxvii.
 Tramways, see Appx.
 Trastevere 337. 145.
 Trattorie 113.
 Tre Fontane 354.
 Tribunale Civile e Correzionale 200.

ROME :

Tribunale di Commercio 200.
 Triclinium of Leo III. 272.
 SS. Trinità de' Monti 149.
 — de' Pellegrini 206.
 Trinity, Ch. of the 154.
 Triumphal Arches, see Arch.
 Trofei di Mario 179. 210.
 Tullianum 237.
 Ufficio di Anagrafe 112.
 Umbilicus Urbis Romæ 227.
 Università della Sapienza 197.
 S. Urbano 351.
 Vatican, the 286.
 Antiquities 304.
 Appartamenti Borgia 321.
 Arazzi, Galleria degli 303.
 Archives 319.
 Belvedere, Cortile del 304.
 —, Vestibule of the 312.
 Boscareccio, il 313.
 Braccio N.ovo 315.
 Bronzes 318.
 Candelabri, Galleria dei 305.
 Cappella di Niccolò V. 299.
 — Paolina 292.
 — Sistina 287.
 Casino del Papa 313.
 Cortile del Belvedere 311.
 — di S. Damaso 286.
 — delle Loggie 287.
 Egyptian Museum 316. xl.
 Etruscan Museum 316. xl.
 Gabinetto delle Maschere 311.
 Galleria degli Arazzi 303.
 — dei Candelabri 305.
 — Geografica 303.
 — Lapidaria 315.
 — delle Statue 309.
 Garden 313.
 Giardino della Pigna 313.
 Hall of the Busts 310.
 Library 319.

ROME :

Vatican :

- Mich. Angelo's Frescoes 288. 291. 292.
 Museo Chiaramonti 313.
 — Etrusco-Gregorian 316.
 — Pio-Clementino 304.
 Museum of Christian Antiquities 320.
 Pauline Chapel 292.
 Picture Gallery 301.
 Portone di Bronzo 286.
 Raphael's Loggie 299. xlvii.
 — Stanze 293. liv.
 — Tapestry 303. lv.
 Sala degli Animali 309.
 — della Biga 305.
 — dei Busti 310.
 — di Costantino 298.
 — a Croce Greca 304.
 — Ducale 292.
 — dell' Immacolata 292.
 — delle Muse 308.
 — Regia 292.
 — Rotonda 308.
 Scala Pia 286.
 — Regia 287.
 Sistine Chapel 287.
 Stanza d'Eliodoro 297.
 — dell' Incendio 293.
 — de Papiri 320.
 — della Segnatura 294.
 Tomb-Paintings 318.
 Tor di Borgia 327. 286.
 Torre de' Venti 316.
 Vases, Collection of 317.
 Vatican Hill 273.
 Velabrum 248.
 Velazquez's Innocent X. 159.
 Velia 231.
 Venus after Praxiteles 221. xxxii.
 Vesta, Temple of 230. 249.
 Vestal Virgins, Palace of the 230.
 Via Agostino Depretis 169. 170. 175.
 — Appia 254. 346. 348.

ROME :

- Via del Babuino 150.
 — de' Banchi Nuovi 201.
 — — Vecchi 201. 205.
 — Baullari 199.
 — del Caravita 155.
 — Cavour 166. 176.
 — de' Cerchi 250.
 — del Clementino 184.
 — de' Condotti 151.
 — Conte Verde 180.
 — delle Convertite 153.
 — de' Coronari 190.
 — della Dataria 174.
 — de' Due Macelli 151.
 — Em. Filiberto 180.
 — dei Falegnami 202.
 — della Fontanella di Borghese 153. 184.
 — del Fontanone 207.
 — Galvani 251. 254.
 — Garibaldi 328.
 — Giulia 207.
 — del Governo Vecchio 191. 199. 201.
 — Gregoriana 150.
 — Labicana 180. 345.
 — Lata 158.
 — Latina 256. 346.
 — di Marforio 163.
 — Maschera d'Oro 190.
 — Merulana 179. 181.
 — di Monserrato 205.
 — di Mortella 202.
 — delle Muratte 152.
 — Nazionale 162. 166. 169.
 — Nova 231.
 — de' Pastini 154. 195.
 — de' Pettinari 206.
 — di Pietra 151.
 — della Pilotta 152.
 — Poli 151.
 — Prænestina 180.
 — Principe Eugenio 180.
 — Quattro Fontane 166. 169. 170.
 — del Quirinale 166. 173.
 — di Ripetta 183.
 — Sacra 222. 226. 231.
 — della Salara 251. 338.
 — Sallustiana 173.
 — del Salvatore 192.
 — della Scrofa 184.
 — Sistina 150. 166.
 — delle Statute 181.
 — di Tor de' Conti 239.
 — Tordinona 184.
 — delle Tre Pile 207.

ROME :

- Via del Tritone 171.
 — Triumphalis 236.
 — della Valle 197. 199.
 — de' Vascellari 331.
 — Venti Settembre 168.
 Viale Principessa Margherita 179.
 Victor Emmanuel, Mon. of 163. 210.
 —, Statue of 148.
 —, Tomb of 195.
 Vicus Jugarius 227.
 — Tuscus 226. 247.
 Villa Albani 338.
 — Aldobrandini 169.
 — Borghese 334.
 — Cælimontana 259.
 — Casali 260.
 — Doria-Pamphilj 355.
 — Farnesina 323.
 — Ludovisi 172.
 — Madama 337.
 — Magistrale (Maltese) 253.
 — Malta 172.
 — Massimi 272.
 — Mattei 259.
 — Medici 149.
 — Mellini 338.
 — Mills 245. 247.
 — di Papa Giulio 337.
 — Spada 341.
 — Torlonia 342.
 — Wolkonsky 272.
 Viminal 145. 166.
 SS. Vincenzo ed Anastasio 152. 354.
 S. Vitale 169.
 S. Vito 179. 181.
 Waldensian Church 170.
 Wall 145.
 Weapons 118. xvii.
 Wine-houses 113.
 Zecca 521.
 Zeus of Otricoli 308.
 Romena 42.
 Ronciglione 73.
 Ronco, the 89. 90.
 Rosaro 56.
 Roselle 3.
 Rosia 37.
 Rosignano 1.
 Rosso, Monte 109.
 Roviano 380.
 Rubicon, the 91.
 Ruffinella, Villa 365.
 Rusellæ 3.
 Sabate 391.
 Sabina, the 68.
 Sabine Mountains, the 373.

- Sabinum (of Horace) 380.
 Sacra, Isola 394.
 Saline 8.
 Salone 373.
 S. Salvatore, Abbey 11.
 Sapis 90.
 Sarteano 61.
 Sasso 8.
 Sassoferrato 109.
 Sassone 367.
 Sassovivo, Abbadia di 80.
 Saturnia 4.
 Savi, Vigna 350.
 Savignano 91.
 Savio, river 90.
 Saxa Rubra 337.
 Scannabechi, river 341.
 Schieggia 101.
 S. Scolastica 381.
 Scopettone, the 56.
 S. Secondo 57.
 Segni 388.
 Selagite, Mt. 11.
 Selci Lama 56.
 Semprevisa, Monte 387.
 Sena Gallica 101.
 — Julia 21.
 Senigallia 101.
 Senio, river 88.
 Sentinum 109.
 Septempeda 108.
 Serpentara 3rd 5.
 Serra Partucci 57.
 — S. Quirico 109.
 Serravalle 104.
 Setia 337.
 Settecamini 374.
 Sette Vene 69.
 S. Severa 7.
 S. Severino 108.
 Sezze 387.
 Sibilla, Mt. 105.
 Sieti 37.
 Siena 20.
 S. Agostino 29.
 Archives 30.
 Bandini, Statue of 32.
 Baptistery 25.
 S. Barbera, Fort 35.
 S. Bernardino, Oratorio di 32.
 Biblioteca Comunale 34.
 Campansi, Monast. 35.
 Cappella di Piazza 24.
 Carmine 30.
 Casa Bambagini-Galletti 20.
 — di S. Caterina 34.
 Casino de' Nobili 25.
 Cathedral 26.
- Siena:
 Cimitero di Misericordia 30.
 SS. Concezione 31.
 Deaf and Dumb Asylum 30.
 S. Domenico 35.
 Fontebranda 34.
 Fontegiusta 36.
 Fonte di Follonica 31.
 — Gaja 25.
 — Ovilo 36.
 — di Pantaneto 31.
 — de' Pispini 31.
 S. Francesco 32.
 S. Giorgio 31.
 S. Giovanni 26.
 S. Girolamo 31.
 House of St. Catharine 34.
 Innocenti 29.
 Istituto delle Belle Arti 32.
 — de' Sordo-Muti 30.
 Library of the Cathedral 28.
 Lizza, La 35.
 Loggia del Papa 30.
 L'Osservanza 36.
 Madonna d. Angeli 31.
 Mangia, Torre del 24.
 S. Maria del Carmine 30.
 — delle Nevi 35.
 — di Provenzano 31.
 — della Scala 29.
 S. Martino 30.
 Metropolitana, Chiesa 26.
 —, Opera della, or — del Duomo 28.
 Osservanza 36.
 Palazzo Arcivescovile 26.
 — Bichi 32.
 — Buonsignori 29.
 — Chigi (now Piccolomini) 29.
 — Ciaia 35.
 — dei Diavoli 36.
 — Finetti 30.
 — Gori 32.
 — del Governo 30.
 — del Magnifico 25.
 — Mocenni 35.
 — Nerucci 29.
 — Palmieri 32.
 — Pecci 29.
 — Piccolomini 29.
 — Pollini 30.
 — Pubblico 24.
 — Reale 28.
 — Saracini 29.
 — Spannocchi 32.
- Siena:
 Palazzo Tolomei 32.
 — de' Turchi 36.
 Peruzzi, House of 36.
 Piazza del Campo (Vittorio Emanuele) 23.
 — dell' Indipendenza 25.
 S. Pietro della Magione 36.
 — — alle Scale 29.
 Porta Camollia 36.
 — S. Marco 30.
 — Ovile 36.
 — Pispini 31. 36.
 — Romana 31.
 Servi di Maria 31.
 S. Spirito 31.
 Statue of Italia 25.
 — of Bandin' 32.
 Tolomei, Collegio 29.
 University 31.
 Sieve, river 37.
 Sigillo 101.
 Signa 13.
 Signia 388.
 S. Silvestro 68.
 Simbruina Stagna 381.
 Sinalunga 18. 42.
 Sinigaglia 101.
 Sinnus 88.
 Sipiniano 69.
 Sirolo 105.
 Somina, Monte 84.
 Soracte, Mt. 68.
 Sovana 4.
 Spello 79.
 Spolegium 82.
 Spoleto 82.
 Staggia 16.
 S. Stefano 385.
 —, Grotte 69.
 —, Porto 3.
 Stia 42.
 Sticciano 18.
 Stimigliano 68.
 Storta, La 389.
 Stroncone 85.
 Subasio, Monte 78.
 Subbiano 42.
 Subiaco 381.
 Sublaqueum 381.
 Sutri 73. 391.
 Sutrrium 73.
- Tadinum 109.
 Talamone 3.
 Tarquinii 5.
 Taverna, Villa 365.
 Tavolato, Osteria del 346. 367.
 Tavollo, river 94.
 Terni 84.

- Terontola 45.
 Teverone, river 373.
 Tiber, river 56. 66. 69.
 87. 143. etc.
 —, Source of the 56.
 Tibur 377.
 Tifernum Tiberinum 56.
 Tivoli 377.
 Todi 55.
 Tolentino 107.
 Tolentinum Picenum
 107.
 Tolfa, La 7.
 Tomba di Nerone 389.
 — dei Pancratii 346.
 — dei Valerii 346.
 Topina, Val 110.
 Topino, the 79.
 Tor Paterno 396.
 — di Quinto 337.
 — Sapienza 345.
 — de' Schiavi 345. 373.
 — di Selce 350.
 — Tre Teste 345.
 Torracchio 350.
 Torre Bertaldo 7.
 — Boacciana 395.
 — di Giove 12.
 — Pignattara 345. 367.
 Torrenieri 17.
 Torretta 368.
 Torri (Val di Merse) 37.
 Torrita 18. 42.
 Toscanella 6. 72.
 Trasimeno, Lago 45.
 Trebia 81.
 Tre Fontane 354.
 Trestina 57.
 Trevi 81.
 —, Monte 387.
 Trevignano 391.
 Tuder 55.
 Tuficum 109.
 Tuoro 46.
 Turchina 5.
 Turre, La 368.
 Tusculana, Villa 365.
 Tusculanum 365.
 Tusculum 365.

 Umbertide 57.
 Umbria 88.
 Urbania 56.
 S. Urbano 351.

 Urbibentum 62.
 Urbino 96. 56.
 Urbisaglia 107.
 Urbs Salvia 107.
 — Vetus 62.
 Urgone, the 91.
 Urvinum Hortense 80.
 — Metaurense 96.
 Uso, river 91.

 Vaccarreccia, Tumulus
 of 390.
 Vada 1.
 Vagnolini, Vigna 348.
 Valca, the 389.
 Valchetta, the 337.
 Val d'Elsa 13.
 — di Pussino 337.
 — Topina 110.
 Valle Aricciana 370.
 — dell' Inferno 338.
 Vallombrosa 94.
 Valmontone 381. 382.
 Valvisciolo, Abbey of
 387.
 Varano 105.
 Varia 380.
 Veii 389.
 Velathri 8.
 Velino, river 86.
 Velitræ 382.
 Velletri 382.
 Vene, Le 81.
 Verna, La 42.
 Vetralla 72.
 Vetulonia 2.
 Via Æmilia 88.
 — Appia 348.
 — — Nuova 346.
 — — Pignatelli 348.
 352.
 — Aurelia 1. 7.
 — Casilina 345.
 — Cassia 69. 389.
 — Clodia 390.
 — Collatina 345.
 — Flaminia 38. 92. 100.
 152. 336. 337. 390.
 — Labicana 345.
 — Latina 346.
 — Laurentina 354.
 — Nomentana 342.
 — Ostiensis 354.
 — Prænestina 345.

 Via Salara 68. 338.
 — Sette Chiese 349. 352.
 — Tiburtina 343. 374.
 — Triumphalis 372.
 — Valeria 379.
 Vicarelle 1.
 Vicarello 391.
 Vico 68.
 —, Lago di 73.
 Vicovaro 380.
 Vignoni, Bagni di 18.
 Villa Adriana 374.
 — Albani 398.
 — Belrespiro 355.
 — Aldobrandini 365.
 — Boncompagni 368.
 — Braschi 379.
 — of Cicero 365.
 — Conti 365.
 — d'Este 379.
 — Falconieri 365.
 — ad Gallinas 337.
 — of the Gordiani 345.
 — of Hadrian 375.
 — of Horace 380.
 — Imperiale 96.
 — Inghirami 11.
 — Lante 71.
 — of Livia 337.
 — of Mæcenæ 378.
 — S. Mezzano 38.
 — Mondragone 365.
 — Piccolomini 365.
 — Ruffinella 365.
 — Spada 341.
 — Taverna 365.
 — Tusculana 365.
 — Vittoria 94.
 Ville Monterchi 56.
 S. Vincenzo 1.
 SS. Vincenzo ed Ana-
 stasio 354.
 Vita, Capo della 12.
 Viterbo 69.
 S. Vito 67.
 Vivo 18.
 Volaterræ 8.
 Volscian Mountains 385.
 Volsinii 65.
 Volterra 8. 1.
 Vulci 4.

 Zagarolo 384.
 Zolforeo, Lago 8.

INDEX OF STREETS AND PLANS OF ROME.

Contents.

1. List of the Omnibus and Tramway Lines.
 2. Cab Tariff.
 3. List of the principal streets, public buildings, etc., of Rome.
 4. General Plan of Rome, showing the main portions of the city.
 5. Large Plan of Rome, in three sections.
-


This cover may be detached from the rest of the book by severing the yellow thread which will be found between pp. 4 and 5 of the list of streets.



I

II

III



Boundaries
of the main portions of
Rome, according to the
arrangement of the descrip-
tion in the Handbook.

- I. Strangers' Quarter & Corso
- II. The Hills of Rome
- III. Rome on the Tiber,
(Left Bank).
- IV. Ancient Rome.
- V. Quarters of the City
on the Right Bank.

Key-Map to R O M E

1: 23,000

0 100 200 300 400 500 600 700 800 900 1000 Yards.



Omnibus Routes.

The fares (10-15 c.) are marked on the omnibuses, and a board at the back gives the name of the terminus towards which the vehicle is running.

1. **Piazza di Venezia — Piazza del Popolo** (Pl. II, 16—I, 18), through the Corso (but after 4 p.m. through the side-streets to the E.: the PIAZZA SS. APOSTOLI, Via dell' Umiltà, PIAZZA DI TREVÌ, Via della Stamperia, Via Due Macelli, PIAZZA DI SPAGNA, and Via del Babuino), every 5 minutes.

2. **Piazza di Venezia — S. Pietro in Vaticano** (Pl. II, 16—I, 4, 7), through the CORSO VITTORIO EMANUELE to the Piazza S. Pantaleo (Pl. II, 13); then through the Via di S. Pantaleo, Piazza del Pasquino, Via del Governo Vecchio, Via del Banco, PONTE S. ANGELO, Borgo Vecchio and Piazza S. Pietro, every 5 minutes.

3. **Piazza di Venezia — S. Francesco a Ripa** (Pl. II, 16—III, 15), through the CORSO VITTORIO EMANUELE, Via Torre Argentina, PONTE GARIBALDI, Lungaretta, MARIA IN TRASTEVERE (Pl. II, 15), and Piazza di S. Calisto, every 10 minutes.

4. **Piazza di Venezia — Lateran** (Pl. II, 16—II, 30, 33), through the Via di Foro Trajano, FORO TRAJANO, Via Alessandrina, Via Croce Bianca, to the PIAZZA DELLE CARRETTE (Pl. II, 20, 23); then through the VIA DEL COLOSSEO, every 12 minutes.

5. **Piazza di Venezia — Piazza Vitt. Emanuele** (Pl. II, 16—II, 28, 29), through the Via del Foro Trajano, Via Alessandrina, Via della Madonna dei Monti, Via Leonina, Via Urbana, PIAZZA DELL' ESQUILINO (S. Maria Maggiore), Via Cavour, Viale Principessa Margherita to the STATION (arrival platform); then through the Via Principe Umberto, and Piazza Manfredi Fanti (aquarium), every 6 minutes.

6. **S. Carlo a Catenari — Piazza del Popolo** (Pl. II, 14—I, 15, 18), through the Via del Monte della Farina, CORSO VITTORIO EMANUELE, Piazza S. Pantaleo (Pl. II, 13), Via Caccagna, PIAZZA NAVONA (Circo Agonale; Pl. II, 13), Via and Piazza Agostino, Via della Scrofa and Via di Ripetta, every 5 minutes.

7. **S. Pantaleo — Piazza Vitt. Em.** (Pl. II, 13—II, 28, 29), through the CORSO VITTORIO EMANUELE, Piazza del Gesù, Corso Nazionale, PIAZZA VENEZIA (Pl. II, 16), Via del Foro Trojano, Via Alessandrina, Via and Piazza della Madonna dei Monti, Via Urbana, S. MARIA MAGGIORE (Pl. II, 25), and Via Merulana, every 6 minutes.

8. **Piazza di Spagna — S. Pietro in Vaticano** (Pl. I, 17, 20—I, 4, 7), through the Via Frattina, Piazza S. Lorenzo in Lucina, PIAZZA BORGHESE, Piazza Nicosia, Via di Monte Brianzo, PONTE S. ANGELO, Borgo Vecchio, Piazza S. Pietro, every 10 minutes.

9. **Piazza del Popolo — Via Cavour** (Pl. I, 25), through the Via del Babuino, PIAZZA DI SPAGNA (Pl. I, 17, 20), Via Due Macelli, Via del Tritone, PIAZZA BARBERINI, Via S. Nicola da Tolentino, Piazza di S. Bernardo, Via Torino, Via Viminale, and Via Principe Umberto, every 7 minutes.

10. **Piazza del Popolo — Piazza del Principe di Napoli** (Pl. I, 27, 30), vià the PORTA PINCIANA (Pl. I, 21), every 10 minutes.

11. **Piazza Montanara — S. Pietro in Vaticano** (Pl. II, 17—I, 4, 7), through the Via Montanara, Piazza Campitelli, Via de' Funari, S. CARLO A CATENARI, Campo de' Fiori, PIAZZA FARNESE, Via de' Banchi Vecchi, PONTE S. ANGELO, Piazza Pia, Borgo Vecchio, and Piazza S. Pietro, every 12 minutes.

12. **Piazza Navona (Circo Agonale) — Porta Pia** (Pl. II, 13—I, 30), through the Via Agonale, Via and Piazza S. Agostino, Via della Scrofa, Via di Stelletta, Piazza Campo Marzio, Piazza di Montecitorio, PIAZZA COLONNA (Pl. I, 16), Piazza S. Claudio, Piazza di S. Silvestro, Via della Mercede, Via Due Macelli, Via del Tritone, PIAZZA BARBERINI (Pl. I, 19, 22), Via S. Nicola da Tolentino, and VIA VENTI SETTEMBRE, every 10 minutes.

13. **Porta Pia — Prati di Castello** (Pl. I, 30—I, 8), through the VIA VENTI SETTEMBRE, Via S. Nicola da Tolentino, PIAZZA BARBERINI (Pl. I, 19, 22), Via del Tritone, Via Due Macelli, PIAZZA DI SPAGNA (Pl. I, 17, 20),

Via Condotti, Via della Fontanella di Borghese, PIAZZA BORGHESE, Piazza Nicosia, Porto di Ripetta, Via Vittoria Colonna, and Via Crescenzo (formerly the Via Reale), every 12 minutes.

14. **Foro Trajano** — **Prati di Castello** (Pl. II, 19—I, 8), through the Via S. Marco, Via delle Botteghe Oscure, Piazza Paganica, Via Torre Argentina, CORSO VITT. EMANUELE, Via dei Baullari, PIAZZA DELLA CANCELLERIA (Pl. II, 13), Via Pellegrino, Via de' Banchi Vecchi, PONTE S. ANGELO, Porta Castello, and Via di Porta Angelica, to the Carabinieri Barracks, every 8 minutes.

15. **Via di S. Apollinare** — **Via Carlo Alberto** (Pl. I, 13—II, 25, 28), viâ the Piazza S. Agostino, Piazza Madama, Piazza di S. Eustachio, and through the Via della Rotonda, Torre Argentina, CORSO VITTORIO EMANUELE, PIAZZA DEL GESÙ (Pl. II, 16), Via Araceli, PIAZZA S. MARCO, Via Foro Trajano, Via Alessandrina, Via della Madonna dei Monti, Piazza dell' Esquilino, and S. MARIA MAGGIORE, every 7 minutes.

16. **Cancelleria** — **Piazza dell' Indipendenza** (Pl. II, 13—I, 29), viâ the Piazza S. Pantaleo, PIAZZA NAVONA (Circus Agonale), and through the Via del Teatro Valle, Piazza di S. Eustachio, PANTHEON, Piazza Capranica, Montecitorio, PIAZZA COLONNA, Via del Tritone, Piazza S. Claudio, Piazza di S. Silvestro, Via della Mercede, Via Due Macelli, Via del Tritone, PIAZZA BARBERINI, Via S. Nicola da Tolentino, VIA VENTI SETTEMBRE, Via Pastrengo, Via Cernaia, Via Volturno, and Via Solferino.

17. **Piazza della Consolazione** — **Campo Verano** (*Cemetery*; Pl. II, 17-35), viâ the FORO ROMANO, and through the Via Cavour, Via dei Serpenti, Via Palermo, Via Agostino Depretis (Quattro Fontane), Piazzale della Ferrovia (*Railway Station*), Viale Princip. Margherita, and Via Tiburtina.

18. **Piazza del Quirinale** — **S. Agnese fuori Porta Pia** (Pl. II, 19—I, 30, etc.), through the Via del Quirinale, VIA VENTI SETTEMBRE, Porta Pia, Via Nomentana, Piazzale di S. Agnese (about $1\frac{3}{4}$ M.).

19. **Piazza S. Silvestro** — **Piazza Vitt. Em.** (Pl. I, 16—II, 23, 29), viâ the Piazza S. Claudio, and through the Via S. Maria in Via, Via dei Crociferi, Via delle Muratte, Via delle Vergini, Piazza SS. Apostoli, FORO TRAJANO, Via Alessandrina, Piazza delle Carrette, VIA DEL COLOSSEO, Piazza di S. CLEMENTE, Via Manzoni, and Via Em. Filiberto, every 10 minutes.

20. **S. Andrea della Valle** — **Porta Salara** (Pl. II, 13—I, 27), through the CORSO VITTORIO EMANUELE, Via dei Cestari, Via del Gesù, Via Piè di Marmo, Piazza and Via di Collegio Romano, Via dell' Umiltà, Via del Lavatore, Via Rasella, VIA QUATTRO FONTANE, VIA VENTI SETTEMBRE, and Via di Porta Salara.

21. **Ponte Sisto** — **Castro Pretorio** (Pl. II, 14—I, 28), through the Via Giulia, Piazza Farnese, Campo di Fiori, CORSO VITT. EMANUELE, Piazza Minerva, Piazza Collegio Romano, FONTANA DI TREVI, Via del Lavatore, Via Rasella, Via Quattro Fontane, VIA VENTI SETTEMBRE, and Piazza delle Terme.

22. **Piazza dei Quiriti** — **Stazione di Trastevere** (Pl. I, 12—II, 15), viâ the Piazza del Risorgimento, Via di Porta Angelica, Piazza di S. PIETRO (Pl. I, 4, 7), Borgo S. Spirito, VIA DELLA LUNGARA, Piazza della Scala, S. MARIA IN TRASTEVERE, Piazza S. Calisto, Via di S. Francesco, and Viale del Re.

23. **S. Lorenzo in Lucina** — **Prato di S. Cosimato** (Pl. I, 16—II, 15), viâ the Campo Marzo, Via de' Perfetti, Via della Serofa, Piazza S. Luigi de' Francesi, Piazza S. Eustachio, Via del Teatro Valle, CORSO VITTORIO EMANUELE, Campo di Fiori, PIAZZA FARNESE, PONTE SISTO, S. MARIA IN TRASTEVERE, Piazza S. Calisto, and Via S. Francesco.

24. **Piazza di Spagna** — **Piazza Montanara** (Pl. I, 20—II, 17), through the Via di Propaganda, Via della Mercede, Piazza di S. Silvestro, Via delle Convertite, PIAZZA COLONNA, Piazza Montecitorio, Piazza Capranica, PANTHEON, Piazza S. Chiara, Via Torre Argentina, Piazza S. CARLO A CATENARI, Via dei Falegnami, Piazza Campitelli, and Via Montanara.

25. **Lateran** — **Casa Bonifatibus** (Pl. II, 30—III, 36), through the Via di Porta S. Giovanni and Via Appia Nuova.

26. **Porto Ripetta** — **S. Onofrio al Monte Mario** (Pl. I, 14—I, 7, etc.), through the Via Vitt. Colonna, Piazza Cavour, Via Terenzio, Via Fabio Massimo, Viale delle Milizie, Via Trionfale, and Forte di Monte Mario, 10-50 c.

Tramway Routes.

1. Piazza Venezia — Piazza delle Terme (Pl. II, 9—I, 25), through the Via Nazionale, Via Cernaia, and Via Volturmo, every 4 minutes.

2. Piazza delle Terme — Campo Verano (*Cemetery*; Pl. I, 25—II, 34), through the Via di Porta S. Lorenzo and Via Tiburtina, every 15-25 min., in connection with the steam-tramway to Tivoli.

3. Piazza delle Terme — Lateran (Pl. I, 25—II, 30), through the Viale Princ. Margherita, Via Gioberti, Via Carlo Alberto, Piazza Vitt. Em., Via Leopardi, and Via Merulana, every $\frac{1}{4}$ hr.

4. Piazza del Popolo — Ponte Molle on the Via Flaminia, every $\frac{1}{4}$ hr.

5. Piazza Montanara — S. Paolo fuori le Mura (Pl. II, 17—III, 16, etc.), through the Via Montanara, Via and PIAZZA BOCCA DELLA VERITÀ, Via della Salara, Via Marmorata, Porta S. Paolo, and Via Ostiense, every $\frac{1}{4}$ hr.

Cab Tariff.

Cabs (*Vetture Pubbliche*) in the principal piazzas.

| | With one horse. | | | | With two horses. | |
|--|-----------------|----------|--------|----------|------------------|----------|
| | Open | | Closed | | | |
| | By day | At night | By day | At night | By day | At night |
| Within the city: | | | | | | |
| Single drive (<i>corsa ordinaria</i>) in one-horse carr. open, for 1-3 pers., closed, for 1-2 pers., or in two-horse carr. 1-4 pers. | — 80 | 1 — | 1 — | 1 20 | 2 — | 2 50 |
| Per hour | 2 — | 2 — | 2 — | 2 20 | 3 — | 3 50 |
| Each additional $\frac{1}{4}$ hr. | — 50 | — 50 | — 45 | — 50 | — 70 | — 85 |
| For each drive, 1 pers. more . . | — 20 | — 40 | — 20 | — 40 | — 20 | — 40 |
| Outside the gates: | | | | | | |
| From or to the tramway terminus outside the Porta Lorenzo . . | 1 20 | 1 60 | 1 20 | 1 60 | 2 50 | 2 80 |
| To the cemetery at S. Lorenzo Fuori (Campo Verano), per hour . . | 2 20 | 2 70 | 2 20 | 2 70 | 3 50 | 4 — |
| Each additional $\frac{1}{4}$ hr. on the foregoing drive | — 50 | — 65 | — 50 | — 65 | — 85 | — 95 |
| To a distance of 500 yds. ($\frac{1}{2}$ Kil.) outside any of the gates, including the Porta S. Lorenzo . . | 1 30 | 1 50 | — | — | — | — |
| To a distance of 2 M. (3 Kil.) outside any of the gates, per hour | 2 50 | — | 3 — | — | 4 — | — |
| Each additional $\frac{1}{4}$ hr. | — 50 | — | — 50 | — | — 80 | — |

Night is reckoned from 7 p. m. to 5 a. m. from April 1st to Sept. 30th, and from 7 p. m. to 6 a. m. from Oct. 1st to March 31st.

If a cab be brought from the stand to the hirer's house or elsewhere, the driver is entitled to the $\frac{1}{4}$ hr. fare, over and above that for the drive.

For longer drives than those above mentioned, there is no tariff, but the above fares afford an idea of what may reasonably be demanded. On the afternoons of the days of the Carnival the vehicles are exempted from the restrictions of the tariff.

Large box 50 c., small box or portinanteau 20 c.; hand-bags, etc., free.

List of Streets in the Plan of Rome.

The plan is divided into three sections, the upper, with *green margin*, numbered 1, the central, *white*, II, the lower, with *red margin*, III. The three columns of figures in the subjoined list correspond to these sections; the numbers indicate the square of the section in which the place in question is to be found (thus: Accademia di S. Luca is in the 14th square of the 1st section). Where space has been too limited to admit of the names being inserted in the plan, they have been replaced by numbers, which in the following list are annexed to each name so omitted (thus: Banco di S. Spirito 15 is No. 15 in the 10th square of the 2nd section). The key to these numbers in their order is also inserted in the plan itself, an arrangement which will often be found useful.

| | I | II | III | | I | II | III |
|--|----|----|-----|---|----|----|-----|
| Abruzzi, Via' | 24 | | | Altamps, Pal. 6 | 13 | | |
| Accademia di Belle Arti di S. Luca | 14 | | | Altieri, Pal. | 16 | | |
| — — —, Picture Gallery (Via Bonella 44). | 20 | | | — —, 29 | 17 | | |
| — di Francia | 20 | | | Altoviti, Pal. | 10 | | |
| — di Napoli | 11 | | | —, Villa | 14 | | |
| Accoramboni, Pal. 2 | 7 | | | S. Ambrogio della Minima | 17 | | |
| Acqua Felice, Acquedotto | 28 | | | American Church (St. Paul) | 22 | | |
| — —, Fontanone dell' | 22 | | | Amerigo Vespucci, Via. | 14 | | |
| — Giulia, Castello dell' | 28 | | | S. Anastasia | 21 | | |
| — Mariana, Vicolo dell' | 32 | | | S. Andrea (near the Lateran) | 30 | | |
| — Paola | 12 | | | — (near S. Gregorio). | 24 | | |
| Acquedotto Antoniniano | 22 | | | S. Andrea, con Collegio Scozzese. 1 | 22 | | |
| — Neroniano dell' Acqua Claudia | 33 | | | —, Oratorio. 2 | 18 | | |
| Adda, Via | 24 | | | — delle Fratte | 19 | | |
| Adice, Via | 27 | | | — del Quirinale | 22 | | |
| Adriana, Via. | 11 | | | — della Valle | 13 | | |
| S. Adriano | 20 | | | — in Vinci. 10 | 17 | | |
| S. Agata. 3. | 15 | | | — e Bernardino. 1 | 23 | | |
| — in Suburra | 22 | | | Anfiteatro Castrense | 36 | | |
| Agnello, Via dell' | 23 | | | — Corea | 14 | | |
| S. Agnese | 13 | | | — Flavio (Colosseo) | 24 | | |
| SS. Agonizzanti. 19 | 13 | | | SS. Angeli Custodi. 8 | 19 | | |
| S. Agostino | 13 | | | Angelo Custode, Via dell' | 19 | | |
| —, Via | 13 | | | Angelica, Porta | 8 | | |
| Albani, Pal. | 22 | | | S. Angelo, Castello | 10 | | |
| —, Via | 27 | | | —, Ponte | 10 | | |
| Alberoni, Pal. 10 | 19 | | | —, Vicolo | 7 | | |
| Aldo Manuzio, Via. | 14 | | | — in Pescheria | 17 | | |
| Aldobrandini, Villa | 19 | | | S. Aniano. 4 | 18 | | |
| Alessandria, Via | 30 | | | Anicia, Via | 15 | | |
| Alessandrina, Via | 20 | | | Anima, Via dell' | 13 | | |
| Alessandro Farnese, Via | 12 | | | S. Anna | 10 | | |
| — Volta, Via | 17 | | | —, Monastero | 15 | | |
| S. Alessio | 18 | | | — de' Calzettari | 18 | | |
| Alfieri, Via | 29 | | | — de' Palafrenieri. 1 | 7 | | |
| S. Alfonso | 25 | | | SS. Anna e Gioacchino | 22 | | |
| Alfredo Cappellini, Via | 28 | | | Annia, Via. | 27 | | |
| Alibert, Via | 18 | | | SS. Annunziata. 9 | 20 | | |
| —, Vicolo | 7 | | | Antonelli, Pal. | 19 | | |
| | | | | Antonino, Tempio di | 20 | | |
| | | | | S. Antonio Abbate | 25 | | |

| I II III | | | I IIIII | | |
|-------------------------------|----|----|-------------------------------|----|----|
| S. Antonio delle Fornaci, Via | 1 | | S. Bartolommeo, No. 19 | 16 | |
| — di Padova 10 | 13 | | —, de' Vaccinari. | 14 | |
| S. Apollinare | 13 | | —, Isola | 17 | |
| —, Piazza | 13 | | Basilica di Costantino | 20 | |
| S. Apollonia | 15 | | — Giulia | 20 | |
| SS. Apostoli | 19 | | — Ulpia | 19 | |
| —, Piazza | 19 | | Bastioni di Castello, Via dei | 8 | |
| —, Vicolo | 16 | | — di Paolo III | 17 | |
| Appia, Via | 23 | | Battistero in Laterano | 30 | |
| — —, Nuova | 36 | | Baullari, Via de' | 13 | |
| Applicazione, Scuola di | 23 | | Belsiana, Via. | 17 | |
| Aquario | 23 | | Benedetta, Via | 11 | |
| Aquiro, Via in | 16 | | S. Benedetto | 13 | |
| Araceli, S. Maria in | 20 | | —, 7 | 16 | |
| —, Via di | 17 | | S. Benedetto in Piscinula | 18 | |
| Arancio, Via dell' | 17 | | Beniamino Franklin, Via. | 14 | |
| Arcaccio, Vicolo dell' | 15 | | Berardi, Pal. 10 | 16 | |
| Arco di S. Calisto | 15 | | S. Bernardo alle Terme | 22 | |
| — di Ciambella. 8 | 16 | | —, Piazza | 22 | |
| — di Costantino | 24 | | Bernini, Pal. 15 | 19 | 14 |
| — di Dolabella | 27 | | S. Biagio | 18 | |
| — di Druso | 28 | | —, 4 | 16 | |
| — di Gallieno | 28 | | — del Fosso. 21 | 13 | |
| — di Giano | 21 | | — della Pagnotta. 13 | 10 | |
| — di M. Aurelio (sito). 7 | 16 | | Bianchi, Via Gust. | 14 | |
| — di Monte, Via. | 14 | | S. Bibiana | 31 | |
| — degli Orefici. 1. | 21 | | —, Via di | 31 | |
| — di Settimio Severo | 20 | | Bixio, Via | 32 | |
| — di Tito | 23 | | Bocca di Leone, Via di | 17 | 14 |
| Ardeatina, Porta | 28 | | Bocca della Verità, Via | 18 | |
| Ariosto, Via | 29 | | Bodoni, Via | 14 | |
| Armata, Via dell' | 10 | | Boezio, Via | 11 | |
| Arno, Via | 27 | | Bologna, Via | 11 | |
| Ascanio, Via di | 13 | | —, Vicolo | 11 | |
| Asinaria, Porta | 33 | | Bolognetti, Pal. 3 | 16 | 14 |
| Astalli, Via degli. | 16 | | Bonaccorsi-Sabini, Pal. 21 | 16 | |
| —, Villa | 33 | | Bonaparte, Pal. 5 | 16 | |
| S. Atanasio de' Greci. 6 | 17 | | —, Villa | 26 | |
| Attilio Regulo, Via. | 11 | | S. Bonaventura | 24 | |
| Aurora, Via dell' | 20 | | Boncompagni, Pal. 5 | 17 | |
| Aventina, Via | 20 | | —, Via | 23 | |
| Aventino, Monte | 18 | | — Simonetti, Pal. 15 | 16 | |
| Avignonesi, Via degli | 19 | | Bonella, Via | 20 | |
| Avila, Piazza d' | 10 | | Borghese, Pal. | 16 | |
| Azeglio, Via | 25 | | —, Piazza | 16 | |
| Babuino, Via del | 17 | | —, Villa | 21 | |
| Baccina, Via. | 23 | | Borgo S. Agata | 22 | |
| S. Balbina | 23 | | — Angelico | 8 | |
| —, Via di | 23 | | — S. Angelo | 7 | |
| Balbo, Via | 25 | 25 | — Laurentino | 31 | |
| Bambin Gesù | 25 | | — S. Michele | 7 | |
| Banchi Nuovi, Via de' | 10 | | — Nuovo | 7 | |
| — Vecchi, Via de' | 10 | | — Pio | 7 | |
| Banco di S. Spirito. 15 | 10 | | — S. Spirito | 7 | |
| —, Via del | 10 | | — Vecchio | 7 | |
| S. Barbara | 14 | | — Vittorio | 7 | |
| — | 24 | | Borgognona, Via | 17 | |
| Barberini, Pal. | 7 | | Borromeo, Pal. 12 | 16 | |
| —, Villa | 22 | | Boschetto, Via del | 22 | |
| —, Piazza | 19 | | Bosco Parrasio dell' Acca- | | |
| S. Bartolommeo | 18 | | demia degli Arcadi | 12 | |

I II III

I II III

| | | | | | |
|---|----|--|--|----|----|
| Botteghe Oscure, Vicolo delle | 17 | | Carrozza, Via | 17 | |
| Branca, Piazza di | 14 | | Cartari, Via | 10 | |
| —, Via Giovanni | 14 | | Cartoni, Villa | 19 | |
| Braschi, Pal. 17 | 13 | | Casa di Crescenzo (di Rienzi or di Pilato). 3 | 18 | |
| S. Brigida. 3 | 13 | | Casali, Pal. 9 | 13 | |
| Brunetti, Via | 15 | | —, Vigna | 27 | |
| Bucimazza, Via | 18 | | Cascine, Vicolo delle | 15 | |
| Bufalo, Pal. del. 6 | 19 | | Caserma de' Carabinieri | 15 | |
| Bufola, Vicolo della | 17 | | — di Cavalleria. 8 | 19 | |
| Buonarroti, Via | 29 | | — de' Vigili. 5 | 16 | |
| Buon Pastore | 11 | | Cassa di Risparmio | 16 | |
| Caccagna, Via | 13 | | Cassiodoro, Via | 11 | |
| Cactani-Sermoneta, Pal. 26 | 17 | | Castelfidardo, Via | 26 | |
| Caffarelli, Pal. 9 | 17 | | Castro Pretorio, Via del | 29 | |
| Cagliari, Via | 30 | | Catalone, Piazza | 7 | |
| Caio Mario, Via | 8 | | Catena, Piazza della | 17 | |
| Cairolì, Via | 29 | | —, Strada della | 4 | |
| — — — | 32 | | S. Caterina de' Funari | 17 | |
| S. Cajo. 5 | 22 | | S. Caterina della Rota. 1 | 10 | |
| Callini, Via | 10 | | — de' Sanesi. 2 | 10 | |
| Camera dei Deputati. 24 | 16 | | — di Siena. 7 | 19 | |
| Camerata, Pal. 18 | 10 | | Catone, Via | 8 | |
| Campana, Pal. | 18 | | Cavalieri di Malta, Pal. de' | 17 | |
| —, Via | 27 | | Cavalleggeri, Porta | 4 | |
| Campidoglio | 20 | | Cavalletti, Pal. 15 | 17 | |
| Campo Carleo, Via del | 20 | | Cavallini, Via | 14 | |
| Campo di Fiori | 13 | | Cavour, Piazza | 11 | |
| — di Maccao, see Campo Militare. | | | —, Via | 25 | 25 |
| — Marzo, Via di | 16 | | S. Cecilia in Trastevere | 15 | |
| — Militare | 29 | | S. Cecilia. 20 | 10 | |
| — Vaccino | 20 | | —, Via di | 18 | |
| Cancelleria, Pal. della | 13 | | Cedro, Via del | 12 | |
| —, Piazza della | 13 | | Celimontana, Via | 27 | |
| Cancellieri, Via | 8 | | Celio, Monte | 30 | |
| Canestrari, Via de' | 13 | | Cellini, Via | 10 | |
| Canestrari, Vicolo de' | 11 | | S. Celso. 4 | 10 | |
| Canneti, Vicolo dei | 36 | | Cenci, Pal. | 17 | |
| Capitolino, Monte | 20 | | —, Piazza | 17 | |
| Capo d'Africa, Via | 27 | | Cerebi, Via and Piazza de' | 21 | |
| Capo di Ferro, Piazza | 14 | | Cernaja, Via della | 26 | |
| Capo le Case, Via | 19 | | Certosa | 26 | |
| Capocci, Via dei | 22 | | S. Cesareo | 23 | |
| Capellari, Via de' | 13 | | Cesarini, Via | 16 | |
| Capponi, Pal. 17 | 10 | | —, Vicolo | 16 | |
| Cappuccini, Convento de' | 20 | | Cesi, Pal. | 4 | |
| Capranica, Piazza | 16 | | — Piccolomini, Pal. 9 | 7 | |
| Capretari, Piazza, near S. Eustachio | 13 | | Cestari, Vicolo de' | 16 | |
| Carbonari, Vicolo de' | 20 | | Cestio, Sepolcro di | 16 | |
| Cardelli, Pal. 14 | 13 | | S. Chiara Via della Rotonda | 16 | |
| — | 15 | | —, Monastero | 26 | |
| —, 14 | 17 | | —, Via | 16 | |
| Cardello, Via del | 23 | | Chiavari, Via | 14 | |
| S. Carlino. 2 | 22 | | Chiesa Nuova | 10 | |
| S. Carlo al Corso | 17 | | Chigi, Pal. | 16 | |
| — a' Catenari | 14 | | Ciampini, Pal. | 25 | |
| Carlo Alberto, Via | 28 | | Ciancaleone, Vicolo | 22 | |
| Carpegna, Pal. 24 | 13 | | Cicerone, Via | 11 | |
| Carrette, Strada delle | 4 | | Cimarra, Via | 22 | |
| —, Via delle | 22 | | Cimatori, Vicolo de' | 10 | |
| | | | Cimitero de' Protestanti | 16 | |

| I II III | | | I II III | | |
|--------------------------------------|----|----|---------------------------------------|----|----|
| Cini, Pal. | 16 | | Corea, Pal. | 17 | |
| Cinque, Via del | | 11 | Cornacchie, Pozzo delle | 13 | |
| Cinquecento, Piazza | 25 | | Coronari, Via de' | 13 | |
| Cinque Lune, Via | 13 | | Corsini, Pal. | | 11 |
| Circo Agonale, see Piazza | | | —, Vicolo | | 11 |
| Navona | 13 | | Corso, Via del | 16 | 16 |
| Circus maximus | 21 | | Corte dei Conti. | | 19 |
| Cisterna, Vicolo della | 15 | | Cortile di Belvedere. 1. | 4 | |
| S. Claudio. 23 | 16 | | — di S. Damaso (delle | | |
| —, Via | 16 | | Logge). 2 | 4 | |
| Claudio, Via | 27 | | — della Panateria. 5 | 19 | |
| Clemente, Via | 11 | | S. Cosimato, Via di | | 15 |
| S. Clemente | 27 | | S. Cosma. 6 | | 13 |
| Clementina, Via | 22 | | SS. Cosma e Damiano. 5 | | 20 |
| Clementino, Via del | 13 | | Costaguti, Pal. 20 | | 17 |
| Cloaca Maxima | 18 | | Costantino, Basilica di | | 20 |
| Codini, Vigna | | 28 | Cremona, Via | | 20 |
| Cola di Rienzi, Piazza | 11 | | Crescenzi, Vicolo. | | 13 |
| —, Via | 8 | | —, Villa | | 12 |
| Coliseo | | 24 | Crescenzio, Via | 8 | |
| Collegio Clementino | 13 | | S. Crisogono | | 15 |
| — de' Copti | 4 | | —, Via di | | 15 |
| — Greco. 7 | 17 | | Croce, Via del | 17 | |
| — Inglese, Vigna del. | | 21 | S. Croce, Via di | | 33 |
| — Irlandese | 20 | | S. Croce de' Lucchesi. 13. | | 19 |
| — Nazzareno | 19 | | — in Gerusalemme, Bas. | | 36 |
| — de Propaganda Fide. 16 | 19 | | Crocebianca, Via di | | 20 |
| — Romano | | 16 | Crociata, Via della. | | 15 |
| Colombo, Via Cristoforo | | 15 | Crociferi, Via de' | 19 | |
| Colonna, Pal. | 19 | | Crocifisso, Cappella del | 7 | |
| —, Piazza | 16 | | Dame del Sacro Cuore, Conv. | | |
| —, Via. | 16 | | delle | | 8 |
| —, Villa | 19 | | Dante, Piazza | | 29 |
| Colonna di Foca | 20 | | Dataria, Via della | 19 | |
| — Trajana. | 19 | | Datti, Pal. 6 | | 16 |
| Colonnelle, Vicolo delle | 17 | | Delfini, Via | | 17 |
| Colonnesei, Via de' | 19 | | S. Dionisio. | 22 | |
| Colosseo | 24 | | Dogali, Via | 24 | |
| —, Via del. | 23 | | Dogana. 18. | 25 | |
| Colosso di Nerone | 23 | | — di Terra (now the Ex- | | |
| Commendatore, Pal. del. 13 | 7 | | change). 18 | 16 | |
| Commercio, Casa del. 2 | 16 | | SS. Domenico e Sisto | | 19 |
| Compagnia di Gesù | 16 | | Dominicani, Conv. de' | | 16 |
| Concezione | 10 | | Doria Pamphili, Pal. | | 16 |
| Condotti, Via | 17 | | S. Dorotea | | 11 |
| Conservatori, Pal. de'. 1 | 20 | | —, Via. | | 11 |
| Conservatorio de' Fanciulli | | | Drago, Pal. del. | 13 | |
| progetti. 14. | 7 | | —, 12 | 19 | |
| Conservatorio della Divina | | | Due Macelli, Via de' | 19 | |
| Provvidenza. 1. | 14 | | Duilio, Via | 12 | |
| Consolato, Vicolo del. | 10 | | S. Efremo | 22 | |
| Consolazione, Via della | 17 | | S. Egidio | | 12 |
| Consulta, Pal. della | 19 | | S. Eligio. 4 | | 10 |
| —, Via della. | 19 | | S. Elisabetta. 9. | | 13 |
| Conte Verde, Via | 32 | | —, 12 | | 10 |
| Conti, Pal. 12 | 16 | | Emanuele Filiberto, Via | | 29 |
| —, Villa | 36 | | Emilia, Via | 23 | |
| Convento de' Padri della | | | English Church (All Saints) | 17 | |
| Missione. 14 | 16 | | — — (Holy Trinity) | 16 | |
| Copelle, Via delle | 13 | | Ennio Quir. Visconti, Via | 14 | |
| Corallo, Vicolo del. | 13 | | Esquilino, Monte | | 29 |

I II III

I II III

| | | | |
|---|----|--|----|
| Esquilino, Piazza dell' . . . | 25 | S. Francesco delle Stimate . . . | 16 |
| S. Eufemia, Via . . . | 19 | Fraati, Vicolo de' . . . | 7 |
| Eurisace, Scpolcro di. . . | 35 | Fratte, Via delle . . . | 15 |
| S. Eusebio . . . | 28 | Fratina, Via . . . | 16 |
| S. Eustachio . . . | 13 | Frezza, Via della . . . | 17 |
| Ezio, Via . . . | 11 | Frusta, Via della . . . | 12 |
| Fabbrica, Porta . . . | 4 | Fnnari, Via dei . . . | 17 |
| Fabio Massimo, Via . . . | 8 | Gabrielli, Pal. . . | 10 |
| Fabricio, Ponte . . . | 17 | Gaeta, Via . . . | 29 |
| Falcone, Vicolo del . . . | 23 | Gaetani, Pal. . . | 25 |
| Falconieri, Pal. . . | 11 | Gaetano-Scrmonea, Pal. 26. . . | 17 |
| Falegnami, Via de'. . . | 17 | Galileo, Via . . . | 29 |
| Fanti, Piazza Manfredo . . . | 28 | Galizin, Pal. 13 . . . | 13 |
| Farini, Via . . . | 25 | S. Galla . . . | 18 |
| Farinone, Vicolo del . . . | 8 | Galli, Orto . . . | 15 |
| Farnese, Pal. . . | 14 | —, Pal. . . | 13 |
| —, Piazza . . . | 14 | S. Gallicano, Via di . . . | 15 |
| Farnesiani, Orti . . . | 21 | Gallo, Pal. del 5 . . . | 19 |
| Farnesina, Villa . . . | 11 | Galluzzo, le . . . | 32 |
| Federico Cesi, Via . . . | 14 | Galvani, Via . . . | 17 |
| Felice, V., see Via Sistina. | | Gambara, Via del . . . | 16 |
| Fenili, Via de' . . . | 12 | Garibaldi, Via . . . | 11 |
| —, Vicolo de' . . . | 20 | —, Ponte . . . | 14 |
| Ferrajuoli, Pal. 20 . . . | 16 | —, . . . | 12 |
| Ferratella, Via della . . . | 30 | Gatta, Via della . . . | 16 |
| Ferruccio, Via . . . | 29 | Gelsomino, Via del . . . | 1 |
| Fiamme, Vicolo delle . . . | 23 | Genova, Via . . . | 22 |
| Fiano, Pal. 8 . . . | 16 | Genovesi, Via de' . . . | 18 |
| Ficnaroli, Vicolo de' . . . | 15 | Germanico, Via . . . | 8 |
| Filippine, Monast. delle . . . | 25 | Gessi, Via Rom. . . | 14 |
| S. Filippo Neri. 8 . . . | 10 | Gesù, il . . . | 16 |
| —, 6 . . . | 7 | —, Via del . . . | 16 |
| Firenze, Pal. di . . . | 13 | Gesù e Maria. 4 . . . | 17 |
| —, Piazza . . . | 16 | — —, Via del . . . | 17 |
| Firenze, Via . . . | 25 | Ghetto, il . . . | 17 |
| Fiume, Via del . . . | 14 | Ghiberti, Via Lorenzo . . . | 14 |
| Flaminia, Porta . . . | 18 | S. Giacomo, Via . . . | 17 |
| Florida, Via . . . | 17 | — in Augusto (degli Incura- bili). 2. . . | 17 |
| Florio, Via . . . | 14 | — S. Scossacavalli. 7. . . | 7 |
| Fondamenta, Via della . . . | 4 | — de' Spagnuoli. 23 . . . | 13 |
| Fontana, Via della . . . | 27 | Gianicolo, Monte . . . | 9 |
| Fontanella, Via . . . | 18 | —, Passeggio Pubbico del . . . | 8 |
| — di Borghese, Via della . . . | 16 | — . . . | 9 |
| Fontanone, Via del . . . | 14 | —, Via del . . . | 7 |
| Foraggi, Via de' . . . | 20 | Giardino, Via del . . . | 16 |
| Fornaci, V. delle, see V. Ga- ribaldi. | | — Rcale, Via del . . . | 19 |
| Foro di Augusto . . . | 20 | Ginnasi, Vicolo de' . . . | 16 |
| — di Nerva (le colonnacce). 7 . . . | 20 | Ginori, Via . . . | 17 |
| Foro Romano . . . | 20 | Gioacchino Belli, Via . . . | 11 |
| — Trajano . . . | 19 | Gioberti, Via . . . | 25 |
| — —, Via del . . . | 19 | Giorgio, Via Mastro . . . | 17 |
| S. Francesca Romana . . . | 17 | S. Giorgio in Velabro . . . | 21 |
| — . . . | 19 | Giovanni Branca, Via . . . | 14 |
| —, al Campo Vaccino . . . | 23 | S. Giovanni . . . | 14 |
| S. Francesco, Via di . . . | 15 | —, Porta . . . | 33 |
| — di Paola . . . | 23 | S. Giovanni, Via . . . | 18 |
| — a Ripa . . . | 15 | — in Aino 6 . . . | 10 |
| — —, Via di . . . | 15 | — Decollato. 5 . . . | 18 |
| — di Sales, Via di . . . | 11 | — de' Fiorentini . . . | 10 |
| — —, Vicolo di . . . | 11 | — in Fonte . . . | 30 |

I II III

I II III

| | | | |
|--------------------------------------|----|---------------------------------|----|
| S. Giovanni de' Genovesi. 7 | 15 | S. Ivo. 12 | 13 |
| — in Laterano, Bas. | 30 | —, 26 | 13 |
| — — —, Via di | 27 | Labicana, Via | 27 |
| — Collegio de' Maroniti. 9 | 19 | Laboratorio di Chimica | 22 |
| — in Oleo, Cappella | 28 | Lamarmora, Mon. | 8 |
| — della Pigna | 16 | La Marmora, Via | 29 |
| — ante Portam Latinam | 28 | Lancellotti, Pal. 1 | 13 |
| — e Paolo | 24 | —, 16 | 13 |
| — —, Via di | 24 | Lancisi, Via | 8 |
| — e Petronio. 8. | 14 | Lante, Pal. | 13 |
| Giraud-Torlonia, Pal. 4 | 7 | —, Villa (Borghese) | 8 |
| S. Girolamo. 1 | 13 | Larga, Via | 10 |
| — de' Schiavoni | 14 | Laterano, S. Giovanni in | 30 |
| Giubbonari, Via de' | 14 | Latina, Porta | 28 |
| Giulia, Via | 10 | —, Via | 28 |
| S. Giuliano | 28 | Laurina, Via | 17 |
| —, 16 | 10 | Lauro, Vicolo del | 20 |
| — de' Fiaminghi. 7 | 13 | Lavaggi, Pal. 15 | 16 |
| Giulio Cesare, Via | 9 | Lavandare, Vicolo delle | 15 |
| — Romano, Via | 20 | Lavatore, Via del | 19 |
| S. Giuseppe | 10 | Lazio, Via | 20 |
| — | 19 | Leccosa, Via | 13 |
| — de' Falegnami (Carcer Ma- | | S. Leonardo | 10 |
| merlinus). 3 | 20 | Leoncino, Via del | 16 |
| Giusti, Via | 23 | —, Vicolo | 4 |
| Giustiniani, Pal. | 19 | Leonc IV., Via | 5 |
| —, Vicolo | 13 | Leonina, Via | 23 |
| Giustizia, Pal. di (progetto) 14 | | Leopardi, Via | 29 |
| Goito, Via | 26 | Lepri, Pal. | 17 |
| Governo Vecchio, Pal. del 20 | 13 | Lentari, Via de' | 13 |
| —, Via del | 13 | Libertà, Piazza della | 15 |
| Gracchi, Via | 8 | Liguria, Via | 23 |
| Grazioli, Pal. 4 | 16 | Lombardia, Via | 20 |
| Greca, Via | 17 | Longara, Via della | 11 |
| Greci, Via de' | 17 | S. Lorenzino in Piscibus. 10 | 7 |
| Gregori, Pal. | 20 | Lorenzo Ghiberti, Via | 14 |
| Gregoriana, Via | 20 | S. Lorenzo, Monast. | 22 |
| S. Gregorio | 14 | —, Porta | 31 |
| — | 17 | —, Vigna | 22 |
| —, Via di | 24 | — in Fonte | 19 |
| — Magno | 24 | — in Lucina | 16 |
| — Taumaturgo. 10 | 20 | — —, Piazza di | 16 |
| Grillo, Via del | 19 | — in Miranda | 20 |
| Grimaldi-Potenziani, Pal. 12 | 19 | — a' Monti | 20 |
| Grotte, Vicolo delle | 14 | — in Panisperna, Via di | 22 |
| Grottino, Via del | 17 | SS. Lorenzo in Damaso | 13 |
| Guardiola, Via della | 16 | — Luca e Martina. 4 | 20 |
| Guarnicri, Pal. | 20 | Lucchesi, Via de' | 19 |
| Gugliclmi, Pal. 25 | 17 | Luce, Via della | 15 |
| Guglielmo Pepe, Piazza | 28 | S. Lucia. 10 | 10 |
| S. Ignazio | 16 | S. Lucia | 17 |
| —, Piazza di | 16 | — del Gonfalone. 9 | 10 |
| —, Via | 16 | — in Selci | 26 |
| S. Ildefonso | 19 | —, Via di | 26 |
| Incurabili, Vicolo degli | 17 | — della Tinta. 11 | 13 |
| Indipendenza, Piazza dell' | 29 | Luciano Manara, Via | 12 |
| S. Isidoro | 20 | Lucina, Via in | 16 |
| —, Via | 20 | Lucrezio Caro, Via | 11 |
| Istituto Archeologico Germa- | | Lucullo, Via | 23 |
| nico. 8. | 17 | Ludovisi, Via | 23 |
| Italia, Corso d'. | 27 | —, Villa | 23 |

I II III

I II III

| | | | | |
|---|----|--|----|----|
| S. Luigi de' Francesi | 13 | S. Maria della Concezione | 23 | |
| Lunetta, Vicolo della | 10 | — della Consolazione | 20 | |
| Lungara, see Longara. | | — in Cosmedin | 18 | |
| Lungaretta, Via della | 15 | — di Costantinopoli. 14 | 19 | |
| Lungarina, Via della | 18 | — in Domnica | | 27 |
| Lupa, Via della | 16 | — Egiziaca | 18 | |
| Lupi, Villa | 25 | — de' Fiori | 15 | |
| Maecarani, Pal. 2 | 19 | — —, Via di | 17 | |
| —, Vigna | 17 | — Maria delle Fornaci | 4 | |
| Maechiavelli, Via | 29 | — delle Grazie | 8 | |
| Macelli, Via de' Due | 19 | — di Grottapinta. 5 | 13 | |
| Macello, Via | 18 | — Imperatrice | 30 | |
| Madama, Piazza | 13 | — Liberatrice | 20 | |
| Maddalena, Via | 16 | — Maddalena | 16 | |
| Madonna di Loreto. 3 | 19 | — Maggiore, Basilica | 25 | |
| Magenta, Via | 28 | — —, Piazza and Via di | 25 | |
| Maggiore, Porta | 35 | — sopra Minerva | 16 | |
| —, Via de | 32 | — —, Piazza di | 16 | |
| Magnanapoli, Via | 19 | — de' Miracoli. 1 | 18 | |
| Magnani, Pal. | 16 | — di Monserrato. 3 | 10 | |
| —, Vigna | 32 | — in Monterone. 12 | 13 | |
| —, Villa | 32 | — in Monte Santo. 2 | 18 | |
| Malatesta, Pal. 13 | 17 | — a' Monti. 3 | 23 | |
| Malghera, Via | 23 | — —, Via di | 23 | |
| Malva, Via della | 18 | — a' Monti della Neve. 2 | 23 | |
| Mamertinus, Carcer 3. | 20 | — in Monticelli | 14 | |
| Mamiani, Via | 28 | — della Morte | 11 | |
| Manara, Via Luciano | 12 | — della Neve. 13 | 19 | |
| Manfroni, Pal. 6 | 16 | — dell' Orto | 15 | |
| —, 10 | 13 | — della Pace. 3 | 13 | |
| Manin, Via | 25 | — del Pianto. 19 | 17 | |
| Mantellate, Via delle | 10 | — di Pietà (Oratorio di Caravita). 14 | 16 | |
| Manzoni, Via | 32 | — di Pietà con Camposanto (Cimitero de' Tedeschi). 4 | 4 | |
| Marana, Via della | 21 | — del Popolo | 18 | |
| Marcantonio Colonna, Via | 12 | — Porta Paradisi. 1 | 17 | |
| S. Marcello | 16 | — in Publicolis. 21 | 17 | |
| Marche, Via | 23 | — della Purificazione | 26 | |
| S. Marco | 16 | — —, 14. | 10 | |
| —, Via di | 19 | — della Purità. 3 | 7 | |
| —, Piazza di | 16 | — di Quercia. 9 | 14 | |
| Mareo Aurelio, Via | 27 | — Regina Coeli | 10 | |
| Marescotti, Pal. 1 | 16 | — Rotonda (Pantheon) | 16 | |
| — —, 9 | 16 | — della Salute | 22 | |
| Marforio, Via di | 20 | — della Sanità | 22 | |
| Margana, Piazza | 17 | — della Scala | 11 | |
| Margherita, Ponte | 15 | — —, Via di | 11 | |
| S. Margherita. 1 | 15 | — de' Sette Dolori | 12 | |
| Margutta, Via | 17 | — del Sole | 18 | |
| —, Vicolo | 18 | — della Stella | 1 | |
| Marj, Pal. (now Gran-Guardia). 11 | 7 | — del Suffragio. 11 | 10 | |
| S. Maria Addolorata | 8 | — della Torre | 15 | 15 |
| — Agata. 6. | 20 | — Traspontina. 5 | 7 | |
| — degli Angeli | 25 | — in Trastevere | 15 | |
| — dell' Anima | 13 | — —, Piazza di | 15 | |
| — in Aquiro. 17 | 16 | — in Trivio | 19 | |
| — in Araceli | 20 | — dell' Umiltà. 11 | 19 | |
| — in Cacaberis. 3 | 14 | — in Vallicella | 10 | |
| — in Campitelli | 17 | — delle Vergini. 1 | 19 | |
| — in Campo Marzo. 2 | 16 | — in Via | 16 | |
| — in Capella | 18 | | | |

I II III

I II III

| | | | | | |
|--------------------------------|----|--|-------------------------------|----|--|
| S. Maria in Via, Via di . . . | 16 | | Ministero di Agricoltura, In- | | |
| — in Via Lata | 61 | | dustria e Commercio . . . | 19 | |
| — in Vinci. 6 | 17 | | — degli Affari Esteri. . . . | 19 | |
| — della Vittoria | 23 | | — delle Finanze | 26 | |
| Marianna Dionigi, Via . . . | 14 | | — di Grazia e Giustizia. . | | |
| Mario de' Fiori, Via di . . . | 17 | | Sb. | 13 | |
| Marmorata, Via della | 18 | | — di Guerra | 22 | |
| Marmorella, Via | 20 | | — dell' Interno. 17. | 13 | |
| Marrana, la (brook) | 21 | | — dell' Istruzione Publica. | | |
| — | 24 | | 18 | 16 | |
| — | 30 | | — dei Lavori Pubblici . . . | 16 | |
| Marroniti, Via de' | 19 | | — della Marina. 8a | 13 | |
| S. Marta | 4 | | Minuzzi, Pal. 3. | 17 | |
| — | 16 | | Miracoli, Vicolo de' | 15 | |
| S. Martino. 6 | 14 | | Missione, Via della | 16 | |
| — a' Monti | 26 | | Modena, Via | 22 | |
| — —, Via di | 26 | | Molara, Piazza | 18 | |
| — de' Svizzeri. 3 | 4 | | Mole, Vicolo delle | 27 | |
| — —, Via | 29 | | Monserato, Via di | 10 | |
| Maschera d'Oro, Piazza. . . | 13 | | Montanara, Piazza | 17 | |
| Mascherino, Vicolo del . . . | 8 | | Montebello, Via | 26 | |
| Mascherone, Via del | 14 | | Monte Brianzo, Via di . . . | 13 | |
| Massimi, Pal. 12 | 17 | | — Caprino, Via di | 17 | |
| — alle Colonne, Pal. 11 . . . | 13 | | — Cavallo, sec Piazza del | | |
| Massimi-Sinibaldi, Pal. 13 . | 13 | | Quirinale | 19 | |
| Massimi, Via dei | 13 | | — Citorio, Pal. di (Camera | | |
| Mastai, Piazza | 15 | | de' Deputati). 24 | 16 | |
| —, Via | 15 | | — Citorio, Piazza di | 16 | |
| Mastro Giorgio, Via | 17 | | — della Farina, Via del . . | 13 | |
| Mattei, Pal. 27 | 17 | | — di Pietà | 14 | |
| —, Villa | 27 | | — —, Piazza di | 14 | |
| — — | 23 | | Monte Tarpeo, Via di . . . | 20 | |
| Mattonato, Via del | 12 | | Monterone, Via | 13 | |
| S. Mauro. 13 | 16 | | Monteverde, Vicolo di . . . | 10 | |
| Mausoleo di Adriano | 10 | | Montoro, Pal. | 10 | |
| — di Augusto | 14 | | —, Via | 13 | |
| Mazzamurelli, Vicolo | 15 | | Monumento dell' Immacolata | | |
| Mazzarina, Via | 22 | | Concezione. 1 | 20 | |
| Mazzini, Via | 28 | | Moretto, Via del | 19 | |
| Medici, Villa | 18 | | Moro, Via del | 15 | |
| Melone, Vicolo del | 13 | | Moroni, Vicolo | 11 | |
| Mercouri, Via | 14 | | —, Vigna | 25 | |
| Mercede, Via di | 19 | | Morte, Via della | 14 | |
| Merulana, Via | 29 | | Mortella, Via della | 14 | |
| Meta Sudante | 24 | | Morticelli, Via de' | 15 | |
| Metastasio, Teatro. Sc . . . | 13 | | Muratte, Via delle | 16 | |
| Metronia, Porta | 27 | | Muronova, Via | 15 | |
| S. Michele Arcangelo | 4 | | Museo Capitolino. 12 | 20 | |
| —, Borgo | 7 | | — Lateranense | 30 | |
| —, Via di | 15 | | Muti-Paparuzzi, Pal. 9 . . . | 19 | |
| SS. Michele e Magno | 7 | | Napolcon III., Via | 28 | |
| Mignanelli, Pal. | 20 | | Napoli, Orto di | 17 | |
| —, Piazza | 20 | | —, Via | 22 | |
| Milano, Via | 22 | | —, Via Principe di | 30 | |
| Milazzo, Via | 28 | | Nari, Pal. 14 | 13 | |
| Milizie, Viale delle | 9 | | Navicella, Piazza della . . . | 27 | |
| Mille, Via dei | 28 | | —, Via della | 24 | |
| Mills (Spada), Villa | 21 | | Navona, Piazza (Circo Ago- | | |
| Mincio, Via | 24 | | nale) | 13 | |
| Minerva Medica, Tempio | | | Nazionale, Via | 22 | |
| di | 32 | | — — | 16 | |

| | I | II | III | | I | II | III |
|-------------------------------------|----|----|-----|-------------------------------------|----|----|-----|
| Nazzareno, Via del, by the | | | | Paglia, Via della | | | 12 |
| Collegio Nazzareno. | 19 | | | Palatino, Monte | | | 21 |
| SS. Nerco ed Achilleo | | 26 | | Palermo, Via. | | 22 | 22 |
| Neroniano, Pal. | | 26 | | Palestro, Via. | | 29 | |
| Niccolini, Pal. 2 | 10 | | | Palle, Vicolo delle | | | 10 |
| S. Nicola | | 16 | | Palline, Vicolo delle | | 7 | |
| — in Arcione. 11 | 19 | | | Palma, Vicolo della | | 19 | |
| — in Carcere | | 17 | | Palombara, Pal. 11. | | | 16 |
| — degli Incoronati. 7 | | 10 | | Palombella, Via della | | | 16 |
| — de' Lorenesi. 8 | 13 | | | Pamphili, Giardino | | | 18 |
| — de' Perfetti. 3 | 16 | | | —, Pal. 18 | | 13 | |
| — da Tolentino | 23 | | | — Villa | | | 9 |
| — —, Vicolo di | 23 | | | S. Pancrazio, Porta | | | 9 |
| Nicosia, Piazza. | 13 | | | Panico, Via di | 10 | | |
| Nome di Maria. 4 | | 19 | | S. Pantalcone | | | 13 |
| Nomentana, Porta | 29 | | | — | | | 23 |
| —, Via | 30 | | | —, Via di | | | 13 |
| S. Norberto | 22 | | | Pantheon | | | 16 |
| Nuova, Via | 19 | | | Paolina, Via | | 25 | |
| Nussiner, Vigna | | 21 | | S. Paolino | | | 14 |
| Oca, Piazza dell' | 15 | | | Paolo Emilio, Via | | 9 | |
| Odescalchi, Pal. | | 16 | | S. Paolo Eremita. | | 22 | |
| S. Offizio, Pal. del | 4 | | | S. Paolo, Porta. | | | 16 |
| —, Via del. | 4 | | | —, Via di | | | 16 |
| Olmata, Via dell' | | 25 | | Paradiso, Via del | | | 13 |
| S. Omobuono. 7 | | 17 | | Parione, Via in | | | 13 |
| S. Onofrio | | 7 | | Parma, Via | | 22 | |
| —, Via | | 7 | | Pasquino, Piazza del | | | 13 |
| Orazio, Via | 11 | | | Passionisti, Giardino de' | | | 24 |
| Orfanotrofio | 25 | | | Pastini, Via de' | | | 16 |
| Orfeo, Vicolo di | 7 | | | Pastrengo, Via. | | 26 | |
| Ornani, Pal. 22. | | 13 | | Patrizi, Pal. | | | 13 |
| Oro, Monte d' | 17 | | | —, Villa | | 30 | |
| Orologio, Piazza dell' | | 10 | | —, — | | | 25 |
| Orsini, Pal. | | 10 | | Pavone, Via del | | | 10 |
| —, Via Virginio | 12 | | | Pellegrini, Piazza dei | | | 14 |
| Orsini-Savelli, Pal. | | 17 | | S. Pellegrino | | 5 | |
| Orso, Via dell' | 13 | | | Pellegrino, Via del | | | 13 |
| S. Orsola. 1 | 10 | | | Pelliccia, Via della | | | 15 |
| —, S. | 17 | | | Penitenza, Vicolo della | | | 11 |
| SS. Orsola e Caterina. 11. | | 17 | | Penitenzieri, Coll. de' | | 7 | |
| Ortaccio degli Ebrei | | 15 | | Pepe, Piazza Guglielmo | | | 28 |
| Orto Botanico | 12 | | | Perfetti, Via de' | | | 16 |
| Ospedale Ecclesiastico. 1 | 14 | | | Pergola, Via | | 17 | |
| — S. Gallicano. | | 15 | | Perucchi, Pal. | | | 20 |
| — di S. Giovanni Calabita | | 17 | | Pescheria, Via della | | | 17 |
| — di S. Giovanni Laterano. | | 30 | | Petrarca, Via | | | 29 |
| — degli Incurabili | 17 | | | Pettinari, Via de' | | | 14 |
| — S. Michele | | 15 | | Pia, Porta | | 30 | |
| — Militare. | 7 | | | —, Piazza | | 10 | |
| — de' Pazzi | | 7 | | Pianellari, Via. | | | 13 |
| Ospizio de' Poveri | 26 | | | Pianto, Via del | | | 17 |
| Osteria, Vicolo dell' | 31 | | | Piè di Marmo, Via del | | | 16 |
| Ostilia, Via | | 27 | | Piemonte, Via | | | 23 |
| Ottaviano Sforza, Via | 8 | | | Pier Luigi da Palestrina, | | | |
| Ottoboni, Villa | | 9 | | —, Via | | | 14 |
| Otto Cantoni, Vicolo dei | 17 | | | Pietra, Piazza di | | | 16 |
| Ovidio, Via | 11 | | | —, Via di | | | 16 |
| Pace, Piazza della | 13 | | | Pietrelle, Vicolo delle | | | 36 |
| Padella, Piazza | 10 | | | Pietro Cossa, Via | | | 14 |
| Paganica, Piazza | 17 | | | S. Pietro in Vaticano, Bas. | | | 4 |

| I II III | | | I II III | | |
|----------------------------------|-------|--|--------------------------------|--|-------|
| S. Pietro in Vaticano, Piazza di | 4 | | Prenestina, Porta | | 31 |
| — — — | 7 | | Presbyterian Church | | 15 |
| —, in Montorio | 12 | | Prince Amedeo, Via | | 28 |
| —, in Vincoli | 23 | | — Eugenio, Via | | 32 |
| — —, Piazza di | 23 | | — di Napoli, Via | | 30 |
| — —, Via di | 26 | | — Umberto, Via | | 28 |
| SS. Pietro e Marellino | 30 | | Principessa Margherita, Via | | 28 |
| Pighini, Pal. 4 | 13 | | S. Prisca | | 21 |
| Pigna, Giardino della. 1 | 5 | | Propaganda Fide. 16 | | 19 |
| Pilotta, Piazza della | 19 | | —, Via di | | 19 |
| —, Via della | 19 | | Properzio, Via | | 8 |
| Pinaco, Via del | 13 | | Protestant Church | | 22 |
| Pinciana, Porta | 21 | | S. Pudenziana | | 25 |
| —, Via di | 24 | | Puglie, Via | | 26 |
| Pincio, Monte | 18 | | Purificazione, Via della | | 20 |
| Pinellari, Via | 13 | | Quaranta Santi | | 27 |
| Pio, Pal. | 14 | | SS. Quattro, Via de' | | 27 |
| Piombino, Pal. 22 | 16 | | SS. Quattro Coronati | | 27 |
| Piombo, Via del | 19 | | Quattro Cantoni, Via | | 25 |
| Piscinola, Via | 18 | | Quattro Capi. 4 | | 17 |
| Plebiscito, Piazza del, see | | | —, Ponte de' | | 17 |
| Piazza Pia | 10 | | Querceti, Via dei | | 27 |
| Plinio, Via | 11 | | Questura | | 16 |
| Po, Via | 27 | | SS. Quirico e Giuditta. 8 | | 20 |
| Polacchi, Vicolo de' | 17 | | Quirinale, Pal. e Giardino del | | 19 |
| Poli, Pal. | 19 | | —, Piazza del | | 19 |
| —, Piazza | 19 | | —, Via del | | 19 22 |
| —, Via | 19 | | Quiriti, Piazza dei | | 12 |
| Politeama | 14 | | Raiff, Vigna | | 26 |
| —, Via del | 14 | | Rasella, Via | | 19 |
| Polveriera, Via della | 23 | | Ratazzi, Via | | 28 |
| Polverone, Via del | 14 | | Ravenna, Pal. | | 25 |
| Pompeo Magno, Via | 12 | | Reggio, Via | | 30 |
| Pomponio Leto, Via | 8 | | Regina, Viale della | | 33 |
| Ponieri, Via de' | 12 | | Regola, Via della | | 14 |
| Ponte, Piazza di | 10 | | Reinach, Villa | | 29 |
| Ponte Nomentano, Via di | 30 | | Renella, Via della | | 15 |
| — Sisto, Vicolo di | 14 | | Renzi, Piazza di | | 15 |
| Pontefici, Via de' | 17 | | Riarj, Vicolo de' | | 11 |
| Popolo, Piazza del | 18 | | Ricasoli, Via | | 28 |
| —, Porta del | 15 | | Ricovero, Via di | | 18 |
| Porta, Pal. della | 17 | | Ripetta, Via di | | 14 |
| Porta Castello, Via di | 7 | | —, Passeggiata di | | 14 |
| — Latina, Via di | 26 | | Risorgimento, Piazza | | 8 |
| — Leone, Via di | 18 | | Risparmio, Cassa di | | 16 |
| — S. Lorenzo, Via di | 28 31 | | Rita, Beata. 11 | | 20 |
| — S. Pancrazio, Via di | 9 | | Robbia, Via della | | 17 |
| — S. Paolo, Via di | 21 | | S. Rocco | | 14 |
| — Pia, Via di | 26 | | Romana, Piazza | | 15 |
| — Pinciana, Corso di | 21 | | de Romanis, Pal. | | 13 |
| — —, Via di | 20 | | S. Romualdo, Via | | 19 |
| — Salara, Via di | 27 | | Roncioni, Orto | | 21 |
| — S. Sebastiano, Via di | 24 | | Rondinini, Pal. | | 17 |
| Portico di Ottavia. 18 | 17 | | — —, 13 | | 16 |
| Porto di Ripa Grande | 18 | | Rosa, Via della | | 16 |
| — di Ripetta | 14 | | Rospigliosi, Pal. | | 19 |
| Portuense, Porto | 14 | | Rossini, Teatro. 17 | | 16 |
| Posta | 16 | | Rotonda, la (Pantheon) | | 16 |
| Pozzetto, Via del | 19 | | Ruaccia, Piazza | | 15 |
| Pozzi, Via de' | 20 | | SS. Rufina e Seconda. 2 | | 15 |
| S. Prassede | 25 | | Ruspoli, Pal. | | 16 |

| I II III | | | I II III | | |
|---|----|----|--|----|----|
| Rusticucci, Piazza | 7 | | Servio Tullio, Aggre di | 28 | 20 |
| S. Saba | 20 | | Sette Sale | 26 | |
| —, Via di | 20 | | — —, Via delle | 26 | |
| S. Sabina | 18 | | Settimiana, Porta | 11 | |
| Sacchetti, Pal. | 10 | | Sforza, Piazza | 10 | |
| —, Via | 15 | | —, Via | 25 | |
| Sacripante, Pal. 5 | 13 | | Sforza-Cesarini, Pal. | 10 | |
| Sagrestia, Piazza della | 4 | | — Pallavicini, Via | 8 | |
| —, Via della | 4 | | Sicilia, Via | 27 | |
| Salara, Porta | 27 | | S. Silvestro | 19 | |
| — —, Via della | 18 | | — in Capite | 16 | |
| Salara Vecchia, Via | 20 | | — —, Piazza di | 16 | |
| Sallustiana, Via | 23 | | S. Silvia | 24 | |
| Salumi, Via de' | 18 | | S. Simone | 13 | |
| S. Salvatore | 14 | | S. Simone e Giuditta. 5 | 10 | |
| — | 13 | | Sistina, Via | 20 | |
| — | 18 | | S. Sisto | 26 | |
| — in Campo. 5 | 14 | 16 | Sisto, Ponte | 14 | |
| — della Corte. 6 | 15 | | Soldato, Via del | 13 | |
| — in Lauro | 10 | | Solferino, Via | 28 | |
| — al Torrione. 5 | 4 | | Sora, Pal. | 13 | |
| Salviati, Pal. | 7 | | —, Piazza di | 13 | |
| — | 19 | | Spada, Pal. | 14 | |
| Sampieri, Pal. (Cicciaporci). 3 | 10 | | — —, 19 | 10 | |
| Santacroce, Pal. 4 | 14 | | —, Villa | 9 | |
| Santinelli, Vigna | 33 | | Spagna, Pal. di | 17 | |
| Saponari, Vicolo de' | 17 | | Spagna, Piazza di | 17 | |
| Sardegna, Via | 24 | | — | 20 | |
| Sassi, Vigna | 28 | | Specchj, Piazza de' | 14 | |
| Saturno, Tempio di | 20 | | S. Spirito, Oratorio di. 16 | 7 | |
| Savelli, Via | 13 | | —, Porta | 7 | |
| Savorelli, Villa | 9 | | — in Sassia. 12. | 7 | |
| Scaccia, Via | 1 | | Spirito Santo de' Napoli- tani. 5 | 10 | |
| Scala Santa | 30 | | Stamperia e Calcografia Ca- merale. 7 | 19 | |
| Scalcaccia, Vicolo della | 18 | | Stamperia, Via della | 19 | |
| Schiavoni, Via de' | 17 | | S. Stanislao | 17 | |
| Sciarra-Colonna, Pal. | 16 | | Statuto, Via dello | 26 | |
| Sciarra, Villa | 12 | | Stazione della Ferrovia | 25 | |
| Scilla, Via | 8 | | S. Stefano | 4 | 18 |
| Scimia, Vicolo della | 10 | | — del Cacco | 16 | |
| Scipioni, Via degli | 12 | | — in Piscinula. 21 | 10 | |
| Scossa-Cavalli, Piazza | 7 | | — Rotondo | 27 | 27 |
| Scrofa, Via della | 13 | | — —, Via di | 27 | 27 |
| Scuole degli Ebrei. 2 | 17 | | Stelletta, Via della | 13 | |
| S. Sebastianello, Via | 17 | | Strozzi, Pal. | 16 | |
| S. Sebastiano de' Mercanti. 24 | 17 | | —, 16 | 17 | |
| S. Sebastiano, Porta | 28 | | Struzzo, Vicolo dello | 10 | |
| Sediari, Via dei | 13 | | Sublicio, Ponte | 18 | |
| Semenzaio comunale | 26 | | S. Sudario, Cappella del. S. | 13 | |
| Seminario. 7. | 13 | | —, Via del. | 13 | |
| —, Via del | 16 | | S. Susanna | 23 | |
| Senato del Regno | 13 | | —, Vicolo | 23 | |
| Senatore, Pal. del 2 | 20 | | Tacito, Via | 11 | |
| Sepolcro di Bibulo. 2 | 19 | | Tanaro, Via | 24 | |
| — de' Scipioni | 25 | | Tartaruga, Piazza | 17 | |
| Serlupi, Pal. | 16 | | Tasso, Via | 29 | |
| — —, 17 | 17 | | Teatro Argentina | 13 | |
| Serpenti, Via de' | 22 | | — Caprauca | 16 | |
| Serristori, Pal. 8 | 7 | | — di Marcello. 5 | 17 | |

| I II III | | | I IIIII | | |
|---------------------------------------|----|----|---|----|----|
| Teatro Metastasio. 8 c. | 13 | | Triclinio Leoniano | | 33 |
| — della Pace | 13 | | S. Trifone. 2 | 13 | |
| —, Via del | 13 | | S. Trinità | 16 | |
| — di Pompeo | 13 | | —, 11 | 17 | |
| — della Valle. 15 | 13 | | — de' Monti | 20 | |
| S. Tecla. 15 | 7 | | — de' Pellegrini | 14 | |
| Telegrafo, Ufficio centrale | 16 | | Tritone, Via del | 19 | |
| Telline, Vicolo delle | 10 | | Trofei di Mario, see Acqua | | |
| Teodoli, Pal. 9 | 16 | | Giulia. | | |
| S. Teodoro | 21 | | Tronto, Via | 27 | |
| —, Via di | 21 | | S. Ufficio, Pal. del | 4 | |
| Terenzio, Via | 8 | | Umberto, Ponte | 13 | |
| S. Teresa. 7. | 14 | | Umiltà, Via dell' | 19 | |
| Terme di Agrippa | 16 | | Unità, Piazza dell' | 8 | |
| — di Caracalla | 23 | | Università della Sapienza. 25 | 13 | |
| — di Costantino | 19 | | Urbana, Via | 22 | |
| — di Diocleziano | 25 | | S. Urbano | 20 | |
| — di S. Elena | 35 | | Vaccarella, Vicolo | 13 | |
| — di Tito | 26 | | Valadier, Via | 11 | |
| Terme, Piazza delle (di Ter- | | | Valentini, Pal. | 19 | |
| mini) | 25 | | —, Villa | 9 | |
| Termini, Fontana, see Acqua | | | Valle, Piazza e Via di | 13 | |
| Felice. | | | Vantaggio, Via del | 14 | |
| —, Piazza di, see Piazza | | | Vanvitelli, Via | 17 | |
| delle Terme. | | | Varese, Via | 28 | |
| Testa spaccata, Via | 19 | | Varrone, Via | 8 | |
| Testaccio, Monte | 13 | | Vascellari, Vicolo de' | 18 | |
| —, Via di | 17 | | Vaschette, Piazza delle | 7 | |
| Tevere, Via | 27 | | Vaticano, Monte | 1 | |
| Tibullo, Via | 8 | | —, Pal. | 4 | |
| Tiburtina, Porta | 28 | | Vecchiarelli, Vicolo | 10 | |
| Ticino, Via | 24 | | Velabro, Via in | 21 | |
| Tomacelli, Via | 17 | | S. Venanzio | 17 | |
| S. Tommaso. 1 | 17 | | Venere e Roma, Tempio di | 23 | |
| — | 13 | | Veneto, Via | 23 | |
| — Cantuari. 2 | 13 | | Venezia, Pal. di | 16 | |
| — in Formis | 24 | | —, Piazza di | 16 | |
| Tor Argentina, Via di | 16 | | —, Via. | 22 | |
| — Cantarelli | 25 | | Venti Settembre, Via | 26 | |
| — de' Conti | 20 | | Vergine, Beata del Car- | | |
| —, Via di. | 23 | | mine. 5 | 15 | |
| — Mellina | 13 | | Vergini, Via delle | 19 | |
| — Sanguinea. 4 | 13 | | Verospi, Pal. 10 | 16 | |
| — de' Specchj, Via di | 17 | | Vespasiano, Via | 5 | |
| Tordinona, Via di | 10 | | Vetrina, Via della | 13 | |
| Torino, Via | 25 | 25 | Vicenza, Via | 28 | |
| Torlonia, Pal. 10 | 17 | | Vidoni, Pal. | 13 | |
| — Bolognetti, Pal. 1 | 19 | | Viminale, Via del | 25 | 22 |
| —, Villa | 29 | | SS. Vincenzo ed Anastasio | 14 | |
| Torre Argentina, Via di | 16 | | —, 3 | 19 | |
| Torre delle Milizie. 6 | 19 | | Virginio Orsini, Via | 12 | |
| Torretta, Piazza | 16 | | Visconti, Via | 14 | |
| Toscana, Via | 23 | | Visitazione, Monastero della | 21 | |
| Trajana, Colonna | 19 | | S. Vitale | 22 | |
| Travicella, Via della | 19 | | —, Via di | 22 | 22 |
| Tre Archi, Via de' | 13 | | Vite, Via della. | 16 | |
| Tre Cannelli. 3 | 17 | | Vitelleschi, Pal. 1 | 16 | |
| Tre Ladroni, Vicolo | 16 | | S. Vito | 25 | |
| Tre Pupazzi, Via dei. | 7 | | SS. Vito e Modesto | 28 | |
| Trevi, Fontana di | 19 | | Vittoria, Via. | 17 | |
| Tribunali, Piazza dei | 13 | | — Colonna, Via | 14 | |

| | I | II | III | | I | II | III |
|----------------------------|----|----|-----|------------------------------|----|----|-----|
| Vittorio Emanuele, Corso . | 10 | 13 | | Zabaglia, Via | . | . | 14 |
| —, Monumento | . | 20 | | Zecca Papale | 4 | . | |
| —, Piazza | . | 29 | | Zingari, Piazza | . | 22 | |
| Volpe, Via del | 13 | | | Zoccolette, Monast. delle. | 2 | . | 14 |
| Volturno, Via | 26 | | | Zuccheri, Palazzo | 20 | . | |
| Wolkonsky, Villa | 33 | | | Zucchette, Via delle | 19 | . | |

Wellcome Library

1. 1. Corallo di S. Stefano
2. 2. Corallo di S. Stefano
3. 3. S. Martino de' S. Stefano
4. 4. S. Maria di Pietà, con lamposanto (carnia di S. Stefano)
5. 5. Salvatore al Torrione
6. 6. S. Bernardino della Ragna
7. 7. 1. S. Anna de' Palatieri
8. 8. Pal. Arcimondi
9. 9. S. Maria della Purità
10. 10. Pal. Bernardi-Torlonia
11. 11. S. Maria Traspontina
12. 12. S. Filippo Neri
13. 13. S. Giacomo Scassavalli
14. 14. Pal. Sorrenti
15. 15. Pal. Ricci-Piccolomini (ora Caserma)
16. 16. S. Lorenzo in Padoa
17. 17. Pal. Magi (ora Gran Guardia)
18. 18. S. Spirito in Sassia
19. 19. Pal. del Commendatore



10. 1. S. Orsola
2. 2. Pal. Niccolini
3. 3. Pal. Sanpiere (Accademia)
4. 4. S. Carlo
5. 5. S. S. Simone e Giuditta
13. 1. Pal. Lanfranco
2. 2. S. Trilone
3. 3. S. Maria della Pace
4. 4. Tur. Sarguignea
5. 5. Pal. Sacripanti
6. 6. Pal. Altemps
7. 7. Seminario
8. 8. S. Nicola de' Lorenzini
9. 9. Ministero della Marina
10. 10. Ministero Giustizia e Affari

9. Pal. Casali
10. S. Antonio di Padova
11. S. Lucia della Tinta
12. S. Ivo
13. Pal. Gualtieri
14. Pal. Caracciolo
15. Teatro Metastasio
14. 1. Conservatorio della Misericordia
16. 1. Pal. Marsicotti
2. 2. S. Maria in Campo Marzo
3. 3. S. Nicola de' Perfetti
4. 4. S. Biagio
5. 5. Caserma de' Vigili
6. 6. Pal. Mancini

1. S. dell'Arco di M. Aurelio
2. Pal. Pisoni
3. Pal. Tondoli
10. Pal. Verospi
11. Pal. Palombaro
12. Pal. Conti
13. Pal. Rondinini
14. Convento de' Padri della Missione
15. Pal. Lavaggi
16. S. Maria Maddalena
17. S. Maria in Aquila
18. Dogana di terra ora Borsa
19. S. Bartolomeo

- a. Isole Britanniche 18 (1)
- b. Albergo di Russia 18 (1)
- c. Londra 17 (1)
- d. Europa 20 (1)
- e. Brighton 20 (1)
- f. Inghilterra 17 (1)
- g. America 17 (1)
- h. del Quirinale 25 (1)
- i. di Roma 17 (1)
- j. Allernaghi 17 (1)
- k. Vittoria 19 (1)
- l. Minerva 16 (1)
- m. Cesari 16 (1)
- n. della Città 17 (1)
- o. Costanti 17 (1)
- p. Albert 17 (1)
- q. Possidoni 17 (1)
- r. degli Stati Uniti (1)
- s. Anglo Americano (1)
- t. New York 17 (1)
- u. del Sud 17 (1)
- v. Moluro 19 (1)
- w. Bristol 22 (1)
- x. del Louvre 23 (1)
- y. della Pace 19 (1)
- z. d'Italia 23 (1)
- aa. d'Oriente e Occidente (1)
- ab. Milano 13, 16 (1)
- ac. Centrale 16 (1)
- ad. dei Tre Re 19 (1)
- ae. Pensione Unione 23 (1)
- af. Canali

1:100000 0 50 100 200 300 400 500 600 700 800 900 1000 Metri





1. S. Maria della Clemenza
2. S. Maria del Redigio
3. S. Caterina della Rota
4. S. Caterina di Sanesi
5. S. Maria di Monserrato
6. S. Egidio
7. S. Spirito Santo de' Napolitani
8. S. Giorgio di S. Spirito
9. S. Maria degli Incarnati
10. S. Filippo Veri
11. S. Lucia del Gonfalone
12. S. Lucia
13. S. Maria del Suffragio
14. S. Eusebio
15. S. Biagio della Pagnotta
16. S. Maria della Purificazione
17. S. Spirito
18. S. Spirito
19. S. Spirito
20. S. Spirito
21. S. Spirito
22. S. Spirito
23. S. Spirito
24. S. Spirito
25. S. Spirito
26. S. Spirito
27. S. Spirito
28. S. Spirito
29. S. Spirito
30. S. Spirito
31. S. Spirito
32. S. Spirito
33. S. Spirito
34. S. Spirito
35. S. Spirito
36. S. Spirito
37. S. Spirito
38. S. Spirito
39. S. Spirito
40. S. Spirito
41. S. Spirito
42. S. Spirito
43. S. Spirito
44. S. Spirito
45. S. Spirito
46. S. Spirito
47. S. Spirito
48. S. Spirito
49. S. Spirito
50. S. Spirito
51. S. Spirito
52. S. Spirito
53. S. Spirito
54. S. Spirito
55. S. Spirito
56. S. Spirito
57. S. Spirito
58. S. Spirito
59. S. Spirito
60. S. Spirito
61. S. Spirito
62. S. Spirito
63. S. Spirito
64. S. Spirito
65. S. Spirito
66. S. Spirito
67. S. Spirito
68. S. Spirito
69. S. Spirito
70. S. Spirito
71. S. Spirito
72. S. Spirito
73. S. Spirito
74. S. Spirito
75. S. Spirito
76. S. Spirito
77. S. Spirito
78. S. Spirito
79. S. Spirito
80. S. Spirito
81. S. Spirito
82. S. Spirito
83. S. Spirito
84. S. Spirito
85. S. Spirito
86. S. Spirito
87. S. Spirito
88. S. Spirito
89. S. Spirito
90. S. Spirito
91. S. Spirito
92. S. Spirito
93. S. Spirito
94. S. Spirito
95. S. Spirito
96. S. Spirito
97. S. Spirito
98. S. Spirito
99. S. Spirito
100. S. Spirito

19. S. Pal. del ballo
20. S. Pal. del ballo
21. S. Pal. del ballo
22. S. Pal. del ballo
23. S. Pal. del ballo
24. S. Pal. del ballo
25. S. Pal. del ballo
26. S. Pal. del ballo
27. S. Pal. del ballo
28. S. Pal. del ballo
29. S. Pal. del ballo
30. S. Pal. del ballo
31. S. Pal. del ballo
32. S. Pal. del ballo
33. S. Pal. del ballo
34. S. Pal. del ballo
35. S. Pal. del ballo
36. S. Pal. del ballo
37. S. Pal. del ballo
38. S. Pal. del ballo
39. S. Pal. del ballo
40. S. Pal. del ballo
41. S. Pal. del ballo
42. S. Pal. del ballo
43. S. Pal. del ballo
44. S. Pal. del ballo
45. S. Pal. del ballo
46. S. Pal. del ballo
47. S. Pal. del ballo
48. S. Pal. del ballo
49. S. Pal. del ballo
50. S. Pal. del ballo
51. S. Pal. del ballo
52. S. Pal. del ballo
53. S. Pal. del ballo
54. S. Pal. del ballo
55. S. Pal. del ballo
56. S. Pal. del ballo
57. S. Pal. del ballo
58. S. Pal. del ballo
59. S. Pal. del ballo
60. S. Pal. del ballo
61. S. Pal. del ballo
62. S. Pal. del ballo
63. S. Pal. del ballo
64. S. Pal. del ballo
65. S. Pal. del ballo
66. S. Pal. del ballo
67. S. Pal. del ballo
68. S. Pal. del ballo
69. S. Pal. del ballo
70. S. Pal. del ballo
71. S. Pal. del ballo
72. S. Pal. del ballo
73. S. Pal. del ballo
74. S. Pal. del ballo
75. S. Pal. del ballo
76. S. Pal. del ballo
77. S. Pal. del ballo
78. S. Pal. del ballo
79. S. Pal. del ballo
80. S. Pal. del ballo
81. S. Pal. del ballo
82. S. Pal. del ballo
83. S. Pal. del ballo
84. S. Pal. del ballo
85. S. Pal. del ballo
86. S. Pal. del ballo
87. S. Pal. del ballo
88. S. Pal. del ballo
89. S. Pal. del ballo
90. S. Pal. del ballo
91. S. Pal. del ballo
92. S. Pal. del ballo
93. S. Pal. del ballo
94. S. Pal. del ballo
95. S. Pal. del ballo
96. S. Pal. del ballo
97. S. Pal. del ballo
98. S. Pal. del ballo
99. S. Pal. del ballo
100. S. Pal. del ballo



1. S. Maria di Guercia
15. S. Margherita
2. Sepolcro di Bidulo
3. Madonna di Loreo
4. Nome di Maria

